


Baedeker's
PARIS
AND ITS
ENVIRONS.

BÆDEKER'S GUIDE BOOKS.

- GREAT BRITAIN, with 15 Maps, 30 Plans, and a Panorama.
Second Edition. 1890. 10 marks.
- LONDON AND ITS ENVIRONS, with 3 Maps and 15 Plans.
Seventh Edition. 1889. 6 marks.
- BELGIUM AND HOLLAND, with 13 Maps and 20 Plans.
Tenth Edition. 1891. 6 marks.
- THE RHINE
Maps and 22 .
- NORTHERN ()
Tenth Editio
- SOUTHERN G
30 Plans. Se
- THE EASTER
LANDS TY
12 Plans, and
- GREECE, with
1889.
- NORTHERN I
VENNA, with
- CENTRAL ITA
a Panorama
- SOUTHERN I
LIPARI ISLANDS, with 12 Maps and 10 Plans. Tenth Edition. 1890. 6 marks.
- CORFU, with 26 Maps and 16 Plans. Tenth Edition. 1890. 6 marks.
- NORWAY AND SWEDEN, with 23 Maps and 13 Plans.
Fourth Edition. 1889. 9 marks.
- PARIS AND ITS ENVIRONS, WITH ROUTES FROM LONDON
TO PARIS. With 11 Maps and 31 Plans. Tenth Edition. 1891. 6 marks.
- NORTHERN FRANCE, with 9 Maps and 25 Plans. 1889.
7 marks.
- SOUTHERN FRANCE, with 14 Maps and 19 Plans. 1891.
9 marks.
- SWITZERLAND, AND THE ADJACENT PARTS OF ITALY,
SAVOY, AND THE TYROL, with 39 Maps, 11 Plans, and 12 Panoramas.
Fourteenth Edition. 1891. 8 marks.
- LOWER EGYPT, WITH THE PENINSULA OF SINAI, with 16
Maps, 30 Plans, and 7 Views. Second Edition. 1885. 16 marks.
- UPPER EGYPT, WITH NUBIA AS FAR AS THE SECOND CATA-
RACT, AND THE WESTERN OASES. With 11 Maps and 26 Plans.
1892. 10 marks.
- PALESTINE AND SYRIA, with 18 Maps, 43 Plans, a Pano-
rama of Jerusalem, and 10 Views. 1876. 20 marks.
- CONVERSATION DICTIONARY in four languages: Eng-
lish, French, German, Italian. 3 marks.
- THE TRAVELLER'S MANUAL OF CONVERSATION, IN
ENGLISH, GERMAN, FRENCH, and ITALIAN. 3 marks.



STANCE, with 36
6 marks.

s and 54 Plans.
8 marks.

with 15 Maps and
8 marks.

BAVARIAN HIGH-
c. With 35 Maps,
1891. 8 marks.

orama of Athens.
10 marks.

t, FLORENCE, RA-
tion. 1892. 8 marks.

aps, 31 Plans, and
6 marks.

CURSIONS TO THE
DINIA, MALTA, AND

PARIS

MONEY TABLE (comp. p. xii).
Approximate Equivalents.

French Money.		American Money.		English Money.		German Money.	
Francs.	Centimes.	Dollars.	Cents.	Pounds.	Shillings	Pence.	Marks. Pfennigs.
—	5 (= 1 sou)	—	1	—	—	$\frac{1}{2}$	—
—	25 (= 5 sous)	—	5	—	—	$\frac{2}{2}$	4
—	50 (= 10 ")	—	10	—	—	$\frac{4}{4}$	20
—	75 (= 15 ")	—	15	—	—	$\frac{7}{4}$	40
1	(= 20 ")	—	20	—	—	$\frac{9}{4}$	60
2	—	—	40	—	1	$\frac{7}{4}$	80
3	—	—	60	—	2	$\frac{4}{4}$	40
4	—	—	80	—	3	$\frac{2}{2}$	20
5	—	—	—	—	4	—	—
6	—	1	20	—	4	$\frac{9}{4}$	—
7	—	1	40	—	5	$\frac{7}{4}$	80
8	—	1	60	—	6	$\frac{4}{4}$	60
9	—	1	80	—	7	$\frac{2}{2}$	40
10	—	2	—	—	8	—	20
11	—	2	20	—	8	$\frac{9}{4}$	80
12	—	2	40	—	9	$\frac{7}{4}$	60
13	—	2	60	—	10	$\frac{4}{4}$	40
14	—	2	80	—	11	$\frac{2}{2}$	20
15	—	3	—	—	12	—	—
16	—	3	20	—	12	$\frac{9}{4}$	80
17	—	3	40	—	13	$\frac{7}{4}$	60
18	—	3	60	—	14	$\frac{4}{4}$	40
19	—	3	80	—	15	$\frac{2}{2}$	20
20	—	4	—	—	16	—	—
25	—	5	—	1	—	—	—
100	—	20	—	4	—	—	—

P A R I S

AND

ENVIRONS

WITH

ROUTES FROM LONDON TO PARIS



HANDBOOK FOR TRAVELLERS

BY

K. BAEDEKER



WITH 11 MAPS AND 31 PLANS

TENTH REVISED EDITION



LEIPSIC: KARL BAEDEKER, PUBLISHER

1891

‘Go, little book, God send thee good passage,
And specially let this be thy prayere
Unto them all that thee will read or hear,
Where thou art wrong, after their help to call,
Thee to correct in any part or all!’

PREFACE.

The chief object of the Handbook for Paris, which is now issued for the tenth time, and corresponds with the thirteenth German edition, is to render the traveller as nearly as possible independent of the services of guides, commissionnaires, and innkeepers, and to enable him to employ his time and his money to the best advantage.

Objects of general interest, described by the Editor from his personal observation, are those with which the Handbook principally deals. A detailed account of all the specialties of Paris would of course far exceed the limits of a work of this character.

The Maps and Plans, upon which the utmost care has been bestowed, will, it is hoped, be found serviceable. Those which relate to Paris itself (one clue-map, one large plan, five special plans of the most important quarters of the city, and one omnibus-plan) have been collected in a separate cover at the end of the volume, and may if desired be severed from the Handbook altogether. The subdivision of the Plan of the city into three sections distinguished by different colours will be found materially to facilitate reference, as it obviates the necessity of unfolding a large sheet of paper at each consultation.

There is probably no city in the world which ever underwent such gigantic transformations in its external appearance as the French metropolis during the reign of Napoleon III., and few cities have ever experienced so appalling a series of disasters as those which befel Paris in 1870-71. Many squalid purlieus, teeming with poverty and vice, were swept away under the imperial régime, to make room for spacious squares, noble avenues, and palatial edifices. The magnificent metamorphosis of Paris 'from brick to marble' was nearly complete when the gay, splendour-loving, pleasure-seeking city was overtaken by the signal calamities occasioned by the Franco-Prussian war and the Communist rebellion. During that period the city sustained many irreparable losses, but since the restoration of peace it has in most respects resumed its former appearance, the

government having done its utmost to restore everything as far as possible to its former condition.

A short account of the routes from London to Paris, and of the principal towns of Northern France, with their magnificent Gothic churches, will be acceptable to most travellers.

In the Handbook are enumerated both the first-class hotels and those of humbler pretension. The latter may often be selected by the 'voyageur en garçon' with little sacrifice of real comfort, and considerable saving of expenditure. Those which the Editor, either from his own experience, or from an examination of the numerous hotel-bills sent him by travellers of different nationalities, believes to be most worthy of commendation are denoted by asterisks. It should, however, be borne in mind that hotels are liable to constant changes, and that the treatment experienced by the traveller often depends on circumstances which can neither be foreseen nor controlled.

The Editor begs to tender his grateful acknowledgments to travellers who have sent him information for the benefit of the Handbook, and hopes that they will continue to favour him with such communications, especially when the result of their own experience.

To hotel-proprietors, tradesmen, and others the Editor begs to intimate that the commendations in the Handbook cannot be secured by purchase, and that advertisements of every form are strictly excluded.

CONTENTS.

Introduction.

	Page
I. Language. Money. Expenses. Season. Passports.	
Custom House	xii
II. Railways	xiii
III. Outline of History	xiv
IV. General Remarks on Paris	xxiii
V. Weights and Measures	xxv
VI. Remarks on Northern France	xxvi
Remarks on French Art	xxix

Preliminary Information.

1. Arrival in Paris	1
2. Hotels	2
3. Restaurants	9
4. Cafés and Confectioners	17
5. Cabs	19
6. Omnibuses and Tramways. River Steamboats	20
7. Railway Stations. Chemin de Fer de Ceinture	22
8. Post and Telegraph Offices	24
9. Theatres, Circuses, Panoramas, etc.	26
10. Concerts, Balls, Sport, and Clubs	32
11. Shops and Bazaars	35
12. Booksellers, Reading Rooms, Libraries, Newspapers	40
13. Baths, Physicians, Maisons de Santé	42
14. Divine Service	44
15. Embassies. Ministerial Offices. Banks	45
16. Topography. Preliminary Drive	46
17. Distribution of Time. Diary	51

Sights of Paris.

Right Bank of the Seine.

Route	
1. From the Palais-Royal to the Bastille, and back by the Boulevards	55
I. The Palais-Royal, and thence to the Hôtel de Ville. — St. Germain-l'Auxerrois. Tour St. Jacques. Place du Châtelet. St. Merri	55

Route	Page
II. From the Hôtel de Ville to the Bastille. — St. Gervais. St. Paul et St. Louis. Colonne de Juillet	64
III. The Boulevards from the Bastille to the Madeleine. — Place de la République. Porte St. Martin. Porte St. Denis. The Bourse. The Opéra	68
IV. From the Madeleine to the Palais-Royal by the Place de la Concorde. — Colonne Vendôme. St. Roch	80
2. Palace and Galleries of the Louvre. The Tuileries	86
I. The Palace of the Louvre	86
II. The Galleries of the Louvre	89
Egyptian Museum	90
Asiatic Museum	93
Ancient Sculptures	95
Mediæval and Renaissance Sculptures	105
Modern Sculptures	108
Musée de Chalcographie	110
Picture Gallery	111
Galerie d'Apollon	136
Salle des Bijoux	139
Collection La Caze	140
Ancient Bronzes	141
Collection of Drawings	141
Smaller Mediæval and Renaissance Antiquities	142
Greek Antiquities	144
Musée Campana	145
Musée de la Marine	146
Musée Ethnographique	147
Musée Chinois	148
Salle des Boîtes	148
III. The Tuileries	148
Arc de Triomphe du Carrousel	148
3. From the Place de la Concorde to the Bois de Boulogne, and back by the Trocadéro	152
I. From the Place de la Concorde to the Place de l'Etoile. — Champs-Élysées. Neuilly	152
II. From the Place de l'Etoile to the Bois de Boulogne. — Fortifications. Hippodrome de Longchamp. Jardin d'Acclimatation	157
III. From the Bois de Boulogne to the Trocadéro and the Place de la Concorde. Auteuil. Musée Guimet	162
4. From the Palais-Royal to Père-Lachaise	168
I. From the Palais-Royal to the Halles Centrales. — St. Eustache	169
II. From the Halles Centrales to the Place de la République. — Conservatoire des Arts et Métiers	172
III. From the Place de la République to Père-Lachaise	175
5. From the Boulevards to La Villette and to Montmartre	185
I. From the Boulevards to La Villette. — St. Laurent. Gare de l'Est. Gare du Nord. Buttes-Chaumont. Market and Abattoirs at La Villette	185
II. From La Villette to Montmartre. — St. Vincent-de-Paul. Butte Montmartre. Cemetery of Montmartre	188
III. From Montmartre to the Boulevards. — Notre-Dame-de-Lorette	194
6. From the Palais-Royal to Batignolles	195
I. From the Palais-Royal to La Trinité. — Bibliothèque Nationale	195
II. From La Trinité to the Parc Monceaux. — Les Batignolles	201

Route	Page
III. From the Parc Monceaux to the Opéra. — St. Augustin. Chapelle Expiatoire. Gare St. Lazare	203
7. From the Louvre to Vincennes	204
I. From the Louvre to the Musée Carnavalet and the Bastille	205
II. From the Bastille to Vincennes	210

The Cité.

8. Palais de Justice. Sainte-Chapelle. Notre-Dame	216
I. Palais de Justice and Sainte-Chapelle. — Tribunal de Commerce. Pont-Neuf. Préfecture de Police	216
II. Notre-Dame. — Hôtel-Dieu. Morgue. Ile St. Louis	221

Left Bank of the Seine.

9. From the Cité to the Panthéon and the Parc Montsouris	225
I. From the Cité to the Musée de Cluny. — Fontaine St. Michel. St. Séverin. Ecole de Médecine	225
II. From the Musée de Cluny to the Panthéon. — Sorbonne. Collège de France. Bibliothèque Ste. Geneviève. St. Étienne-du-Mont	235
III. From the Panthéon to the Parc Montsouris. — Val-de-Grâce. Catacombs	241
10. From the Louvre to the Luxembourg and the Cemetery of Montparnasse	244
I. Institut. Hôtel des Monnaies. Ecole des Beaux-Arts	244
II. From the Ecole des Beaux-Arts to the Luxembourg. — St. Germain-des-Prés. St. Sulpice	250
III. Palace, Gallery, and Garden of the Luxembourg	253
IV. From the Luxembourg to the Cemetery of Montparnasse	259
11. From the Louvre to the Jardin des Plantes and the Gobelins.	262
I. From the Louvre to the Jardin des Plantes	262
II. From the Jardin des Plantes to the Gobelins	267
12. From the Tuileries to the Invalides and the Trocadéro	270
I. From the Tuileries to the Invalides. — Chambre des Députés. Ste. Clotilde	270
II. Hôtel des Invalides. — Musée d'Artillerie. Eglise des Invalides. Tomb of Napoleon	274
III. Champ-de-Mars. — Fontaine du Progrès. Dôme Central. Exhibition Palaces. Ecole Militaire	280

Environs of Paris.

13. From Paris to Versailles	285
From Versailles to St. Germain-en-Laye	307
14. From Versailles to Rambouillet	307
15. From Paris to St. Cloud, Sèvres, and Meudon	308
From St. Cloud to St. Germain-en-Laye.	311
16. From Paris to St. Germain-en-Laye.	313
From Rueil to St. Germain-en-Laye 314. — From St. Germain to Maisons-Laffitte	318
17. From Paris to St. Denis, Enghien, and Montmorency, and back to Paris via Argenteuil	318
a. From Paris to St. Denis	318

Route	Page
b. From St. Denis to Enghien and Montmorency. — From Epinay to Noisy-le-Sec and to Argenteuil	325
c. From Enghien to Paris viâ Argenteuil. — From Argenteuil to Conflans-Ste. Honorine	326
18. From Paris to Fontainebleau	327
19. Sceaux and the Valleys of the Bièvre and the Yvette . .	335
a. From Paris to Sceaux	335
b. From Sceaux to the Valley of the Bièvre. — From Massy-Palaiseau to Valenton and to Juvisy	337, 338
c. From the Valley of the Bièvre to the Valley of the Yvette	339
20. From Paris to the Valley of the Oise	341
a. From Paris to Pontoise	341
1. Viâ St. Denis or Argenteuil. 341. — 2. Viâ Achères	341
b. From Pontoise to Beaumont	343
c. From Beaumont to Paris	344
1. Viâ Montsoult. — From Montsoult to Luzarches	344, 345
2. Viâ Valmondois and Ermont. — Abbaye du Val	345
21. Chantilly and its Environs.	346
a. From Paris to Chantilly	346
b. From Chantilly to Paris viâ Creil and Beaumont	348
c. From Chantilly to Paris viâ Senlis and Crépy-en-Valois	349
1. From Chantilly to Crépy-en-Valois	349
2. From Crépy-en-Valois to Paris	350

Routes from London to Paris.

22. By Folkestone, Boulogne, and Amiens	351
23. By Dover, Calais, and Amiens	356
24. By Newhaven, Dieppe, and Rouen	357
25. By Southampton, Havre, and Rouen	365
List of Artists	369
Index	378

List of Maps and Plans.

A. Maps.

1. Railway Map of France, at the end of the book.
2. Immediate Environs of Paris, p. 284.
3. Remoter Environs of Paris, p. 334.
4. Bois de Boulogne, p. 157.
5. Vincennes and its Environs, p. 212.
6. Asnières and Mont Valérien, p. 286.
7. St. Cloud and Sèvres, p. 308.
8. Environs of St. Germain-en-Laye, p. 316.
9. Forest of Meudon, p. 313.
10. Forest of Fontainebleau, p. 329.
11. Forest of Chantilly, p. 348.

B. Plans.

- | | |
|--|---------------------------------|
| 1. Key-Plan of Paris. | } In the Cover after the Index. |
| 2. Plan of Paris in three sections. | |
| 3. Special Plan of Arc de l'Etoile and Champ-de-Mars District. | |
| 4. " " " Champs-Elysées, W. Boulevards, and Louvre. | |
| 5. " " " E. Boulevards. | |
| 6. " " " Hôtel des Invalides and Palais du Luxembourg District. | |
| 7. " " " Cité, Place de la Bastille, and Jardin des Plantes. | |
| 8. Omnibus and Tramway Plan of Paris. | |
| 9. Historical Plan of the Louvre and Tuileries, p. 88. | |
| 10, 11, 12. Galleries of the Louvre, between pp. 88, 89. | |
| 13. Conservatoire des Arts et Métiers, p. 173. | |
| 14. Père-Lachaise, p. 177. | |
| 15. Cemetery of Montmartre, p. 191. | |
| 16. Bibliothèque Nationale, p. 197. | |
| 17. Musée de Cluny, p. 228. | |
| 18. Ecole des Beaux-Arts, p. 247. | |
| 19. Jardin des Plantes, p. 264. | |
| 20. Musée d'Artillerie, p. 276. | |
| 21. Town and Park of Versailles, p. 287. | |
| 22, 23. Musée de Versailles, ground, first, and second floors, pp. 292, 293. | |
| 24. St. Germain-en-Laye, p. 315. | |
| 25. Fontainebleau, p. 329. | |
| 26. Park of Chantilly, p. 348. | |
| 27. Boulogne, p. 351. | |
| 28. Amiens, p. 354. | |
| 29. Dieppe, p. 358. | |
| 30. Rouen, p. 360. | |
| 31. Le Havre, p. 365. | |

Abbreviations.

M. = Engl. mile; hr. = hour; min. = minute; r. = right; l. = left; N. = north, northwards, northern; S. = south, etc.; E. = east, etc.; W. = west, etc.; R. = room; B. = breakfast; D. = dinner; A. = attendance; L. = light. The letter *d* after a name, with a date, indicates the year of the person's death.

Asterisks

are used as marks of commendation.

INTRODUCTION.

I. Language. Money. Expenses. Season. Passports. Custom House.

LANGUAGE. For those who wish to derive instruction as well as pleasure from a visit to Paris, the most attractive treasury of art and industry in the world, some acquaintance with French is indispensable. The metropolis of France, it is true, possesses English hotels, English professional men, English 'valets de place', and English shops; but the visitor who is dependent upon these is necessarily deprived of many opportunities of becoming acquainted with the most interesting characteristics of the place.

MONEY. The decimal Monetary System of France is extremely convenient in keeping accounts. The Banque de France issues *Banknotes* of 5000, 1000, 500, 200, 100, and 50 francs. The French *Gold* coins are of the value of 100, 50, 20, 10, and 5 francs; *Silver* coins of 5, 2, 1, $\frac{1}{2}$, and $\frac{1}{5}$ franc; *Bronze* of 10, 5, 2, and 1 centime (100 centimes = 1 franc). '*Sou*' is the old name, still in common use, for 5 centimes; thus, a 5-franc piece is sometimes called 'une pièce de cent sous', 2 fr. = 40 sous, 1 fr. = 20 sous, $\frac{1}{2}$ fr. = 10 sous. Italian, Belgian, Swiss, and Greek gold and silver coins are also received at their full value, and the new Austrian gold pieces of 4 and 8 florins are worth exactly 10 and 20 fr. respectively. The only foreign copper coins current in France are those of Italy, and occasionally the English penny and halfpenny, which nearly correspond to the 10 and 5 centime piece respectively.

English banknotes, gold, and even silver are generally received at the full value, except at the shops of the money-changers, where a trifling deduction is made. The table at the beginning of the book shows the comparative value of the French, English, American, and German currencies, when at par. The currency of Belgium, Switzerland, Italy, and Greece is the same as that of France.

The traveller should always be provided with small change (*petite monnaie*), as otherwise he may be put to inconvenience in giving gratuities, purchasing catalogues, etc.

EXPENSES. The cost of a visit to Paris depends of course on the tastes and habits of the traveller. If he selects a hotel of a high class, dines at the table d'hôte, or perhaps the 'Dîner de Paris', partakes of wine of good though not extravagant quality, visits the theatres, drives in the parks and environs, and finally indulges in

suppers *à la carte*, he must be prepared to spend 30-40 fr. a day or upwards. Those, however, who visit Paris for the sake of its monuments, its galleries, its collections, and not for its pleasures, will have little difficulty, with the aid of the information in the Handbook, in limiting their expenditure to 15-20 fr. a day. It need hardly be observed, that, in a city where luxury is raised to a science, and where temptations to extravagance meet one at every step, each traveller must be his own mentor.

SEASON. Spring and autumn are the best seasons for a visit to Paris, the former perhaps deserving the preference as having fewer rainy days. The long days of summer are in some respects admirably adapted for sight-seeing; but the heat is often excessive, and the absence of a large proportion of the ordinary residents deprives the city of one of its most characteristic features. The winter is not generally severe, but the short days are inconvenient for sight-seers.

PASSPORTS. These documents are now dispensed with in France, but they are often useful in proving the traveller's identity, procuring admission to museums on days when they are not open to the public, etc., and they must be shown in order to obtain delivery of registered letters. The *visa* of a French ambassador or consul is unnecessary. Application for passports may be made to W. J. Adams, 59 Fleet Street; Lee and Carter, 440 W. Strand; Dorrell & Son, 15 Charing Cross; Webster & Larkin, 60 Piccadilly; or E. Stanford, 26 Cockspur Street, Charing Cross.

CUSTOM HOUSE. In order to prevent the risk of unpleasant detention at the 'douane' or custom-house, travellers are strongly recommended to avoid carrying with them any articles that are not absolutely necessary. Cigars and tobacco are chiefly sought for by the custom-house officers. The duty on the former amounts to about 16s., on the latter to 7-11s. per lb. Articles liable to duty should always be 'declared'. Books and newspapers occasionally give rise to suspicion and may in certain cases be confiscated.

II. Railways.

The network of railways by which France is now overspread consists of lines of an aggregate length of 20,600 M. The fares per English mile are approximately: 1st cl. 18 c., 2nd cl. 13½ c., 3rd cl. 10½ c., to which a tax of ten per cent on each ticket costing more than 10 fr. is added. The express trains (*'trains express', 'rapides'*) generally convey first-class passengers only. The carriages are inferior to those in most other parts of Europe. The trains are not always provided with smoking carriages, but in the others smoking is allowed unless any one of the passengers objects.

Before starting, travellers are generally cooped up in the close and dusty waiting-rooms, and are not admitted to the platform until

the train is ready to receive them; nor is any one admitted to the station to take leave of friends without special permission. Tickets for intermediate stations are usually collected at the 'sortie'; those for termini, before the station is entered. Travellers within France are allowed 30 kilogrammes (66 Engl. lbs.) of luggage free of charge; those who are bound for foreign countries are allowed 25 kilogr. only (55 lbs.); 10 c. is charged for booking. At most of the railway-stations there is a *consigne*, or left-luggage office, where a charge of 10 c. per day is made for one or two packages, and 5 c. per day for each additional article. Where there is no *consigne*, the employés will generally take care of luggage for a trifling fee. The railway-porters (*facteurs*) are not entitled to remuneration, but it is usual to give a few sous for their services.

Return-tickets (*Billets d'aller et retour*) are issued by all the railway-companies at a reduction of 15-25 per cent; those issued on Sat. and on the eves of great festivals are available for three days. The custom of raising the fares on the suburban railways on Sundays and holidays has fallen almost entirely into desuetude.

The most trustworthy information as to the departure of trains is contained in the *Indicateur des Chemins de Fer*, published weekly, and sold at all the stations (75 c.). There are also separate and less bulky time-tables for the different lines ('*Livrets Châir*'): du Nord, de l'Est, de l'Ouest, etc. (40 c.).

Railway time is always that of Paris, which differs considerably from that of the adjacent countries. Thus the Belgian time is 8 min., the German 22 min., and the Swiss 26 min. in advance of French railway time.

III. Outline of History.

At the time of the conquest of Gaul by Julius Cæsar, the *Parisii* were a tribe settled on the banks of the *Sequana* or Seine, and their chief town was *Lutetia*, situated on the present island of *La Cité* (comp. p. 216).

The first event in the town's history worthy of mention was the introduction of Christianity by St. Denis, who, according to tradition, suffered martyrdom on Montmartre about the year 250. — Constantius Chlorus is said to have founded the Palais des Thermes (p. 234) between 292 and 306. — Julian resided at Lutetia in 360. The name of the town was then changed to Parisii, and the political franchise bestowed upon it. — In the vicinity of Paris, Gratian was defeated and slain by Maximus in 383.

Merovingians. Clovis, son of Childeric, king of Tournay, finally expelled the Romans about the year 496, embraced Christianity, and became the founder of the *Merovingian Dynasty*, which was so named from *Meroveus*, father of Clovis. Clovis erected a church to St. Peter and St. Paul, which he subsequently dedicated

to Ste. Geneviève, who died in his reign. Few of the monarchs of this or the subsequent dynasty resided at Paris.

Carlovingians. **PEPIN** (*Le Bref*), who became king of France in 752, was the founder of the second or *Carlovingian Dynasty*. **CHARLEMAGNE**, 768.

LOUIS I. (*Le Débonnaire*), 814.

CHARLES II. (*Le Chauve*), 840. Paris sacked by the Normans, 857. — The subsequent monarchs neglected the city, and, when it was again attacked by the Normans in 885, left it to its own resources. The dynasty was deposed in consequence, and the crown given to **COUNT ODO**, or *Eudes*, who had been instrumental in repelling the Normans, and who was the ancestor of the Capetian family.

Capetians. **HUGH CAPET**, grand-nephew of Eudes, was the founder of the third or *Capetian Dynasty* (987). The city now increased rapidly, and a palace on the site of the present Palais de Justice was begun.

ROBERT II. (*Le Pieux*), 996.

HENRI I., 1031.

PHILIP I., 1060. *William, Duke of Normandy*, conquers England, 1066. First Crusade under *Godfrey de Bouillon*, 1096.

LOUIS VI. (*Le Gros*), 1108, founded a palace on the site of the Louvre. *Suger*, abbot of St. Denis, the king's minister.

LOUIS VII. (*Le Jeune*), 1137. His divorced wife, Eleanor of Guienne and Poitou, married Henry Plantagenet, afterwards Henry II. of England. Foundation-stone of Notre-Dame laid by Pope Alexander III. in 1163.

PHILIP II. (*Auguste*), 1180, extended the city considerably, and surrounded it with a wall and turrets. Undertakes the third Crusade, in company with *Richard Coeur de Lion*, 1189. On his return he attacks the English possessions in France, occupies Normandy, Maine, and Poitou, and defeats the English, Flemish, and German troops at *Bouvines* in 1214.

LOUIS VIII. (*Le Lion*), 1223.

LOUIS IX. (*St. Louis*), 1226. Crusades to Egypt and Tunis. Paris obtains various municipal privileges. The *University of the Sorbonne* founded by Robert Sorbon, the king's chaplain, 1250.

PHILIP III. (*Le Hardi*), 1270.

PHILIP IV. (*Le Bel*), 1285, founded the *Parlement*, or court of justice, and convoked the *Etats-Généraux* for the first time. He caused the papal residence to be transferred to Avignon, and in 1307 abolished the order of Knights Templar.

LOUIS X. (*Le Hutin*), 1314.

PHILIP V. (*Le Long*), 1316.

CHARLES IV. (*Le Bel*), 1322, died without issue.

House of Valois. **PHILIP VI.**, 1328. War with England, 1339 ('*Guerre de Cent Ans*' 1339-1453). Battle of *Crécy*, 1346.

JOHN (*Le Bon*), 1350; defeated and taken prisoner by the English at *Poitiers*, 1356. Peace of *Brétigny*, 1360.

CHARLES V. (*Le Sage*), 1364, founder of the Royal Library, the Bastille, and the Palais des Tournelles. The city extended and re-fortified. The English expelled by *Bertrand du Guesclin*.

CHARLES VI., 1380; became insane twelve years afterwards. Defeat of the Flemings under Artevelde at *Rosbeck*, 1382. War of the Armagnacs. The French under the *Constable d'Albret* defeated by Henry V. of England at *Agincourt* or *Azincourt*, 1415. Paris occupied by the English, 1421.

CHARLES VII., 1422. The siege of Orleans raised by *Joan of Arc*, 1429. Coronation at Rheims. Joan burned at Rouen as a witch, 1431. The English expelled. At Paris 50,000 persons die of the plague (1437-8), which is followed by a famine.

LOUIS XI., 1461. Introduction of printing, and establishment of post-office.

CHARLES VIII., 1483; conquers Naples, 1495. Battle of *St. Jacques* near Bâle against the Swiss, 1444.

LOUIS XII., '*Le père du peuple*', 1498, first king of the younger branch of the House of Valois, conqueror of Milan and (in alliance with the Spaniards) of Naples. Having quarrelled with his Spanish allies, he was defeated by them on the *Garigliano* in 1503, on which occasion *Bayard* was present. The League of Cambrai is formed for the purpose of expelling the Venetians from the mainland of Italy. The Venetians defeated at *Agnadello*, 1509; but they succeed in destroying the League, and in forming the Ligue Sainte for the purpose of expelling the French from Italy. They defeat the French at *Ravenna*, 1512.

FRANCIS I., 1515, defeats the Swiss at *Marignano*, and recovers the Duchy of Milan. Four wars with Charles V. for the possession of Burgundy and Milan. Francis defeated and taken prisoner at *Pavia*, 1525. The city was more considerably altered and improved in this than in any of the preceding reigns. Many new edifices were erected, churches repaired, and the fortifications extended. Palace of the Louvre and Hôtel de Ville begun.

HENRI II., 1547, husband of *Catherine de Médicis*, accidentally killed at a tournament (p. 64). Metz, Toul, and Verdun annexed to France, 1556. Final expulsion of the English.

FRANCIS II., 1559, husband of *Mary Stuart* of Scotland.

CHARLES IX., brother of Francis II., 1560. Regency of *Catherine de Médicis*, the king's mother. Beginning of the *Religious Wars*. Louis de Condé, Antoine de Navarre, and Admiral Coligny, leaders of the Huguenots; François de Guise and Charles de Lorraine command the Roman Catholic army. The Tuileries erected. *Massacre of St. Bartholomew*, 24th August, 1572.

HENRI III., 1574, brother of his two predecessors; flies from Paris, where a rebellion had broken out, by the advice of his

mother, Catherine de Médicis (d. 1588); assassinated at St. Cloud by Jacques Clément, a Dominican friar.

House of Bourbon. HENRI IV., 1589, first monarch of the *House of Bourbon*, defeats the Roman Catholic League at *Arques* in 1589, and at *Ivry* in 1590, becomes a Roman Catholic in 1593, captures Paris in 1594. *Sully* his minister. Religious toleration granted by the Edict of Nantes. Henry, divorced from Margaret of Valois in 1599, marries Marie de Médicis the following year; assassinated by Ravaillac in 1610. The metropolis greatly embellished during this reign. The Pont-Neuf completed, additions made to the Louvre and Tuileries.

LOUIS XIII., 1610; his mother Marie de Médicis, regent; she is banished to Cologne, where she dies in 1642. *Richelieu*, his minister (d. 1642). English fleet defeated at *Ré*, 1627; *La Rochelle* taken from the Huguenots. France takes part in the Thirty Years' War against Austria. The Palais-Cardinal (now 'Royal') begun by Richelieu, and the Luxembourg by Marie de Médicis. New bridges, quays, and streets constructed. Jardin des Plantes laid out.

LOUIS XIV., 1643, under the regency of his mother, *Anne of Austria*. Ministers: Mazarin (d. 1661), Louvois (d. 1691), and Colbert (d. 1683). Generals: Turenne (d. 1675), Condé (d. 1686), Luxembourg (d. 1695).

War of the *Fronde* against the court and Mazarin. Condé (Duc d'Enghien) defeats the Spaniards at *Rocroy* in 1643, and at *Lens* in Holland in 1645. Turenne defeats the Bavarians at *Freiburg* and at *Nördlingen*, 1644. Submission of the Fronde. Peace of the Pyrenees, with Spain, 1659.

Death of Mazarin, 1661. The king governs alone.

Louis marries *Maria Theresa*, 1660. After the death of his father-in-law, Louis lays claim to the Low Countries. Turenne conquers Hainault and part of Flanders, 1667. Condé occupies the *Franche Comté*. Peace of Aix-la-Chapelle, in consequence of the Triple Alliance, 1668.

War with Holland, Passage of the Rhine, 1672. Occupation of the provinces of Utrecht and Guelderland. Victories of Turenne over the Imperial army at *Sinzheim*, *Ensisheim*, *Mülhausen* (1674), and *Türkheim* (1675). Death of Turenne at *Sassbach*, 1675.

Admiral Duquesne defeats the Dutch fleet near *Syracuse*, 1676. Marshal Luxembourg defeats William of Orange at *Montcassel*, 1677. Peace of *Nymwegen*, 1678. Strassburg occupied, 1681. Occupation of Luxembourg. Revocation of the Edict of Nantes, 1685. Devastation of the Palatinate, 1688. Marshal Luxembourg defeats the Imperial troops at *Fleurus* (1690) and *Steenkerke* (1692), and William of Orange at *Neerwinden*, 1693. The French fleet under Admiral Tourville defeated by the English at *La Hogue*, 1692. Peace of *Ryswyk*, 1697.

Spanish war of succession, 1701. Victory of Vendôme at *Luzara* (1702), and of Tallard at *Speyer* (1702). Taking of *Landau*,

1702. Victory at *Höchstädt* (1703); defeat at *Höchstädt*, or *Blenheim* (1704), by the Duke of Marlborough and Prince Eugene of Savoy. Marshal Villars defeated by Prince Eugene at *Turin* (1705), and by Marlborough and the Prince at *Ramillies* (1709), *Oudenarde* (1708), and *Malplaquet* (1709). Peace of *Utrecht* and *Rastadt*, 1714.

During this reign upwards of eighty new streets and thirty-three churches were constructed. Hôtel des Invalides, Observatory, and the colonnade of the Louvre completed. Collège Mazarin, Gobelins, etc., begun. Fortifications converted into boulevards.

Louis XV., 1715; ten years' regency of the *Duke of Orleans*. Marries *Marie Leszcinska* of Poland. Austrian war of succession (1740-48). Defeat at *Dettingen* by George II. of England. Defeat of the Dutch and English at *Fontenoy* (1744), of the Austrians under Charles of Lorraine at *Rocoux* (1746), and of the Allies near *Lauffeld* (*Lawfeld*) in 1746. Taking of *Maastricht* and Peace of *Aix-la-Chapelle*, 1748. Naval war against England.

Seven years' war with England. Duke of Cumberland defeated by Marshal d'Estrées, 1757. The French under Prince de Soubise defeated the same year by Frederick the Great at *Rosbach*, and in 1758 at *Crefeld*, by the Duke of Brunswick. The latter defeated by Marshal Broglie at *Bergen*, 1759. The French defeated at *Minden* (1759), etc.

The Panthéon, Ecole Militaire, Palais du Corps Législatif, Hôtel des Monnaies, and many other important buildings were erected during this reign. Jardin des Plantes extended.

Louis XVI., 1774, married to Marie Antoinette, daughter of Francis I. and Maria Theresa. American War of Independence against England, 1777-83. Exhaustion of the finances of France; Vergennes, Turgot, Necker, Calonne, Brienne, and Necker (a second time), ministers of finance.

1789. REVOLUTION. Assembly of the *States General* at Versailles, 5th May. Their transformation into a *National Assembly*, 17th June. Oath of the *Jeu de Paume* (p. 289), 20th June. Storming of the Bastille, 14th July. The 'Femmes de la Halle' at Versailles, 5th Oct. Confiscation of ecclesiastical property, 2nd Nov.

1790. National fête in the Champ-de-Mars.

1791. The Emigration. The royal family escape from Paris, but are intercepted at Varennes, 22nd June. Oath to observe the Constitution, 14th Sept. *Assemblée Législative*.

1792. War with Austria, 20th April. Storming of the Tuileries, 10th Aug. The king arrested, 11th Aug. Massacres in Sept. Cannonade of *Valmy* against the Prussians, 20th Sept. The *National Convention* opened, and royalty abolished, 21st Sept.

REPUBLIC proclaimed, 25th Sept. Custine enters *Mayence*, 21st Oct. Battle of *Jemappes* against the Austrians, 6th Nov. Conquest of Belgium.

1793. Louis XVI. beheaded, 21st Jan. Republican reckoning of time introduced, 22nd Sept.†. Reign of Terror. The queen beheaded, 16th Oct. Worship of Reason introduced, 10th Nov. Loss of Belgium.

1794. Robespierre's fall and execution, 27th July. Jourdan's victory at *Fleurus*, 16th June. Belgium reconquered.

1795. Conquest of Holland by Pichegru. Bonaparte commander of the troops of the Convention against the Royalists under Darnican, 3rd Oct. DIRECTORY established, 27th Oct.

1796. Bonaparte's successes in Italy (*Montenotte*, *Millesimo*, *Lodi*, *Milan*, *Mantua*, *Castiglione*, *Bassano*, and *Arcole*).

1797. Victory at *Rivoli*, 17th Jan. Taking of *Mantua*, 2nd Feb. The Austrians commanded by Archduke Charles, at first victorious, are defeated by Bonaparte. Peace of *Campo Formio*, 17th Oct. Change in the Directory on 18th Fructidor (4th Sept.).

1798. Bonaparte in Egypt. Victory of the *Pyramids*, 21st July. Defeated by Nelson at the battle of the Nile, 1st Aug.

1799. Bonaparte invades Syria. Acre defended by Sir Sidney Smith. Victory of *Aboukir*, 25th July. Fall of the Directory, 9th Nov. Establishment of the CONSULATE, 24th Dec. Bonaparte First Consul.

1800. Bonaparte's passage of the St. Bernard, 13-16th May. Victories at *Piacenza*, *Montebello*, *Marengo*, and *Hohenlinden*. Attempt to assassinate Napoleon at Paris, 23rd Dec.

1801. Peace of Lunéville with Germany, 9th Feb.

1802. Peace of Amiens with England, 27th March. Bonaparte (with Cambacérès and Lebrun) elected Consul for life.

1804. FIRST EMPIRE. NAPOLEON I. proclaimed Emperor by the Senate, 18th May; crowned by Pope Pius VII., 2nd Dec.

1805. Renewal of war with Austria. Capitulation of *Ulm*, 17th Oct. Defeat of *Trafalgar*, 21st Oct. Battle of *Austerlitz*, 2nd Dec. Peace of *Pressburg*, 26th Dec.

1806. Establishment of the Rhenish Confederation, 12th July. War with Prussia. Battles of *Jena* and *Auerstädt*, 14th Oct. Entry into Berlin, 27th Oct. Continental blockade.

† The year had 12 months: Vendémiaire (month of the *vendange*, or vintage) from 22nd Sept. to 21st Oct., Brumaire (*brume*, fog) 22nd Oct. to 20th Nov., and Frimaire (*frimas*, hoar-frost) 21st Nov. to 20th Dec., were the three autumn-months; — Nivôse (*neige*, snow) 21st Dec. to 19th Jan., Pluviôse (*pluie*, rain) 20th Jan. to 18th Feb., and Ventôse (*vent*, wind) 19th Feb. to 20th March, winter-months; — Germinal (*germe*, germ), 21st March to 19th April, Floréal (*fleur*, flower) 20th April to 19th May, and Prairial (*prairie*, meadow) 20th May to 18th June, spring-months; — Messidor (*moisson*, harvest) 19th June to 18th July, Thermidor (*therme*, warmth) 19th July to 17th Aug., and Fructidor (*fruit*, fruit) 19th Aug. to 16th Sept., summer months. — Each month had 30 days, and consisted of 3 decades, weeks being abolished. At the close of the year there were 5 *jours complémentaires*, 17th Sept. to 21st. — The republican calendar was discontinued by a decree of 9th Sept., 1805.

1807. War with Russia and Prussia. Battles of *Eylau* and *Friedland*. Treaty of *Tilsit*, 8th July. Occupation of Lisbon, 30th Nov.

1808. War in Spain, in order to maintain Joseph Bonaparte on the throne.

1809. Conquest of *Saragossa*. Renewed war with Austria. Battle of *Eckmühl*. Vienna entered, 13th May. Battles of *Aspern*, or *Essling*, and *Wagram*. Peace of Vienna, 14th Oct. Abolition of the temporal power of the pope.

1810. Marriage of Napoleon with Marie Louise, daughter of Francis II. of Austria, 11th March.

1812. Renewed war with Russia. Battles of *Smolensk* and the *Moskova*. *Moscow* entered, 15th Sept. Retreat begun, 19th Oct. Passage of the *Beresina*. — Wellington's victory at *Salamanca*.

1813. Battles of *Lützen*, *Bautzen*, *Grossbeeren*, *Dresden*, *Katzbach*, *Kulm*, *Leipsic* (16-18th Oct), *Hanau*, etc.

1814. Battles of *Brienne*, *La Rothière*, *Montmirail*, *Laon*, *Arcis-sur-Aube*, and *Paris*. Entrance of the allies into Paris, 31st March. Abdication of the Emperor, 11th April. His arrival at *Elba*, 4th May.

The frightful scenes of devastation enacted during the Revolution, especially in 1793, were at least beneficial in sweeping away the overgrown conventual establishments, which occupied the best sites and one-third of the area of the city. Under the Directory the museum of the Louvre was begun. Vast improvements were effected under Napoleon; the mean buildings which formerly occupied the Place du Carrousel were demolished; the N. gallery between the Louvre and the Tuileries and the handsome Rue de Rivoli were begun; new streets, spacious markets, three bridges, several quays, canals, etc., constructed; numerous fountains and monuments erected; churches restored and embellished; the Bourse and other public edifices founded.

1814. **Restoration.** Louis XVIII. proclaimed King, 6th April. First Treaty of Paris, 30th May.

1815. Napoleon's return from Elba; at *Cannes* on 1st, and at Paris on 20th March. Battles of *Ligny* and *Waterloo*, 16th and 18th June. Second entrance of the allies into Paris, 7th July. Napoleon banished to St. Helena, where he died (5th May, 1821).

1823. Spanish campaign, to aid Ferdinand VII., under the Duc d'Angoulême, son of Charles X.

1824. CHARLES X.

1830. Conquest of *Algiers*.

1830. REVOLUTION OF JULY (27th-29th). Louis Philippe elected King, 7th Aug. Continued war in Africa; consolidation of the French colony of Algeria.

Civic improvements progressed comparatively slowly under Louis XVIII. and Charles X. Under Louis Philippe they were resumed with fresh vigour. Many handsome new streets were

opened, churches and public edifices completed, vast works undertaken for the drainage of the city, new bridges and quays constructed, gardens and squares laid out, etc., at an outlay exceeding 100 million francs.

1848. REVOLUTION OF FEBRUARY (23rd and 24th).

1848. **Republic.** Sanguinary conflicts in Paris, 23rd to 26th June. *Louis Napoleon*, son of the former king of Holland, elected President, 10th Dec.

1851. Dissolution of the Assemblée, *Coup d'Etat*, 2nd Dec.

1852. **Second Empire.** NAPOLEON III., elected emperor by *plébiscite*, 2nd Dec.

1854. War with Russia. Crimean campaign. — 1859. War with Austria. Battles of *Magenta* (4th June) and *Solferino* (24th June). Peace of *Villafranca*, 11th July. — 1862. Mexican expedition. — 1867. Dispute with Prussia about Luxembourg.

1870. War with Prussia. Declaration of war, 19th July. Battles in August: *Weissenburg* (4th), *Wörth* (6th), *Spichern* (6th), *Borny*, *Rezonville*, and *Gravelotte* (14th, 16th, 18th), *Beaumont* (30th). Battle of *Sedan*, 1st Sept. Surrender of Napoleon III.

Republic proclaimed, 4th Sept. Capitulation of *Strassburg*, 27th Sept., and of *Metz*, 27th Oct. Battles near *Orleans*, 2nd-4th Dec.

1871. Battle of *St. Quentin*, 19th Jan. Capitulation of *Paris*, 28th Jan. The Germans enter Paris, 1st March.

The siege of Paris in 1870-71 ranks among the most remarkable occurrences in the annals of modern warfare. After the decisive battle of Sedan the victorious German troops pushed forward to Paris without delay, while the Government of the National Defence under *General Trochu* made the most strenuous exertions to place the capital in a state of defence. Cattle and grain were sent into the city in immense quantities, the roads by which the Germans would probably march were rendered impassable, and the arming of the forts and the Enceinte (p. 158) was proceeded with as rapidly as possible. The troops in Paris at the beginning of the siege numbered about 200,000 men, but of these 60,000 or 70,000 only were regular soldiers. The besieging force was composed of six army-corps under the Crown Prince of Prussia and the army of the Meuse under the Crown Prince of Saxony, the full strength of which consisted of 202,000 infantry, 34,000 cavalry, and 900 guns.

By 15th Sept., 1870, the advanced guard of the Crown Prince's army was within 10 M. of Paris, and on the 17th a pontoon bridge was thrown across the Seine at *Villeneuve-St. Georges* (p. 327). After a short but severe contest at *Seaux* with General Ducrot, *Versailles* was reached, and here a few days later the German Headquarters were established (comp. p. 288). Meanwhile the army of the Meuse had occupied the ground on the right banks of the Seine and Marne, thus completing the investiture. The aim of the besiegers was the reduction of the city by famine, while the only course of defence practicable to the besieged was to pierce the investing lines and establish communication with the relief army on the Loire.

The first important *sortie* took place on 30th Sept., when General Vinoy, with 10,000 men, made an ineffectual effort to break the German lines at *Villejuif*, to the S. of Paris. A second attempt in the direction of *Clamart* (p. 286) on 13th Oct., and a third on *Malmaison* and *Buzanval* (pp. 314, 311) on 21st Oct. were equally ineffectual. It was during the latter that St. Cloud was set on fire by a shell from Mont Valérien. The *sortie* of 29th Oct. towards the N. was at first more successful, as the

French gained possession of the village of *Le Bourget*. The Germans, however, succeeded in recapturing it on the 31st, after prolonged fighting and heavy loss. The besieged did not again assume the offensive till 30th Nov., when Generals Trochu and Ducrot led large bodies of troops against the German positions on the S.E. of Paris. For three days the conflict was severely contested, but on 3rd Dec. the French generals were compelled to withdraw their soldiers, enfeebled by cold and hunger, into the city, leaving their object unaccomplished. A sortie towards *Le Bourget* on 21st Dec. met with the same fate as the others.

In the meantime the besiegers had decided on a general bombardment of the city. On 29th Dec. *Mont Avron* succumbed before the German artillery, and from 5th Jan., 1871, onwards an active cannonade was directed against the city from almost every point of its environment. The distress of the besieged now reached its climax. The hopelessness of the situation was recognised by all military authorities, but a final sortie was undertaken in deference to public opinion. The National Guards, who had hitherto been spared active service, took part in this sally, which was directed against *Versailles*, under cover of the guns of *Mont Valérien*. The French were once more driven back, with immense loss, on 19th January.

Resistance was now at an end. On 23rd Jan. Jules Favre came to *Versailles* to negotiate an armistice, which was arranged on 28th Jan. On the following day the Germans were put in possession of the forts. The preliminaries of peace were concluded on 24th Feb. and signed on 28th Feb. Part of the German army made a triumphal entry into Paris on 1st Mar., but was withdrawn in two days on the prompt ratification of the treaty of peace by the National Assembly at Bordeaux.

1871. COMMUNIST INSURRECTION, 18th March. Seat of government removed to Versailles, 20th March. Second siege of Paris, 2nd April. *Peace of Frankfurt*, 10th May. Paris occupied by the Government troops, 25th May. The Communist insurrection finally quelled, 28th May. — M. Thiers, who had been chief of the executive since 17th Feb., appointed President of the Republic.

1873. Death of Napoleon III., 9th Jan. — Marshal Macmahon appointed President instead of M. Thiers, 14th May. Final evacuation of France by the German troops, 16th Sept. — Macmahon's tenure of the presidency fixed at seven years, 20th Nov.

1875. Republican Constitution finally adjusted, 25th Feb.

1879. M. Jules Grévy becomes President in place of Marshal Macmahon. The Chambers of the Legislature return from Versailles to Paris.

1881. Expedition to Tunis. — 1882-85. Expeditions to Tonquin and Madagascar. — 1885. Peace with China, 9th June. Peace with Madagascar, 17th Dec. — 1887. M. Sadi Carnot becomes President in place of M. Grévy, 3rd Dec. — 1889. Universal Exhibition at Paris, commemorating the Revolution of 1789. Eiffel Tower and Exhibition Palaces in the Champ de Mars built.

Paris underwent immense improvements during the second empire. Dense masses of houses and numbers of tortuous streets were replaced by broad boulevards, spacious squares, and palatial edifices. Public works of vast magnitude were undertaken, and those begun in former reigns successfully completed. The Bois de Boulogne and the Buttes-Chaumont were for the first time laid out as public parks; several other promenades and pleasure-grounds were either

brought into existence or greatly embellished; and, what is of incalculable importance, the city was thoroughly well drained, lighted, paved, and supplied with water. For several years after the war many of the public works were necessarily suspended, but the municipal authorities have done their utmost to remove all traces of the Communist outrages.

IV. General Remarks on Paris.

Paris, the capital and by far the largest town of France, covers an area of nearly 30 sq. M. and contained in 1890 a population of 2,423,000 souls. As early as the end of the 13th cent. the number was nearly 200,000; in 1675, under Louis XIV., it reached 540,000; in 1789 it was 600,000; in 1852, 1,053,762; in 1860, after the inclusion of the faubourgs, 1,525,235; and in 1870, 1,825,274. The defence of this huge city is provided for by an elaborate system of fortifications, described at p. 158, and by a garrison of nearly 50,000 men. Its administration is shared between a *Prefect of the Seine*, appointed by government, and a *Town Council*, elected by the citizens. The annual budget amounts to 300,000,000 fr. (upwards of 10,000,000*l.*). Each *Arrondissement* (see p. 47) is governed by a mayor and two councillors.

Paris is not only the political metropolis of France, but also the centre of the artistic, scientific, commercial, and industrial life of the nation. Almost every branch of French industry is represented here, from the fine-art handicrafts to the construction of powerful machinery; but Paris is specially known for its 'articles de luxe' of all kinds.

Paris has long enjoyed the reputation of being the most cosmopolitan city in Europe, where the artist, the scholar, the merchant, and the votary of pleasure alike find the most abundant scope for their pursuits. Nor does this boast apply to modern times only; for there have been periods when it was more generally admitted to be justifiable than at the present day. An idea of the importance of Paris so early as the 12th cent. is afforded by the mediæval poems which treat of the traditional twelve 'Masters of Paris', who seem to have somewhat resembled the Seven Wise Men of Greece. For its cosmopolitan character, however, the city is chiefly indebted to its University, to which students of all nationalities flocked in order to be initiated into the mysteries of the scholasticism which was taught here by its most accomplished professors. At the same time industrial and commercial pursuits made rapid strides under the fostering care of the monarchs and owing to the favourable situation of the city. The great annual fair which took place in the extensive plain between Paris and St. Denis (*Foire du Landit*) and the famous Commercial Code drawn up by Etienne Boileau in 1258 afford additional proof of the early commercial importance of Paris, in con-

sequence of which the population increased rapidly, and an extension of the municipal boundaries was repeatedly rendered necessary. The building enterprise of the 12th and 13th centuries, though but few traces of it now remain, also bears testimony to the energy of the citizens at that period. During the subsequent centuries of the middle ages Paris was indeed deprived of the patronage of her kings, whose adverse fortunes frequently compelled them to give up their residence in the capital; but the municipal element which thenceforward predominated, and which has found expression in the national literature and poetry, continued steadily to develop itself, and at the present day forms the chief characteristic of the city.

The triumphant position of the French monarchy in the reign of Louis XIV. also contributed to the growth and embellishment of the city, and from that period dated many of the public buildings which adorned Paris down to the dawn of the new era in 1848. The decorative arts in particular received a great impulse, and now began to extend their influence over the whole of Europe. As the monarchy engrossed the whole of the political power of the nation, so Paris gradually attracted to herself the skill and talent of the whole country. During the Revolution and the period immediately succeeding it, this system of centralisation, which had now reached its highest pitch, received a temporary check from the political disorganisation of the day; but under the Directory, and particularly during the first empire, the city speedily regained its pre-eminence.

During the somewhat inglorious period of the Restoration the city enjoyed a golden era of prosperity, and the inhabitants reaped the benefits of the Revolution and the Napoleonic laurels without participating in the terrible sacrifices through which they had been attained. Persons of the more enlightened classes began to aspire to the higher ideals of liberty, whereby their energy and enthusiasm were stimulated, and the long lost blessings of peace now seemed to them doubly desirable. It was at this period that liberal politicians achieved their greatest triumphs, that French literature and art used their utmost endeavours to resume their world-wide sway, and that French society exhibited itself in its most refined and amiable aspect. At this period *Benjamin Constant* and *Royer-Collard* exercised very great influence on public opinion; *Thiers* and *Mignet*, *Victor Hugo* and *Lamartine* began their respective careers; the 'Romantic School' attained high importance; and Paris became the recognised headquarters of Oriental studies and a number of other important sciences. What had been begun in the period of the Restoration was continued, though hardly with the same success, during the years which followed the July Revolution, until at length by the outbreak of a new Revolution in 1848 the municipal machine was again thrown completely out of gear. Under the second empire the city speedily regained her ancient prestige and

underwent an almost entire transformation, on a scale of magnificence hitherto unparalleled. At the close of that period (1870-71) she was overtaken by appalling disasters, which indeed threatened her very existence; but with her wonted buoyancy she has again almost entirely recovered from the shock, and has seldom or never presented a gayer and more prosperous appearance than on the occasion of the opening of the Exhibition of 1878. Persons well acquainted with the Paris of the earlier part of the present century sometimes declare that the former spirit of French society is well-nigh extinct; but whether it has really lost a degree of its characteristic sprightliness, or is merely superficially obscured by the ever-increasing anxieties of so populous a city, is a question which we need not here attempt to decide.

V. Weights and Measures.

(In use since 1799.)

The English equivalents of the French weights and measures are given approximately.

Millier = 1000 kilogrammes = 19 cwt. 2 qrs. 22 lbs. 6 oz.

Kilogramme, unit of weight, = $2\frac{1}{5}$ lbs. avoirdupois = $2\frac{7}{10}$ lbs. troy.

Quintal = 10 myriagrammes = 100 kilogrammes = 220 lbs.

Hectogramme ($\frac{1}{10}$ kilogramme) = 10 décagrammes = 100 gr.

= 1000 décigrammes. (100 grammes = $3\frac{1}{5}$ oz.; 15 gr.

= $\frac{1}{2}$ oz.; 10 gr. = $\frac{1}{3}$ oz.; $7\frac{1}{2}$ gr. = $\frac{1}{4}$ oz.)

Myriamètre = 10,000 mètres = $6\frac{1}{5}$ Engl. miles.

Kilomètre = 1000 mètres = 5 furlongs = about $\frac{5}{8}$ Engl. mile.

Hectomètre = 10 décamètres = 100 mètres.

Mètre, the unit of length, the ten-millionth part of the spherical distance from the equator to the pole = 3,0784 Paris feet = 3,281 Engl. feet = 1 yd. $3\frac{1}{3}$ in.

Décimètre ($\frac{1}{10}$ mètre) = 10 centimètres = 100 millimètres.

Hectare (square hectomètre) = 100 ares = 10,000 sq. mètres = $2\frac{1}{2}$ acres.

Are (square décamètre) = 100 sq. mètres.

Déciare = $\frac{1}{10}$ are = 10 sq. mètres.

Centiare = $\frac{1}{100}$ are = 1 sq. mètre.

Hectolitre = $\frac{1}{10}$ cubic mètre = 100 litres = 22 gallons.

Décalitre = $\frac{1}{100}$ cubic mètre = 10 litres = $2\frac{1}{5}$ gals.

Litre unit of capacity, = $1\frac{3}{4}$ pint; 8 litres = 7 quarts.

The following terms of the old system of measurements are still sometimes used: —

Livre = $\frac{1}{2}$ kilogramme = $1\frac{1}{10}$ lb.

Pied = $\frac{1}{3}$ mètre = 13 in.

Aune = $1\frac{1}{5}$ mètre = 1 yd. 11 in.

Toise = $1\frac{9}{10}$ mètre = 2 yds. 4 in.

Lieue = $2\frac{1}{2}$ miles.

Arpent = $1\frac{1}{25}$ acre.

Sétier = $1\frac{1}{2}$ hectolitre = 33 gals.

The thermometers commonly used in France are the Centigrade and Réaumur's. The freezing point on both of these is marked 0°, the boiling-point of the former 100°, of the latter 80°, while Fahrenheit's boiling-point is 212° and his freezing-point 32°. It may easily be remembered that 5° Centigrade = 4° Réaumur = 9° Fahrenheit, to which last 32° must be added for temperatures above freezing. For temperatures below freezing the number of degrees obtained by converting those of Centigrade or Réaumur into those of Fahrenheit must be subtracted from 32. Thus 5° C = 4° R. = 9 + 32 = 41° F.; 20° C = 16° R. = 36 + 32 = 68° F. Again, — 5° C = — 4° R. = 32 — 9 = 23° F.; — 20° C = — 16° R. = 32 — 36 = — 4° F.

VI. Remarks on Northern France.

The majority of visitors to Paris will find comparatively little to interest them in the provinces of Northern France. The scenery is seldom so attractive as to induce a prolonged stay, while the towns are mere repetitions of the metropolis on a small scale. The modern taste for improvement, which has been so strongly developed and so magnificently gratified in Paris, has also manifested itself in the provincial towns. Broad and straight streets with attractive shop-windows are rapidly superseding old and crooked lanes; whole quarters of towns are being demolished, and large, regular squares taking their place; while ramparts of ancient fortifications are converted into boulevards, faintly resembling those at Paris. Admirably adapted as these utilitarian changes doubtless are to the requirements of the 19th century, it cannot but be deeply regretted that the few characteristic remnants of antiquity which survived the storms of the wars of the Huguenots and the great Revolution, and have hitherto resisted the mighty centralising influence of the metropolis, are now rapidly vanishing. Those who were acquainted with such towns as Rouen and Angers about the year 1850 or earlier will now become painfully aware of this fact.

The towns of France, as a rule, present less variety than those

of most other countries. They almost invariably rejoice in their boulevards, glass-arcades, 'jardins des plantes', theatres, and cafés, all of which are feeble reproductions of their great Parisian models. Each also possesses its museum of natural history, its collection of casts and antiquities, and its picture-gallery, the latter usually consisting of a few modern pictures and a number of mediocre works of the 17th and 18th centuries.

The magnificent churches, however, which many of these towns possess, offer attractions not to be disregarded by even the most hasty traveller. The Gothic style, which originated in France, has attained a high degree of perfection in the northern provinces, especially in Normandy, which was a district of great importance in the middle ages. Architects will find abundant material here for the most interesting studies, and even the amateur cannot fail to be impressed by the gems of Gothic architecture, such as St. Ouen at Rouen, or the cathedral of Chartres, notwithstanding the alterations which most of them have undergone. The Huguenots made deplorable havoc in the interiors of the churches, and the Revolution followed their example and converted the sacred edifices into 'Temples of Reason'. The task of restoring and preserving these noble monuments has been begun and is now everywhere progressing.

HOTELS of the highest class and fitted up with every modern comfort are found in such towns only as Havre, Rouen, Dieppe, and Tours, where the influx of visitors is very great, and where the charges are quite on a Parisian scale. In other places the inns generally retain their primitive provincial characteristics, which, were it not for their frequent want of cleanliness, might prove rather an attraction than otherwise. The usual charges at houses of the latter description are — R. 2 fr., L. 25-50 c., A. 50 c.; the table d'hôte dinner (3-4 fr.) at 5. 30 or 6 o'clock is generally better than a repast procured at other places or hours. The déjeuner (1½-2 fr.) at 10 or 11 o'clock will be regarded as superfluous by most English travellers, especially as it occupies a considerable time during the best part of the day. A slight luncheon at a café, which may be partaken of at any hour, will be found far more convenient and expeditious. In southern districts, as on the Loire, wine is usually included in the charge for dinner. In Normandy a kind of cider is frequently drunk in addition to, or as a substitute for wine. The usual fee for attendance at hotels is 1 fr. per day, if no charge is made in the bill; if service is charged, 50 c. a day in addition is generally expected. At the cafés also the waiters expect a trifling gratuity, but the obnoxious system is not carried to such an extent as in the metropolis.

THE CHURCHES, especially the more important, are open the whole day; but, as divine service is usually performed in the morning and evening, the traveller will find the middle of the day or the afternoon the most favourable time for visiting them. The

attendance of the sacristan, or 'Suisse', is seldom necessary; the usual gratuity is $\frac{1}{2}$ franc.

Considerable English communities are resident in many of the towns mentioned in the Handbook, and opportunities of attending English churches are frequent (*e. g.* at Calais, Boulogne, Dieppe, Havre, and Rouen).

The MUSEUMS are generally open to the public on Sundays and Thursdays from 12 to 4 o'clock, when they are often crowded. Visitors may always obtain access at other times for a gratuity (1 fr.). Catalogues may be borrowed from the concierge.

A fuller account of N. France is given in *Baedeker's Handbook to Northern France*.

Remarks on French Art

by

PROF. ANTON SPRINGER.

The visitor to the Metropolis of France will naturally be desirous of knowing something about the character and history of the national art, the chief monuments of which, at least in the provinces of painting and sculpture, are collected in the great public galleries of the Louvre and the Luxembourg. The Frenchman and the foreigner alike will be chiefly attracted by the works of the modern school in these collections; but the works of an earlier period are also deserving of notice, both on account of their historical value, and as tending to throw light on the recent development and present position of French art.

The different phases through which art has passed in France in the course of centuries have been surprisingly numerous. For a long period French artists served an apprenticeship with Netherlanders, Italians, and other foreign masters, until at length they evolved a peculiar style of their own which gained them universal applause. They attained this distinction in the 18th century, and they enjoy a renewal of it at the present day, but their earliest triumphs were in the department of architecture so far back as the 12th and 13th centuries. It is well known that the *Gothic Style* was first brought to perfection in Northern France, and that it was afterwards more or less directly adopted and imitated throughout the whole civilised world. In France itself, however, its development was frequently interrupted by political dissensions and civil war. In the 15th century, when the country had recovered its political stability and was preparing to enter on a career of great historical importance, the Flemings took precedence of their French neighbours in the province of art. A busy traffic in works of art between the two countries now began, and richly-illuminated MSS. in particular were frequently executed in Flanders for the French court. The precise period at which France ceased to be exclusively the recipient has not yet been ascertained. As a great painter of the 15th century, we may mention *Jean Fouquet* of Tours (born about 1415), who seems to have been educated both in Italy and in France itself. The Renaissance era now began, but it was not without hesitation that the French painters followed in the footsteps of the Italians. *François Clouet*, surnamed *Jehannet* (born at Tours in 1500, died about 1572), for example, still follows in his portraits (Charles IX. and his consort) the stiff old Frankish style. The

architects, on the other hand, adopted the new style more readily, incorporating it with their own in a series of baronial châteaux, particularly in Touraine, and thus unconsciously, but effectually establishing the FRENCH RENAISSANCE ARCHITECTURE, a style which has to some extent again come into vogue at the present day.

In the 17th century art in France was still dependent, partly on that of Italy, and partly on that of the Netherlands. Thus *Simon Vouet* (1590-1649) adopted the style of the Italian school, in which a stirring revival took place in his time; and to the same school belonged *Nicolas Poussin* (1594-1665), the most admired master of his age, whose skill and industry, however, hardly sufficed to conceal his natural want of freshness and originality. His compositions are too studied, each group betrays the deliberate calculation with which it has been designed, and it is evident that his reason has too often entirely overruled his imagination; whereas Rubens, on the other hand, an equally learned and accomplished man, has often obviously had difficulty in curbing the natural exuberance of his conceptions. Poussin's historical and mythological pictures are therefore rather admired as a duty than enjoyed by the spectator. His landscapes, however, particularly those of his later years, when his colouring moreover became more vigorous, are pervaded with a poetic sentiment which still renders them attractive. His most famous work of this kind is the 'Arcadian Shepherd', who is represented kneeling before a tombstone and mournfully reading the inscription, 'Et in Arcadia ego'. — Though a native of France, *Claude Lorraine*, or *Claude Gelée*, (1600-82), does not properly belong to the French school, his style having been formed and matured in Italy. Claude and *Gaspar Dughet*, surnamed *Poussin* (1613-75), are among the most distinguished representatives of the idealistic school of landscape-painting, and Claude in particular surpasses all his contemporaries in his skill in presenting finely-composed and beautiful landscapes, with their characteristic accessories of cloud and atmosphere.

Contrasting strikingly with Poussin, the next painter of importance is *Philippe de Champaigne* (1612-74) of Brussels, a master of great natural ability, who went to Paris early in life, and was much employed by Marie de Médicis, Richelieu, and Louis XIII. His religious compositions are tinged with the austerity of the Cistercian monks of Port-Royal at Paris, whose mystic and ascetic doctrines were highly revered at that period, while his portraits are remarkable for their warm, rich colouring and their strong individuality. Portrait-painting was indeed the province in which the French masters of the 17th century chiefly excelled. No one can now be roused to enthusiasm by *Lesueur's* (1617-55) feeble scenes from the life of St. Bruno, or admire *Lebrun's* (1619-90) theatrical heroism, unless it be remembered that he was merely a showy decorator and the 'Directeur des Gobelins'; and even *Jouvenet's*

(1644-1717) able and vigorously-coloured works in Poussin's style will now interest but few spectators; whereas the portraits by *Mignard*, *Largillière*, *Rigaud*, and others still delight us with their lifelike freshness and refined individuality.

The ostentatious and declamatory element in French culture which was developed in the reign of Louis XIV. survived down to a late period in the 18th century. And yet there existed a second element, which played a still more important part throughout the whole of that century, although not, so to speak, officially recognised. The victory gained by this new element was due to the material changes which had taken place in the social life of the country. Paris had become the intellectual centre of the nation, and the importance of the court had rapidly and signally decreased. The court had indeed itself betrayed its uneasiness under the burden of the traditional bombast, and shown its preference for the enjoyment in incognito of unrestrained amusement. The most marked outcome of these changes was the development of the *Rococo Style* of architecture and ornamentation, a style which may be described as emanating from the ladies' boudoir. The same taste was manifested in the plastic forms which now came into vogue, particularly in the pleasing groups of miniature figures and other knickknacks executed for the private drawing-room; and in the prevailing love of comic tableaux, pastoral scenes, mythological travesties, and joyous masquerades, painted in delicate roseate hues.

Most deserving of careful study among the painters of the rococo period is *Antoine Watteau* of Valenciennes (1684-1721), the most interesting of whose works are preserved in the Collection La Caze at the Louvre. His 'Gilles', one of the chief characters in French comedy, possesses far higher artistic merit than his famous 'Embarkation for the Island of Love', while his 'Indifférent' and 'Finette' are masterly delineations of character, entitling him, even as a mere colourist, to a much higher rank than any of his contemporaries. The chief exponent of the less refined Rococo type is *François Boucher* (1713-70), whose pictures, however, soon weary the spectator with their artificiality and sickliness. In the same style, but more pleasing, are the love-scenes depicted by *Fragonard* (1732-1806), a master of Provence, who, like Watteau, is best represented in the La Caze Collection.

Again in sympathy with changes in the literary and social world, French painting entered on another new phase about this period, and began to draw its themes unvarnished from humble life, and to aim at greater fidelity to nature. Thus we find *Chardin* (1699-1779), who was also an accomplished painter of still life, abandoning the shepherds and comedians of his contemporaries, and executing such works as the 'Grace before Dinner', the 'Industrious Mother', and the 'Card House', which derive their themes from the picturesque features of humble society. The chief illustrator of

domestic drama, however, was *Jean Baptiste Greuze* (1734-1805), whose style occasionally borders on the sentimental, and at other times degenerates into triviality. His 'Marriage Contract', 'Paternal Curse', and 'Broken Jar' are so cleverly conceived and so full of meaning as to rivet the attention of all beholders and suggest to them the whole surrounding history of the scene; but his talent as a painter unfortunately fell short of his poetical taste, and, as in the case of Fragonard, his peculiar style was but short-lived and soon fell into oblivion.

About the middle of the 18th century, when antiquarian pursuits began to become the fashion and to influence social life, artists again began to resort to antiquity for their inspirations. Even before the Revolution there appeared numerous harbingers of this return to archaic subjects and forms, while the Revolution itself, which boasted of being founded to a great extent on ancient republican institutions, enabled the new school to gain a complete victory. The most distinguished representative of this school, and at the same time the father of modern painting in France, was *Jacques Louis David* (1748-1825), whose political importance, as well as the fact that his school was largely visited both by Frenchmen and foreigners, contributed not a little to enhance his reputation. His style somewhat resembles that of Raphael Mengs, his German contemporary, and his earlier works in particular betray the declamatory element and a cold and calculated imitation of the antique. His 'Horatii and Curiatii', his 'Death of Socrates', his 'Brutus', and even his 'Sabine Women', a work in which he aimed at reviving the Greek style of art, now possess little more than historical interest. — His contemporaries, *Girodet* (1767-1824) and *Prud'hon* (1758-1823), alone asserted their independence of David's school of painting. Prud'hon in particular endeavoured to attract by refined sentiment and delicacy of colouring; but owing to the temper of the age and the influence of David, which continued dominant throughout Napoleon's régime, his efforts were attended with but little success. — The chief painters of the Napoleonic period were *Gérard* (1770-1837), *Gros* (1771-1835), and *Guérin* (1774-1833). Gérard's portraits are not only interesting as studies of costume, but show the skill of the master in representing his subjects in the most favourable light, and bear traces of his appreciation of the true province of art. They at least possess far higher artistic merit than the pictures of public ceremonies and battles which were so much in vogue in his day. These painters, however, have already lapsed into a kind of historical twilight, as they have rarely produced works of great intrinsic value, and are deficient in those high artistic qualities which immortalise pictures and render them independent of changes of taste and style.

The era of modern French art properly begins with the period of the Restoration, and its dawn may be said to have been inau-

gured by the exhibition of *Théodore Géricault's* (1791-1824) 'Shipwreck of the Medusa' in the year 1819. Géricault was even more revolutionary in his views than David; he repudiated the traditions of the past more completely, and introduced thorough innovations with greater boldness. He was the first to give expression to passion and unrestrained emotions, he preferred fidelity to nature to all other aims, he did not shrink from the melodramatic element, he aimed at vigorous and effective colouring, and used every effort to enhance the impression produced on the spectator. His example proved a powerful stimulant to a series of younger painters, and at length gave rise to the establishment of the ROMANTIC SCHOOL, which after violent opposition eventually became dominant, owing partly to the sympathy of a cognate school of poetry and the patronage of the liberal opposition. Its success was farther materially promoted by the circumstance that its disciples evinced an intelligent interest in the public topics of the day and paid sincere homage to literary culture. They were enthusiastic admirers of Dante, the great mediæval poet, and showed their acquaintance with most celebrated poets and authors of other nations. They drew their favourite inspirations from Shakspeare, Goethe, Byron, and Walter Scott, and were at the same time skilful illustrators of the most interesting pages in their own national history. Holding but little intercourse with the art of the past, they devoted themselves entirely to the life of the present. The hostile outcry with which their first appearance had been greeted now gradually subsided, and differences were smoothed over. The Romanticists used their victory with moderation, and their opponents learned to appreciate many of their good qualities, and particularly their skill in depicting emotions drawn directly from actual life and their effective style of colouring. The whole of Europe now rang with their praises. Foremost among their ranks are the distinguished names of *Eugène Delacroix*, *Ary Scheffer*, *Horace Vernet*, *Paul Delaroche*, and *Jean Auguste Dominique Ingres*. The reputation of Ary Scheffer was the first to fade away; but the works of Delacroix, a thorough Romanticist, who was little disposed for compromises, exercised great influence long after his death. The same may be said of the works of Ingres, whose remarkable versatility enabled him both to take the position of leader of the Idealists and to compete with the Romanticists.

EUGÈNE DELACROIX (1799-1833) appeared for the first time in the Salon of Paris (p. 154) in 1822, when he exhibited his 'Dante and Virgil'. Two years later he produced his 'Massacre of Chios', which awakened much interest owing to the general sympathy felt for the Greeks, but at the same time roused intense indignation among artists of the older schools. It might indeed be called a massacre of all academic rules, of all sacred traditions: drawing and grouping seemed alike objectionable.

Delacroix, however, persevered in his course and proceeded to develop his style consistently. He invariably composed with a view to produce effective colouring, and grouped his figures in accordance with their contrasts in colour. He intensified the lights, and collected the masses of contrasting tints, imparting to them a subdued glow according admirably with the passionate emotions and the often exaggerated vehemence of action depicted by him. This method is best exemplified by his 'Marino Falieri' and the 'Assassination of the Bishop of Liège'. A visit to Algiers extended his range of subjects, and enabled him to handle his kaleidoscope colouring with still greater effect. Examples of this later period are his 'Jewish Wedding in Morocco' and the 'Convulsionaries of Tanguis'. Towards the end of his life he evinced a preference for religious compositions, in which he has embodied the tragic element with very striking success. In order, however, thoroughly to appreciate Delacroix's style, the traveller should also inspect his mural paintings in the Palais du Corps Législatif, in the Luxembourg, and in the Chapelle des Anges in the church of St. Sulpice.

Greatly inferior to Delacroix was his contemporary ARY SCHEFFER (1795-1858) of Dordrecht, who was formerly regarded as one of the chief representatives of the Romantic School, but rather from his choice of subjects than his adoption of its style of colouring. The amiable character of the master, however, accounts to a great extent for the reputation he enjoyed during his lifetime. His 'Battle of the Suliots' (1827) was the first work that brought him into notice. His pictures from Goethe ('Marguerite') and Uhland were gratefully regarded by the Germans as a well-meant tribute to their national poetry, while his religious pieces, strongly tinged with sentimentality, delighted numerous female admirers.

HORACE VERNET (1789-1863) is another master of the same group whose lustre has begun to pale. He was once the most popular painter in Europe, particularly in his own country, the glorious exploits of which he so magnificently illustrated, and was highly honoured and almost treated as an equal by princes of all nations. Within the first few years of the Restoration period he dedicated his art to the service of the French army. The reminiscences of the Napoleonic era afforded him abundant materials, while the national exasperation at the humiliation of the country and the hope of revenge ensured a welcome to every picture which fostered these feelings. Vernet attained the zenith of his reputation in 1830-40, when he painted the exploits of the army in the wars of the Revolution and in Algeria. He possessed a remarkable knowledge of military manœuvres, and succeeded in grouping the most complicated battle scenes in a manner clear and intelligible to the spectator. He was thoroughly familiar with the characteristics of the French soldier, of whom he has painted a number of admirable types, while the technical details of his battles are depicted with

the utmost spirit. His works, however, can boast of none of the more refined and subtle charms of his art. His scenes from Roman life, with which he became well acquainted during his stay in Rome as director of the French Academy, are destitute of freshness and originality, and their attractions are therefore superficial only. To Vernet is due the chief merit of introducing Oriental subjects into French painting, and of being the first to endeavour to render Biblical scenes more attractive by representing them with their appropriate surroundings.

Closely trenching on Horace Vernet's fame during the 'July Monarchy', was that of PAUL DELAROCHE (1797-1856), to whom historical pictures are mainly indebted for their long-lived popularity in France. His works appeal directly to the spectator's interest in the progress of culture, he utilises for his pictures the historical poetry for which a taste then prevailed, and is judicious in his choice of objects. Moderate in character, averse to extremes and exaggeration, and a keen and intelligent observer, he adopts many of the methods of the Romanticists, and in particular learns from them the art of effective colouring, while by no means insensible to the merits of the opposite school of art. Though correct enough in style to satisfy the adherents of the idealistic school, he succeeds in imparting sufficient life and freshness to his figures to prevent the Romanticists from regarding him as an antagonist. In 1829 his 'Death of Queen Elizabeth' caused great sensation. The figures are of life-size, the colouring of the drapery is manifestly calculated for effect, and the expression of the pain attendant on the death-struggle is unrestrained. Among his other works resembling scenes from an historical romance, in which the harsh and unpleasing features of his characters are softened by their genre-like treatment, and which have become extensively known from engravings, may be mentioned his 'Richelieu and Cinq Mars', his 'Mazarin on his Deathbed', his 'Cromwell by the coffin of Charles I.' and his 'Sons of Edward'. Probably the best of his scenes from French and English history are his 'Lady Jane Grey' and his 'Assassination of the Duc de Guise'. His strong points, consisting of delicacy in expressing individuality and skill in arrangement of detail, as well as his inefficiency in the construction of groups, are equally traceable in his so-called Hemiocle in the Ecole des Beaux-Arts. Towards the end of his life, like Delacroix, he showed a preference for religious themes, chiefly of a sombre character, such as the Sufferings of Mary, a style to which he was inclined owing to a tendency to melancholy increased by domestic afflictions.

Older than these contemporaries, J. A. D. INGRES (1780-1867) survived them all. His labours extended over a period of sixty years. He began his career as an artist as a pupil of David in 1801. Within the next ten years, after having expanded his ideas by a sojourn in Italy, he produced his 'Venus Anadyomene' and his

'Œdipus with the Sphinx', works which vie with those of his later life, and to the style of which he afterwards to some extent reverted. A venerator of antiquity and an enthusiastic admirer of the nude female form, Ingres nevertheless wandered far into the realms of far-fetched allegory, frequently chose religious themes, and achieved great success in his studies of colour. So widely divergent in character are many of this fertile painter's works that it is difficult to believe that they possess a common origin. What a contrast, for example, is presented by his apotheoses of Homer and Napoleon, his 'Francesca da Rimini', 'Pope Pius VII. in the Sixtine Chapel', 'The Spring', and 'The Vow of Louis XIII.'! Even his portraits of Cherubini, Bertin, and Mad. Devauçay show great differences of style. It was chiefly owing to this versatility that he was unreservedly admitted to be the greatest French painter of his time, although he never attained to so great popularity as Horace Vernet. — The most distinguished of his pupils was *Hippolyte Flandrin* (1809-64), whose skill was chiefly dedicated to religious frescoes. Numerous and important as are the frescoes in Parisian churches painted since the second quarter of the present century, it may be confidently asserted that Flandrin's pictorial frieze in the church of St. Vincent de Paul is the finest work of the kind in France. His conceptions are indeed so able, his forms so beautiful, and his execution so masterly, that Flandrin's works are probably nowhere surpassed in the realms of modern fresco-painting.

Coæval with these great painters there flourished a considerable number of other able masters, some of whose works are extremely pleasing, although their authors never attained great distinction. Thus, few masters surpass *Decamps* (1803-60) as a colourist of Oriental scenes; and very effective historical genre-pieces have been produced by *Robert-Fleury*, *Steuben*, *Devéria*, *Charles Comte*, and *Coignet*. The last-named also attained a high reputation as a teacher of his art. — A pupil of David, and afterwards moulded in Italy, *Léopold Robert* (1794-1835) dedicated his art to humble life. He began with pictures of brigands, but afterwards succeeded admirably in themes drawn from Italian life and character. His compositions are vigorous and impressive, and the individual figures very attractive. He introduces us, indeed, merely to fishermen, rustics, and reapers; yet they seem endowed with a slumbering heroism of character reminiscent of the mighty past of their nation. — Towards the middle of the century *Diaz* excelled in the art of depicting female charms in their most captivating form, thus foreshadowing the taste of a somewhat later period. So, too, *Couture's* 'Romans of the Decline', exhibited in 1847, was one of the first modern works which manifested a tendency to depict classical themes in their sadder aspects, and an endeavour more effectively to adapt the colouring to the subject. — On the other hand several more recent painters have clung to the style of their predecessors,

such as *Chenavard* and *Gleyre*, a master rarely appreciated as he deserves, both of whom belong to the Idealistic School; *Hébert*, who trod in the footsteps of Robert, though somewhat sickly in taste; and *Léon Benouville*, who died young, the most worthy successor of Ingres and Flandrin.

The SECOND EMPIRE inaugurated a new era in the history of French art. The influence of the earlier masters had begun to wane, and the new institutions and customs of the new generation now sought and found expression in a new school of art. That this school possesses various merits, and in some respects surpasses its predecessors, cannot be denied. Its chief superiority consists in greater ease and mastery of manipulation, and it has benefited by the experience of its elders in the management of colouring; but its weak points are not less clearly apparent. A disregard for the higher objects of painting as a branch of culture has unfortunately crept in. Figures, nude and clothed, are now painted with consummate skill and with sensuously-admirable fidelity; but the souls by which they are animated are too often of the shallowest type. Instead of attempting compositions on a large scale, most of the painters of the present day prefer to execute small groups or single figures, in which perfection of form and effectiveness of colouring are their great aims, so that the French school is becoming more strongly individualised than ever. Each painter strives to solve his favourite problem in his own way, and to exhibit his own particular talent; the result of which is that the school can scarcely be said, like the Romanticists, to possess any worthier object of ambition in common. It is therefore hardly possible to group these most modern masters in any well-defined classes, particularly as some of them have practised several different styles at one and the same time. In portrait-painting this interchange of style has acted very beneficially, by counteracting the natural tendency of that branch of art to stereotyped monotony. Eminent historical and genre painters, and even a number of sculptors, have turned their attention to portrait-painting with marked success, bringing to it a richer sense of form and a wider and more penetrating conception of character than are usually possessed by the ordinary portrait-painter. Four of the most successful modern portrait-painters are *Florentin Bonnat*, *P. Baudry*, *Ricard*, and *Mlle. Nélie Jacquemart*.

Of the masters of the new school *Louis Ernest Meissonier* (1815-1891) is generally admitted to be the most distinguished. His pictures, which are often of very small size, recall in many respects the Dutch masters of the 17th century, rivalling them in sterling merit and skilful execution. His colouring is less brilliant than that of many other masters, but is remarkable for its clearness and the delicacy of its silvery grey tones. His characters, admirably true to nature, are often pervaded by an innocence and amiability which lend a great charm to many of his pictures; but he was less success-

ful as a painter of battle-scenes containing numerous figures. Meissonnier's graceful costumes and correspondingly pleasing figures rarely date from an earlier period than the 18th century, but a number of his contemporaries seek to attract admirers by the quaintness and uncommonness of their scenes. *Fromentin* and *Bida*, for example, have ransacked the East for this purpose, and seek to enhance the effect of their works by the representation of striking landscapes. The portrayal of ancient customs has now become a special province of painting to which many artists have devoted themselves entirely. The versatile *Léon Gérôme* may be regarded as one of the chiefs of this department. While thoroughly accurate in the archaic garb in which he presents his works, he at the same time studiously humours the taste of the present day by the sensuousness or sensational character of his scenes. *Hamon* has chosen the attractive Pompeian frescoes, resembling a kind of porcelain painting, for his model. Other masters, too, while chiefly aiming at representing the attractions of the female form, frequently introduce antiquarian adjuncts. How far such works are the embodiment of ideal conceptions, and to what extent they are merely tributes to the popular voluptuousness of taste, is often not easily determined. The most famous works of this character are the creations of *P. Baudry*, whose paintings in the New Opera House bear magnificent testimony to the fertility of his imagination. Next in order may be mentioned *Cabanel*, who has also distinguished himself as a portrait-painter and a decorator, and among others *Gust. Moreau*, *Amaury-Duval*, and *Em. Lévy*.

Strongly contrasting with these refined idealists, *Gustave Courbet*, a prominent political agitator, is the chief modern votary of the coarsest realism. Naturally talented, and really successful as a painter of hunting-scenes and landscapes, he afterwards descended to the lowest depths of society for some of his themes, and ruined others by his love of singularity, paradox, and exaggeration. His views, as gathered from his later pictures, seem to be that the object of art is not to embellish life, but to sadden it, and to illustrate the infinite hideousness of the world. — There are other artists, however, whose commendable object is to cast a pleasing poetic halo around the simple annals of humble and domestic life. At the head of these stands *Jean François Millet*, the well-known delineator of peasant-life, whose works are distinguished by their admirable union of finely-toned landscape with fresh and characteristic figures, and by the artist's partiality for depicting the peasant at work rather than in his moments of relaxation. *Jules Breton*, another painter of the same class, suffuses his village-scenes with a kind of idealistic glow that invests them with a peculiar charm. Rustic life in different provinces of France has been admirably illustrated by *Gustave Brion* and *Gustave Jundt* (Alsace), *Ad. Leleux* and *Eug. Leroux* (Brittany), and others. *Florentin Bonnat* has

signalled himself as a painter of Italian scenes. — Landscape-painting, too, has undergone vicissitudes and conflicts similar to those already mentioned. In this province also, after the abandonment of painting in the classical style and on a large scale, the school which has become dominant devotes itself almost exclusively to the study of unambitious subjects, taken directly from nature, and rendered attractive by sedulous attention to light and shade. It was long before *Théodore Rousseau*, *Cabat*, *Dupré*, *Français*, and *Daubigny*, the most distinguished modern landscape-painters in France, attained the reputation due to their merits; but, like their contemporaries in other departments, these masters show a marked tendency to individualism, and a taste for engaging in a number of divergent styles. The painting of scenes of military life, always popular in France, has found in *Alphonse de Neuville* and *Edouard Detaille* worthy successors of H. Vernet, *Charlet*, *Raffet*, and other eminent battle-painters of an earlier generation. In the province of animal-painting *Troyon*, who will even bear comparison with the great Dutch masters, is 'facile princeps'; and second to him must be mentioned the talented *Rosa Bonheur*.

Paris contains more numerous private picture-galleries than any other city on the continent, to some of which amateurs will perhaps succeed in gaining access; but if unable to see them, the traveller may rest satisfied with the Louvre and the Luxembourg as affording him a sufficient survey of the history and development of French painting. The Luxembourg gallery enables us to make acquaintance with the most recent styles, among which we may mention the intensified system of colouring adopted by *Regnault*, who fell in a skirmish at Buzanval, and *Carolus Duran's* method of painting ladies' portraits resembling the lay-figures of the 'modiste'.

It is a more difficult matter for the traveller to obtain a complete survey of modern French SCULPTURE, as the numerous monuments in the churches, as well as those of a public character, are so widely scattered throughout the city. Père-Lachaise may, however, be recommended to the notice of visitors as almost the only place where numerous specimens of sculpture are to be found side by side. The classical style was adhered to in French sculpture much longer than in painting, though frequently modified by the modern taste for gracefulness and sensation. The chief representative of this style was *Pradier* (1790-1852), whose sculptures for a long period formed the standard works of the kind. An opposite style, practised by *David d'Angers* (1789-1856), found less favour, except perhaps in the province of portrait-sculpture, of which he produced numerous examples. Genre-sculpture, bordering to some extent on the Renaissance style, has been practised of late with much success. Among the most popular works of the kind are *Rude's* 'Neapolitan Fisherman', *Duret's* 'Tarantella Dancer', and *Jouffroy's* 'Young Girl'. Most of the latest sculptors, while inclin-

ing to idealistic principles, have also admitted naturalistic elements; they show a preference for the portrayal of action and passion, and do not always avoid an approach to the picturesque. Since the time of Pradier and David d'Angers two new generations have sprung up, among whom *Guillaume, Cavelier*, and *Dumont* (1761-1884) are the most distinguished seniors, while *Perraud, Bourgeois, Barrias* ('Oath of Spartacus'), *Moreau, Mercié* ('Gloria Victis'), *Maindron* (1801-1884), *Chapu* (1833-1891), and *Carpeaux* are also names of high repute. In the special department of animal-sculpture the most marked success has been achieved by *Barye*. In the execution of his 'Florentine Singer' *Paul Dubois* (1829-1883) took a very promising step by reverting to the early Italian Renaissance style.

One of the chief glories of the French plastic art, however, as is well known, consists in its bronze works, which are unrivalled both in technical manipulation and in artistic taste. Indeed the intimate association of the artist and the art-handicraftsman, and the perfection to which the works of the latter are brought in almost every branch, form the most characteristic features of Parisian art, and are traceable to the foundation of the Gobelins Manufactory (p. 268) by *Colbert* in 1666.

PARIS.

PRELIMINARY INFORMATION.

1. Arrival in Paris.

Travellers with luggage-tickets have usually about 10 min. to wait till the baggage is all arranged for distribution on the long tables in the *Salle des Bagages*. This interval should be employed in engaging one of the fiacres or cabs which are in waiting outside the station. (The cabs in the first row are generally pre-engaged.) After receiving the driver's number and telling him to wait for the luggage (*'restez pour attendre les bagages'*), the traveller may proceed to superintend the examination of luggage (comp. p. xiv). Hand-bags and rugs should not be lost sight of, or deposited in the cab, before the traveller is himself ready to take his seat, as there are numerous thieves always on the look-out for such opportunities.

As soon as the traveller is released from the custom-house examination, he should secure the services of a porter (*facteur*, 25-50 c.), telling him the number of the fiacre engaged. The fare from the station into the town during the day is $1\frac{1}{2}$ fr. for a cab with seats for two, and 2 fr. for one with seats for four persons; at night the fares are $2\frac{1}{4}$ and $2\frac{1}{2}$ fr. respectively. The charge for each trunk or other large article of luggage is 25c. (see also Appx. p. 32). When the driver has had to wait more than $\frac{1}{4}$ hr. the fare per hour is charged (p. 20).

The *Omnibus de Famille* is a comfortable conveyance for families or large parties, and may be ordered by letter the day before arrival, either from a hotel or from the Chef du Bureau des Omnibus at the station where the traveller is to alight. The charge varies according to the station and the size of the omnibus required (usually with 7 or 12 seats). Detailed information may be found in the *'Renseignements Généraux'* of the various lines in the *Indicateur des Chemins de Fer* (p. 23).

The ordinary omnibuses are not available for travellers with luggage, and considerable acquaintance with Paris is moreover necessary to understand the various lines (comp. p. 20).

Travellers arriving late at night, and not wishing to put up at one of the large hotels mentioned at p. 3, had better proceed on foot with their hand-huggage to the nearest hotel, leaving their heavy luggage (the receipt for which they retain) to be claimed next day. The following hotels may be mentioned †: — Near the GARE

† For explanation of references to Plan, see end of the book, before the index of streets. The italicised Roman numerals (*II*) refer to the special or district plans. The streets parallel with the Seine are numbered from E. to W., while the numbers of the cross-streets begin at the end next the river; the even numbers are on the right, the odd on the left.

du NORD (Plan, Brown, 23, 24): *Grand Hôtel du Chemin de Fer du Nord*, at the corner of the Boulevard de Denain; *Hôtel Cailleux*, opposite the exit from the station, at the corner of the Rue de Dunkerque and the Rue St. Quentin; *Hôtel Belge*, Rue St. Quentin 35bis; *Hôtel de la Gare du Nord*, Rue St. Quentin 31.

Near the GARE DE L'EST (Plan B, 24): *Grand Hôtel St. Laurent & de Mulhouse*, Rue de Metz 4, to the left on leaving the station; *Hôtel de Bâle*, same street, 6, R. 3-6, L. 1½, B. 1¼ fr.; then, in the Boulevard de Strasbourg: 78, *Grand Hôtel de Strasbourg*; 74, **Grand-Hôtel de l'Europe*, R. 2½-7, L. 1½, B. 1-1¼, lunch 2½, D. 3 fr.; 72, *Hôtel de Paris*. Nearer the station: *Hôtel du Chemin de Fer*, Rue de Strasbourg 11; *Hôtel Français*, with restaurant, same street, 13 (R. from 3½ fr.).

Near the GARE ST. LAZARE (*Ouest, Rive Droite*; Plan B, 18): *Hôtel Terminus*, see p. 4; *Hôtel de Londres & de New York*, Rue du Havre 15, opposite the station, R. 4-6, B. 1½, lunch 3, D. 4 fr.; adjacent, *Hôtel Anglo-Américain*, Rue St. Lazare 113; *Gr.-Hôtel de Rome*, Rue de Rome 15.

Near the GARE MONTPARNASSE (*Ouest, Rive Gauche*; Plan, Gray, 16): *Grand Hôtel de France & de Bretagne*, Rue du Départ 1, with restaurant; *Hôtel de la Marine & des Colonies*, Boulevard Montparnasse 59.

Near the GARE DE LYON (Plan G, 28): *Grand Hôtel & Restaurant du Chemin de Fer de Lyon*, Boulevard Diderot 19 & 21; *Hôtel de l'Univers*, Rue de Châlon 46, on the side for starting.

Near the GARE D'ORLÉANS (Plan G, 25): *Hôtel du Chemin de Fer*, Boulevard de l'Hôpital 8, opposite the side of arrival.

2. Hotels.

Alphabetical list at the end of the Book, after the Index.

The traveller has ample latitude in the selection of a hotel in Paris, and his choice must generally be determined by the price he is willing to pay for accommodation. Travellers for pleasure, with whom economy is of no serious moment, will naturally prefer either the Boulevards or the principal streets in the vicinity of the Opéra, the Louvre, and the Bourse, especially if ladies are of the party. Gentlemen travelling alone may, on the other hand, secure very comfortable quarters at a much more moderate rate in the less-frequented houses in various side-streets, as well as on the left bank of the Seine.

Charges for rooms vary from 2 to 30 fr. according to their size, floor, and comfort, and according to the situation of the hotel and the style of its accommodation, which in some of the older houses is far from inviting. Charges are also influenced by the season of the year, by the length of the visitor's stay, and by the demand for accommodation. The charge for a room does not include light or attendance.

In the hotels in the Boulevards Montmartre, des Italiens, des Capucines, and de la Madeleine, in the Avenue de l'Opéra, Rue de la Paix, Place Vendôme, Rue Castiglione, and Rue de Rivoli, rooms on the third

or fourth floor (*i. e.* 'au-dessus de l'entre-sol', and consequently the fourth or fifth above the 'rez-de-chaussée' or ground-floor) are let at 5 fr. at least, while the lowest charge for those on the first or second floor is 10 fr. per day. The charges are somewhat more moderate (third or fourth floor 3 fr., first and second floors 5-7 fr.) in the Rues St. Honoré, de Richelieu, Vivienne, des Petits-Champs, Daunou, and other streets lying between the Rue de Rivoli and the Boulevards, and in the Rues du Helder, Taitbout, Laffitte, Le Peletier, Drouot, and other streets between the Boulevards and the Rue de Lafayette. In the third-rate streets in the same localities or in the more remote and less convenient quarters on the other bank of the Seine, such as the Rues des Saints-Pères, Bonaparte, de Lille, de l'Université, and Jacob, rooms may be obtained for 2½-3 fr., but apartments at these charges are of very modest pretensions.

Enquiry as to prices should always be made on the day of arrival or the day following, to prevent unwelcome surprises. This is quite customary, even when the visit is to be of a night's duration only. The charge for the first breakfast (tea or coffee with bread and butter), which it is better to take in the hotel than at a café (see p. 17), varies from 1¼ to 2 fr. The second breakfast or luncheon (*déjeuner*; about noon) and dinner (from 5. 30 to 7 p.m.) may be taken where the traveller pleases, it being by no means necessary to return to the hotel for these meals.

When a prolonged stay is contemplated the bill should be obtained every two or three days, in order that errors, whether accidental or designed, may be detected. When the traveller intends to start early in the morning, he had better pay, or at least examine, his bill on the previous evening, as overcharges are apt to escape detection in the hurry and confusion of departure. Even when *Attendance* is an item in the bill, it is usual to give the concierge, the 'boots', and the waiter by whom the traveller has been specially attended, a fee of 1-3 fr. each according to the length of the sojourn in the hotel. When, as is often the case at the *maisons meublées*, the payment for service is discretionary, a sum at the rate of ½-1 fr. per day should be distributed among the servants at the end of the traveller's stay, besides which an additional gratuity may occasionally be given to ensure civility.

Articles of Value should never be kept in the drawers or cupboards at hotels. The traveller's own trunk is probably safer; but it is better to entrust them to the landlord, from whom a receipt should be required, or to send them to a banker. Doors should be locked at night.

The following list of Parisian hotels comprises merely a selection of the better known houses in the quarters frequented by strangers. It is often difficult to draw the line between houses of the first, and those of the second class, but the situation and charges may generally be regarded as determining this point (p. 2). When ladies are of the party an unmistakably first-class hotel should always be selected.

The information as to charges has been supplied by the hotel-keepers themselves in answer to a circular issued by the editor, and is here given solely on their authority. Where charges are not shown in the following list, no answer has been received from the hotels concerned. The charge for meals includes wine, unless the contrary is stated; and lights and attendance are sometimes included in the charge for rooms.

Right Bank of the Seine. The largest hotels in Paris are: the *HÔTEL CONTINENTAL, Rue de Castiglione 3, and Rue de Rivoli (Plan, Red, 18; special plan *II*), opposite the Garden of the Tuileries. — The GRAND HÔTEL, Boulevard des Capucines 12, adjoining the Opera House (Plan, R, 18; *II*), with *dépendance* (Hôtel Scribe). — The *GRAND HÔTEL DU LOUVRE, Rue de Rivoli 172, adjoining the Palais-Royal (comp. Plan, R, 20; *II*), somewhat re-

duced in size since its disconnection from the Magasins du Louvre. — The *HÔTEL TERMINUS, at the Gare St. Lazare (Pl. Brown, 18), not quite so well situated as the others, but perhaps the most comfortable. — The *HÔTEL MODERNE, Place de la République (Pl. R, 27; *III*), beyond the strangers' quarters, with lower charges for R.

These hotels, magnificent edifices occupying whole blocks of streets, and each containing 300-700 rooms, are admirably managed and replete with every comfort. Travellers are sure to find accommodation at any of them, at any hour of the day or night; but many will prefer the smaller, quieter, and less expensive houses, especially when ladies and children are of the party. On arrival a room at the desired charge is asked for at the bureau, where also the bill is afterwards paid. It is not necessary to take any meals in the house, and articles are paid for as consumed. In favourable seasons about 300 guests, including many from other hotels, frequently dine at the tables d'hôte. The amount given away in gratuities is generally smaller in these houses than in other hotels, as fees to the waiters are less usual. The 'boots' and chambermaid each expect 1-2 fr., while the porter who conveys the luggage from the room to the cab receives 1 fr. The hotels are, of course, provided with lifts. The ordinary charges are: R. 4 to 40 fr., L. 1 (electric light at the Terminus $1\frac{1}{2}$ fr.), A. 1- $1\frac{1}{2}$ fr., first breakfast 1- $2\frac{1}{2}$ fr., déj. 5 fr., table-d'hôte 6 (Louvre), 7, or 8 fr. (Grand Hôtel).

Next to these enormous hotels rank the following: —

In the *Rue de Rivoli*: 206, *HÔTEL DU JARDIN DES TUILERIES, R., L., & A. 5-20, déj. 4, D. 6, 'pens.' incl. R. 15 fr. — 228, *MEURICE; 226, *WINDSOR; 218, *BRIGHTON; 208, *WAGRAM; 202, *RIVOLI. The last five, opposite the Garden of the Tuileries (Plan, R, 18; *II*), are much frequented by English travellers. Charges: R. from 2 (Rivoli) and 4 (Wagram) to 7, 10, 12, and 20 fr. (Tuileries); L. 1, A. 1- $1\frac{1}{2}$ fr., first breakfast 1-2, déj. from 3, D. 6 or 7 fr. (Brighton), wine extra. — Rue de Rivoli 83, farther E., *HÔTEL STE. MARIE, R. 2-8, first B. $1\frac{1}{4}$, déj. 3, D. 3-4 fr.

In the *Rue du Louvre*: 40, HÔT. CENTRAL DE LA BOURSE DE COMMERCE, R. 4-10, incl. A., déj. 4, D. 6 fr.

In the *Rue St. Honoré* (Pl. R, 18; *II*), first-class: CHOISEUL, 241; HÔTEL DE FRANCE ET DE BATH, 239; HÔTEL DE LILLE ET D'ALBION, 223 (R. 4-8, A. 1, 1st B. $1\frac{3}{4}$, déj. 4, D. 5 fr., wine extra); GRAND HÔTEL ST. JAMES, 211 (R., L., & A. 4-8, déj. and D. as above, 'pens.' incl. R. 12-15 fr.).

Good second-class hotels in the streets lying between the Rues de Rivoli and St. Honoré (Pl. R, 18; *II*): in the *Rue St. Roch*, 4 and 6, GRAND-HÔTEL DE PARIS ET D'OSBORNE (R., L., & A. 3-11, déj. $2\frac{1}{2}$, D. 3 fr., wine extra); 3, HÔTEL DE LA COURONNE; 5 and 7, ST. ROMAIN (R. 3-10, L. 1, A. $1\frac{1}{2}$ fr.). — *Rue de la Tamise*, 4, HÔTEL DE LA TAMISE, R. $2\frac{1}{2}$ -8, L. $\frac{3}{4}$, A. 1, déj. $3\frac{1}{2}$, D. 5 fr., wine extra. — METROPOLITAN HOTEL, Rue Cambon 8.

In the *Place Vendôme* (Pl. R, 18; II), first-class: *BRISTOL, Nos. 3 & 5; *DU RHIN, Nos. 4 & 6; VENDÔME, No. 1.

In the *Rue Castiglione*, a handsome street leading southwards from the *Place Vendôme*, are the following large hotels, much frequented by English visitors: CONTINENTAL, No. 3 (see p. 3); BALMORAL, No. 4; DE LONDRES, 5 (R. from 4, A. 1, 1st B. 2, déj. 4 fr., wine extra); ANGLO-FRANÇAIS, 6 (R. from 3, 1st B. from 1½, déj. 3, D. 5 fr., wine extra); DOMINICI, 7; DE LIVERPOOL, 11; CASTIGLIONE, 12 (R. from 4, A. 1, 1st B. 1½-2, D. 6 fr. wine extra).

In the *Rue de la Paix*, leading northwards from the *Place Vendôme*: *MIRABEAU, 8, a family hotel, with comparatively few R. (5-15 fr.); DE WESTMINSTER, 11 & 13; DE HOLLANDE, 20; DES ILES BRITANNIQUES, 22 (R. 4-25 fr.).

In the *Avenue de l'Opéra* (Pl. R, 18, 21; II): *BELLEVUE, 39 (R. 4-12, L. 1, A. 1, 1st B. 1½, déj. 4, D. 6 fr., wine extra); *DES DEUX MONDES, 22. — In the *Rue de l'Echelle*: 11 and 7, HÔTEL BINDA and GRAND HÔTEL NORMANDY, both frequented by the English, R. from 4-5, 1st B. 1½-2, D. 6 fr.; HÔTEL THÉRÈSE, Rue Ste. Anne 11bis, R. 4-7, L. 1½, A. 1½, 1st B. 1¼, déj. 3½, D. 4 fr.

In the *Rue Daunou* (Pl. R, 18; II): DE L'EMPIRE, 7; DE RASTADT, 4; DE L'AMIRAUTÉ, 5 (R. 5-12, L. ¾, A. 1, 1st B. 1½-2, déj. 6, D. 7 fr.); D'ORIENT, 6 & 8 (R. from 5 fr.); DE CHOISEUL ET D'EGYPTE, 1; CHATHAM, 17 & 19 (slightly dearer; English guests).

To the W. of the *Rue de la Paix*: *Rue des Capucines*, No. 5, HÔTEL DE CALAIS, R. from 3, L. ¾, A. ¾, 1st B. 1½, déj. 3, D. 4 fr., wine extra. In the *Rue Volney*, No. 11, HÔTEL DE L'ALMA.

In the *Rue Louis-le-Grand* (Pl. R, 18; II), leading southwards from the *Boulevard des Capucines* and intersected by the *Avenue de l'Opéra*: DE BOSTON, 22 (R. 2-8, déj. 3, D. 4 fr.), well spoken of; LOUIS-LE-GRAND, 2 (*Hôtel meublé*).

In the *Rue d'Antin*: DES ETATS-UNIS, 16; D'ANTIN, 18, R., L., & A. 3-10, 1st B. 1¼, déj. 3½, D. 4 fr.; *Maisons Meublées*, 16, 20, and 22. — In the *Rue de Port-Mahon*: GRAND HÔTEL DE PORT-MAHON, 9, R., L., & A. 3-8, déj. 3, D. 3½, 'pens.' incl. R. 8-14 fr.

In the *Boulevard des Capucines* (Pl. R, 18; II): *GRAND HÔTEL DES CAPUCINES, 37; two large *Maisons Meublées*, 25 and 29.

Near the *Madeleine* (Pl. R, 18; II): *Cité de Retiro*, 5, HÔTEL PERRY (R. 3-8 fr., déj. 3, D. 4 fr., wine extra); 9, HÔT. & PENS. TÊTE, slightly less expensive. — HÔTEL VOUELLMONT, Rue Boissy d'Anglas 15.

To the W. of the *Madeleine*, in the *Rue de l'Arcade*: BEDFORD, 17 & 19, English (R. 3-20, L. 1, A. 1½, 1st B. 1½, déj. 4, D. 6 fr., wine extra); NEWTON, 13, unpretending; DE L'ARCADE, 7, R. 2-5, L. & A. ¾, 1st B. 1, déj. 2½, D. 3 fr. — *Passage de la Madeleine*, at the end of the *Place*: 4, HÔTEL LARTISIEN, unpretending; 6, HÔTEL PFEIFFER, R. 3½-6, L. & A. 1, déj. 3, D. 4 fr. — *Rue de Sèze*, 16, HÔTEL DE SÈZE, R. 3-8, L. 1½, déj. 3½, D. incl. wine

4½ fr. — In the *Rue Pasquier*: BUCKINGHAM, 32 (D. 4 fr.). — In the *Rue d'Anjou*: HÔTEL DU PRINCE DE GALLES, Nos. 24 & 26. — *Boulevard Malesherbes*: HÔTEL MALESHERBES, 26, R. 5-8, L. 1½, A. 1, 1st B. 1½-2, déj. 5, D. 7 fr.

More moderate hotels in the conveniently-situated streets to the S. of the Boulevard de la Madeleine. *Rue Richempanse*: 15, HÔT.-PENS. RAPP, pens. from 10 fr., well spoken of; 11, HÔTEL DU DANUBE; 14, RICHEMPANSE. — *Rue Duphot*: DE L'AMIRAUTÉ, 20; BURGUNDY, 8 (R. 2-10, L. 1½, 1st B. 1½, déj. 3, D. 4 fr.), frequented by English visitors.

Nearer the Opéra, to the N. of the Boulevard: *Rue de Caumartin*: 14, GRANDE BRETAGNE (R. 3-6 fr.); 33 & 35, *DE ST. PÉTERSBOURG, R. 4-12, déj. 3, D. 4 fr. — *Rue Scribe*, 15, adjoining the Opéra, GRAND HÔTEL DE L'ATHÉNÉE (R. 4-20 fr.). — *Rue de la Bienfaisance* 16, GRAND HÔTEL ALEXANDRA (boarding-house), a large house near St. Augustin, opposite the Avenue Portalis (déj. 3, D. 4 fr.).

Boulevard des Italiens (Pl. R, 21; II): 32, and Rue du Helder 6, *HÔTEL DE BADE, R. 4-10, L. 1, A. 1, déj. 3½-5, D. 6 fr.; same Boulevard, 2, and Rue Drouot 1, *HÔTEL DE RUSSIE R. 6-16, déj. 4, D. 5 fr.

To the N. of the Boulevard des Italiens, in the *Rue du Helder*: 8, DU TIERRE, inexpensive; 9, HÔTEL DU HELDER (R. 5-7, A. 1, 1st B. 2, déj. 4, D. 6 fr.); 10, DU NIL, *RICHMOND, 11 (good family-hotel); 16, *DU BRÉSIL ET D'ORIENT, R. 4-8, 1st B. 1½, déj. 3, D. 3½ fr.; *Maison Meublée*, 13. — In the adjacent *Rue Taibout*: *D'ESPAGNE ET DE HONGRIE, 4 & 6 (déj. 3, D. 4½ fr.); TAITBOUT, 12 (R. from 3 fr.).

In the *Rue Laffitte*, also issuing from the Boulevard des Italiens (Pl. B, 21; II): 38, *LAFFITTE (R. 3-7, 1st B. 1½, déj. 3, D. 3½ fr.); 20, BYRON (R. 4-6 fr.); 32, DES PAYS-BAS; 33, DE FRANCE, beyond the Rue de Lafayette (R. 3-6 fr.); 16, *Maison Meublée*.

In the *Rue Le Peletier*, parallel to the Rue Laffitte: DE L'EUROPE, 5; *Maisons Meublées* at Nos. 13 and 27. — In adjacent streets: *Rue Rossini*, 22, GRAND HÔTEL VICTORIA; 16, ROSSINI, R. 3-10 fr.; meals 3, 4, and 6 fr. — *Rue de la Grange-Batelière*: DE JERSEY, 3; DU LIBAN, 4 (unpretending).

In the *Rue de Lafayette*, parallel to the Boulevards on the N. (Pl. B, 21): SUISSE, 5, near the Opéra, R. 3-6, L. 1½, A. 1½, 1st B. 1½, déj. 3, D. 4 fr. — Adjoining the last, in the *Cité d'Antin*: 10, HÔTEL VICTORIA, R. 2-10, L. & A. ¾, déj. 3½, D. 4½ fr.

Farther on in the Rue de Lafayette: CENTRAL, 56; D'ANGLETERRE ET DES ANTILLES, 60.

To the S. of the Boulevard des Italiens (Pl. R, 21; II), well situated: *Rue de la Michodière*, 9, HÔTEL DE GAND ET DE GERMANIE, R. 2-6, L. 1½, 1st B. 1½, déj. 2½, D. 3½ fr. — *Rue de Choiseul*, 23, HÔTEL DU CANADA, R. 2½-9, déj. 2½, D. 4 fr. — *Rue Mon-*

signy, opposite the Bouffes Parisiens: 9, DE LA NÉVA (R. 3-8, déj. 3, D. 4 fr.); 1, MONSIGNY. — *Rue Marivaux*: 9, RICHELIEU (R. 3-5 fr.); 5, FAVART, R. 3-7 fr., L. 75-60 c., A. $1\frac{1}{2}$, 1st B. $1\frac{1}{4}$ fr. — *Rue de Grammont*: 2, DU PÉRIGORD (R. 4 fr.); 1, DE MANCHESTER.

In the *Rue-de-Richelieu* (Pl. R, 21; II, III), to the S. of the Boul. des Italiens and the Boul. Montmartre: 17, D'ORLÉANS; 63, DE MALTE (R. $3\frac{1}{2}$ -5, L. $1\frac{1}{2}$, A. $1\frac{1}{2}$ - $\frac{3}{4}$, déj. 4, D. 5 fr.); 69, DE VALOIS, these two opposite the National Library. — In the *Square Louvois*, *GRAND HÔTEL LOUVOIS, R. 3-6, déj. 4, D. $4\frac{1}{2}$ fr.

Rue Vivienne (Pl. R, 21; II): 40, VIVIENNE; 41 & 43, FRASCATI, near the boulevards, R. 3-12, L. $\frac{3}{4}$, A. $1\frac{1}{2}$, 1st B. $1\frac{1}{2}$, déj. $3\frac{1}{2}$, D. $4\frac{1}{2}$ fr. — *Place de la Bourse* (Pl. R, 21; III): 13, CLAISE, first-class.

Rue Notre-Dame des Victoires (Pl. R, 21; III), at the back of the Bourse: 36, DE NICE; 17, DE LA BOURSE ET DES AMBASSADEURS; 11, NATIONAL, R. $2\frac{1}{2}$ -12, L. $\frac{1}{2}$, 1st B. $1-1\frac{1}{4}$, déj. 3, D. $3\frac{1}{2}$ fr., A. at discretion. — *Rue Paul-Lelong*, 27, HÔTEL DES COLONIES, R. $2\frac{1}{2}$ -5, L. $\frac{3}{4}$, A. $1\frac{1}{2}$, 1st B. 1, déj. 3, D. 4 fr.

Rue Croix-des-Petits-Champs (Pl. R, 20, 21; II, III), near the Palais Royal: 48, DE LA MARINE FRANÇAISE; 27, *DU LEVANT (R. 3-6 fr., L. 60 c., A. $\frac{1}{2}$, déj. 3, D. $\frac{1}{2}$ fr.); 10, DE L'UNIVERS ET DU PORTUGAL, well spoken of (R. $2\frac{1}{2}$ -5 fr., L. 60 c., A. $\frac{1}{2}$, 1st B. $1-1\frac{1}{4}$, déj. 3, D. $3\frac{1}{2}$ fr.); 4, DU GLOBE.

Between this street and the Palais-Royal: *Rue Radzivil*, 31, GRAND HÔTEL DE HOLLANDE (*Maison meublée*; another entrance Rue de Valois 46).

Rue Montmartre (Pl. R, 21; III), near the Bourse: HÔTEL DE FRANCE ET DE CHAMPAGNE, 132 (R. $2\frac{1}{2}$ -5, L. 1, A. 1, 1st B. $1\frac{1}{2}$, D. $4\frac{1}{2}$ fr.); D'ANGLETERRE, 56 and 58.

Boulevard Montmartre (Pl. R, 21; III): No. 3, GRAND HÔTEL DORÉ ET DES PANORAMAS; 10, DE LA TERRASSE JOUFFROY, Passage Jouffroy, R., L., & A. 4-8, 1st B. $1-1\frac{1}{2}$, déj. 3, D. 5 fr.

Boulevard Poissonnière (Pl. R, 21; III): No. 32, HÔTEL BRÉBANT; 30, BEAU-SÉJOUR, with fine view (R. 3-20 fr.); 16, ROUGEMONT.

In the *Cité Bergère*, to the N. of the last-named boulevard, are some cheaper houses: DE FRANCE, 2^{bis}; DU RHIN, 3; DE LA CITÉ & BERNAUD, 4; LACOMBE, 6; DES ARTS, 7; DE LA HAUTE VIENNE, 8; DE MOSCOU, 10; DES DEUX CITÉS, 12. — *Rue du Faubourg-Montmartre*: 38, *GR.-HÔT. DE PARIS, R. $2\frac{1}{2}$ -8, L. $\frac{1}{2}$, A. $\frac{1}{2}$, 1st B. $1\frac{1}{2}$, déj. 3, D. 4 fr. — *Rue Bergère* 34, *GR.-HÔT. BERGÈRE, R. 3-5 fr., L. $\frac{3}{4}$, A. 1, 1st B. $1\frac{1}{2}$, déj. 4, D. 5 fr.

Rue Richer (Pl. R, 21; III): RICHER, 60, corner of the Rue du Faubourg-Montmartre; 3, BRÉSILIEN, R. 2-6, 1st B. $\frac{1}{2}$ - $1\frac{1}{2}$, déj. 3, D. 4 fr. — *Rue de Maubeuge*, 2, corner of the Rue du Faubourg-Montmartre, GRAND HÔTEL DE CHANTILLY.

Rue de Trévise (Pl. R, 21; III), a quiet street: 10-12, *HÔTEL DE COLOGNE, R. 3-6, L. $\frac{1}{2}$, 1st B. $1\frac{1}{4}$, déj. $3\frac{1}{2}$, D. 4 fr.; 7, DE BELGIQUE ET DE HOLLANDE; 18, DE TRÉVISE; 44, DE LA HAVANE.

Rue du Conservatoire (Pl. R, 21; III), parallel to the last: 17, *DE BAVIÈRE; 7, DE LYON.

To the N. of the Boul. Bonne-Nouvelle (Pl. R, 24; III), *Rue de l'Echiquier*; 36, at the corner of the Rue d'Hauteville, which leads to the boulevard: *DU PAVILLON, R. 2-5 fr., L. 60 c., A. $\frac{3}{4}$, 1st B. $1\frac{1}{2}$, déj. 3, D. $3\frac{1}{2}$ fr. — *Passage Violet*, 4-10, between the Rues du Faubourg-Poissonnière and d'Hauteville: *VIOLET, a block of seven houses (R. from 3 fr.).

The hotels in the Rue St. Denis, Boul. de Sébastopol, Boul. de Strasbourg, and that neighbourhood, are somewhat distant from the principal sights, but well situated for business purposes. — *Rue St. Denis*, 155: *DE ROUEN, unpretending. — *Rue du Caire*, 4: DE FRANCE, near the Square des Arts et Métiers, R. 3-4, L. $\frac{1}{2}$, 1st B. $1-1\frac{1}{4}$, déj. 3, D. $3\frac{1}{2}$ fr. — *Rue de Turbigo*: GRAND HÔTEL EUROPÉEN, 67, R. $2\frac{1}{2}-6$, L. $\frac{1}{2}$, 1st B. 1, déj. 3, D. $3\frac{1}{2}$ fr.; HÔTEL MODERNE, see p. 4. — *Avenue Victoria*, 20, near the Hôtel de Ville: HÔTEL BRITANNIQUE, well spoken of, R. $1\frac{1}{2}-6$, L. $\frac{1}{2}$, A. $\frac{1}{2}$, 1st B. $1\frac{1}{4}$, D. 3 fr.

In the *Champs-Élysées*: MEYERBEER, Rue Montaigne 2, at the Rond-Point; SUFFREN, Avenue des Champs-Élysées 71; D'ALBE, Avenue des Champs-Élysées 101 and Avenue de l'Alma 73, R. 5-20, L. 1, A. 1, 1st B. 2, déj. 'à part' 5, D. 7 fr. — Near the Arc de Triomphe (Pl. B, 12; I): *Avenue de Friedland*, 43, *ROYAL HÔTEL; 61, HÔTEL CAMPBELL. — *Rue Balzac*, 11, HÔTEL CHATEAUBRIAND; 4, VILLA BALZAC; 3, HÔTEL DU DERBY; 8, HÔTEL BEAUJON. — *Rue Lord-Byron*, 16, VILLA LORD BYRON. — *Rue Chateaubriand*, 18, MAISON DE FAMILLE. Most of these are second-class family hotels.

There are several HÔTELS-PENSIONS at Neuilly, near the Bois de Boulogne, which are pleasant enough for a long stay in fine weather but inconveniently distant from the centre of the town.

Left Bank of the Seine. The hotels on the S. side of the river, being at some distance from the Palais-Royal and the Boulevards, are less conveniently situated than the above for sight-seeing, especially if the traveller's stay be short.

Quai Voltaire, 19 (Pl. R, 17; IV), near the Pont des Sts. Pères: HÔTEL VOLTAIRE, R. 3-6, L. $\frac{1}{2}$, A. $\frac{3}{4}$, 1st B. $\frac{3}{4}-1\frac{1}{2}$ fr. — *Rue de Seine*, 63, DU MONT-BLANC. — *Rue de Lille*, 45, DES AMBASSADEURS, R. 2-8, L. $\frac{1}{2}$, A. $\frac{1}{2}$, 1st B. $1\frac{1}{4}$, déj. $3\frac{1}{2}$, D. 4 fr. — *Rue Jacob*, 29, D'ISLY, corner of the Rue Bonaparte, R. $1\frac{1}{2}-5$ fr. (25-125 per month), L. 30-50 c., 1st B. 1, déj. $2\frac{1}{2}$, D. $3-3\frac{1}{2}$ fr. — *Rue des Saints-Pères*, 65, DES SAINTS-PÈRES, R. 3-5, L. $\frac{1}{2}$, A. $\frac{1}{2}$, 1st B. $1\frac{1}{4}$, déj. $3\frac{1}{2}$, D. 4 fr. — *Rue de Grenelle*, 16 & 18, *DU BON LAFONTAINE. The last two hotels are frequented by the clergy. — *Rue Bonaparte*, 3, DE LONDRES, near the Ecole des Beaux-Arts (Pl. R, 17, 20; IV), patronised by visitors prosecuting art-studies. — *Rue de Tournon*, 7, near the Palais du Luxembourg, Foyot.

The following are in the *Quartier Latin* (comp. p. 225). *Boule-*

vard St. Michel (Pl. R, 19; V): D'HARCOURT, 3, R. 2 $\frac{1}{2}$ -6, L. 1 $\frac{1}{2}$, A. 1 $\frac{1}{2}$, 1st B. 1-1 $\frac{1}{4}$ fr.; DU MUSÉE DE CLUNY, 18; DE SUEZ, 31, R. 2-5 fr. (30-100 fr. per month), L. 30 c., L. 1 $\frac{1}{4}$, 1st B. 1, déj. 1 $\frac{1}{2}$, D. 2 fr.; *Maisons Meublées*, 21, 41, and 44. — *Rue Racine*, close to the Boulevard St. Michel 2, DES ÉTRANGERS, R. 2 $\frac{1}{2}$ -4 (30-80 fr. monthly), 1st B. 1, déj. 2, D. 2 $\frac{1}{2}$ fr. — *Rue de l'Ecole de Médecine*, 4, *ST. PIERRE, R. 1 $\frac{1}{2}$ -3 $\frac{1}{2}$ (20-60 fr. monthly), L. 1 $\frac{1}{2}$, 1st B. 3 $\frac{1}{4}$, déj. 2, D. 2 fr. — *Rue du Sommerard*, 22, DU MIDI, R. 2 $\frac{1}{2}$ -3 $\frac{1}{2}$ (30-60 fr. monthly), 1st B. 3 $\frac{1}{4}$ fr. — *Rue des Carmes*, 5 and 7, HÔTEL DES CARMES, R. 2-5 (25-60 fr. monthly), L. 40 c., A. 1 $\frac{1}{2}$ fr., 1st B. 60 c.-1 fr., déj. 1 $\frac{3}{4}$, D. 2 fr. — *Rue Corneille*, 5, CORNEILLE, adjoining the Odéon, R. 2 $\frac{1}{2}$ -5 fr., 1st B. 60-80 c., déj. 1 $\frac{1}{2}$, D. 2 fr.

Furnished Apartments are easily obtained in all the principal quarters of Paris. A *yellow* ticket on the door indicates furnished, a *white* unfurnished rooms. In winter a furnished room in the vicinity of the Boulevards costs 80-120 fr. per month, a small suite of rooms 250-500 fr.; in summer prices are much lower. A room in the Latin Quarter may even be obtained for 30-50 fr.

3. Restaurants.

Alphabetical list at the end of the Book, after the Index.

Paris is indisputably the cradle of high culinary art. As the ordinary tables d'hôte convey but a slender idea of the perfection to which the art is carried, the 'chefs d'œuvre' must be sought for in the first-class restaurants, where, however, the connoisseur must be prepared to pay 10-15 fr. for his dinner, exclusive of wine.

We shall enumerate a few of the best restaurants, especially those in the most frequented situations (Palais-Royal, Boulevards, etc.). The least expensive are those at some distance from the most fashionable streets; and at such establishments the cuisine is often as good as in the more showy houses. The charges are stated approximately, but, like those of the hotels, they generally have an upward tendency.

HOURS. The Parisian's first breakfast generally consists of a cup of coffee and a roll at an early hour. The second breakfast, or *Déjeuner à la Fourchette*, is a substantial meal, resembling dinner, and is served at the restaurants between 11 and 1 o'clock. The Parisian dinner-hour is 6-8 p.m.; to avoid the crowd, strangers should not be too late. Most of the restaurants on the Grands-Boulevards are kept open almost the whole night.

'*Garçon, l'addition, s'il vous plaît!*' 'Waiter, the bill!' The waiter then brings the account from the '*dame de comptoir*', and on receiving payment expects a '*pourboire*' of 5 or 6 sous (3-4 in the inferior restaurants). When three persons dine together, it is sufficient to double the above pourboire.

RESTAURANTS À LA CARTE. At these restaurants (pp. 12-14) the portions are generally so ample, that one portion suffices for two persons, or two portions for three. The visitor should there-

fore avoid dining alone. It is even allowable to order one portion for three persons. Ladies may dine at the best restaurants with perfect propriety.

Most of the larger restaurants, particularly those in the Boulevards, have '*cabinets particuliers*', or private dining-rooms, with separate entrances and a distinct staff of servants, where the charges are much higher than in the public rooms.

The Bill of Fare usually presents a very extensive choice of viands. At the large restaurants whatever dish is selected is sure to be found unexceptionable of its kind, but at the smaller restaurants it is not prudent to order anything not mentioned in the '*carte du jour*'. Waiters, when asked what can be had, naturally enumerate the most expensive dishes first.

The following list comprises the names of the commonest dishes. The triumphs of Parisian culinary skill consist in the different modes of dressing fish and '*filet de bœuf*', and in the preparation of '*fricandeaus*', '*mayonnaises*', and sauces.

1. POTAGES (Soups).

Polage au vermicelle, vermicelli soup.

Pâte d'Italie, soup with macaroni.

Polage à la Julienne, soup containing finely-cut vegetables.

Purée aux croûtons, a kind of pea-soup with dice of toast.

Consommé aux œufs pochés, broth with eggs.

Tapioca, a kind of sago soup.

2. HORS D'ŒUVRE.

Huitres, oysters.

Rôties, pieces of toast.

Saucisson, sliced sausage.

Cornichons, pickled cucumbers.

Tourte, pâté with fish or meat.

Vol au Vent, light pastry with meat.

Escargots, snails.

Grenouilles, legs of frogs.

3. BŒUF (beef).

Boeuf au naturel, boiled beef.

Boeuf sauce tomate, beef with tomato sauce.

Beefsteak, or *bifelek aux pommes*, beefsteak with potatoes (*bien cuit*, well-done; *saignant*, underdone).

Châteaubriand, a kind of steak.

Filet aux truffes, fillet of beef with truffles.

Filet au jus, fillet with gravy.

4. MOUTON (mutton).

Côtelette panée, cutlets with bread-crumbs.

Blanquette d'agneau, fricassée of lamb.

Gigot de mouton, leg of mutton.

Ragoût de mouton or *Navarin aux pommes*, mutton with potatoes and onion-sauce.

5. VEAU (veal).

Ris de veau, sweetbreads.

Fricandeau de veau, slices of larded roast-veal.

Blanquette de veau, fricassée of veal.

Cervelle de veau au beurre noir, calf's-head with brown sauce.

Foie de veau, calf's-liver.

Rognons de veau, veal kidneys.

Veau rôti, roast veal.

6. PORC (pork).

Pieds de cochon à la Ste. Menehould, pig's trotters seasoned.

Porc rôti, roast pork.

7. VOLAILLE (poultry).

Chapon, capon.

Poulet, chicken, prepared in various ways. *Un quart de poulet*, enough for one person, and even for two persons at the large restaurants. (*l'aile ou la cuisse?* the wing or the leg? the former being rather dearer).

Croquette de volaille, baked fowl.

Canard aux navets, duck with young turnips.

Caneton, duckling.

Oie, goose.

Dindon, turkey.

Pigeon, pigeon.

8. GIBIER (game).

Perdrix, partridge (*aux choux*, with cabbage and sausages).

Perdreux, young partridges.
Caille au gratin, quail with bread-crumbs.

Filet de chevreuil, roast venison.
Civet de lièvre, ragout of hare.

9. PÂTISSERIE.

Pâté au jus, meat-pie.
Pâté de foie gras aux truffes, a kind of paste of goose-liver and truffles.

10. POISSON (fish).

Saumon, salmon.
Sole au gratin, baked sole.
Limande, a kind of flat fish.
Brochet, pike.
Carpe, carp.
Anguille, eel.
Turbot, turbot.
Raie, roach (*au beurre noir*, with brown sauce).
Maquereau, mackerel.
Truite, trout; *truite saumonée*, salmon-trout.
Matelote, ragout of fish.
Morue, cod.
Moules, mussels.
Ecrevisses, crabs.
Homard, lobster.
Crevettes, shrimps.

11. SALADES (salads).

Salade suivant la saison, salad according to the season.
Laitue (pommée), lettuce-salad.
Chicorée, endive-salad.

12. ENTREMETS OR LÉGUMES (vegetables).

Lentilles, lentils.
Asperges, asparagus.
Artichauts, artichokes.
Petits pois, green peas (*au beurre*, with butter-sauce; *purée de pois*, mashed peas).
Haricots verts or *flageolets*, small green beans, French beans; *haricots blancs* or *soissons*, white beans.
Choux, cabbages; *choux fleurs*, cauliflower; *choux blancs*, white cabbages; *choux raves*, kohlrabi; *choux de Bruxelles*, Brussels sprouts; *choucroute*, pickled cabbage (*garnie*, with lard and sausages).
Pommes, potatoes (it is not customary to add *de terre*).

The bread of Paris is excellent and has been famed since the 14th century.

If the diner partakes of the '*hors d'œuvre*' presented to him between the courses, consisting of radishes, butter, prawns, etc., his bill will swell into proportions for which he is probably not prepared.

Pommes frites, fried potatoes.
Pommes sautées, potatoes stewed in butter.

Pommes à la maître d'hôtel, potatoes with butter and parsley.
Purée de pommes, mashed potatoes.
Epinards, spinach.
Chicorée, endives.
Oseille, sorrel.
Carottes, carrots.
Navets, turnips.
Betteraves, beetroot.
Oignons, onions.
Tomates, tomatoes.

13. ENTREMETS SUCRÉS (sweet dishes).

Omelettes of various kinds (*au sucre*, *soufflée*, *aux confitures*, *aux fines herbes*, etc.).
Beignets, fritters.
Charlotte de pommes, stewed apples.
Crème à la vanille, vanilla-cream.
Tourte aux confitures, jam-tart.
Nougat, pudding flavoured with nuts or almonds.

14. DESSERT.

Various kinds of fruit.
Meringue à la crème, cream-tarts.
Parfait, coffee-ice.
The usual varieties of cheese are:
Fromage (à la crème) Suisse or *Chevalier* (the name of a manufacturer), a kind of cream-cheese.
Fromage de Gruyère, Gruyère cheese.
Fromage de Neufchâtel (Normandy), Neufchâtel cheese.
Fromage de Roquefort (Aveyron), green cheese made of a mixture of sheep's milk and goat's milk.

15. WINES.

The finer wines principally in vogue are: — Red Bordeaux or Claret: *St. Emilion* and *St. Julien* (3-4 fr.), *Château Larose*, *Ch. Latour*, and *Ch. Lafitte* (6-8 fr.). White Bordeaux: *Sauternes* (3-4 fr.). — Red Burgundy: *Beaune* (2½-4 fr.), *Pomard*, *Volnay*, *Nuits* (4-5 fr.), *Romanée* and *Chambertin* (5-8 fr.). White Burgundy: *Chablis* (1½-2½ fr.), *Montrachet* (4 fr.), and *Hermitage* (6 fr.).
Vin frappé, wine in ice.
Carafe frappée, carafe of iced water.

A whole bottle of the ordinary red table-wine, or *vin ordinaire*, is generally placed on the table for each person. If, however, the traveller expressly states that he only wishes half a bottle, he has to pay only for what he consumes. At the smaller restaurants it is often advisable to mix the *vin ordinaire* with water or mineral water; the best-known varieties of the latter are *Eau de Seltz* (siphon or demi-siphon), *Eau St. Galmier*, *Eau de Vals*, *Eau de Monrand*, and *Eau Bussang*.

RESTAURANTS À PRIX FIXE. The '*Dîner à Prix-fixe*' resembles a table d'hôte in being a complete repast at a fixed charge, which varies from 1 to 5 fr. in accordance with the number and quality of the dishes; but the diner is at liberty to come at any time between 6 and 8, and is enabled to dine as expeditiously or as leisurely as he pleases. Payment in some instances is made at the door on entering. Where a whole bottle of table-wine is included in the charge for dinner, half a bottle of a better quality may always be obtained in its stead. Meats and vegetables are served separately, but may be ordered together if desired. The cuisine is sometimes little inferior to that of the best restaurants. These establishments are recommended to travellers who are not *au fait* at ordering a French dinner.

The connoisseur in the culinary art will, however, avoid the '*dîner à prix fixe*', and betake himself with one or two discriminating friends to a restaurant of the best class; and even the solitary traveller will often prefer a less showy, but more substantial repast at a good '*restaurant à la carte*'.

Besides the restaurants enumerated here, there are many others of every kind in every part of the city. Wherever the traveller may chance to take up his abode, he may depend on obtaining a tolerable breakfast and dinner at some restaurant in the vicinity, although the house may not be mentioned in the Handbook.

Visitors are generally admitted to the table-d'hôte of the hotels even when not staying in the house, but in some instances previous notice is required. The dinners of the large hotels mentioned at p. 3 are patronised by numerous outsiders.

Restaurants à la Carte in and near the Palais-Royal.

Galerie Montpensier (W. side): *Corazza*, 9-12, first class. — Galerie Beaujolais, facing the Théâtre du Palais-Royal on the N.: **Grand Véfour*, 79-82, one of the best-known restaurants in Paris (expensive). The celebrated '*Frères Provençaux*', formerly in this gallery, has long been closed. — Galerie de Valois: *Petit-Véfour*, 106-109. — Galerie d'Orléans (S. side) 30-40, towards the garden 208-213: *Café d'Orléans*.

Before entering the Galerie Montpensier from the end next the Louvre, we observe the '*Maison Chevet*', Galerie de Chartres 12 and 15, an unvalued emporium of delicacies, but not a restaurant. Those who wish to give a really good dinner get their materials from Chevet. Laffitte, the

celebrated banker, and minister of Louis Philippe, is said to have sent to Chevet for fish for a dinner to be given at Dieppe.

Rue de Valois 8, at the S. end of the Galerie d'Orléans: *Au Boeuf à la Mode*, comparatively moderate.

Restaurants à la Carte in the Boulevards.

The even numbers are on the N., the uneven numbers on the S. side (comp. p. 1, note).

Place de la Madeleine: 2, *Durand*, high charges; 3, *Larue*; 9, *Madeleine-Tavern* (Lucas).

Boulevard des Capucines: 12, *Café de la Paix*, connected with the *Grand Hôtel*; 4, *Café Américain*; 3, *Restaurant Julien*.

Boulevard des Italiens: No. 38, *Restaurant de la Chaussée-d'Antin*; 20, **Maison Dorée*, fashionable; 16, **Café Riche*, elegantly fitted up; 13, **Café Anglais*, similar; 29, **Café du Helder*, déjeuner on the ground-floor, dinner upstairs. All these are expensive. — In the vicinity, Rue du Helder 7, *Au Lion d'Or*, 'cabaret françois', quaintly fitted up. — In the Passage des Princes, near the Rue de Richelieu, Nos. 24-30: *Noël-Peters*, quiet.

Boulevard Poissonnière: No. 27, *Splendide Taverne*, also a café-brasserie, handsome establishment; 26, *Désiré Beaurain*; 16, *Restaurant Rougemont*; 9, *Restaurant de France*; 2, *Poissonnière*. All these are reasonable. — Boulevard Bonne-Nouvelle: No. 36, *Marguery*, with terrace, a favourite resort of merchants, well spoken of. — Boulevard St. Denis: 18-14, *Maire* (good wine). — Boulevard St. Martin (or rather, No. 50 Rue de Bondy, which here meets the boulevard): *Lecomte*. — Boulevard du Temple, 29-31: *Bonvalet*, not expensive, with a fine terrace. — Boulevard Beaumarchais, 3, near the Place de la Bastille: *Aux Quatre Sergents*.

Other Restaurants à la Carte on the Right Bank.

Avenue de l'Opéra: 32, *Bignon* (Café Foy), expensive; 41, *Café de Paris*.

Rue Daunou, to the S. of the Boulevard des Capucines: 22, **Vian*. — Rue St. Augustin: 30, *Gaillon*, at the Place Gaillon.

To the S. of the Boulevard Montmartre: Rue de Richelieu 100, in the court, *Lemardelay*.

Place de la Bourse 13: *Champeaux*, with garden, first class.

Rue St. Honoré 261, and Rue Cambon 16, *Voisin* (good wine).

CHAMPS-ÉLYSÉES. Most of the restaurants here are expensive. — To the left on entering, *Ledoyen*, to the right, *des Ambassadeurs*, both with fine terraces; farther on, *Café-Restaurant du Rond-Point*, to the right at the Rond-Point; *Grand Café du Cirque*.

Avenue du Bois de Boulogne: 10, *Ory*, moderate. At the end of this Avenue, the *Pavillons Chinois*, in the Chinese style (p. 158).

BOIS DE BOULOGNE. Near the entrance, close to the Porte Maillot: *Gillet*, Avenue de Neuilly 25. Near the Jardin d'Acclimatation: **Pavillon d'Armenonville*, beautifully situated. There is also a

restaurant in the Jardin d'Acclimatation. — The *Restaurants de la Cascade* (p. 159), near the Cascade and the race-course, and *de Madrid* (p. 160), at the gate of that name, are also well situated.

BOIS DE VINCENNES. On the small island in the Lac des Minimes, *Restaurant de la Porte-Jaune* (p. 213).

Restaurants à la Carte on the Left Bank.

Quai d'Orsay 1: *Café d'Orsay*.

Rue de Lille 33: **Blot*.

Rue des Saints-Pères 20, corner of the Rue Jacob: *Caron*.

Rue Mazet 3, first street diverging from the Rue Dauphine to the right when approached from the Pont-Neuf (Pl. R, 20): **Magny*. — On the adjacent Quai des Grands-Augustins: 51, **Lapérouse*.

Restaurants of every kind abound in the QUARTIER LATIN. One of the best is *Foyot*, Rue de Tournon 33, near the Luxembourg (Pl. R, 19). — Boulevard St. Germain: 110, opposite the Ecole de Médecine, *Mignon*; 25, *Café-Restaurant Soufflet*. — Quai de la Tournele 15, and Boul. St. Germain 6: *de la Tour d'Argent*.

Restaurants with Special Cuisine.

ENGLISH: *Lucas*, Place de la Madeleine 9, and Rue Boissy d'Anglas 28; *Weber*, Rue Royale 21; *Taverne de Londres*, Place Boieldieu, opposite the Opéra Comique.

ITALIAN: *Beretta*, Passage des Panoramas, Galerie Montmartre (second on the left side) 12.

JEWISH RESTAURANTS: Rue Mazagan 12; Rue Geoffroy Marie 5, *Neuve Levi*, D. 2½-3½ fr.

Restaurants near the Stations.

Gare du Nord: *Buffet*, to the right of the façade; *Lequen*, Boulevard de Denain 9; *Barbotte*, Rue de Dunkerque and Rue de Compiègne, well spoken of; *Bouillon Duval*, at the corner of the Boulevard Magenta and Rue de la Fayette. — Gare de l'Est: *Restaurant Schaeffer*, at the Hôtel Français, Rue de Strasbourg 13. — Gare St. Lazare: *Buffet*, beside the Cour du Havre; *Restaurant du Terminus*; *Restaurant Moderne*, Rue du Havre 11 (2-2½ fr.) — Gare Montparnasse: *Café-Restaurants*, below the station, opposite it, and in the Rue de Rennes (p. 16). — Gare de Lyon: *Buffet*.

Restaurants à Prix-fixe in the Palais-Royal and Vicinity.

Where two prices are stated, the second includes a better quality of wine.

Galerie Montpensier (W. side, pleasantest on summer afternoons, because in the shade), beginning from the end next the Louvre: No. 23, *Rest. de Paris* (Laurent Catelain), déj. 2, D. 2½ fr.; 40, 41, *Bouvier-Vidrequin*, déj. 1 fr. 15 or 1 fr. 25, D. 1 fr. 60 c. or 2 fr.; 65, *Aux Cinq Arcades*, déj. 2, D. 2½ or 3 fr.

Galerie Beaujolais (N. side): 88, **Tissot*, déj. 1¾, D. 2¼ fr.

Galerie de Valois (E. side), returning towards the Louvre: 145, *Tavernier Aîné*, déj. 2, D. 2½ fr.; 160, *Rest. Henri IV.*, déj. 1½, D. 2 fr.; 173, **Dîner National* (Catelain Aîné), déj. 3, D. 5 fr. (paid on entering).

Passage Vivienne 18, at the back of the Palais-Royal, between the Rues Vivienne and de la Banque: *Restaurant des Galeries*, déj. 1 fr. 15, D. 1 fr. 25 or 1 fr. 60 c.

Rue Croix-des-Petits-Champs 5, near the Louvre: *Grand Restaurant de l'Univers*, déj. 1 fr. 10, 1 fr. 30, or 1 fr. 50 c., D. 1 fr. 20, 1 fr. 60 c., or 2 fr.

The following TABLES D'HÔTE may also be mentioned: **Excoffier* (Philippe), Rue et Galerie de Valois, Palais-Royal, 43 and 105, déj. 1 fr. 60, D. 2 fr. 10 c.; *Grande Table d'Hôte Vivienne*, Rue Vivienne 2, same prices; *Grande Table d'Hôte du Mail*, Rue du Mail 6 and Rue du Faubourg-St. Denis 19, same prices; etc.

Restaurants à Prix-fixe in the Boulevards and Vicinity.

Boulevard Montmartre: 12, **Dîner de Paris*, an old-established house, déj. 3, D. 3½ fr.; also à la carte. — Passage Jouffroy: 10, *Restaurant de la Terrasse Jouffroy*, déj. 3, D. 5 fr.; 16, *Dîner du Rocher*, déj. 2½, D. 3 fr. — Passage des Panoramas: 24, *Restaur. du Commerce*, déj. 1 fr. 60, D. 1 fr. 75 c.

Boulevard des Italiens 14, and Rue Le Peletier 2: *Dîner Européen*, déj. 3, D. 5 fr. — Boulevard des Italiens: 27, **Dîner Français* (table d'hôte Excoffier), déj. 3½, D. 4½ fr. (good wine). — Rue de Richelieu: 104, *Restaurant Richelieu* (Lecœur), with winter and summer gardens, 2-2½ fr. — Boulevard Poissonnière: 24, *Bruneaux*, déj. 3, D. 4 fr. — Boulevard St. Martin: 55, *Grand Restaurant de la Porte St. Martin*, déj. 1 fr. 15 or 1 fr. 60 c., D. 1¼-2 fr.; 47, *Restaurant des Nations*, déj. or D. 1¾-2¾ fr.; 15, *Maison-Boulon*, déj. or D. 1¾-2½ fr. — Boulevard du Temple: 29-31, *Bonvalet*, déj. 2½, D. 3 fr., also à la carte. — Boulevard Beaumarchais: 1, adjoining the Bastille, *Taverne Gruber*, déj. 2 fr. 60, D. 3 fr., coffee included.

TABLES D'HÔTE. *Excoffier*, at the *Dîner Français* (see above), Boulevard des Italiens 27; *Table d'Hôte Bouillod*, Passage des Panoramas, Galerie Montmartre 6, 2-3 fr.; *Blond* (Moine), Boulevard Montmartre 2 (first floor), 1½-2 fr.

Restaurants à Prix-fixe in Other Quarters.

Near the Madeleine, Rue Royale, corner of the Rue St. Honoré: *Darras*, déj. 3, D. 5 fr. — Rue Montmartre: 158, near the boulevards, *Dîner Français*, déj. 1 fr. 60, D. 1 fr. 60 c.-2 fr.

Rue de la Bourse: 3, *Au Rosbif*, déj. or D. 1 fr. 40 c.

Near the Tour St. Jacques, Rue St. Denis: 4, *Restaurant du Commerce*, déj. 1 fr. 15-1 fr. 40 c., D. 1¼, 1 fr. 60 c., or 2 fr.

LEFT BANK. Place de l'Odéon 2, opposite the theatre: **Hupet*, déj. 1 fr. 50 c., D. 1¾ or 2 fr. 10 c. — Boulevard St. Germain: 262,

opposite the Ministry of War, *Restaurant de la Légion d'Honneur*, déj. 2½, D. 3 fr. — Square Ste. Clotilde: *Restaurant Ste. Clotilde*, déj. 1 fr. 60, D. 1 fr. 75 c. — Rue de Rennes: 53, near the Boulevard St. Germain, *Café-Restaurant de l'Océan*, déj. 2½, D. 3 fr.; 161, not far from the Gare Montparnasse, *Restaurant Léon*, déj. 1 fr. 30 c.-1½ fr., D. 2-2½ fr.)

Etablissements de Bouillon.

These are restaurants of a peculiar kind, founded originally by a butcher named *Duval*. As in the case of the 'dîners à prix-fixe', the number of dishes to choose from is very limited. The meat is generally good, but the portions are small, and each dish, bottle of wine, and even bread is reckoned separately. The guests are waited on by women, soberly garbed, and not unlike sisters of charity. These houses are very popular with the middle and even upper classes, and may without hesitation be visited by ladies. Each guest on entering is furnished with a card, on which the account is afterwards written.

Usual charges: serviette 5, bread 10, carafon of wine 20, ½ bottle 50, 'demi-siphon' of aerated water 15, soup 25, meat, fish, etc., 30-60, vegetables 25 c.; the charge for an ordinary dinner will therefore amount to 2-2½ fr. or upwards. A fee of 15-20 c. is left on the table for attendance; the bill is then paid at the bar and receipted, and is finally given up to the 'contrôleur' at the door. The largest of these houses is in the Rue Montesquieu, No. 6, to the E. of the Palais-Royal. The following, among many others, are some of the principal branch-establishments: Rue de Rivoli 194 (Tuileries) and 47, Avenue de l'Opéra 31, Boulevard de la Madeleine 27, Boulevard Poissonnière 11, Boul. Montmartre 21, Place de la République 17, Rue de Turbigo 45 (corner of Rue St. Martin) and 3, Boul. de Sébastopol 141 (corner of Boul. St. Denis), Boulevard St. Denis 26, Boul. de Magenta 101 (near the Gare du Nord), Rue des Filles St. Thomas 7, Rue du Quatre-Septembre 1 (near the Bourse), Boul. St. Michel 26 (at the corner of Rue de l'Ecole de Médecine), Rue du Pont-Neuf 10 (corner of Rue de Rivoli).

On the left bank, *Bouillon Boulant*, Boulevard St. Michel 34.

The **Grands Bouillons Parisiens** are more elegant but also more expensive: Boulevard des Italiens 9; Boul. des Capucines 35; Boul. Poissonnière 6 and 32; Boul. St. Martin 2; Rue St. Lazare 100-102, etc.

Beer Houses.

English, Bavarian, Strassburg, Vienna, and other beer may be obtained at most of the cafés (p. 17) and also at the numerous *Brasseries*, many of which are handsomely fitted up in the old French or Flemish style, with stained-glass windows and quaint wainscoting and furniture. Most of the following are also restaurants.

A small glass of beer (*un quart*) costs 30-35 c., a large glass (*un demi*) 50-60 c.; *brune, blonde*, dark and light beer.

ON THE BOULEVARDS: *Pousset*, Boul. des Italiens 14, handsome establishment (Munich beer); *Zimmer*, Boul. Montmartre 18, ditto; *Taverne Montmartre*, Rue du Faubourg Montmartre 61 (corner of Rue de Châteaudun), fine rooms; *Taverne du Coq-d'Or*, Rue Montmartre 149, near the boulevard, another handsome establishment. — *Splendide Taverne*, quaint style, Boul. Poissonnière 27; *Gruber*, Boul. Poissonnière 13 and Boul. St. Denis 15 (Strassburg beer); *Müller*, Boul. Bonne-Nouvelle 35; *Ducastaing*, Boul. Bonne-Nouvelle 31; *Dreher*, same boul., 26; *Taverne des Gaulois*, same boul., 23; **Taverne Flamande*, Boul. de Sébastopol 137, tastefully fitted up; *Tournier*, Boul. de Sébastopol 135; *Eden Brasserie*, Boul. de Sébastopol 17 (concerts in the evening); *Gruber*, Boul. Beaumarchais 1; *Grande Brasserie Dreher*, Rue St. Denis 1, Place du Châtelet. — *Cabaret du Lion Rouge*, Rue de Rivoli 30, fine rooms; *Brasserie de la Palette d'Or*, same street 124, fine rooms. — *Weber*, Rue Royale 21, near the Madeleine (English ale); *Grande Brasserie Rhénane*, Boul. Richard-Lenoir 3, Place de la Bastille; etc.

ON THE LEFT BANK: *Lipp*, Boul. St. Germain 151; *Müller*, Rue Soufflot 19.

4. Cafés and Confectioners.

Cafés form one of the specialties of Paris, and some of them should be visited by the stranger who desires to see Parisian life in all its phases. An hour or two may be pleasantly spent in sitting at one of the small tables with which the pavements in front of the cafés on the Boulevards are covered on summer-evenings, and watching the passing throng. Chairs placed in unpleasant proximity to the gutter should, of course, be avoided. Most of the Parisian men spend their evenings at the cafés, where they partake of coffee, liqueurs, and ices, meet their friends, read the newspapers, or play at cards or billiards. Letters may also be conveniently written at a café, the waiter furnishing writing materials on application. Most of the cafés are open until 1 a.m., some even longer.

When coffee is ordered at a café during the forenoon the waiter brings a large cup (*une tasse*, or *une grande tasse*, with bread $\frac{3}{4}$ -1 $\frac{1}{2}$ fr., waiter's fee 10 c.). In the afternoon the same order produces a glass of *café noir*, which costs 30-60 c. (waiter 10 c.). A *petit verre* of Cognac or Kirsch costs 30-40 c. Sometimes a bottle of cognac is placed on the table unordered, and a charge made according to the quantity drunk, from 10 c. upwards. — Those who wish to dilute their coffee ask for *un mazagran*, and are supplied with coffee in a large glass and a bottle of water; *un Capucin* is a glass of *café au lait*.

Tea is generally sold in portions only (*thé complet*), costing
BAEDEKER. Paris. 10th Edit. 2

1-1½ fr. Déjeuner may be obtained at nearly all the cafés for 2¼-3 fr., and cold meat for supper.

Beer may also be procured at most of the cafés, '*un bock*', costing 30-40 c., '*une canette*', 50-80 c.

Liqueurs, diluted with water, largely consumed in warm weather are: Absinthe, Cognac, Bitters or Amers, Curaçao, Sirop de Groseille or de Framboise, Orgeat (prepared from almonds), and Sorbet.

Smoking is generally prohibited at the cafés until the evening, unless there be chairs outside. The best cafés may with propriety be visited by ladies, but those on the N. side of the Boulevards Montmartre and des Italiens should be avoided, as the society there is far from select. — *Cafés Chantants*, see p. 33.

Cafés in and near the Palais-Royal.

Galerie d'Orléans (S. side): *Café d'Orléans* (see p. 12). — Rue St. Honoré: No. 161, **Café de la Régence*, opposite the Palais Royal, a famous rendezvous of chess-players.

Cafés in the Boulevards.

Place de la Madeleine 2, corner of the Rue Royale: *Café Durand*, also a restaurant, like many others of the under-mentioned.

Boulevard des Capucines. N. side: No. 14, *Grand Café*, elegantly fitted up; 12, *de la Paix*, on the ground-floor of the Grand Hôtel; 4, *Café Américain*. — S. side: No. 43, *du Congrès*; 3, *Julien*; 1, *Glacier Napolitain*, noted for ices (see p. 19).

Avenue de l'Opéra: 41, *Café de Paris*; 31, *Café St. Roch*.

Boulevard des Italiens. N. side: 16, **Riche*. — S. side: No. 29, **du Helder*; 1 & 3, *Cardinal*.

Boulevard Montmartre. N. side: No. 8, *Café Mazarin* (may be visited by ladies); 8, *de Madrid* (good déj.; foreign newspapers). — S. side: No. 13, *Véron*; 9, *des Variétés*; 5, *de Suède*; 1, *de la Porte-Montmartre* (foreign newspapers).

Boulevard Poissonnière: S. side: No. 27, *Splendide Taverne*. — N. side: No. 32, *Café Brébant*; 14, *Café du Pont-de-Fer*.

Boulevard Bonne-Nouvelle. N. side: No. 30, **Café de la Terrasse* (Chauvet), well supplied with newspapers, recommended for déjeuner. — S. side: No. 39, *Déjeuner de Richelieu*, noted for chocolate.

Boulevard St. Denis No. 9, and Boul. de Sébastopol 114, *Café de France*.

Cafés on the Left Bank of the Seine.

Café d'Orsay, opposite the Pont Royal; *Voltaire*, Place de l'Odéon 1. The numerous cafés in the Boul. St. Michel are chiefly frequented by students and 'étudiantes': 27, *Vachette*; 25, *Soufflet*, corner of the Rue des Ecoles; 20, *du Musée de Cluny*, at the corner of the Boul. St. Germain.

Ices.

Ices (*glaces*) are to be had at most of the cafés in summer. The best places are the following: *Tortoni*, Boul. des Italiens 22; *Imoda*, No. 3, and *Rouzé*, No. 25, Rue Royale, opposite the Madeleine; *Café-Glacier Napolitain*, Boul. des Capucines 1, fruit-ices (1 $\frac{1}{4}$ fr.), etc.; *A la Dame Blanche*, Boul. St. Germain 196 (on the left bank). — *Sorbet* is half-frozen syrup or punch.

Confectioners.

There are two classes of confectioners at Paris, the *Pâtissiers* (pastry-cooks) and the *Confiseurs* (sellers of sweetmeats; see p. 36). The best pâtissiers are: *Guerre*, at the corner of the Rue de Castiglione and Rue de Rivoli; *Julien Jeune* (Jourlet), Avenue de l'Opéra 14; *Frascati*, Boul. Montmartre 21; *Chiboust*, Rue St. Honoré 163, Place du Théâtre Français; *Laudrée*, Rue Royale 16.

5. Cabs.

The number of cabs in Paris (*Voitures de Remise* or *de Place*, *Fiacres*) is about 15,000. Some have seats for two, others for four persons (somewhat cramped), besides the vacant seat on the box. There are also small omnibuses, with 6 seats, which ply for hire like cabs. *Landaus*, which may be opened at pleasure, have 4 seats; their fares are higher than that of ordinary cabs. Only vehicles with four and six inside seats are provided with a railing on the top for luggage. The carriage-lamps are coloured differently according to the *Dépôt* to which the cab belongs, and, as cabmen sometimes raise objections when required to drive to a great distance from their *dépôt* late at night, it may be convenient to note the following arrangements: cabs belonging to the Popincourt-Belleville *dépôt* (N.E.) have blue lamps; Poissonnière-Montmartre (central), yellow; Passy-Batignolles (W.), red; Invalides-Observatoire (S.), green.

Une Course is a single drive; *à l'heure*, by time, in which case the hirer shows his watch to the driver. The hirer should, before starting, obtain the driver's number (*votre numéro!*), which consists of a ticket containing the tariff of fares and the number, and keep it in case any dispute should take place, or any article be left in the cab. Complaints may be made to the nearest policeman, or at one of the offices which are to be found at every cab-stand. — The former *TARIFF* was repealed as from April 1st, 1891, but as the arrangements for the new *Tarif Horo-Kilométrique* are not quite complete, it is probable that the old tariff will remain in force until 1892. Comp. Appendix, p. 32.

The Bois de Boulogne and Bois de Vincennes are beyond the fortifications. The driver is bound to drive to any of the entrances of either (Porte Maillot, Dauphine, de la Muette, de Passy, d'Auteuil; de Picpus, de Reuilly, de Charenton) without additional payment and without demanding return-money.

If a cab is sent for and kept waiting more than $\frac{1}{4}$ hr., the driver is entitled to charge by time; if it is sent back at once, half a *course*, or if after $\frac{1}{4}$ hr., a whole *course* must be paid for.

If the cab be hired for a *course*, the driver may select his own route; if *à l'heure*, he must obey the directions of his employer. If one of the passengers alights before the termination of the *course*, no additional charge can be made, unless luggage placed outside the vehicle be also removed, in which case one hour must be paid for. Cabs hired *à l'heure* must drive at the rate of at least 5 M. per hour.

If the cab is engaged before 12.30 at night the *day-charges* only can be demanded, if before 6 (or 7) a.m. the *night-charges* must be paid, although the drive be prolonged beyond these limits.

Drivers are not bound to convey passengers beyond the fortifications between midnight (or in winter 10 p.m.) and 6 a.m.

If the horses are used beyond the fortifications for 2 consecutive hours, the driver may demand a rest of 20 min. at the expense of the hirer. If a carriage is engaged beyond the fortifications to return to the town, the town-charges by time can alone be exacted; in the reverse case, the increased rate is paid from the time when the fortifications are passed.

For a drive to a theatre, concert, or hall, the fare must be paid in advance.

Drivers may refuse to carry a passenger on the box-seat, or to convey dogs or other animals.

Gratuities cannot be demanded by the drivers, but it is usual to give 20 c. per drive, or 25-30 c. per hour, in addition to the fare.

Those who are desirous of exploring Paris expeditiously and comfortably are recommended to hire a *Voiture de Grande Remise* (without a number) by the day (40 fr.), or by the week. Application should be made at the offices of the Compagnie Générale des Voitures, Place du Théâtre Français 1, Boul. Montmartre 17, Boul. des Capucines 22, or Rue du Havre 9.

6. Omnibuses and Tramways. River Steamboats.

The Parisian omnibus, tramway, steamboat, and railway services for city and suburban communication are admirably arranged, and, if properly used, enable the visitor to save so much time and money, that it will repay him to study the various routes and 'correspondances'. The plan of omnibus-lines in the appendix to the Handbook will be found useful, but its perfect accuracy cannot be guaranteed, as changes are constantly taking place. The traveller is therefore advised to purchase the latest *Itinéraire des Omnibus et Tramways dans Paris* (1 fr.) at one of the omnibus-offices.

Omnibuses and Tramways. Omnibuses and tramways cross the city in every direction from 7 a.m. till midnight, and at many points a vehicle passes every five minutes. There are also tramway-lines

to Versailles, St. Cloud, and other places in the suburbs (see Plan in the Appendix).

There are 34 different lines of *Omnibuses*, distinguished by the letters of the alphabet (from A to Z, and from AB to AJ). With the exception of a few running in connection with the railways, all the omnibuses belong to the *Compagnie Générale des Omnibus*. There are two different kinds of vehicle in use: the old omnibuses with two horses and places for 26 persons (14 inside), and the new omnibuses with two or three horses and commodation for 30 or 40 passengers. The new omnibuses are provided with a staircase similar to those in the tramway-cars, rendering the outside accessible to ladies. Passengers are also permitted to stand on the platform behind the large omnibuses. The omnibuses of different shape, or with coverings over the top, are special vehicles plying to the stations, the race-courses, etc.

The *Tramways*, of which there are 40 lines, are divided at present into the *Tramways de la Compagnie des Omnibus*, the *Tramways Nord*, and the *Tramways Sud*, but it is proposed to amalgamate these three companies. The first 20 lines are distinguished by the letters A to S and AB (preceded by T), and the others by the names of their termini. With the exception of the steam-cars on part of line D, the tramway-cars of the *Compagnie des Omnibus* are large and cumbrous vehicles of an antiquated type, with 'impériales' or outside places, to which ladies are admitted. Those on the other lines resemble the cars of most other towns, but most of them also have impériales; some are steam-cars.

The termini of the lines are placarded on the sides of both omnibuses and tramway-cars, and another board is hung behind, showing the destination towards which the vehicle is proceeding. The principal places passed *en route* are also indicated, and the letter of the line is marked on different parts of the vehicle. The carriages are also distinguished by their own colour and that of their lanterns. Comp. the tables in the Appendix, pp. 24, 25.

Passengers may either hail and stop the omnibus in the street as in England, or wait for it at one of the numerous omnibus-offices. In the latter case, if there are other intending passengers, it is usual to ask for a numbered ticket (*numéro*; no charge) for the line required. As soon as the omnibus appears, places are assigned to the ticket-holders in order; when the omnibus is '*complet*' it drives off, and the disappointed ticket-holders have to wait for the next.

The fares on all the lines within Paris are the same, 30 c. inside, and 15 c. outside (*impériale*). The fares for places beyond the fortifications are from 10 to 50 c. higher (inside; outside 5 to 25 c.) according to the distance.

One of the most admirable features in the arrangements of the Parisian omnibus-lines is the system of *Correspondances*, or permission to change from one line to another. Thus, if no omnibus

go in the direct route to the passenger's destination from the part of Paris in which he is, he may demand from the conductor a *correspondance* for the line which will convey him thither. He will then receive a ticket, and will be set down at the point where the two lines cross. Here he proceeds to the omnibus-bureau, receives a number, which, without additional payment, entitles him to a seat in the first omnibus going in the desired direction, and finally gives up his ticket to the conductor of the latter. Outside-passengers are not entitled to *correspondance*, unless they pay full fare (30c.). The tables and map in the Appendix will show what lines have *correspondance* with each other. The letters in the second column of the table indicate the lines that correspond with the line denoted by the letter in the first column. It should be noted that the *bureau de correspondance* is not invariably the same as the office at which the passenger alights, but is sometimes a little way off.

Correspondances are also issued at a small additional charge for places beyond the fortifications.

River Steamboats. The *Bateaux-Omnibus*, or small screw-steamers which ply on the Seine, are recommended to the notice of the traveller in fine weather, as they afford a good view of the quays and banks of the river; but being small, they are apt to be crowded.

There are three different services, belonging, however, to the same company (*Bateaux Parisiens*): (1) From Charenton to Auteuil, by the left bank of the river within Paris; (2) From the *Pont d'Austerlitz* to Auteuil, by the right bank; (3) From the *Pont-Royal* to Suresnes, also by the right bank. Comp. the route map and the table in the cover at the end of the book.

The Charenton steamboats may be recognized by the benches placed across the bridge; those for Suresnes by their larger size and white colour. In the latter boats the fares for the whole or any part of the distance are the same. Tickets are taken on board. Fares (which are liable to vary): From Charenton to Pont d'Austerlitz 10 c., on Sun. and holidays 15 c.; from Charenton to Auteuil 20 and 25 c.; Pont d'Austerlitz to Auteuil, 10 and 20 c.; Pont Royal to Suresnes 20 and 40 c.

The sailing of these boats may be interrupted by the state of the river, fog, ice, etc.

7. Railway Stations. *Chemin de Fer de Ceinture.*

The numerous railways† radiating from Paris start from nine different stations. All the lines have sub-offices (*bureaux suc-*

† Railway-station, *la gare* (also *l'embarcadère*); booking-office, *le guichet* or *bureau*; first, second, or third class ticket, *un billet de première, de seconde, de troisième classe*; to take a ticket, *prendre un billet*; to register the luggage, *faire enregistrer les bagages*; luggage-ticket, *bulletin de bagage*; waiting-room, *salle d'attente*; refreshment-room, *le buffet* (third class refreshment-room, *la buvette*); platform, *le quai, le trottoir*; railway

cursales) in various parts of the city, from which railway-omnibuses run in connection with the trains. Passengers may book their luggage, and in some cases even take their tickets, at these sub-offices, which, however, they must generally reach 1 hr. before the departure of the train. The office of the *Compagnie Internationale des Wagons-Lits* (sleeping-carriages) is on the ground-floor of the Grand Hotel, Rue Scribe 2. The *South Eastern Railway* and the *London, Chatham, and Dover Railway* have also offices in Paris (Boulevard des Italiens 4 and 30).

The '*Indicateur des Chemins de Fer*', and the *Livrets Chaix* (p. xiv) give complete information regarding all trains. — *Hotels* near the termini, see p. 2.

I. Chemin de Fer de l'Ouest. Three Stations.

(1). GARE ST. LAZARE (comp. p. 204), between the Rue St. Lazare, the Rue d'Amsterdam, and the Rue de Rome (Pl. B, 18), for the *Ligne de Petite Ceinture*; the *Lignes de Banlieue*, serving *St. Cloud*, *Versailles* (right bank), *St. Germain*, *Argenteuil*, and *Ermont*; and the *Lignes de Normandie* (Buffet). — The railway-omnibuses start from the Place de la République, the Pointe St. Eustache, and the Bourse de Commerce (Halles).

(2). GARE MONTPARNASSE, Boulevard Montparnasse 44 (Pl. G, 16), for the *Ligne de Banlieue* to *Sèvres* and *Versailles* (left bank), the *Lignes de Bretagne*, and the *Chemins de Fer de l'Etat*. The booking-offices for the line to Versailles and for the suburban stations are situated downstairs, to the left; those for the main lines are above, reached by an outside staircase and by an inclined plane.

(3). GARE DU CHAMP-DE-MARS (probably to be called Gare de l'Esplanade des Invalides), for a branch of the Chemin de Fer de Ceinture and the new line along the bank of the Seine viâ *Sèvres*, *St. Cloud*, and *Suresnes* to *Puteaux* (p. 285), where it joins the line to Versailles.

II. Chemin de Fer d'Orléans. Two Stations.

(1). GARE D'ORLÉANS, Quai d'Austerlitz (Pl. G, 25), for the lines to *Orléans*, *Tours*, *Bordeaux*, the *Pyrenees*, *Spain*, etc.

(2). GARE DE SCEAUX, Boulevard Raspail (Pl. G, 20), for the local lines to *Sceaux* and *Orsay-Limours*. This station will probably be removed to near the Jardin du Luxembourg (p. 258). — Omnibus from the Place de la Bourse (30 c.; 50 c. after midnight).

III. Chemin de Fer de Paris à Lyon et à la Méditerranée.

GARE DE LYON, Boulevard Diderot 20 (Pl. G, 25, 28). Trains to *Fontainebleau*, *Dijon*, *Châlon-sur-Saône*, *Mâcon*, *Neuchâtel*, *Geneva*, *Lyons*, *Marseilles*, *Italy* viâ the *Mont Cenis Tunnel* or viâ *Nice*, etc.

carriage, *le wagon*; compartment, *le compartiment*, *le coupé*; smoking compartment, *fumeurs*; ladies' compartment, *dames seules*; guard, *conducteur*; porter, *facteur*; to enter the carriage, *monter en wagon*; take your seats! *en voiture!* alight, *descendre*; to change carriages, *changer de voiture*; express train to Calais, *le train express pour Calais*, *l'express de Calais*.

IV. Chemin de Fer de l'Est. Two Stations.

(1). GARE DE L'EST, or DE STRASBOURG, Place de Strasbourg (Pl. B, 24; p. 186), for the lines to *Nancy* etc., and to *Germany* and *Switzerland* *viâ Metz, Strassburg, and Belfort*. The Belfort line has a special departure platform, to the left, behind the principal building.

(2). GARE DE VINCENNES, Place de la Bastille (Pl. R, 25; V), for the line to *Vincennes* and *Brie-Comte-Robert*. — Omnibus from the Place de la Bourse and the Boulevard des Capucines, near the Grand Hotel (30 c. inside, 20 c. outside).

V. Chemin de Fer du Nord. GARE DU NORD, Place Roubaix 18 (Pl. B, 24; comp. p. 186), for the *Lignes de Banlieue* to *St. Denis, Enghien*, etc.; and for the *Lignes du Nord* to *England, Belgium, Germany* *viâ Liège*, etc. The booking-offices for the trains of the Banlieue, except for the stations beyond *St. Denis* on the Chantilly line, are in front; for the other trains, in the arcade to the left. — *Buffet* to the right in the first arcade.

VI. Chemin de Fer de Ceinture. — The 'Chemin de Fer de Ceinture' is a railway forming a complete circle round Paris, within the line of the fortifications, and connecting the different suburbs. The length of the line is 23 M., but owing to the frequency of the stoppages the circuit is not performed in less than 2 hrs. 5 minutes. For details see the table in the cover at the end of the Handbook. Trains run in both directions almost every $\frac{1}{2}$ hour; in the oldest part, the section between *St. Lazare* and *Auteuil*, there are 6 trains per hour on week-days. The chief station of arrival and departure is the Gare *St. Lazare* (p. 23). There is no third class. The fare to the Avenue du Bois de Boulogne, or any previous station, is 40 and 30 c.; to the Avenue du Trocadéro, Passy, and *Auteuil* 45 and 30 c.; and for all distances over 12 M. (including the entire circuit) 85 and 55 c. — Comp. the *Indicateur des Chemins de Fer*.

Travellers may avail themselves of this railway to visit points of interest in the suburbs, such as the Bois de Boulogne, Père Lachaise, and the Buttes-Chaumont, or to make the complete circuit of the city. On every side of the town, however, except the S.W., the line runs between walls or through deep cuttings and tunnels. The seats on the outside ('impériale') are very draughty, and are not to be recommended except in hot weather.

The Chemin de Fer de Grande Ceinture, which forms a wide circle round Paris, connecting the Chemins de Fer de l'Est, de Vincennes, de Lyon, and d'Orléans, is of little interest for the tourist except for the trip from Versailles to *St. Germain* (p. 307) and for the excursion to the valley of the Bièvre (p. 333).

The *Chemin de Fer Métropolitain*, or Paris Metropolitan Railway, is still a thing of the future.

8. Post and Telegraph Offices.

Post Office. The *Poste Centrale*, or *General Post Office*, is in the Rue du Louvre (Pl. R, 21; III). The offices open to the public

are entered from the colonnade on this side; the poste restante and enquiry offices from another colonnade to the right (comp. p. 170). There are also in the different quarters of the town 87 branch-offices, distinguished at night by blue lamps.

The following are the BUREAUX D'ARRONDISSEMENT, or District Offices. (Meaning of the asterisks, see below.)

1. *Arrond.* (Louvre): **Hôtel des Postes (p. 170); **Avenue de l'Opéra 2; *Rue des Capucines 13; *R. Cambon 9; *R. St. Denis 90; *R. des Halles 9. — 2. *Arrond.* (Bourse): **Place de la Bourse 4 and R. Feydeau 5; **R. de Cléry 28; **R. Marsollier; *R. de Choiseul 18 & 20. — 3. *Arrond.* (Temple): *R. Réaumur 47; *Boul. Beaumarchais 68; *R. des Haudriettes 4. — 4. *Arrond.* (Hôtel de Ville): *Hôtel de Ville; *Tribunal de Commerce; etc. — 5. *Arrond.* (Panthéon): *R. de Poissy 9; etc. — 6. *Arrond.* (Luxembourg): *Boul. St. Germain 104; *R. Bonaparte 21; etc. — 7. *Arrond.* (Palais Bourbon): *Boul. St. Germain 242; *R. de Bourgogne 2; *R. de Grenelle 103; etc. — 8. *Arrond.* (Elysée): *R. d'Amsterdam 19; *Boul. Malesherbes 6; Avenue des Champs-Élysées 33; etc. — 9. *Arrond.* (Opéra): *R. Taithout 46; *R. Milton 1; *R. de la Fayette 35; R. Bleue 14; etc. — 10. *Arrond.* (St. Laurent): *R. d'Enghien 21; R. de Strasbourg 8 (Gare de l'Est); *Gare du Nord; Place de la République 10; etc. — 11. *Arrond.* (Popincourt): Boul. Beaumarchais 68; etc.

The ordinary offices are open daily from 7 a.m. (8 a.m. in winter) till 9 p.m. (6 p.m. on Sun. and holidays). Letters for the evening-trains must be posted at the ordinary offices before 5.30 p.m.; at the offices marked with one asterisk before 5.45 p.m.; at those with two asterisks before 6 p.m.; at the railway-stations they may be posted till within 5-10 minutes of the starting of the trains.

The Poste Restante Office is in the General Post Office and is open till 10 p.m. (Sun. 7 p.m.). Travellers may also direct *poste restante* letters to be addressed to any of the district-offices. In applying for letters, the written or printed name, and in the case of registered letters, the passport of the addressee should always be presented. It is, however, preferable to desire letters to be addressed to the hotel or boarding-house where the visitor intends residing.

Letter-boxes (*Boîtes aux Lettres*) are also to be found at most public buildings and in all tobacconists' shops, where stamps (*timbres-poste*) may also be purchased.

Postage of Letters, Post-Cards, Printed Papers, etc.

Ordinary Letters within France, including Corsica, Algeria, and Tunis, 15 c. per 15 grammes prepaid; for countries of the Postal Union 25 c. (The silver franc and the bronze sou each weigh 5 grammes; 15 grammes, or three of these coins, are equal to 1/2 oz. English.) — *Registered Letters* (*lettres recommandées*) 25 c. extra.

Post Cards 10 c. each, with card for reply attached, 20 c.

Post Office Orders (*mandats de poste*) are issued for most countries in the Postal Union at a charge of 25 c. for every 25 fr. or fraction of 25 fr., the maximum sum for which an order is obtainable being 500 fr.; for Great Britain, 20 c. per 10 fr., maximum 252 fr.

Printed Papers (*imprimés sous bande*): 1 c. per 5 grammes up to the weight of 20 gr.; 5 c. between 20 and 50 gr.; above 50 gr. 5 c. for each 50 gr. or fraction of 50 gr.; to foreign countries 5 c. per 50 gr. The wrapper must be easily removable, and must not cover more than one-third of the packet.

Parcels. Small parcels not exceeding 7 lbs in weight may be forwarded by post at a moderate rate within France and to some of

the other countries of the Postal Union. The Parisian parcel-post was reorganized in 1890 and now has five deliveries daily (two on Sun.). Charges 20 c. per parcel prepaid, or 60 c. when postpaid at the office, 85 c. postpaid at recipient's house. To England, parcels not exceeding 3 lbs. (1360 grammes) 1 fr. 60 c.; from 3 to 6½ lbs., 2 fr. 10 c. — The following *Expéditeurs*, or goods-agents, may be recommended: *Camus & Cie.*, Rue Daunou 20 and Rue du Faubourg-Poissonnière 25; *Müller & Co.*, Rue d'Hauteville 47; *E. Herse*, Rue de Trévis 35bis (for Germany and Russia); *Elie Marcon & Co.*, Rue de la Grange-Batelière 26 (for Russia).

Telegraph. The telegraph-offices at the district post-offices are open to 9 p.m. The following amongst others are open till 11 p.m.: Avenue des Champs-Élysées 33; Rue d'Amsterdam 19; Boul. St. Martin 41; Gares du Nord and de Lyon; the Luxembourg; Place de la République 10. The offices at Avenue de l'Opéra 4, Rue Boissy d'Anglas 3, and the Grand Hotel are open till midnight. Telegrams may be sent at any hour of the day or night from the offices at the Bourse (night entr. on the left); Rue de Grenelle 103; and the Ecole Militaire.

For the countries of Europe and for Algeria telegrams are charged for at the following rates per word: for France 5 c. (minimum charge 50 c.); Algeria and Tunis 10 c. (minimum 1 fr.); Luxembourg 5-10 c.; Switzerland and Belgium 10-12½ c.; Germany 15 c.; Netherlands 16½ c.; Great Britain, Austria-Hungary, Portugal, Italy, and Spain 20 c.; Sweden, Denmark, Roumania, etc., 30; Norway and Russia in Europe 40 c.; Greece 55-60 c.; Turkey 55 c.

Telegraphic Orders (*mandats télégraphiques*) for not more than 5000 fr. are issued between French offices.

There is also a system of PNEUMATIC TUBES (*Télégraphie pneumatique*) for the transmission of messages within Paris, at the rate of 30 c. for open cards (*cartes télégrammes ouvertes*), 50 c. for closed cards (*cartes télégrammes fermées*), and 75 c. for letters not weighing more than 7 grammes. The cards may be obtained at the telegraph-offices, to which special letter-boxes for the pneumatic post are also attached.

Telephone. Most of the post and telegraph offices have telephonic communication with all parts of Paris (fee 50 c. per 5 min.), and with several of the outlying suburbs (1 fr.). Paris also communicates with Rheims, Rouen, Havre, Lille, Elbeuf, Lyons, Marseilles, etc. (50 c. per 100 kilomètres); and with Brussels (3 fr.). Paris and London are now also in telephonic communication (fee 10 fr. per 3 min.).

9. Theatres, Circuses, Panoramas.

Paris now possesses about 20 large theatres, in the proper sense of the word, and the traveller doing the 'sights' of Paris should not omit to visit some at least of the principal houses. An intimate acquaintance with colloquial French, such as can be

acquired only by prolonged residence in the country, is absolutely necessary for the thorough appreciation of the acting; visitors are therefore strongly recommended to purchase the play (*la pièce*; 1-2 fr.) to be performed, and peruse it beforehand. Dramatic compositions of every kind are sold by *Tresse*, Palais-Royal, Théâtre Français 8-11, *Ollendorff*, Rue de Richelieu 28bis, at the *Magasin Théâtral*, Boul. St. Martin 12, and at the *Librairie Nouvelle*, Boulevard des Italiens 15. The plays may also be procured in most instances at the theatres themselves.

Performances generally begin between 7.30 and 8.30 p.m., and last till nearly midnight. Two or three pieces are as a rule played each evening, the first being the so-called *lever rideau*, a one-act piece or farce during which the house gradually fills. Play-bills (*le programme*, *le programme détaillé*), or theatrical newspapers with the programme of the evening (*l'Entre-Acte*, *l'Orchestre*, and others), are sold in the theatres. Some of the other newspapers, particularly those published in the afternoon, give lists of the pieces and characters.

The best seats are the *fauteuils d'orchestre*, or seats next to the orchestra, behind which are the *stalles d'orchestre*. The *fauteuils p'amphithéâtre* in the Opera House may also be recommended, but in most other theatres the amphitheatre is indifferent both for seeing and hearing. The *fauteuils de balcon*, or *de la première galerie*, corresponding to the English dress-circle, are good seats, especially for ladies. The centre seats in the two following galleries (*loges des premières*, *des secondes de face*) come next in point of comfort. The *avant-scènes* or *loges d'avant-scènes* are the stage-boxes, which may be *du rez-de-chaussée* (on a level with the stage), *de balcon*, etc. *Baignoires*, or *loges du rez-de-chaussée*, are the other boxes on the ground-floor of the theatre. At several of the theatres ladies are not admitted to the orchestra stalls, the space between each row of seats being so narrow, that even gentlemen have some difficulty in passing in and out. The arrangement and naming of the seats differ in the different theatres, but in all of them the side-seats of the two upper galleries should be avoided. At the Opera the *stalles de parterre*, behind the *fauteuils d'orchestre*, are rendered unpleasant by the presence of the 'claque' (p. 28). As a rule the price of a seat is the best criterion of its desirability.

It is a wise precaution, especially in the case of very popular performances and when ladies are of the party, to secure a good seat by purchasing a ticket beforehand (*billet en location*) at the office of the theatre (*bureau de location*, generally open from 10 or 11 to 6), where a plan of the interior is shown. Seats booked in this manner generally cost $1\frac{1}{2}$ -2 fr. more than *au bureau*, i.e. at the door, but the purchaser has the satisfaction of knowing that his seat is numbered and reserved. Box-places, however, cannot thus be obtained in advance except by taking a whole box (4-6 seats). Places

may also be secured beforehand at one of the *theatrical offices* in the Boulevards, but the booking-fee demanded there is often 5 fr. and upwards. Visitors are cautioned against purchasing their tickets from vendors in the street.

The different charges for admission given below vary according to the season and the popularity of the piece and of the actors. At the so-called *premières* (scil. *représentations*), or first performances of pieces by favourite authors, the charges for boxes are often extravagantly high.

The *parterre* or pit is always crowded, and the places are not numbered, except at the Opera. Those who wish to secure a tolerable seat in this part of the theatre should be at the door at least an hour before the beginning of the performance, and fall into the rank (*faire queue*) of other expectants. The doors are opened half-an-hour before the curtain rises. Women are seldom seen in the *parterre*, except in the smaller theatres.

Tickets taken at the door are not numbered, and do not give the purchaser a right to any particular seat in the part of the house to which they apply. The door-keeper will direct the visitor to one of the unengaged places; but if any unfair play be suspected, visitors may demand *la feuille de location*, or list of seats booked for the night, and choose any seats which do not appear on this list.

The *Claque* ('*Romains*', '*Chevaliers du Lustre*'), or paid applauders, form an annoying, although characteristic feature in most of the theatres. They generally occupy the centre seats in the pit, under the chandelier or '*lustre*', and are easily recognised by the obtrusive and simultaneous vigour of their exertions. There are even '*entrepreneurs de succès dramatiques*', a class of mercantile adventures who furnish theatres with *clagues* at stated terms. Strange as it may seem to the visitor, all attempts to abolish this nuisance have hitherto failed.

Overcoats, cloaks, shawls, etc., are left at the '*Vestiaire*' or cloak-room (fee 25-50 c. each person). Gentlemen take their hats into the theatre, and may wear them during the intervals of the performances. The attendants of the *vestiaire* usually bring a footstool (*petit banc*) for ladies, for which they expect a gratuity of 10-25 c.

A list of the most important Parisian theatres, in their usual order, is here annexed.

The **Opera** (Pl. B, R, 18; *II*). The admirable performances of the Parisian opera take place on Mon., Wed., and Frid., in winter on Sat. also. The ballet and the *mise en scène* are unsurpassed. Government allots an annual subvention of 800,000 fr. towards the support of the Opera. The staff of performers is about 250 in number. A good tenor receives a salary of 100-120,000 fr. Composers and authors of new pieces are entitled to 7 per cent of the gross receipts in the first year of performance and 8 per cent in all subsequent years. — The seats are all comfortable.

Loges de face des *premières* 19; fauteuils d'amphithéâtre and *premières loges* de côté 17; fauteuils d'orchestre, loges de face des *secondes*, and *baïnoires*, 16; *secondes loges* de côté, 12; loges de face des *troisièmes* 10; stalles de *parterre* 9; loges de côté des *troisièmes* 7; loges de face des *quatrièmes* and fauteuils d'amphithéâtre des *quatrièmes*, 5 fr., etc. Ladies are not admitted to the orchestra seats. Evening-dress *de rigueur* in the fauteuils d'orchestre and the 1st gallery.

The **Théâtre Français** (Pl. R, 21; *II*), or *Comédie Française*, Place du Théâtre-Français, on the S.W. side of the Palais-Royal, occupies the highest rank among the theatres of Paris. The acting is admirable, and the plays are generally of a high class. This theatre was founded in 1600, and was under the superintendence of *Molière* from 1658 down to his death in 1673. The theatre receives a subsidy of 240,000 fr. a year from government. For a description of the edifice itself, see p. 58.

Avant-scènes des premières loges 10; loges du rez-de-chaussée, premières (first gallery), avant-scènes des deuxièmes, and baignoires de face 8; fauteuils de balcon 10-8; fauteuils d'orchestre, 7; loges de face de deuxième rang 6; loges découvertes de deuxième rang 5; loges de face de troisième rang 3½; loges découvertes de troisième rang 3; parterre 2½; troisième galerie et fauteuils de la quatrième, 2 fr. Ladies are not admitted to the orchestra seats.

The **Opéra Comique**, Place Boieldieu, was destroyed on May 25th, 1887, by a terrible fire accompanied by a great loss of life. It was intended originally for the performance of the lesser operas, such as *La Dame Blanche*, the *Postillon de Lonjumeau*, *Fra Diavolo*, etc., but has latterly been devoted to the more ambitious operas and to lyrical dramas such as *Mignon*, *Romeo and Juliet*, *Lakmé*, *Carmen*, etc. It receives an annual subsidy of 300,000 fr. from government. At present the Opéra Comique is installed in one of the theatres in the Place du Châtelet (Pl. R, 23; *V*; p. 61).

Avant-scènes du rez-de-chaussée and de balcon 10 fr.; loges de balcon, baignoires, fauteuils d'orchestre, and faut. de balcon 8; avant-scènes and loges de la première galerie 6 and 5; fauteuils de la deuxième galerie 4; stalles de parterre and avant-scènes de la deuxième galerie 3; stalles de la deuxième galerie 2½ fr.

The **Odéon**, Place de l'Odéon (Pl. R, 19; *IV*), near the Palais du Luxembourg (p. 253), ranks next to the Théâtre Français, and is chiefly devoted to the performance of classical dramas. A large proportion of the audience consists of students, especially at the Monday performances with reduced prices. Some of the plays of Casimir Delavigne, Ponsard, and George Sand were performed here for the first time. The Odéon is closed in June, July, and August.

Avant-scènes des premières and du rez-de-chaussée 12 fr.; baignoires d'avant-scène 10; premières loges de face 8; fauteuils d'orchestre 6; fauteuils de la première galerie 6; stalles de la deuxième galerie 3½; deux. loges de face and parterre 3; parterre 2½ fr.

The **Gymnase** (Pl. R, 24; *III*), Boulevard Bonne-Nouvelle 38, chiefly for comedies, deserves commendation, and its pieces are frequently deemed worthy of being performed in the Théâtre Français. Scribe wrote most of his plays for this theatre. Vict. Sardou, Alex. Dumas the Younger, Emile Augier, and Octave Feuillet have also achieved great successes here.

Avant-scènes du rez-de-chaussée and des premières 12 fr.; fauteuils de balcon 9 and 8; loges de balcon 8; avant-scènes, fauteuils, and loges de foyer 6 and 5; loges de deuxième galerie 3 and 2½ fr.

The **Vaudeville** (Pl. R, 18, 21; *II*), at the corner of the Rue de la Chaussée d'Antin and the Boulevard des Capucines, a handsome

building, completed in 1869, is admirably fitted up. It is chiefly destined for vaudevilles and comedies.

Avant-scènes du rez-de-chaussée and des premières 10; premières and fauteuils de balcon, premier rang 8; deuxième rang and fauteuils d'orchestre 7; avant-scènes or fauteuils de foyer 5; loges de foyer 4; troisièmes 3 fr.

The Variétés (Pl. R, 21; *III*), Boulevard Montmartre, excellent for vaudevilles, farces, operettas, and similar lively pieces of essentially Parisian character.

Avant-scènes du rez-de-chaussée and des premières 10; premières loges 8; fanfils d'orchestre and de balcon 7; loges de foyer de face 5; troisièmes loges 4½; loges de côté 4; deuxième galerie 3 fr., etc.

Théâtre du Palais-Royal, at the N.W. corner of the Palais Royal, 74, 75 (Pl. R, 21; *II*), a small but very popular theatre, where vaudevilles and farces of broad character are performed.

Avant-scènes 8 fr.; premières loges, fauteuils de première galerie and d'orchestre 7; fauteuils de balcon des deuxièmes and deuxièmes de face 5; avant-scènes des deuxièmes and stalles d'orchestre 4; stalles des troisièmes 2½ fr. Ladies not admitted to the orchestra seats.

Théâtre de la Porte St. Martin (Pl. R, 24; *III*), in the Boulevard St. Martin, burned down by the Communists in May, 1871, but since rebuilt. Dramas and spectacular pieces.

Avant-scènes du rez-de-chaussée and des premières 16; premières de face 10, fauteuils de balcon 12 and 10; fauteuils d'orchestre 9; avant-scènes des deuxièmes, deuxièmes de face, and fauteuils des deuxièmes 6; stalles d'orchestre 5; deuxièmes de côté and avant-scènes des troisièmes, 3 fr.; etc.

Théâtre de la Renaissance (Pl. R, 24; *III*), next door to the preceding. Modern comedies.

Avant-scènes du rez-de-chaussée and du premier balcon 12; loges de balcon de face and fauteuils de balcon, premier rang 7; other rangs 5; fauteuils d'orchestre 6; stalles d'orchestre, fanfils and loges de face de la première galerie, premier rang 4; other rangs 3 fr. etc.

Théâtre de la Gaîté (Pl. R, 24; *III*), Square des Arts et Métiers. It has several times changed its name and its specialty; at present spectacular pieces and operettas are given.

Avant-scènes du rez-de-chaussée and de première galerie 10; loges and fauteuils de première galerie 8 and 7; fanfils d'orchestre 7; avant-scènes, loges and fauteuils de deuxième galerie 5; stalles d'orchestre 4; stalles de deuxième galerie 3; stalles de troisième galerie 2½ and 2 fr.

Théâtre du Châtelet, Place du Châtelet (Pl. R, 24; *V*), a very roomy edifice, specially fitted up for fairy scenes and ballet, lighted by a large reflector in the roof, which can be removed in summer for ventilation.

Fauteuils de balcon de premier rang 8; fauteuils d'orchestre and loges 7; stalles d'orchestre 5; pourtour 4; parterre 2½; deuxième amphithéâtre 2 fr.

Bouffes Parisiens (Pl. R, 21; *II*), a small theatre in the Passage Choiseul near the Italian Opera, the specialty of which is comic operettas and parodies. It was established by Offenbach in 1855.

Avant-scènes 10; loges de balcon 8; fauteuils d'orchestre and de balcon 7; avant-scènes, loges, and fauteuils de la première galerie 5 and 4 fr. — Ladies not admitted to the orchestra stalls.

Théâtre des Nouveautés (Pl. R, 21), Boulevard des Italiens 28. Vaudevilles and operettas.

Avant-scènes du rez-de-chaussée and des premières 12½; premières loges 8; fauteuils de balcon and d'orchestre 8 and 7; stalles d'orchestre,

deuxièmes, and fauteuils de galerie 5 and 4 fr. Ladies not admitted to the orchestra places.

Ambigu-Comique (Pl. R, 24; *III*), Boulevard St. Martin 2; dramas, melodramas, and 'patriotic' pieces.

Premières avant-scènes 8; premières loges and fauteuils de balcon, premier rang 8; other rangs 6 and 4; fauteuils d'orchestre 7, 6, and 5; fauteuils de foyer 4 and 3 fr.

Folies Dramatiques (Pl. R, 27; *III*), Boulevard St. Martin, or rather Rue de Bondy 40, near the Place de la République. Operettas, etc. Seats for 1600.

Avant-scènes du rez-de-chaussée and loges de balcon de face 8; avant-scènes du théâtre 7½; avant-scènes des premières, loges de face, fauteuils d'orchestre, and fauteuils de la première galerie, premier rang 6; other fauteuils of the première galerie 5; stalles d'orchestre 2½; stalles de balcon and avant-scènes des deuxièmes, 2 fr.

Eden Théâtre (Pl. R, 18; *II*), Rue Boudreau, for pantomimes and ballets. Promenoir 2 fr., reserved seats 3-6 fr.

Among the best of the other theatres are the following: —

Théâtre de Cluny, Boul. St. Germain 71, near the Musée de Cluny, the 'Gymnase' of the left bank (seats 6 fr. to 1¼ fr.). — **Château d'Eau**, now the **Théâtre Historique**, Rue de Malte 50, near the Place de la République. — **Théâtre Beaumarchais**, Boul. Beaumarchais, often closed. — **Théâtre Déjazet**, Boul. du Temple 47. — **Théâtre des Menus Plaisirs**, Boul. de Strasbourg 14; etc.

The **Théâtre Robert Houdin**, Boulevard des Italiens 8, for conjuring of all kinds, may also be mentioned here. Admission 2 to 5 fr.

EQUESTRIAN PERFORMANCES, accompanied by acrobatic feats, pantomime, etc., are exhibited at the following circuses: —

Cirque d'Été (Pl. R, 15; *II*), formerly called the *Cirque de l'Impératrice*, near the Rond-Point des Champs-Élysées (Pl. R, 15; *II*), to the right in ascending. Performances every evening from April to October. Seats for 3500. Admission 4 (on Wed. and Sat. 5), 3, and 1 fr.

Cirque d'Hiver (Pl. R, 27; *III*), formerly the *Cirque Napoléon*, Boulevard des Filles-du-Calvaire. Performances every evening, from 1st Nov. to 30th April. Premières loges 2, deuxièmes 1, troisièmes ½ fr.

The **Hippodrome** (Pl. R, 12; *I*), between the Avenue de l'Alma and the Avenue Marceau, is a vast circus holding 10,000 spectators. Performances on afternoons (Wed. and Sun.) and evenings in summer. The roof is generally removed in fine weather. Admission, 1 to 5 fr.

Nouveau Cirque, Rue St. Honoré 251 (Pl. R, 18; *II*), with an arena which may be flooded at a moment's notice for aquatic spectacles. The floor is formed of perforated planks covered with a rough carpet; at a given signal the carpet is rolled up, the planking descends, and water gushes in on all sides. Adm. 5, 3, and 2 fr.

Cirque Fernando (Pl. B, 20), Boulevard Rochechouart 63. Admission, 3 fr. to 50 c.

Gran Plaza de Toros, for bull-fights in summer, Rue Pergolèse 3 and Boulevard Lannes (Pl. B, 9), near the Bois de Boulogne, Admission 3 to 20 fr.; tickets also at Place de l'Opéra 6.

Panoramas have again become fashionable in Paris as at the beginning of the century, when there were three in the Passage des Panoramas alone. — **PANORAMA DES CHAMPS-ÉLYSÉES** (Pl. R, 15; II), beyond the Palais de l'Industrie (p. 155): *Siege of Paris*, by Philippoteaux. — **PANORAMA MARIGNY** (Pl. R, 15; II), nearly opposite the first (p. 155): *Ancient Jerusalem*, by Ol. Pichat, and a diorama of *Paris à travers les âges*. — **PANORAMA NATIONAL** (Pl. R, 12; I), Rue de Berry 5: *Battle of Champigny*, by Detaille and De Neuville. Admission to all these, 2, Sun. 1 fr. — **PANORAMA OF THE HISTORY OF THE CENTURY**, by Stevens and Gervex, in the Jardin des Tuileries (p. 152), etc.

Other sights of a similar kind are the reproductions of the *Bastille*, near the Champ de Mars (p. 284), and of the *Tour du Temple*, near the Trocadéro (p. 165).

The **Musée Grévin**, founded by the well-known draughtsman of that name, Boul. Montmartre 8, adjoining the Passage Jouffroy, is a collection of wax figures; adm. 2, Sun. 1 fr., children at half-price.

10. Concerts, Balls, Sport, and Clubs.

Concerts. The concerts of the *Conservatoire de Musique*, Rue du Faubourg-Poissonnière 15, which enjoy a European celebrity, take place every Sunday from January to April. The highest order of classical music, by Haydn, Händel, Mozart, Beethoven, etc., as well as by the most celebrated French and Italian composers, is performed with exquisite taste and precision. There are also three sacred concerts given at the Conservatoire during Passion and Easter weeks. Strangers cannot easily obtain access to them, as almost all the seats are occupied by regular subscribers. Application may, however, be made at the office, Rue du Conservatoire 2, open 1-3 p.m. on the day before a concert and 1-2 p.m. on the day itself. Balcon and premières loges 12 fr.; stalles d'orchestre, loges du rez-de-chaussée, and secondes loges 9 fr.; troisièmes loges and amphithéâtre 5 and 4 fr.

The best Church Music is heard at *St. Eustache* (p. 171), the *Madeleine* (p. 79), *St. Roch* (p. 85), *La Trinité* (p. 200), *Notre Dame* (p. 221), *St. Sulpice* (p. 251), and *Ste. Clotilde* (p. 273).

The *Concerts Lamoureux*, established in 1881, now stand in the foremost rank. Classical music, selections from Wagner, and new pieces are given at these concerts, which also take place on Sundays in winter in the Cirque d'Été (p. 31). Adm. 2-8 fr.

Similar to the last are the *Concerts du Châtelet* or *Colonne*, which are held in the Théâtre du Châtelet (adm. 1¹/₄-7 fr.). The compositions of Berlioz are frequently performed.

Besides the above regular concerts, others are given occasionally at the concert-rooms of *Erard*, Rue du Mail 13; *Pleyel*, Rue Rochecouart 22; *Herz*, Rue de la Victoire 38; and other places. See bills and newspaper advertisements. — Lent is the principal season for concerts in Paris.

Open-air concerts are given in summer at the *Jardin d'Acclimatation* (p. 160). *Military Bands* also play generally on Sun. and Thurs. (4-5 or 5-6 p.m.); in the gardens of the Tuileries (Sun., Tues., and Thurs.), the Palais-Royal (Sun., Wed., and Frid.), and the Luxembourg (p. 258) and in several other parks and squares; the favourite is that of the Garde Républicaine (programmes in the daily papers).

The concerts of the *Jardin de Paris* (Pl. R, 15; *II*), given in summer in the open air, under the trees at the back of the Palais de l'Industrie, in the Champs-Élysées, are attended by a somewhat mixed company (also public balls). Adm. 1 fr.

Cafés Chantants, etc. The music and singing at these establishments and at the '*spectacles-concerts*' is never of a high class, while the audience is of a very mixed character. The entertainments, however, are often amusing, and sometimes consist of vaudevilles, operettas, and farces. Smoking allowed. — The following may be mentioned: *Café des Ambassadeurs*, in the Champs-Élysées, the first on the right, before the circus is reached; the *Alcazar d'Été*, the second on the right; and the *Café de l'Horloge*, on the left. In winter: the *Eldorado*, Boul. de Sébastopol, near the Boul. St. Denis; opposite to it, the *Scala*, with a handsome saloon, unroofed in summer; *Grand Concert Parisien*, Rue du Faubourg-St. Denis 37; *Eden Concert*, Boul. de Sébastopol 17. The alluring display of the words '*entrée libre*' outside the cafés-chantants is a ruse to attract the public, as each visitor is obliged to order refreshments (a '*consommation*'), which are generally of inferior quality, at a price of 1-3 fr., according to the reputation of the place. — Miscellaneous entertainments of a similar class are given in various other establishments. The *Folies-Bergère*, Rue Richer 32 (Pl. B, 21; *III*), is a very popular resort, half theatre, half café-chantant. Visitors either take seats or promenade in the gallery, while the performances are going on on the stage. Smoking allowed. Adm. 2-5 fr. — The *Casino de Paris*, Rue Blanche 15 and Rue de Clichy 16 (Pl. B, 18), is a large new establishment, handsomely fitted up, with two orchestras, electric light, etc. Adm. 2-8 fr. — The *Moulin-Rouge*, Place Blanche (Pl. B, 17), opposite the Rue Fontaine, provides similar entertainments and balls. Adm. to the evening-fêtes 2 fr. — The *Montagnes Russes*, Boul. des Capucines 28 (adm. from 2 p.m. to midnight 2 fr.) may also be mentioned in this connection.

Balls. The public masked balls given weekly during Lent (see announcements in newspapers and placards) are among the most striking and extravagant of the peculiar institutions of Paris. These '*bals masqués*' begin at midnight and last till dawn. The most im-

portant are those in the Opera House (admission for gentlemen 20, ladies 10 fr.; ladies in masks, gentlemen in masks or evening costume). Visitors with ladies had better take a box. During the Carnival a *Bal des Artistes* takes place in the Grand Opéra, and masked balls are held in the *Casino de Paris* (p. 33) during the Carnival (gentlemen 10, ladies 5 fr.).

SALLES DE DANSE. The 'balls', which take place all the year round at these public dancing-rooms, may be regarded as one of the specialties of Paris. Many of these entertainments, however, have for some years past been to a great extent 'got up' for the benefit of strangers, numbers of the supposed visitors being hired as decoys by the lessee of the saloon. It need hardly be said that ladies cannot attend these balls.

Since the discontinuance of the famous *Jardin Mabille*, the best-known of these places of amusement is the *Elysée Montmartre*, Boul. Rochechouart 80, where balls are held on Sun., Tues., Thurs., and Sat. (adm. 1 or 2 fr. according to the day; see advertisements). — The dances of the *Moulin Rouge*, the *Jardin de Paris* (p. 33), the *Tivoli*, Rue de la Douane 12-16, near the Place de la République, and the *Salle Wagram*, Avenue Wagram, near the Arc de Triomphe, etc., are also popular.

At the *Bal Bullier*, or *Closerie des Lilas*, in the Carrefour de l'Observatoire (Pl G, 19; p. 260), in the Quartier Latin, a famous establishment in its way, the dancing of the students and artisans with their 'étudiantes' and 'ouvrières' is generally of a wild and Bacchanalian character. Here the famous 'cancan' may be seen. Balls on Sat., 'soirées dansantes' on Sun., 'grandes fêtes' on Thurs.; adm. 1 fr. Masked balls during the Carnival.

Horse Races (*Courses*) take place from February to November, at Auteuil (p. 159); Longchamp (p. 159), where the Grand Prix, the chief French race, is decided in May; Chantilly (p. 347); Vincennes (p. 213); La Marche (p. 311); Le Vésinet (p. 314); Enghien (p. 325); Maisons-Laffitte (p. 341); St. Germain (Achères; p. 342); St. Ouen (p. 204), etc. — Members of the English Jockey Club are admitted to all the privileges of the French Jockey Club (see p. 35).

Boating is a favourite summer-recreation of the youthful Parisian, the chief starting-points being Asnières (p. 285), Argenteuil (p. 326), and Bougival (p. 314) on the Seine, and Joinville-le-Pont (p. 213) and Nogent (p. 213) on the Marne. Regattas are frequently held.

Skating is also much practised in Paris, the favourite resort being the artificial ponds in the Bois de Boulogne. There is a *Skating Club*, for which one of the ponds is reserved (see p. 160).

Clubs. The following are the principal clubs of Paris, to most of which strangers are admitted during their stay on the introduc-

tion of a member: *Jockey Club*, Rue Scribe, 1bis; *Cercle National Militaire*, Avenue and Place de l'Opéra; *Cercle National*, Avenue de l'Opéra 5; *Union Artistique (Cercle des Mirlitons)*, Rue Boissy d'Anglas 5; *Nouveau Cercle*, Place de la Concorde 4; *Cercle de l'Union*, Boulevard de la Madeleine 11; *Cercle Artistique-Littéraire*, Rue Volney 7; *Cercle des Beaux-Arts et Franco-Américain*, Place de l'Opéra 4; *Cercle du Commerce et de l'Industrie*, Boul. Poissonnière 14bis; *Sporting Club*, Boul. des Capucines 8; *Cercle de la Presse*, Boul. des Capucines 6; *Yacht Club*, Boul. des Capucines 1bis; *Grand Cercle*, Boul. Montmartre 16; *Cercle Central*, Rue Vivienne 36; *Cercle Agricole*, Boul. St. Germain 284; *Cercle de la Librairie*, Boul. St. Germain 117; *Alpine Club*, Rue du Bac 30; *Cercle des Chemins de Fer*, Rue de la Michodière 22; *Cercle Commercial du Louvre*, Place du Louvre 3. Gaming is practised extensively in most of the clubs.

11. Shops and Bazaars.

Shops. With the exception of the houses in the aristocratic Faubourg St. Germain, there are few buildings in Paris which have not shops on the ground-floor. The most attractive are those in the Boulevards, especially towards the W. end, in the Palais-Royal, the Rue de la Paix, Avenue de l'Opéra, Passage Jouffroy, Passage des Panoramas, Rue Vivienne, and Rue de Rivoli.

A few of the best and most respectable of the innumerable and tempting 'magasins' of Paris are here enumerated. The prices are generally somewhat high, and not always fixed, especially when the purchaser is not thoroughly versed in French. Strangers should avoid shops in which 'English spoken' is announced, as the English-speaking shopman is almost always 'temporarily absent', and the use of English only invites an attempt to fleece the foreigner. Those shops which announce a *Vente Forcée* or *Liquidation* should also be avoided. Those are most satisfactory in which the price of each article is marked on it in plain figures.

'ARTICLES DE VOYAGE': *Bazar du Voyage*, Avenue de l'Opéra 3; at several other establishments in the same street, and at the *Bazaars*.

BONNETS, LADIES': *Viro*, Rue de la Paix 12; *Mme. Ode*, Rue du Quatre-Septembre 8; *Grande Maison de Modes*, Boul. Poissonnière 7. — Straw hats: *Au Palmier*, corner of the Rues de Richelieu and du Quatre-Septembre.

BOOKSELLERS (reading-rooms, etc.), see p. 40.

BOOTMAKERS (*bottier, cordonnier*; boots and shoes, *chaussures*): *Tucker*, Avenue de l'Opéra 6; *Roche*, Rue Vivienne 16; *Delail*, Passage Jouffroy 46; *Bacquart*, Passage Jouffroy 35. — For Ladies: *Pinet*, Rue de Paradis-Poissonnière 44; *Tucker* (see above); *Ferry*, Rue Scribe 11 and Rue Auber 2; *Chapelle*, Rue de Richelieu 85. — Ready-made boots and shoes may be procured in almost every street; *Au Prince Eugène*, Rue de Turbigo 29; *Fretin*, Rue de Rennes 64, etc.

BRONZES (*bronzes d'art*): *Barbedienne*, Boul. Poissonnière 30; *Thiébaud*, Avenue de l'Opéra 32; *Colin*, Boul. Montmartre 5; *Susse Frères*, Place de la Bourse 31. See also Leather wares.

CARPETS (made at Aubusson): *Braquenié*, Rue Vivienne 16; *Sallandrouze*, Boul. Poissonnière 23.

CHEMISTS AND DRUGGISTS: *Pharmacie Normale*, Rue Drouot 19; *Ferré*, Rue de Richelieu 102; *Arnaud*, Rue Montmartre 141; *Tanret*, Rue Basse-du-Rempart 64; *Pharmacies Homéopathes*, Rue St. Honoré 352, near the Place Vendôme, Rue du Helder, and Boul. Haussmann 17; *Béral*, Rue de la Paix 14; *Hogg*, Rue Castiglione 2; *Swann*, Rue Castiglione 12; *Roberts & Co. (Shorthose)*, Rue de la Paix 5 (the last four are English).

CHINA, see Glass.

CHOCOLATE: *Compagnie Coloniale*, Aven. de l'Opéra 19; *Compagnie Française*, Rue Ste. Anne 4 (Avenue de l'Opéra); *Marquis*, Passage des Panoramas 57-59, Rue Vivienne 44, and Boul. des Capucines 39; *Lombart*, Boul. des Italiens 11; *Masson*, Boul. de la Madeleine 9, Rue de Rivoli 91, and Rue du Louvre 8; *Guérin-Boutron*, Boul. Poissonnière 29; *Devinck*, Rue St. Honoré 175 and Rue de Lafayette 76; *Potin*, see Delicacies. *Suchard's*, *Ménier's*, *Lombart's*, and *Ibied's* chocolates are sold at many other shops.

CIGARS. The manufacture and sale of tobacco ('caporal ordinaire' and 'supérieur') and cigars is a monopoly of government. The shops, called *débîts de la régie*, are distinguished by their red lamps. The prices and quality are the same everywhere. Good imported cigars (30 c. each, and upwards) can only be purchased at the principal dépôt, Quai d'Orsay 63, at the Place de la Bourse 15, and at the Grand-Hôtel. The home-made cigars usually smoked are the *Bordelais* at 5 c. each, *Étrangers* at 10 c., *Médianitos* at 20 c., *Régalias* at 25 c., and *Londrès* at 30 c.; there are also *Conchas* sold at 1 fr. 60 c., and *Londrès extra* at 2 fr. 10 c. per packet of six. Cigarettes 2-5 c. each. Good Oriental tobacco and cigarettes are to be had at Boul. des Italiens 32. Passers-by may avail themselves of the light burning in every tobacco-shop without making any purchase.

CLOTHING, see Tailors, Milliners, etc.

CONFECTIONERS, see p. 19.

CONFISEURS (comp. p. 19): *Boissier*, Boul. des Capucines 7; *Gouache*, Boul. de la Madeleine 17; *Siraudin & L. Marquis*, Place de l'Opéra 3 and Boul. des Capucines 17; *Bonnet*, Rue Vivienne 31; *Jourdain*, Rue de la Michodière 2 and Rue St. Augustin 28; *Seugnot*, Rue du Bac 28; *Au Chat Noir*, Rue St. Denis 32. See also Preserved Fruits.

DELICACIES (preserved meats, etc.; *comestibles*): *Chevet*, Palais-Royal (see p. 12); *Corcelet*, Galerie de Valois, also at the Palais-Royal, 103, 104; *Potel & Chabot*, Boul. des Italiens 25 and Rue Vivienne 28; *Lemasson*, Rue Vivienne 22; *Potin*, Boul. de Sébastopol 101, 103; *Jacob*, Rue du Bac 30.

DRAPERY (linen, etc.): *Grande Maison de Blanc*, Boul. des Capucines 6; *May*, Boul. des Italiens 14; *Chemiserie Spéciale*, Boul. de Sébastopol 102; *Longueville*, Rue Vivienne 47; *A la Belle Jardinière* (see p. 39). Also in the Grands Magasins de Nouveautés, etc. (see Haberdashery).

DRESSMAKERS: *Worth*, Rue de la Paix 7; *Pingat*, Rue Louis le Grand 30; *Laferrière*, Rue Taitbout 28 (these three fashionable and expensive); *Husson*, Boul. des Capucines 39; *Mme. Cavalley*, Boul. des Capucines 8; *Mme. Mantel* (Compagnie Lyonnaise), same boul., 37; *Adolphe*, Boul. des Italiens 15; *Mme. Danzel*, Rue Louvois 10; the *Grands Magasins*, see below.

DRUGGISTS, see Chemists.

ELECTRO-PLATE (*ruolz*, *alfénide*): *Christofle & Cie.*, Boul. des Italiens 33; *Alfénide*, Boul. de Sébastopol 40; *A la Ménagère*, Boul. Bonne-Nouvelle 20.

ENGRAVINGS (*estampes*, *gravures*) AND **PHOTOGRAPHS**: *Goupil & Cie.*, Boul. Montmartre 19, and Place de l'Opéra 2; *Braun*, Avenue de l'Opéra 43 (photographs of paintings; comp. p. 114); *Martinet*, Boul. des Capucines 12, at the Grand-Hôtel, and Rue de Rivoli 172; *Hautecoeur*, Avenue de l'Opéra 35 (views of Paris); *A la Bibliothèque Nationale*, Rue Vivienne 8.

FANCY ARTICLES, see 'Articles de Voyage', Toy-shops, Bronzes, Leather; also Bazaars (p. 38).

FURRIERS: *Revillon*, Rue de Rivoli 79; *Lachnitt*, Rue St. Honoré 165; *Compagnie Russe*, Rue de la Chaussée-d'Antin 26; *Grands Magasins de Nouveautés*, etc.

GLASS (porcelain, etc.): *Boutigny*, Passage des Princes 5 bis (Boul. des Italiens), Galerie Montpensier 21 & 22, and Galerie de Chartres 24-26 (Palais-Royal); *Grand Dépôt*, Rue Drouot 21. Also several shops in the Rue Paradis (Pl. B, 24; III).

GLOVERS (glove, *le gant*; kid glove, *gant de chevreau* or *de peau de chevreau*, or *de peau*): *Jouvin*, Place de l'Opéra 3; *A la Petite Jeannette*, Boul. des Italiens 3 (English ties, hosiery, etc.); *Au Carnaval de Venise*, Boul. de la Madeleine 3 (English goods); *Persin*, Passage Jouffroy 32; *Au Roi d'Yvetot*, Pass. Jouffroy 31.

GOLDSMITHS AND JEWELLERS: very numerous and tempting, especially in the Rue de la Paix and the Palais-Royal. All genuine gold and silver articles bear the stamp of the Mint. — *Imitation Jewellery* is best obtained in the shops of the Palais-Royal.

HABERDASHERY ('Nouveautés', etc.). The *Grands Magasins de Nouveautés*, large establishments for the sale of all kinds of materials for ladies' dress, haberdashery, laces, etc., form a very important feature of modern Paris, and owing to the abundant choice of goods they offer are gradually superseding the smaller shops. The largest of these establishments, containing an immense selection of goods, is the *Grands Magasins du Louvre*, in the Place du Palais-Royal (Pl. R, 20; II; p. 55), with reading and writ-

ing rooms, and a buffet where refreshments are dispensed gratis. Nearly as large is the *Bon Marché*, Rue du Bac 135 and 137, and Rue de Sèvres 18-24 (Pl. R, 16; IV), rather distant from the centre of the town, and somewhat cheaper than the Magasins du Louvre. Of a similar character are: *Au Printemps*, at the corner of the Boul. Haussmann and the Rue du Havre; *Au Gagne-Petit*, Avenue de l'Opéra 21-23; *Au Petit St. Thomas*, Rue du Bac 27-35; *A la Ville de St. Denis*, Rue du Faubourg-St. Denis 91-95; *Pygmalion*, corner of the Rues St. Denis and de Rivoli, and Boul. de Sébastopol 9-13. The prices affixed to articles in the windows and at the doors of these establishments are often no criterion of those charged within.

Similar to these Grands Magasins de Nouveautés are the *BAZAARS*, at which all kinds of household requisites and luxuries may be obtained. Among the most attractive are *A la Ménagère*, Boul. Bonne-Nouvelle 20; the *Galerie Orientale*, Boul. Montmartre 12, to the left of the Passage Jouffroy; *Bazar de l'Hôtel-de-Ville*, Rue de Rivoli 54; *Bazar de la Rue d'Amsterdam*, to the right of the Gare St. Lazare.

HAIRDRESSERS in almost every street. — 'Taille de cheveux' 30-50 c., 'coup de fer' (curling) 25-50 c., 'pour faire la barbe' 20-30 c., 'friction' (washing the hair) 50 c. — Three good 'coiffeurs' for ladies are *Auguste*, Rue de la Paix 7; *Lecomte*, same street 13; and *Clémentel*, Rue de Castiglione 8.

HATTERS (*chapelières*): *Delion*, Passage Jouffroy 21 and 25; *Berteil*, Rue du Quatre-Septembre 10, Rue de Richelieu 79, and Boulevard St. Germain 134; *Gibus* (inventor of the folding hat), Rue Vivienne 20; *Pinaud & Amour*, Rue de Richelieu 89; *Bravard*, Boul. St. Michel 45; *A la Belle Jardinière* (p. 39).

HOSIERS AND SHIRTMAKERS. *Grande Maison de Blanc*, Boul. des Capucines 6; *May*, Avenue de l'Opéra 34; *Chemiserie Spéciale*, Boul. de Sébastopol 102. See also Glovers.

JEWELLERS, see Goldsmiths.

LEATHER WARES (*maroquinerie*): *Klein*, of Vienna, Boul. des Capucines 6, novelties of Paris and Vienna, bronzes and objects of art; *Boudel*, Boul. des Capucines 43. See also 'Articles de Voyage'.

MUSIC: *Au Ménestrel*, Rue Vivienne 2 bis; *Brandus*, Rue de Richelieu 103 (music on hire); *Girod*, Boul. Montmartre 16.

MUSICAL INSTRUMENTS. Pianos: *Erard*, Rue du Mail 13; *Pleyel-Wolff*, Rue Rochechouart 22; *Herz*, Rue St. Lazare 20; *Baudel*, Rue Favart 20. — Organs: *Cavaillé-Coll*, Avenue du Maine 5; *Merklin*, Rue Delambre 22. — Harmoniums: *Alexandre*, Rue de Richelieu 106. — Stringed Instruments: *Gand & Bernardel*, Passage Saulnier 4; *Collin*, Faubourg Poissonnière 10; *Martin*, Boul. St. Martin 4; *Lamy*, Rue Réaumur 68.

OPTICIANS (spectacles, *des lunettes*; opera-glass, *une lorgnette*, or *des jumelles*; eye-glasses, *un lorgnon* or *binocle*): *Chevalier*, Ga-

lerie de Valois 158 (Palais-Royal); *Bunoust*, Gal. de Valois 131; *Lafontaine*, Galerie Montpensier 18; *Soleil*, Gal. Vivienne 21, 23; *Fischer*, Rue de la Paix 7; *Cerf*, Boul. des Italiens 18; *Derogy*, Quai de l'Horloge 33.

PERFUMERY: *Société Hygiénique*, Rue de Rivoli 55, Boul. de la Madeleine 19, and numerous branch-depôts; *Piver*, Boul. de Strasbourg 10, Place Vendôme 28, and Rue Vivienne 29; *Violet*, Boul. des Italiens 29; *Pinaud*, Boul. de Strasbourg 37; *Gellé Frères*, Avenue de l'Opéra 6; *Rimmel* (English), Boul. des Capucines 9; *Guerlain*, Rue de la Paix 15; *Agnel*, Avenue de l'Opéra 16, Rue du Quatre Septembre 2, Boul. des Capucines 21, Boul. Malesherbes 31 & 83, and Rue Auber 9; *Botot*, Rue de la Paix 17, and Rue St. Honoré 229; *Bully* (vinaigre de toilette), Rue Montorgueil 67; *Stephen & Lucca* (English), Avenue de l'Opéra 14; *Lubin*, Rue Ste. Anne 55.

PHOTOGRAPHERS: *Tourtin*, Boul. des Italiens 8; *Morgan*, same boul., 29; *Mulnier*, same boul., 25; *Braun*, Rue Louis le Grand 18; *Boyer*, Boul. des Capucines 35; *Pierre-Petit*, Place Cadet 31; *Reutlinger*, Boul. Montmartre 21; *Van Bosch*, same boul. 10; *Chalot*, Rue Vivienne 18; *Nadar*, Rue d'Anjou 51; *Liebert*, Rue de Londres 6; *Waléry*, same street, 9^{bis}; *Pirou*, Rue Royale 23 and Boul. St. Germain 5. — For sellers of photographs, see Engravings.

PORCELAIN, see Glass.

PRESERVED MEATS, see Delicacies.

PRESERVED FRUITS: (*fruits confits*, *chinois blonds*, *marrons glacés*, etc.): *Callu*, Rue St. Honoré 43; *Debrun*, Rue Montmartre 58; *Jourdain*, Rue de la Michodière 2, and Rue St. Augustin 28; *Seugnot*, Rue du Bac 28; and at most of the '*Confiseurs*' (p. 36). The usual price is 5 fr. per kilogramme.

SHAWLS, CASHMERE: *Compagnie des Indes*, Rue de Richelieu 80, and at the *Grands Magasins de Nouveautés*.

SILK MERCERS: *Louvet*, Rue Vivienne 10; at the *Grands Magasins de Nouveautés* (p. 37).

TAILORS: *J. Dusautoy*, Boul. des Capucines 8, expensive; *Renard*, Boulevard des Italiens 2; *Blanc*, same boulevard, 12; *A. Dusautoy*, same boul., 14; *Laurent Richard*, same boul., 18; *Sordelli*, Avenue de l'Opéra 39; *Janssens & Morlen*, Galerie d'Orléans 33-39 (Palais-Royal); *Van Roey*, Rue du Bac 11. — For children: *Vivier*, Boul. des Italiens 28; *Au Petit Prodige*, same boulevard, 38. — READY-MADE CLOTHING: *A la Belle Jardinière*, Rue du Pont-Neuf 2; *Coutard*, Boul. Montmartre 4; *Old England*, Boul. des Capucines 12; *Maison de l'Opéra*, Avenue de l'Opéra 20.

TOBACCO, see Cigars.

TOY SHOPS: *Au Nain Bleu*, Boul. des Capucines 27; *Aux Enfants Sages*, Pass. Jouffroy 13-17; *Gillard*, Gal. Vivienne and Rue des Petits-Champs 4; *Au Paradis des Enfants*, Rue de Rivoli 156, and Rue du Louvre 1; *Magasin des Enfants*, Passage de l'Opéra.

TRAVELLING REQUISITES, see 'Articles de Voyage'.

WATCHMAKERS: *Leroy et Cie.*, Galerie Montpensier 13, Palais-Royal; *Rodanet*, Rue Vivienne 36; *Bréguet*, Rue de la Paix 12; *Au Nègre*, Boul. St. Denis 19.

WINES AND LIQUEURS: *Société Œnophile*, Rue Montmartre 161, near the boulevard, with several agencies; *Compagnie des Grands Vins de Bourgogne*, Rue Royale 6; *Aux Caves de la Couronne*, Rue de la Paix 6, Boul. Malesherbes 44, Boul. de Sébastopol 60, and Rue du Bac 86; *Caves du Grand Hôtel*, Boul. des Capucines; *Roe-derer & Cie.*, Rue de Lafayette 44; *Moët & Chandon*, Place de l'Opéra 8; *Bordier Fils*, Avenue Montaigne 6; *Veuve Cliquot-Ponsardin*, Rue Taitbout 5; *Bodega* (Spanish wines), Rue Castiglione 1 (Hôtel Continental). See also *Delicacies*, etc.

Those who desire to transmit purchases direct to their destination should procure the services of a goods-agent (see p. 26).

12. Booksellers. Reading Rooms. Libraries. Newspapers.

Booksellers. *Galignani's Library*, Rue de Rivoli 224, an old establishment with a large assortment of English and American books. *Galignani's Messenger*, the well-known English paper, is published here. This daily journal (20 c.), which has been in existence for 70 years, contains an excellent summary of political and commercial news, the latest information from England, the United States, and the whole of the Continent, and a list of the principal sights and amusements of Paris. It gives a daily list of English and American visitors in Paris, and another on Fridays of English and American visitors to the chief cities of Europe. The English and American places of worship (p. 44) are enumerated every Saturday. — The *American Register* is an American journal of a similar kind, published every Saturday (price 30 c.). — A European edition of the *New York Herald*, most of the contents of which are telegraphed from New York, appears every morning (15 c.). — Other English and American booksellers: *Neal*, Rue de Rivoli 248; *Brentano's*, Avenue de l'Opéra 17.

Ollendorff, Rue de Richelieu 28^{bis} (general agent for Baedeker's Handbooks); *Truchy*, Boulevard des Italiens 26; *Nilsson*, Rue de Rivoli 212, English books. — *Vieweg*, Rue de Richelieu 67; *C. Klincksieck*, Rue de Lille 11; *Ghio*, Palais-Royal, Galerie d'Orléans 17; these chiefly for French and German literature. — *Haar & Steinert*, Rue Jacob 9, and *Le Soudier*, Boul. St. Germain 174, for German books. — *Librairie Nouvelle* (Lévy), Boul. des Italiens 15; *Marpon & Flammarion*, Boul. des Italiens 40, Boul. St. Martin 8, and Galeries de l'Odéon, etc.; *Arnaud & Labat*, Palais-Royal; *Dentu*, Avenue de l'Opéra 36. Rare books: *Fontaine*, Passage des Panoramas 35; *Morgand*, same passage, 55. For the addresses of other 'libraires-éditeurs', consult the Directory of Paris (p. 49). — The famous house of *Hachette & Cie.* is in the Boul. St. Germain (No. 79).

Reading Rooms. Reading-room of the *New York Herald*, Avenue de l'Opéra 49 (adm. 25 c. per day, 4 fr. per month), well supplied with American, English, and French newspapers, and frequented by ladies. — *Salon Littéraire*, in the Passage de l'Opéra (N. side of the Boul. des Italiens), Galerie du Baromètre 11 and 13, French, German, and English newspapers; adm. 30 c., per week 2 fr., fortnight 3½ fr., month 6 fr.; open 9 a.m. to 11 p.m. — *Salons de Lecture* of the same kind at the *Librairie de Paris*, Boul. Montmartre 20. — On the left bank of the Seine: Rue Casimir Delavigne 10, near the Odéon; Rue de la Sorbonne 6.

These reading-rooms are convenient places for letter-writing. Materials for the purpose may also be procured at any of the cafés.

Circulating Libraries. *Neal*, Rue de Rivoli 248 (English books); *Voreaux*, Rue Chauveau-Lagarde 14 (2 fr. per week, 6 fr. per month); *La Lecture Universelle*, Rue des Moulins 5, etc. (15 c. per vol., 1½-3 fr. per month, 5-32 fr. per annum); *Bibliothèque Cardinal*, Rue de Rennes 51.

Newspapers. The oldest Parisian newspaper is the 'Gazette de France', which was founded in 1631. No fewer than 150 new journals appeared in 1789, 140 in 1790, and 85 in 1791, but most of these were suppressed at various times by government, Napoleon finally leaving only thirteen in existence. On the restoration of the monarchy about 150 newspapers and periodicals were published, but only eight of these concerned themselves with political matters. Since then the number has been constantly on the increase, and now amounts to 1550. The political papers number about 70, and are sold in the streets or at the 'kiosques' in the Boulevards (p. 69).

The larger papers cost 10, 15, or 20 c., the smaller 5 c. — *Galignani's Messenger* and the *American Register*, see p. 40.

MORNING PAPERS. Republican: *Le Journal des Débats* (20 c.; one of the best Parisian papers); *La République Française*; *Le Siècle*; *Le XIX^e Siècle*; *L'Événement*; *Le Voltaire*; *Le Rappel*; *La Justice*; *Le Mot d'Ordre*; *L'Intransigeant* (Henri Rochefort); *Le Radical*; *Le Cri du Peuple*; *Le Petit Journal* (circulation of 1,200,000); *La Petite République*; *La Lanterne*; *La Paix*; *Le Petit National*; *Le Gil Blas* (the Republican 'Figaro'). — Royalist: *Le Gaulois*; *Le Soleil*; *Le Petit Moniteur*. The *Figaro*, the most widely circulated of the larger papers (80-100,000), may also be called Royalist, but is rather a witty literary sheet than a serious political journal. — Bonapartist: *L'Autorité* (Paul de Cassagnac). — Unclassified: *Le Matin*; *Le Journal Officiel*.

EVENING PAPERS. Republican: *La France*; *Le Temps* (well edited and influential); *Le National*; *Le Soir*; *Le Télégraphe*; *Le Courrier du Soir*; *L'Echo de Paris*. — Royalist: *La Gazette de France*; *L'Univers* (Ultramontane); *Le Monde* (clerical); *Le Moniteur Universel*. — Bonapartist: *La Patrie*; *Le Pays*. — Unclassified: *La Liberté*.

REVIEWS AND PERIODICALS: *La Revue des Deux Mondes*; *La Revue Britannique*; *La Nouvelle Revue*; *La Revue Bleue* (political and literary); *Les Lettres et les Arts*; *Le Moniteur Scientifique*; *La Nature*; *La Revue Indépendante*.

ILLUSTRATED JOURNALS: *L'Illustration*; *L'Univers Illustré*; *Le Monde Illustré*; *Le Journal Amusant*; *Le Journal pour Rire*; *Le Charivari*; *La Vie Parisienne*; *Le Journal Illustré*. Most of these are issued weekly.

English, German, and other Foreign Journals are sold in the kiosques near the Grand-Hôtel and in some others on the principal boulevards.

Strangers desiring to learn French or other languages will find ample facilities at the *Institut Rudy* or *Association Internationale des Professeurs*, where a course of three lessons per week costs 10-15 fr. a month. Private lessons are also given. The headquarters of the association are at Rue Royale 7, and it has a branch-establishment at Rue de l'Odéon 12. The *Institut Polyglotte*, Rue de la Grange-Batelière 16, is a similar establishment. The addresses of private teachers may be obtained from Galignani and the other booksellers.

13. Baths. Physicians. Maisons de Santé.

Baths. WARM BATHS in the floating establishments on the Seine, and in many others in different parts of the town. Charge from 50 c. to 1 fr., an additional charge being made for towels. *De la Samaritaine*, below the Pont-Neuf, right bank (Pl. R, 20; III); *des Tuileries*, near the Pont-Royal, same side; *de Diane*, Rue Volney 5; *Vivienne*, Rue Vivienne 15; *Ste. Anne*, Rue Ste. Anne 63 and Passage Choiseul 58; *de Jouvence*, Boul. Poissonnière 30 and Rue du Faubourg-Montmartre 4; *de la Chaussée d'Antin*, Chaussée d'Antin 46; *Ventadour*, Rue des Petits-Champs 48; *de la Madeleine*, Rue du Faubourg-St. Honoré 30, and Rue Boissy-d'Anglas 35 (80 c.-3 fr.); *Taranne*, Boul. St. Germain 180; *Racine*, Rue Racine 12.

TURKISH, VAPOUR, and other baths: *Le Hammam*, Rue des Mathurins 18, corner of the Rue Auber (entrance for ladies, Boul. Haussmann 47), very handsomely fitted up (Turkish bath 5 fr.); *Le Baumeum*, Rue Cadet 16^{bis}, of the same category (2 fr.); *Hammam Monge*, Rue Cardinal-Lemoine 63, on the left bank (bath 1½-2½ fr.), etc. — **BAINS GUERLOIS**, Rue du Bourg-l'Abbé 7. — **BAINS DE L'UMIGATIONS**, Rue de Dunkerque 5-6. — **COMPRESSED AIR BATHS** (*Bains d'Air Comprimé*), Rue des Pyramides 17.

COLD BATHS in the Seine: *Deligny*, Quai d'Orsay, near the Place de la Concorde (Pl. R, 14, 15; II), admirably fitted up, more than 325 ft. long, with 350 separate baths; *du Pont-Royal* (entered from the Quai Voltaire); *Henri IV.* (entrance near the statue on the Pont-Neuf); *Ouarnier*, Quai de Béthune (Ile St. Louis; Pl. R, 22; V), recommended to ladies also; *Bains des Fleurs*, Quai de la Mégisserie, to the right of the Pont-Neuf, for ladies also.

The usual charges at these cold baths are: admission 20-60, swimming-drawers and towel 25, fee to the 'garçon' 10 c. — It should be observed that one-half of each bath is generally very shallow, being intended for non-swimmers, while the other half is often not more than 6-9 ft. in depth. Divers should therefore use great caution.

Physicians. Should the traveller require medical advice during his stay in Paris, he should obtain from his landlord the name of one of the most eminent practitioners in the neighbourhood of his hotel or lodgings. Information may also be obtained at the English and other chemists' shops (p. 36), or at *Galignani's* (p. 40). As changes of address are not infrequent, the '*Bottin*', or Directory,

may also be consulted. Usual fee from 10 to 20 fr. per visit or consultation. The following may be mentioned: —

Dr. Anderson, Avenue de la Grande-Armée 8; *Dr. Chapman*, Rue de Rivoli 224; *Dr. Herbert*, Rue Duphot 18; *Dr. Barnard*, Rue St. Honoré 362; *Dr. Faure Miller*, Rue Matignon 28; *Dr. Dupuy*, Avenue Montaigne 53; *Dr. Loughnan*, Rue de Berri 38; *Dr. MacGavin*, Rue St. Philippe-du-Roule 4; *Dr. Jennings*, Rue Marbeuf 33; *Dr. Warren* (American), Rue Caumartin 15; *Dr. Clarke*, Rue de Suresne 17; *Dr. Prendergast*, Boul. Malesherbes 36; *Dr. Austen*, Rue Cambon 42.

OCULISTS: *Dr. Loubrieu*, Rue de Rivoli 50; *Dr. Meyer*, Boul. Haussmann 73; *Dr. Sichel*, Rue Chaptal 17; *Dr. de Wecker*, Avenue d'Antin 31; *Dr. Bull*, Rue de la Paix 4.

DENTISTS: *Adler*, Avenue de l'Opéra 16; *Hy. Didsbury*, Rue Meyerbeer 3; *J. Didsbury*, Rue de la Paix 10; *Dugit*, Rue du 29 Juillet 6; *Duchesne fils*, Rue de Lafayette 45; *J. Evans*, Avenue de l'Opéra 19; *T. W. Evans*, Rue de la Paix 15; *George*, Rue de Rivoli 224; *Luis*, Boul. des Italiens 25; *Miller*, Rue Vignon 15; *Neech Watson*, Rue Basse-du-Rempart 64; *Préterre*, Boul. des Italiens 29; *Rogers*, Rue St. Honoré 270; *Rossi-Hartwich*, Rue St. Honoré 185; *Ryan*, Rue Royale 25; *Seymour*, Rue Castiglione 10; *Ward*, Avenue de l'Opéra 35; *Warde*, Rue du Faubourg-Montmartre 47; *Weber*, Rue Duphot 25; *Wilkie*, Rue Halévy 14.

CHEMISTS AND DRUGGISTS, see p. 36.

Hospitals. Maisons de Santé. In case of a serious or tedious illness, the patient cannot do better than take up his quarters at one of the regular sanitary establishments. There are many well-conducted houses of the kind in Paris and the environs, where patients are received at from 150 to 1000 fr. per month, including board and lodging, medical attendance, baths, etc., and where drawing-rooms, billiard-tables, gardens, etc., as well as good tables d'hôte, are provided for convalescents. The following may be recommended: — *Maison Municipale de Santé* (Dubois), Rue du Faubourg St. Denis 200 (terms 4-15 fr. per day, everything included); *Maison des Hospitaliers de St. Jean-de-Dieu*, Rue Oudinot 19; *Etablissement Hydrothérapique d'Auteuil*, Rue Boileau 12; *Maison Rivet*, at St. Mandé, Grande Rue 106, for ladies.

The ***HERTFORD BRITISH HOSPITAL**, or *Hospice Wallace* (Pl. B, 8), is a large Gothic edifice in the Rue de Villiers, at Levallois-Perret, near Neuilly, built and endowed by Sir Richard Wallace. It has accommodation for between thirty and forty patients, and is surrounded by a large garden. — Mention may also be made of the Protestant *Hospice Suisse* (for men; apply at the Swiss Embassy, Rue Cambon 4) and the *Maison des Diaconesses Protestantes* (for ladies), Rue de Reuilly 95.

The *Institut Pasteur*, for the treatment of hydrophobia, is at Rue Dutot 25 (Pl. G, 13).

14. Divine Service.

English Churches. For the latest information, visitors are recommended to consult the *Stranger's Diary* of the Saturday number of *Galignani's Messenger* (p. 40). At present the hours of service are as follows: —

EPISCOPAL CHURCH: — *English Church*, Rue d'Aguesseau 5, Faubourg St. Honoré, near the English Embassy; services at 11, 3.30, and 8. — *English Church*, Rue Boissy-d'Anglas 35; services at 7, 8.30, 10, 11, 3.30, and 8. — *Christ Church*, Boul. Eugène 33 and Boul. Bineau 49, Neuilly; services at 10.30 and 4. — *Church of England*, Rue des Bassins 5 (Avenue d'Iéna); services at 10.30, 3, and 8. — *Church of the Holy Trinity* (Amer.), Avenue de l'Alma 19; services at 9, 11, and 4.

ENGLISH CONGREGATIONAL CHAPEL, Rue Royale 23; services at 11.15 and 7.30.

ENGLISH ROMAN CATHOLIC CHURCH: *Eglise St. Joseph*, 50 Avenue Hoche or de la Reine-Hortense, mass at 6, 7, 8, 9, 10, and 11.30, on Sundays; sermons at 10.30 and 3.

AMERICAN CHAPEL, Rue de Berri 21; service at 11 a.m.

CHURCH OF SCOTLAND, Rue Bayard 17, Champs-Élysées; services at 11 and 3.15.

WESLEYAN METHODIST CHURCH, Rue Roquépine 4, adjoining No. 41 Boulevard Malesherbes, near the Madeleine. Service on Sundays at 11, 4 (in German), and 7.30, on Wednesdays 8 p.m. — Also at Asnières, near the railway-station.

BAPTIST CHAPEL: Rue de Lille 48; English service at 11.30.

French Protestant Churches (Temples Protestants). **CALVINIST:** *L'Oratoire*, Rue St. Honoré 149; service at noon. — *St. Marie*, Rue St. Antoine 216, near the Bastille; service at noon. — *Temple de l'Etoile*, Avenue de la Grande-Armée 54; services at 10 and 4. — *Temple des Batignolles*, Boul. des Batignolles 46; service at 10 a.m. — *Pentemont*, Rue de Grenelle 106 (noon). — *St. Esprit*, Rue Roquépine 5 (10 a.m.). — *Temple de Passy*, Rue des Sablons 65 (10 a.m.). — *Temple de Neuilly*, Rue du Marché 17 (10.30 a.m.).

LUTHERAN (Confession d'Augsbourg): *Temple des Billettes*, Rue des Archives 18, to the N. of the Hôtel de Ville; service at 12 in French, at 2 in German. — *Temple de la Rédemption*, Rue Chauchat 16; service in German at 10, in French at 12.

FREE (Libres): *Eglise Taitbout*, Rue de Provence 42; service at 10 a.m. — *Eglise du Nord*, Rue des Petits-Hôtels 17; service at 10 a.m. — *Chapelle St. Honoré*, Rue Royale 23 (10 a.m. and 3 p.m.). — *Chapelle du Luxembourg*, Rue Madame 58 (10.30 a.m. and 8 p.m.).

Synagogues: Rue Notre-Dame-de-Nazareth 15; Rue de la Victoire 44 (a handsome edifice); Rue des Tournelles 21, near the Place des Vosges; Rue Buffault 28 (Portuguese).

Missions. For those interested in home mission work the following notes may be of service. The *McAll Mission* has now between 30 and

40 stations, of which the most important are at Boul. de Sébastopol 10 and Boul. Bonne-Nouvelle 8; meetings every week-day at 8 p.m. Sunday meetings at 8.15 p.m. at Rue du Faubourg St. Antoine 142 and Rue Letailier 59 (Grenelle). Mr. McAll's address is Villa Molitor 28, Auteuil. — *Miss de Broen's Mission*, Rue Bolivar, Belleville, and Rue Clavel 25; meetings every evening and on Sun. at 3.30 and 8.30 p.m. Dispensary on Mon., Tues., Thurs., and Frid., at 10 a.m. — *The Home for English Girls*, Avenue de Wagram 77, is a most deserving and interesting institution. — *Comité Parisien de la Mission Intérieure*: sec., Mr. G. Meyer, Rue Boulainvilliers 43.

15. Embassies. Ministerial Offices. Banks.

Embassies. The following are the present addresses, but a change of residence sometimes takes place: — The offices are generally open from 1 to 3.

Austria, Rue de Varenne 57. — Consulate, Rothschild's, Rue Laffitte 21.

Belgium, Rue Bizet 6 (Avenue Marceau).

Brazil, Rue de Téhéran 17.

Denmark, Rue de Courcelles 29. — Consulate, Rue d'Hauteville 53.

Germany, Rue de Lille 78 (12-1 $\frac{1}{2}$). — Consulate, Rue Goethe 7.

Great Britain, Rue du Faubourg-St. Honoré 39 (11-3).

Greece, Rue Pierre Charon 46. — Consulate, Rue Taitbout 20.

Italy, Rue de Penthièvre 11. — Consulate, Rue Vezelay 4.

Netherlands, Rue La Pérouse 21 (also consulate).

Russia, Rue de Grenelle 79.

Spain, Boul. de Courcelles 34. — Offices and consulate, Rue Bizet 6.

Sweden and Norway, Rue Bassano 12. — Consulate, Rue Pasquier 15.

Switzerland, Rue Cambon 4.

United States of N. America, Rue Galilée 59 (11-3). — Consulate, Avenue de l'Opéra 36.

Turkey, Rue de Presbourg 10. — Consulate, Place St. Ferdinand 31.

Ministerial Offices. *Affaires Etrangères*, Rue de l'Université 130. *Agriculture*, Rue de Varenne 78.

Commerce, Industrie, Postes et Télégraphes, Rue de Varenne 80 and Rue de Grenelle 99-105.

Finances, at the Louvre, Rue de Rivoli (Pl. R. 20; II).

Guerre, Boul. St. Germain 231.

Instruction Publique et Beaux-Arts, Rue de Grenelle 110.

Intérieur, Rue Cambacérès 7-13; Rue de Grenelle 103; Rue de l'Université 176.

Justice et Cultes, Place Vendôme 11 and 13; office at the back, Rue Cambon 36.

Marine et Colonies, Rue Royale 2.

Travaux Publics, Rue de Grenelle 244 & 248.

Some of these offices are open to the public, but the hours of admission are frequently changed.

Banks. *Banque de France*, Rue de la Vrillière and Rue Croix des Petits-Champs (Pl. R. 21; II); *Caisse des Dépôts et Consigna-*

tions, Rue de Lille 56 (Pl. R, 17; II, IV); *Caisse d'Epargne*, Rue Coq-Héron 9 (Pl. R, 21; III); *Crédit Foncier*, Rue des Capucines 17 and 19 (Pl. R, 18); *Crédit Lyonnais*, Boulevard des Italiens 15-21, with 22 agencies; *Société Générale*, Rue de Provence 54 and 56, with 32 agencies; *Crédit Mobilier*, Place Vendôme 15; *Comptoir National d'Escompte*, Rue Bergère 17 (Pl. B, 21; III); *Rothschild*, Rue Laffitte 21-25.

MONEY CHANGERS (*changeurs*) are found in almost every part of Paris, particularly in the Palais-Royal, near the Exchange, the Boulevards, the Rue Vivienne, and the other streets frequented by strangers. That at the *Crédit Lyonnais* (see above) may be recommended.

16. Topography. Preliminary Drive.

Nothing is better fitted to make the traveller feel at home in the labyrinths of a great city like Paris, than a good general idea of its topography, derived from a careful description, the study of a good plan, and a preliminary drive through the principal streets. In this section an endeavour is made to supply such a description, and to indicate a suitable course for such a drive, while for all other needful information the reader is referred to the plans at the end of the Handbook.

Paris is situated in 48° 50' N. lat., and 2° 21' E. long., and lies on the river *Seine*, which flows through it from S.E. to S.W., forming a bold curve towards the N. The city occupies a basin of tertiary formation, the borders of which are about 200-300 ft. above the level of the river and 420 ft. above that of the sea. The most elevated points in or adjoining the city are the heights of *Charonne*, *Ménilmontant*, *Belleville* (330 ft.), *la Villette*, and *Montmartre* (420 ft.) on the right bank of the *Seine*, and those of *la Maison Blanche*, the *Butte-aux-Cailles*, and *Ste. Geneviève* (198 ft.) on the left. The length of the part of the *Seine* within the city is about 7 M. It contains two islands of some size, the *Ile St. Louis* and the *Ile de la Cité*, each formed by the union of several islets.

Paris is thus naturally divided into three parts; the quarters on the right bank, the Cité with the island of St. Louis, and the quarters on the left bank. The old distinctions between Old Paris, the Faubourgs, and the Communes Annexées have entirely disappeared amid the great transformations of the past thirty years, during which many of the ancient streets have been destroyed, the main arteries of traffic prolonged to the fortifications, and the whole area covered with large and handsome edifices. The only sensible difference between the various districts now consists in the greater traffic observable in the central quarters. A glance at the Plan will show the limits of OLD PARIS, bounded by the first circle of boulevards, the so-called *Grands Boulevards* (p. 68). It should be noted, however, that on the left bank the old city of Paris extended as far as the boulevards to the S. of the garden of the Luxembourg. Outside the Great Boulevards lie the OLD FAUBOURGS or suburbs,

the names of which are still preserved in those of the chief streets radiating from the centre of the city, and extending to the *Outer Boulevards* (*Boulevards Extérieurs*, p. 69). The Faubourgs themselves are generally named after the corresponding district of the old town. The most important on the right bank, named from E. to W., are the *Faubourgs St. Antoine, du Temple, St. Martin, St. Denis, Poissonnière, Montmartre*, and *St. Honoré*. Those on the left bank are less known, with the exception of the *Faubourg St. Germain*, which from an early period formed part of the old city. The Faubourgs of St. Antoine and the Temple are the great industrial districts, the former being the headquarters of the manufacture of furniture, and the latter of the various fancy articles classed together as 'articles de Paris' (real and imitation jewellery, artificial flowers, toys, articles in leather and carved wood, etc.). The Faubourgs of St. Martin, St. Denis, and Poissonnière are rather commercial than industrial, and form the centre of the wholesale and export trade of the great capital. The streets near the centre of the town, however, particularly the Great Boulevards, contain many of the finest retail shops in Paris. The Faubourg Montmartre and the quarters of the Exchange, the Palais-Royal, and the Opéra are the financial quarters of the town, and also contain nearly all that is necessary for the comfort and entertainment of visitors to Paris. The Faubourg St. Honoré and the Champs-Élysées are occupied by the mansions of the aristocracy of wealth, while the Faubourg St. Germain is more or less sacred to the aristocracy of blood, and contains most of the embassies and ministerial offices. The *Quartier Latin* or *Quartier des Ecoles*, which adjoins the Faubourg St. Germain on the E., owes its name to the fact of its being the seat of the university and of many of the scientific institutions of Paris. It also contains several of the chief libraries.

The principal COMMUNES ANNEXÉES, or outlying districts within the fortifications, but not incorporated with the city till 1860, are the following, enumerated from E. to W.: *Bercy*, carrying on an extensive wine and export trade; *Charonne, Ménilmontant, Belleville, La Villette, La Chapelle*, and *Montmartre*, the principal quarters of the working classes and the seat of the largest workshops; *Les Batignolles*, with the studios of numerous artists and many handsome private houses (on the side next the Park of Monceau); *Passy* and *Auteuil*, with their villas; *Grenelle*, with iron foundries and chemical works; *Vaugirard, Montrouge*, etc., inhabited by persons of moderate means, small shopkeepers, and artisans, and containing numerous large market-gardens.

Paris is estimated to occupy nearly 20,000 acres of which 12,000 are covered with buildings. There are 3750 streets and boulevards and 30 bridges over the Seine.

For administrative purposes Paris is divided into twenty ARRONDISSEMENTS, separated from each other by the principal arteries

of traffic: 1. *Louvre*; 2. *Bourse*; 3. *Temple*; 4. *Hôtel de Ville*; 5. *Panthéon*; 6. *Luxembourg*; 7. *Palais-Bourbon*; 8. *Elysée*; 9. *Opéra*; 10. *Enclos St. Laurent* (between the Rue du Faubourg-Poissonnière and the Rue du Faubourg-du-Temple); 11. *Popincourt* (extending from the Faubourg du Temple to the Faubourg St. Antoine), 12. *Reuilly* (between the Faubourg St. Antoine and the Seine); 13. *Les Gobelins*; 14. *Observatoire*; 15. *Vaugirard*; 16. *Passy*; 17. *Les Batignolles*; 18. *Montmartre*; 19. *Les Bulles-Chaumont*; 20. *Ménilmontant*.

The general appearance of Paris is more uniform than that of most other towns of its size, partly owing to the mixture of classes resulting from the Great Revolution, but principally on account of the vast schemes of improvement carried out in our own days.

The stranger is almost invariably struck by the imposing effect produced by the city as a whole, and by the width, straightness, and admirable condition of the principal streets. Picturesqueness has doubtless been greatly sacrificed in the wholesale removal of the older buildings, but the superior convenience and utility of those spacious thoroughfares is easily appreciated; and the amount of traffic in them proves that their construction was a matter of almost absolute necessity. Most of them, built at the same period and often as a mere building speculation, exhibit an almost wearisome uniformity of style, but in those at a distance from the central quarters considerable variety of taste is often shown.

The central quarters of the city are remarkably bustling and animated, but owing to the ample breadth of the new streets and boulevards and the fact that many of them are paved with asphalt or wood, Paris is a far less noisy place than many other large cities. Its comparative tranquillity, however, is often rudely interrupted by the discordant cries of the itinerant hawkers of wares of every kind, such as 'old clothes' men, the vendors of various kinds of comestibles, the crockery-menders, the 'fontaniers' (who clean and repair filters, etc.), the dog-barbers, and newspaper-sellers. As a rule, however, they are clean and tidy in their dress, polite in manner, self-respecting, and devoid of the squalor and ruffianism which too often characterise their class. In many cases they claim to have plied their vociferous trades ever since the middle-ages. Their pronunciation will of course often puzzle the uninitiated. On the long vowels and the letter *r* they usually lay prodigious stress, while the short vowels are either pronounced in a very light and airy fashion or altogether omitted. Another characteristic, though modern, feature in the street-noises of Paris consists of the hoarse blasts of the horns of the tramway-cars.

As a rule the Parisian may be said to invite and deserve the confidence of travellers. Accustomed by long usage to their presence, he is skilful in catering for their wants, and recommends

himself to them by his politeness and complaisance. In return the traveller in France should accustom himself to the inevitable '*s'il vous plaît*', when ordering refreshments at a café or restaurant, or making any request. It is also customary to address persons even of humble station as '*Monsieur*', '*Madame*', or '*Mademoiselle*'.

The *Sergents de Ville*, or *Gardiens de la Paix*, who are to be met with in every street and public resort, are always ready to give information when civilly questioned. Visitors should avoid the less frequented districts after night-fall and should in general be on their guard against the huge army of pickpockets and other rogues, who are quick to recognize the stranger and skilful in taking advantage of his ignorance.

The Parisian directory, published annually, and familiarly known as the '*Bottin*', which may be consulted at the principal hotels and cafés and also (for a fee of 10-15 c.) at various book-shops, will often be found useful by those who make a prolonged stay at Paris. It consists of two huge volumes, one of which contains a list of the streets and their inhabitants, while the other gives the addresses of the most important persons in the provinces, and even of a number of persons in foreign countries.

The best way of obtaining a general idea of the appearance of Paris is to take a drive on the top of an omnibus or tramway-car, or in an open cab, through the principal streets. If a cab is hired it should be engaged *à l'heure*, and the driver desired to take the following route.

CAB DRIVE. The *Palais-Royal* (p. 55) is chosen as a convenient starting-point. Thence we drive to the E. through the Rue de Rivoli (p. 58), passing the Tour St. Jacques (p. 60) and the Hôtel de Ville (p. 62); then through the Rue St. Antoine, as far as the Place de la Bastille (p. 65) and the Colonne de Juillet (p. 67), and along the Grands Boulevards (p. 68 et seq.) to the Madeleine (p. 79), and so to the Place de la Concorde (p. 84). We next ascend the Champs-Élysées (p. 153) to the Arc de l'Étoile (p. 155). Then we drive to the Pont de l'Alma (p. 168), and across it to the Champ-de-Mars (p. 280) and Hôtel des Invalides (p. 274); Rue de Grenelle, Ste. Clotilde (p. 273), Boulevard St. Germain as far as St. Germain-des-Prés (p. 250), Rue Bonaparte to St. Sulpice (p. 254), and on to the Palais du Luxembourg (p. 253); the Rue de Médicis, at the end of which is the Rue Soufflot leading to the Panthéon (p. 236). Thence down the Boulevard St. Michel (p. 225), passing the Sorbonne (p. 235) and Hôtel de Cluny (p. 226) on the right, and the Fontaine St. Michel (p. 225) on the left; next traverse the Boulevard du Palais and the 'Cité', where Notre-Dame (p. 224) is observed on the right, at some distance, and the Palais de Justice (p. 217) on the left, beyond which we regain the right bank of the

Seine at the Place du Châtelet (p. 60). Soon after we again reach the Rue de Rivoli, where we may dismiss the cab and descend through the Boulevard de Sébastopol to the Grands Boulevards.

The drive will occupy about 3 hrs. and (according to the vehicle) cost 7-10 fr., including 1 fr. gratuity.

OMNIBUS DRIVES. Gentlemen may explore the city by taking a similar excursion on the outside of an omnibus or tramway-car, which will occupy nearly double the time, but costs about 90 c. only. The route appears a little complicated, but will be easily traced with the aid of the map and list of omnibus lines (see Appx.). Take an omnibus from the Madeleine (p. 79) to the Bastille, line *E*, without 'correspondance' (15 c.), as far as the office at the beginning of the Boulevard Bourdon, at the Place de la Bastille (p. 65); thence take a tramway-car (coming from Vincennes; 15 c.) to the Hôtel de Ville (p. 62), and hence proceed by an omnibus of line *C* as far as the Arc de Triomphe de l'Etoile (p. 155). Here alight, and return by the same line to the Place de la Concorde (p. 81), without correspondance. Walk down to the quay and take line *AF* to the Panthéon (p. 236), without correspondance. Walk thence by the Boulevard St. Michel to the Jardin du Luxembourg (p. 258) and the Odéon (p. 29). Here take the Odéon and Batignolles-Clichy line *H* as far as the Palais-Royal (p. 55); or, better still, walk (in about 10 min.) from the Odéon by the Rue Racine to the Boulevard St. Michel, and take there a tramway of the Montrouge and Gare de l'Est line. Proceeding thence along the old Boulevards we may either alight at the N. end of the Boulevard de Sébastopol, or follow the Boulevard de Strasbourg to the Gare de l'Est.

Instead of returning from the Arc de Triomphe to the Place de la Concorde, we may take a car of the Tramway Place de l'Etoile and Gare Montparnasse to beyond the Pont de l'Alma, and thence proceed by a car of the Tramway Pont de l'Alma and Bastille, along the Seine and past the Hôtel des Invalides, and then through the Boulevard St. Germain to Square Cluny. Here we alight and walk in a few minutes to the Rue Soufflot and the Panthéon, whence the route may be continued as above.

Good walkers may, of course, perform parts of this route on foot and so obtain a closer view of the objects of interest. They may, *e.g.*, walk along the Grands Boulevards to the Place de la République (about 2 M. from the Opéra); from the Hôtel de Ville to the Place de la Concorde (about 1½ M.); from the Luxembourg to the Rue de Rivoli (nearly 1 M.), or to the Grands Boulevards (¾ M. farther).

A good general view of the city may be obtained from the *Towers of Notre Dame* (p. 223), or from the Eiffel Tower (p. 284), but for this purpose clear weather is necessary, and that occurs seldom more than might be supposed. Even when the sun is shining, the middle distance is frequently indistinct, a fact which may also be noticed

from the ground in the longer streets. The best views are obtained when the weather is clearing just after a shower, and on dry windy days; but in the latter case the wind is often disagreeable on the top of the towers. A general survey from another point of view is afforded by a visit to the *Butte Montmartre* (p. 189).

Having acquired a general idea of the external appearance and topography of the city, the traveller may then proceed at his leisure to explore it in detail.

17. Distribution of Time.

A stay of a fortnight or three weeks in Paris may suffice to convey to the visitor a superficial idea of the innumerable attractions which the city offers, but a residence of several months would be requisite to enable him satisfactorily to explore its vast treasures of art and industry. The following plan and diary will aid him in regulating his movements and economising his time. The routes in the Handbook are arranged as far as possible so as to avoid loss of time and unnecessary detours, but they may easily be resolved into new combinations or made in a reverse direction, as the convenience or pleasure of the sight-seer may dictate. Fine days should be spent in the parks, gardens, and environs. Excursions to the country around Paris, in particular, should not be postponed to the end of one's sojourn, as otherwise the setting in of bad weather may preclude a visit to many beautiful spots in the neighbourhood. Rainy days should be devoted to the galleries and museums.

The table at p. 54 shows when the different collections and objects of interest are open to visitors, but does not include buildings that are open gratis every day, which must be looked for in the index. Parks, public gardens, cemeteries, and the like are also omitted, as they are practically always open. The days and hours enumerated, though correct at present, are liable to alteration; and the traveller is therefore referred to *Galignani's Messenger* (p. 40), to the principal French newspapers, and to the bills posted on the advertising pillars in the boulevards. The museums and collections are apt to be uncomfortably crowded on Sundays and holidays.

LIBRARIES are generally open on week-days from 10 a.m. to 3 or 4 p.m., and some of them also from 8 to 10 p.m.

CHURCHES are usually open from morning till dusk, but the afternoon is the best time for a visit, as no service is then held. It should be noted that many churches are so dark that the works of art cannot be properly seen except by gaslight. The Madeleine (p. 79) is not open to visitors till 1 p.m., and several other churches are closed at 5 p.m. Sundays and festivals are not, of course, suitable days for inspecting the works of art in the churches, but they frequently offer opportunities of hearing

excellent music and good preachers. See p. 32, and the notices of the principal churches. The hours of service are announced on boards in the interior of the buildings. High mass is usually at 10 a.m. The masses at midday and 1 p.m. are especially attended by the fashionable world; and the scene on the conclusion of service at the Madeleine (p. 79) and other leading churches is both interesting and characteristic. Chairs within the churches are let for 5 c. each; on festivals 10 c.

The traveller should always be provided with his passport, or at least visiting-cards, which will often procure him admission to collections on days when the public are excluded.

The numbers in the following tables refer to the Routes of the Handbook.

Diary.

Days	Objects of interest	Days	Objects of interest
Every day	<ol style="list-style-type: none"> 1. Palais Royal, Bastille, Madeleine, Pl. de la Concorde (p. 55). 3. Champs Elysées and Bois de Boulogne ((p. 152). 15. St. Cloud, Sèvres, Meudon (p. 303). 17. St. Denis, Enghien, Montmorency, Argenteuil (p. 318). 18. Fontainebleau (p. 329). 19. Sceaux, Valleys of the Bièvre and the Yvette (p. 335). 20. Valley of the Oise (p. 341). 	Sunday	<ol style="list-style-type: none"> but not the Gobelins (p. 262). 12. As below, except the tomb of Napoleon (p. 274). 16. St. Germain-en-Laye (p. 315). 21. Chantilly and its Environs (p. 346).
Every day except Monday	<ol style="list-style-type: none"> 1, 15, 17 to 20, as above. 2. Louvre and Tuileries (p. 86). 8, 9. The Cité, Cluny, Panthéon, Montsouris (p. 216). 10. Institut, Beaux Arts, Luxembourg (p. 244). 13. Versailles (p. 287). 	Monday	<ol style="list-style-type: none"> 1, 15, 17-20, as above. 5. La Villette and Montmartre (p. 185).
		Tuesday	<ol style="list-style-type: none"> 1, 2, 4, 8-11, 13, 15-20, as above. 6. Bibliothèque Nationale, La Trinité, Les Batignolles (p. 195). 12. Chamber of Deputies, Ste. Clotilde, Invalides (p. 270).
		Wednesday	<ol style="list-style-type: none"> 1, 2, 8, 9, 10, 13, 15, 17-20, as above. 11. As above, except the natural history galleries (p. 262).
		Thursday	<ol style="list-style-type: none"> 1, 2, 3, 4, 5, 7-21, as above.
		Friday	<ol style="list-style-type: none"> 1, 2, 6, 8-11, 13, 15, 17-20, as above.
Sunday	<ol style="list-style-type: none"> 1, 2, 8, 9, 10, 13, 15, 17-20, as above. 3. Trocadéro, Passy, and Auteuil (p. 162). 4. Halles Centrales, Arts et Métiers, Père-Lachaise (p. 168). 7. Archives, Musée Carnavalet, Vincennes (p. 204). 11. Jardin des Plantes, 	Saturday	<ol style="list-style-type: none"> 1, 2, 8, 9, 10, 13, 15, 17-20, as above. 11. Jardin des Plantes and the Gobelins (p. 262).

Visit of Three Weeks.

Beginning on —	Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday	Beginning on —	Sunday	Monday	Tuesday	Wednesday	Thursday	Friday
Sunday ..	{ 1 7 16 + Last day at pleasure	{ 5 15 18	{ 2 4 17	{ 8,9 13 19	{ 3 12 21	{ 10 6 20	{ 2 11 +	Wednesday (continued)	{ 7 13	{ 17 20	{ 16 +	{ 13 +	{ 21 12	{ 18 8,9 17
Monday ..	{ — 16	{ 1 5 16	{ 2 4 17	{ 8,9 13 18	{ 3 13 21	{ 10 6 19	{ 2 11 20+	Thursday	{ 3 16	{ 5 15 19	{ 4 20	{ 10 13 +	{ 1 12 21	{ 2 8,9 17
Tuesday ..	{ — 16 20	{ — 5 +	{ 1 4 13	{ 2 10 17	{ 3 12 21	{ 8,9 6 18	{ 2 11 19	Friday ..	{ 3 16	{ 5 15 18	{ 4 13 19	{ 8,9 17 20	{ 10 21 +	{ 1 6 12
Wednesday	{ — 3	{ — 5	{ — 4	{ 1 10	{ 2 12	{ 8,9 6	{ 2 11	Saturday	{ 3 16	{ 5 15 18	{ 2 10 19	{ 8,9 13 20	{ 4 12 21	{ 6 17 +

Visit of a Fortnight.

Beginning on —	Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday	Beginning on —	Sunday	Monday	Tuesday	Wednesday	Thursday	Friday
Sunday ..	{ 1 7	{ 5 15	{ 2 12	{ 8,9 13	{ 4 16	{ 10 6	{ 3 11	Thursday	{ — 7	{ — 15	{ — 16	{ — 13	{ 1 10	{ 2 6
Monday ..	{ — 15	{ 1 6	{ 2 12	{ 8,9 13	{ 4 16	{ 10 6	{ 3 11	Friday ..	{ 3 7	{ 5 15	{ — 12	{ 8,9 13	{ — 16	{ 1 6
Tuesday ..	{ — 16	{ — 5	{ 1 12	{ 2 8,9	{ 4 13	{ 10 6	{ 3 11	Saturday	{ — 7	{ — 15	{ — 12	{ — 13	{ — 16	{ — 10
Wednesday	{ — 13	{ — 5	{ — 12	{ 1 8,9	{ 2 4	{ 10 6	{ 3 11							

Visit of a Week.

Beginning on —	Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday	Beginning on —	Sunday	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday
Sunday	11,12	5,6	2	8,9,11	4,7,13,15	10,3		Thursday	{ — 4,7	{ — 5,6	{ — 10,12	{ — 13,15	{ 1,3	{ 2	{ 8,9
Monday	{ — 10,12	{ 1,3	2	8,9,11	4,7,13,15	5,6		Friday	{ — 4,7	{ — 5,6	{ — 10,12	{ — 8,9,11	{ — 13,15	{ 1,3	{ 2
Tuesday	{ — 10,12	{ — 5,6	{ 1,3	2	4,7,13,15	8,9,11		Saturday	{ — 2	{ — 5,6	{ — 10,12	{ — 8,9,11	{ — 4,7	{ — 13,15	{ 1
Wednesday	{ — 10,12	{ — 5,6	{ — 13,15	{ 1,3	4,7	2	8,9,11								

Table showing the Days and Hours of Admission to the principal Museums, etc., of Paris.

Museums, Picture Galleries, etc.	See page	Sun and holid.	Mon.	Tues.	Wed.	Thurs.	Frid.	Sat.	Remarks
<i>Archives Nationales</i> . . .	205	12-3	—	—	—	10-3+	—	—	+1
<i>Arts & Métiers (Cons. des)</i>	173	10-4	+	10-4	+	10-4	+	+	+1
<i>Beaux-Arts (Ecole des)</i>	246	12-4	10-4+	10-4+	10-4+	10-4+	10-4+	10-3+	+2
<i>Biblioth. Nation. Exhib.</i>	197	—	—	10-4	—	—	10-4	—	—
<i>Bourse</i>	73	—	12-3	12-3	12-3	12-3	12-3	12-3	—
<i>Chambre des Députés</i> . . .	272	9-5,6	9-5,6	9-5,6	9-5,6	9-5,6	9-5,6	9-5,6	3
<i>Fontainebleau (Pal. de)</i>	32f	{ 10-5 11-4	{ 10-5 11-4	{ 10-5 11-4	{ 10-5 11-4	{ 10-5 11-4	{ 10-5 11-4	{ 10-5 11-4	—
<i>Gobelins (Manuf. des)</i>	268	—	—	—	1-3	—	—	1-3	—
<i>Invalides (Hôtel des)</i> . .	274	12-4	12-4	12-4	12-4	12-4	12-4	12-4	—
<i>Imprimerie Nationale</i> . . .	207	—	—	—	—	2	—	—	1
<i>Jardin des Plantes, Men.</i>	264	11-4,5	11-4,5	11-4,5	11-4,5	11-4,5	11-4,5	11-4,5	4
— — Conservatoires . . .	265	—	—	1-4+	—	—	1-4+	1-4+	+1
— — Nat. Hist. Collec.	265	11-3	—	11-3+	—	11-3	11-3+	11-3+	+1
<i>Luxembourg (Palais du)</i>	253	—	9-5,6	9-5,6	9-5,6	9-5,6	9-5,6	9-5,6	5
<i>Monnaie, Mus. & Studio</i>	246	—	—	12-3+	—	—	12-3+	—	+1
<i>Musée Carnavalet</i> . . .	208	11-4	—	—	—	11-4	—	—	—
— <i>d'Artillerie (Inval.)</i>	275	12-3,4	—	12-3,4	—	12-3,4	—	—	—
— <i>de Cluny</i>	227	11-4,5	—	11-4,5	11-4,5	11-4,5	11-4,5	11-4,5	—
— <i>de Minér. et Géolog.</i>	259	—	—	—	—	11-3	—	11-3	—
— <i>des Arts Décoratifs</i>	154	10-4,5	10-4,5	10-4,5	10-4,5	10-4,5	10-4,5	10-4,5	6
— <i>du Conserv. de Mus.</i>	72	—	—	—	—	12-4	—	—	—
— <i>du Garde-Meuble</i> . . .	280	10-4	—	—	—	10-4	—	—	—
— <i>du Louvre</i>	86	{ 10-4 10-4	—	{ 9-5 10-4	{ 9-5 10-4	{ 9-5 10-4	{ 9-5 10-4	{ 9-5 10-4	7
— <i>du Luxembourg</i> . . .	255	{ 10-4 10-6 10-4	—	{ 10-6 11-4	{ 10-6 11-4	{ 10-6 11-4	{ 10-6 11-4	{ 10-6 11-4	8
— <i>Guimet</i>	166	{ 10-4 10-4	—	{ 11-4 11-4	{ 11-4 11-4	{ 11-4 11-4	{ 11-4 11-4	{ 11-4 11-4	6
<i>Notre-Dame. Treasury</i>	223	—	10-4	10-4	10-4	10-4	10-4	10-4	9
<i>Palais de Justice</i>	217	—	11-4	11-4	11-4	11-4	11-4	11-4	—
<i>Pantheon</i>	236	10-4	—	10-4	10-4	10-4	10-4	10-4	—
<i>St. Denis. Tombs</i>	319	8½-5½	8½-5½	8½-5½	8½-5½	8½-5½	8½-5½	8½-5½	10
<i>St. Germain. Museum</i>	315	10½-2-4	—	10½-2-4	—	10½-2-4	—	—	11
<i>Ste. Chapelle</i>	218	11-4,5	11-4,5	11-4,5	11-4,5	11-4,5	11-4,5	11-4,5	—
<i>Salon (Exposition du)</i> . .	154	8-6	12-6	8-6	8-6	8-6	8-6	8-6	12
<i>Sèvres. Manufactory</i> . .	312	12-4,5	12-4,5	12-4,5	12-4,5	12-4,5	12-4,5	12-4,5	13
<i>Tobacco Manufactory</i>	280	—	—	—	—	10-4	—	—	1
<i>Tomb of Napoleon I.</i> . . .	279	—	12-3,4	12-3,4	—	12-3,4	12-3,4	—	—
<i>Trocadero, Aquar.</i> . . .	165	9-11, 1-5	9-11, 1-5	9-11, 1-5	9-11, 1-5	9-11, 1-5	9-11, 1-5	9-11, 1-5	14
— <i>Ethnog. Museum.</i> . . .	165	12-4	—	—	—	12-4	—	—	—
— <i>Sculptures</i>	164	11-4,5	—	11-4,5	11-4,5	11-4,5	11-4,5	11-4,5	—
<i>Val-de-Grâce (Egl. du)</i>	241	12-2	12-2	12-2	12-2	12-2	12-2	12-2	—
<i>Versailles. Pal. & Gall.</i>	289	11-4,5	—	11-4,5	11-4,5	12-4,5	11-4,5	11-4,5	—
— <i>Triansons</i>	306	11-4,5	—	11-4,5	11-4,5	12-4,5	11-4,5	11-4,5	—
— <i>Jeu-de-Paume</i>	289	12-4	—	12-4	2-41	10-4	12-4	12-4	—

REMARKS (see last column of Table). — 1. Special permission necessary. — 2. Fee. — 3. During the vacation; fee. — 4. Botanical Garden open all day. — 5. Different parts closed on different days. — 6. In winter 11 to 4 or 5; adm. on week-days 1 fr., Sun. 50 c. — 7. Paintings and Antique Sculptures, the rest at 11 a.m.; in winter 10-4. — 8. In summer 9-5. — 9. Adm. 50c. — 10. Except during service. In winter till dusk. — 11. Till 5 p.m. in summer. — 12. From 1st May to 20th June; see p. 154. — 13. Special permission necessary for the work-rooms. — 14. In summer till 6 p.m.

RIGHT BANK OF THE SEINE.

The modern business and fashion of Paris are chiefly confined to the quarters on the right bank of the Seine, which contain the principal *Boulevards*, the handsomest streets, and the most attractive shops, cafés, and restaurants in the city. Here, too, are situated the most important *Theatres*, the *Bourse*, the *Bank*, the *Palais-Royal*, the *Hôtel des Postes*, and the *Halles Centrales*. The *Hôtel de Ville*, the headquarters of the municipal authorities, and the *Tuileries*, once the seat of the court but now entirely demolished, are the great centres around which the whole of modern French history has been enacted; and in the same region of the city is the *Louvre*, containing the greatest art-collection in France.

1. From the Palais-Royal to the Bastille, and back by the Boulevards.

The following routes or itineraries are arranged to suit travellers whose stay in Paris is moderately long, and it is taken for granted that they devote the entire day to sight-seeing. Those who are pressed for time are referred to the remarks at p. 51. If the preliminary drive recommended at p. 49 has been taken, the visitor need not return to the Bastille, but may proceed to the Place de la République by a more direct route, inspecting on the way (if they are open, p. 54) the Musée Carnavalet (p. 208), the Archives (p. 205), or the Conservatoire des Arts et Métiers (p. 173). Another opportunity of returning from the Bastille will be found on p. 210. — Luncheon may be taken near the Tour St. Jacques (pp. 13, 15), near the Bastille (pp. 13, 15), or in the Boulevard St. Martin (p. 13, 15).

I. THE PALAIS-ROYAL, AND THENCE TO THE HOTEL DE VILLE. St. Germain-l'Auxerrois. Tour St. Jacques. Place du Châtelet. St. Merri.

The small PLACE DU PALAIS-ROYAL† (Pl. R, 20; II), enclosed by the Palais-Royal on the N., the Louvre (p. 87) on the S., and the Magasins du Louvre on the E., occupies almost the centre of

† With regard to the arrangement of our Plan of Paris, see note preceding the list of streets. The three sections of the tripartite plan, coloured respectively brown, red, and gray, are referred to in the text by the corresponding letters B, R, and G. If the place sought for is also to be found in one of the five special plans of the more important quarters of the city, that plan is indicated by a Roman Italic numeral. The above reference therefore indicates that the Place du Palais-Royal is to be found in the *Red Section*, *Square 20*, and also in the *Special Plan*, *No. II*.

Paris, and is one of the best starting-points for exploring the city. The means of communication between this point and other quarters are very numerous, and visitors who live near the Opera may reach it by a pleasant walk along the Avenue de l'Opéra (p. 76).

The **Palais-Royal** is formed of two quite distinct parts, — the Palace properly so called, with its façade in the square, and the *Garden* surrounded with *Galleries*, the most interesting part, behind.

The **Palace** is at present occupied by the *Conseil d'Etat*, and is not open to the public.

This Palace was erected by Cardinal Richelieu in 1629-34, and named the *Palais-Cardinal*. After his death it was occupied by Anne of Austria, the widow of Louis XIII., with her two sons Louis XIV. and Philip of Orleans, then in their minority, and since then the building has been called the *Palais-Royal*.

Louis XIV. presented the palace to his brother Duke Philip of Orleans, whose second wife, Elizabeth Charlotte, Princess of the Bavarian Palatinate (b. at Heidelberg 1652, d. 1722), wrote a number of exceedingly curious letters to her German relations with reference to the court of Louis XIV. The princess, to whom her husband's court was distasteful, occupied separate apartments in the palace. Her son, *Philip of Orleans* (d. 1723), who was regent during the minority of Louis XV., afterwards indulged here in those disgraceful orgies which are described by his contemporary the *Duc de St. Simon*. The Palais-Royal remained in possession of the Orleans family. *Philippe Egalité*, who was beheaded in 1793, grandson of the regent, led a scarcely less riotous and extravagant life than his grandfather. In order to replenish his exhausted coffers, he caused the garden to be surrounded with houses, still existing in their original form, which he let for commercial purposes, and thus materially improved his revenues. The cafés on the ground-floor soon became a favourite rendezvous of democrats and malcontents. It was here that *Camille Desmoulins*, one of the most vehement republican ringleaders, called the populace to arms on 12th July, 1789, and so well concerted were his plans that on the following day he organised a 'Garde Nationale', led the way to the Bastille (p. 65), and captured that fortress (14th July). The building was now called the *Palais-Egalité*, and subsequently, when Napoleon assembled the Tribunal here in 1801-7, the *Palais du Tribunat*.

On the Restoration of the Bourbons in 1815 the Orleans family regained possession of the Palais-Royal, and it was occupied by *Louis Philippe* down to the end of 1830. Shortly before the outbreak of the revolution of July, he gave a sumptuous ball here in honour of the Neapolitan notabilities then visiting Paris, which gave rise to Salvandy's famous witticism — '*Nous dansons sur un volcan*'. On 24th February, 1848, the mob made a complete wreck of the royal apartments. After this the building was styled

the *Palais-National*; but its original name was restored by Napoleon III., who assigned the S. wing, opposite the Louvre, as a residence for his uncle, Prince Jérôme Napoleon, the former King of Westphalia (d. 1860). After the death of the latter it was occupied by his son (d. 1891), who bore the same name.

On 22nd May, 1871, the Communists set the Palais-Royal on fire, and the S. wing, with the exception of the S.W. corner where the Théâtre Français is situated, became a prey to the flames. The palace has since been completely restored.

The principal entrance to the *GALLERIES and the GARDEN is to the left of the façade, between the Palais and the Théâtre Français (p. 58). In the first gallery to the left, the *Galerie de Chartres*, is the shop of *Chevet* (p. 12), one of the first in Paris for provisions. Then to the right is the handsome *Galerie d'Orléans*, dating only from 1830. It succeeded some wooden galleries, in which were situated gaming-houses, etc.; it was here that the Duc de Masséna lost 700,000 fr. in a single night. — A small building, partly subterranean, in the middle of the court between the palace proper and this gallery, contains the engines used to supply the electric light for the Théâtre Français, the Palais Royal, and the Bibliothèque Nationale.

The ground-floors of the houses inclosing the garden are occupied almost exclusively by jewellers' and similar shops. The restaurants mentioned at p. 14 are mostly on the first floor; though some of the best known are on the ground-floor (p. 12). — The E. side of the square is called the *Galerie de Valois*, the W. side the *Galerie Montpensier* (with the *Théâtre du Palais-Royal*, p. 30), and the N. side the *Galerie Beaujolais*.

The GARDEN, 250 yds. in length and 110 yds. in breadth, and hardly deserving of the name, is scantily shaded by a quadruple row of elms and limes. In the centre is a circular basin of water, 22 yds. in diameter, near which a military band generally plays in summer on Sun., Wed., and Frid. from 4 to 5 or 5 to 6 p.m. (p. 33). The garden is embellished with several sculptures, *viz.*, from S. to N.: Eurydice bitten by a serpent, by *Nanteuil*; Mercury, by *Cugnot*; the Charmer, by *Thabard*; Boy struggling with a goat, by *Lemoine*; the Versailles Diana, after the antique, and a Youth bathing, by *Espercieux* (d. 1840). The small cannon on the grass, at the S. end of the flower-garden, is fired by means of a burning-glass at noon precisely. The chairs under the trees are let at 10 c. each. All the entrances to the garden are closed at midnight, but the galleries remain open.

The Palais-Royal, long a favourite rendezvous of visitors to Paris, is now becoming gradually more and more deserted. Like the Place des Vosges (p. 209), which formerly played the same rôle, it is being superseded by the newer and more elegant quarters farther W.; while its unobtrusive entrances, accessible only to foot-passengers, are not calculated to attract strangers. A marked proof of its decline is the fact that the Café de la Rotonde has been demolished after standing tenantless since 1884.

At the back of the Palais-Royal is the Bibliothèque Nationale (p. 195), to the right of which is the Rue Vivienne, leading past the Bourse, and to the left the Rue de Richelieu (p. 196). To the N.E. are the Place des Victoires, the Banque de France, etc., described at p. 169.

Almost adjoining the Place du Palais-Royal on the W. is the small *Place du Théâtre-Français* (Pl. R, 21; II), embellished with two handsome modern fountains by Davioud, with statues in bronze by Carrier-Belleuse and Moreau. The Avenue de l'Opéra and the Rue de Richelieu connect the Place with the Boulevards.

The **Théâtre Français** was built in 1782, but the façades towards the Rue St. Honoré and the Place have both been renewed in recent years. The exterior is unattractive. The handsome Doric vestibule contains a statue of Talma, the tragedian (d. 1826), by *David d'Angers*, and figures of Tragedy and Comedy by *Duret*, bearing respectively the features of the celebrated actresses Mlle. Rachel (d. 1858) and Mlle. Mars (d. 1847). The 'foyer du public' is adorned with a statue of *Voltaire* (d. 1778) by Houdon, with a chimney-piece with a relief representing comedians crowning the figure of Molière, by *Lequesne*, with busts and scenes from the writings of celebrated French dramatists, and with a new ceiling-painting, by *Dubufe*, of Truth enlightening the world. In one of the corridors is a statue of George Sand (d. 1876), by *Clésinger*. The ceiling of the interior represents France distributing laurels to her three great dramatists: Molière, Corneille, and Racine. Performances, see p. 29.

Between the Place du Palais-Royal and the Louvre runs the ***Rue de Rivoli**, one of the most important streets in Paris after the Boulevards, and named in honour of Napoleon's victory over the Austrians at Rivoli in 1797. Leaving the Place de la Concorde, it runs parallel with the Seine for $1\frac{3}{4}$ M., and ends at the Rue St. Antoine, which forms a prolongation connecting it with the Place de la Bastille. This fine street was constructed between 1802 and 1865, having been finally completed during the second empire by the demolition of 300 houses between the Place du Palais-Royal and the Hôtel de Ville. It passes the Garden of the Tuileries, the Louvre, and the Place du Palais-Royal, this part of the street as far as the Rue du Louvre being flanked by arcades on the N. side, upwards of $\frac{1}{2}$ M. in length, where there are many attractive shops and hotels of the highest class. We follow it to the left, coming from the Palais-Royal, and leaving the Place de la Concorde behind us. On the right rises the *Palais du Louvre* (p. 86); on the left the *Magasins du Louvre* (p. 37). To the left, farther on and partly concealed by the last arcades, is the *Temple de l'Oratoire*, a church erected by the priests of the Oratoire in 1621-30, but now used as a Protestant place of worship (p. 44). A statue of *Admiral Coligny*, one of the victims of the Night of St. Bartholomew (p. 87), by Crauk, was erected here in 1889; it represents the admiral between his Fatherland and Religion.

At this point the arcades terminate, and the Rue de Rivoli is intersected by the *Rue du Louvre*, which was prolonged to the new Hôtel des Postes (see p. 170) in 1888. The first building to the right in the Rue du Louvre is the Vieux Louvre, with the famous Colonnade by Perrault (p. 88). Opposite rises the *Mairie of the 1st Arrondissement* (Louvre), which has been erected, with a view to secure harmony of effect, in a style similar to that of the adjoining church of St. Germain l'Auxerrois. The 'Salle des Mariages' in the Mairie is adorned with paintings by Besnard. Between the Mairie and the church is a square tower with a chime of bells, constructed by Ballu to fill up the gap.

The church of **St. Germain l'Auxerrois* (Pl. R, 20; III), founded in the time of Charlemagne, dates in its present form from the 12th and 16th centuries, but numerous portions dating from the three preceding centuries have been retained. The porch, added by *Jean Gausse* at the beginning of the 15th cent., consists of three large and two small arcades, surmounted by a kind of terrace with a balustrade, which also runs round the whole church. Above the terrace, but farther back, rises the gable façade of the nave, pierced with an arched window of rich Flamboyant rose-tracery and flanked by two hexagonal turrets. The gable is crowned with an Angel of the Last Judgment by *Marochetti*. The interior of the porch is adorned with frescoes on a gold ground, by *Mottet*, now sadly defaced. The three portals are richly adorned with statues and gilded statuettes; that in the centre dates from the 13th century. — When the gate is closed, visitors are admitted by the side-entrance.

THE INTERIOR, to which the lowness of the roof gives a depressed character, consists of nave and double aisles, and is surrounded with chapels. The pillars of the nave were converted into fluted columns in the 17th cent., and the handsome woodwork of the choir-stalls dates from the same period.

The walls are covered with modern frescoes, the finest of which is a Descent from the Cross, in the S. transept, by *Guichard* (1845). The large chapel of Notre-Dame, to the right of the entrance, occupying the whole of this side of the church as far as the transept, is closed by handsome woodwork, and contains a Tree of Jesse, in stone, of the 14th cent., a Gothic altar designed by *M. Viollet-le-Duc*, several paintings, and stained glass by *Amaury-Duval*. The marble **Basin* for holy water in the S. transept, designed by Mme. de Lamartine and executed by *Jouffroy*, deserves inspection. It consists of three shells, and is surmounted by a finely-sculptured group of three angels around a cross. — The fourth chapel of the choir beyond the Sacristy contains monuments in marble to the chancellor *Etienne d'Aligre* (d. 1635) and his son (d. 1674). — The chapel beyond that of the apse contains two statues from a mausoleum of the Rostaing family. The chapel after the next contains a monument to St. Denis, who is said to have been interred at this spot after his martyrdom (p. 189). The chapel of Notre Dame de la Compassion, adjoining the N. transept, contains an altar-piece in wood in the Flamboyant style, representing the history of Christ and the Virgin. — The signal for the massacre of St. Bartholomew (Aug. 24th and 25th, 1572) was given from the little bell-tower of this church, to the right of the transept.

From the end of the Rue du Louvre we obtain a good view of the Pont-Neuf with the statue of Henri IV. (p. 220), and of the dome of the Panthéon (p. 236) rising in the background.

Beyond the Rue du Louvre the Rue de Rivoli intersects the Rue du Pont-Neuf, leading from the bridge of that name to the Halles Centrales (p. 170), which are visible to the left. Farther on, to the left, diverge the Rue des Halles, the Rue St. Denis (p. 72), and the *Boulevard de Sébastopol*. The last, one of the magnificent streets constructed under Napoleon III. by M. Haussmann, Préfet de la Seine, is terminated at the S. end by the Place du Châtelet (see below).

In a small public garden to the right rises the —

***Tour St. Jacques** (Pl. R, 23; III, V), a handsome square Gothic tower, 175 ft. in height, erected in 1508-22, a relic of the church of *St. Jacques de la Boucherie* which was sold and taken down in 1789. The tower was purchased by the city in 1836 and subjected to a process of restoration. In the hall on the ground-floor is a statue (by Cavelier) of the philosopher *Pascal* (d. 1662), who on the summit of this tower made his first experiments with regard to atmospheric pressure. The ***VIEW** from the summit of the Tour de St. Jacques is one of the finest in Paris, as the tower occupies a very central position, but the public are not allowed to ascend except with a permit obtained gratis at the Hôtel de Ville (Direction des Travaux) daily 11-5, except Sun. and holidays.

The *Squares* of Paris, like the great majority of the other promenades of the city, are not only ornamental; they discharge also the useful function of opening up and ventilating the crowded districts, and provide healthful playgrounds for the children of the people. Though they have been constructed on the model of the London squares, the enjoyment of the gardens with which they are laid out is by no means confined to a few privileged individuals, but is free to all comers. As soon as the weather is warm enough they are filled with crowds of children from the neighbouring streets. The formation of squares of this sort has been a prominent feature of the modern street improvements of Paris. Besides that at the Tour St. Jacques, the chief are the squares des Arts et Métiers (p. 172), du Temple (p. 71), Montholon (p. 194), de la Trinité (p. 201), and des Batignolles (Pl. B, 14).

The Square de la Tour St. Jacques is embellished with bronze sculptures of the Bread-bearer, 'Ducks and Drakes' ('Le Ricochet'), and Cyparissa, by Contan, Vital Cornu, and H. Plé.

The new *Avenue Victoria*, which skirts the S. side of the Square de la Tour de St. Jacques, leads hence to the Hôtel de Ville (p. 62).

The **Place du Châtelet** (Pl. R, 20, 23; V), the site of which was occupied till 1802 by the notorious prison of that name, lies at the S. end of the Boulevard de Sébastopol, on the bank of the Seine. The *Fontaine de la Victoire*, designed by Bosio, and erected here in 1807, commemorates the first victories gained by Napoleon I. It is adorned with four figures representing Fidelity, Vigilance, Justice, and Power, and surmounted by the 'Colonne du Palmier', on which are inscribed the names of 15 battles. On the summit is a gilded statue of Victory. The monument originally stood farther from the Seine, but was removed *entire* on the construction of the Boulevard de Sébastopol in 1855, and re-erected here on a pedestal

adorned with four sphinxes. On this side of the fountain is the mansion of the *Chambre des Notaires*, with a plan of the Châtelet on the façade. On the right and left of the Place du Châtelet are situated the *Théâtre du Châtelet* (p. 30) and the temporary *Théâtre de l'Opéra Comique* respectively (see p. 29).

In the Place du Châtelet is the usual entrance to the vast network of Sewers (*Egouts*) by which Paris is undermined and which form one of the most interesting sights of the city. They are generally shown to the public on the first and third Wednesday of each month in summer. Intending visitors make written application to the *Préfet de la Seine* on a stamped paper costing 60 c., and receive a card determining the time and place of starting. The visit, in which ladies need have no hesitation in taking part, usually ends at the Place de la Madeleine.

The system of drainage in Paris is very complete and has had a most beneficial effect on the health of the population. The contents are ultimately conducted to the Seine by a long tunnel joining the river below the bridge of Asnières. The total length of the network of sewers of Paris is now about 740 M., most of them having been constructed under the direction of *M. Belgrand* since 1852. Not less than 180 M. remain still to be made. The aggregate length of the sewers now in use is thus greater than the distance from Paris to Berlin (670 M.), about 24 hrs. journey by railway. The basin in which the city lies is divided into four parts by two large sewers at right angles with the Seine, and running under the Boul. de Sébastopol and Boul. St. Michel respectively. These, which flow, not into the river, but into 8 channels parallel with it, are augmented by about 15 tributaries, which in their turn receive the contents of numerous smaller drains. The various tributary drains are called *Egouts Collecteurs*.

All the 'collecteurs' empty themselves into a '*Collecteur Général*' in the Place de la Concorde, which descends thence to Asnières, nearly $3\frac{1}{2}$ M. distant. This main drain carries off about 340,000 cubic feet of water per hour, but is capable of passing five times that quantity. The 'collecteurs' of the left bank are united at a point a little above the Pont de la Concorde, from which they are carried across the bed of the Seine by a huge iron pipe, 170 yds. in length, and in the inside upwards of 3 ft. in diameter. This drain runs at a depth of about 100 ft. below the Avenue Marceau, the Place de l'Etoile, and the village of Levallois-Perret, and falls into the 'collecteur général' not far from its mouth.

These channels are all of such ample dimensions as to carry off with ease the whole drainage and surface-water of the city, even after the heaviest rains. The smallest are about 7 ft. high and 4 ft. wide, the largest 16 ft. high by 18 ft. wide. All the drains are constructed of solid masonry, and lined with waterproof cement. The 'collecteurs' are flanked with pavements or ledges, between which the water runs, and above one or both of which is a conduit for pure water. All these channels communicate with the streets by numerous iron ladders, and each is furnished with its distinctive mark and the name of the street above.

The cleaning of the larger sewers, in which there is a channel flanked with ledges, is effected by a very ingenious system. In the 'grand collecteur' there are four boats of the same width as the channel, each provided with a vertical gate or slide, which when let down exactly fits the channel. Each boat, having been placed at its assigned starting-point, has its slide adjusted, and is then propelled downwards by the force of the stream, scraping clean the bottom and sides of the sewer as it advances. In the 'grand collecteur' this process occupies sixteen days. In the smaller sewers, where the current is not strong enough to be available in this way, the boats are replaced by small waggons running on rails at the bottom of the channel, and propelled by the workmen walking along the pathways at the sides.

On its arrival at Asnières the liquid part of the sewage is allowed to escape, while the remainder is conducted to the peninsula of *Gennevilliers*, and there utilised as manure. The value of land in this once sterile tract is said to have been quintupled by this process.

The *Pont au Change*, of equal breadth with the Boulevard itself, is one of the chief channels of communication between the Cité (p. 216) and the left bank. The bridge, which is one of the most ancient and renowned in Paris, was entirely rebuilt in 1858-59. Its name is derived from the shops of the money-changers and goldsmiths with which the old bridge was flanked. The bridge commands a fine view of the buildings on the Ile de la Cité.

In the Rue St. Martin, a little to the N. E. of the Tour St. Jacques, rises the church of **St. Merri** (Pl. R, 23; *III*), properly *St. Médéric*, from Prior Médéric of Autun, who was buried about the year 700 in the Chapelle de St. Pierre which then occupied this site. The church is a good Gothic building, although begun as late as 1520, and not completed till 1612. It possesses a beautiful though unfinished portal in the Flamboyant style, flanked on one side by a tower with round arches near the top and on the other by a slender turret. The interior is in a pseudo-classical style, dating in its present form from the time of Louis XIV. Among the most noteworthy contents are a large marble crucifix, by *Dubois*, at the high-altar; a Pieta by *Slodtz*, in the second chapel to the left; two good pictures by *C. Vanloo* (d. 1765), at the entrance to the choir; and a painting by *Belle* (d. 1806), in the left arm of the transept. The chapels of the ambulatory are adorned with fine frescoes by *Cornu*, *Lehmann*, *Amaury-Duval*, *Chassériau*, *Lépaulle*, etc.; and the large chapel on the right contains several statues by *J. B. Débay*. — The Rue du Cloître St. Merri, on the left of the Church, was the scene of a long and bloody struggle during the rising of June 5th and 6th, 1832.

We now return to the Rue de Rivoli, where we soon reach, on the right, the ***Hôtel de Ville** (Pl. R, 23; *V*), or town-hall of Paris, in many respects one of the finest buildings in the city. The present edifice, which replaces the old Hôtel de Ville, burned by the Communists in 1871, was erected under the superintendence of *Ballu* and *Deperthes*. The construction of the old Hôtel de Ville was begun in 1533 by the Italian architect *Domenico Boccadoro da Cortona*, but was not completed till the beginning of the following cent., in the reign of Henri IV. As it afforded too little accommodation for the residence and offices of the chief municipal functionary of Paris, who was called '*Prévôt des Marchands*' down to 1789, and afterwards '*Préfet de la Seine*', it was gradually enlarged; and when the additions were completed in 1841, the edifice was four times the size of the Hôtel de Ville of Henri IV. Notwithstanding its vast size, it was again found necessary in 1857 to make further provision for the offices of the Préfecture by erecting two buildings opposite the principal façade, on the other side of the Place.

The new Hôtel de Ville may be described as an enlarged reproduction of the original building, with richer ornamentation and more convenient arrangements. It is a rectangular structure in the

French Renaissance style, with dome-covered pavilions at the angles, mansard windows, lofty decorated chimneys, and a graceful tower. The richly-articulated MAIN FAÇADE, in the centre of which is a handsome clock, is adorned with numerous sculptures. In the niches of the principal stories are statues of celebrated Parisians of all ages, while above are allegorical groups and figures representing the chief towns of France. The roof is surmounted by ten gilded figures of heralds. The three courts also contain several statues, some of which have been preserved from the old building. The whole edifice is surrounded by a sunken area and railing. The *Salle du Conseil Municipal*, or council-chamber, occupies the centre of the first story; the meetings are open to the public. The apartments of the Prefect are also on the side next the Seine. The small garden on which they look out contains a bronze *Equestrian Statue of Etienne Marcel* (p. 257), by Idrac and Marqueste, erected in 1888. On the ground-floor is the *Salle de St. Jean*, intended for large meetings, above which is the huge *Salle des Fêtes*, while on the floor above is the public *Bibliothèque Administrative*. The entrances on the rear side are guarded by bronze lions, by *Caïn* and *Jacquemart*.

Permission to visit the interior may be obtained on week-days from 1 to 3 p.m., on application to the director of the works or to the porter at the entrance from the Rue de Rivoli, and visitors may at all times inspect the handsome courts. The old Hôtel de Ville was most gorgeously fitted up and adorned with paintings by some of the most eminent French artists; and the new rooms are equally magnificent, though some of the paintings will not be finished for several years. In the central court is a sculptured group, 'Gloria Victis', by *Mercié*, and in the vestibule next the Place, casts of the 'Dernières Funerailles', by *Barrias*, and 'Paradise Lost', by *Gautherin*. The last is reproduced in marble in the Parc Monceaux (p. 202).

The Hôtel de Ville has played a conspicuous part in the different revolutions, having been the usual rallying-place of the democratic party. On 14th July, 1789, the captors of the Bastille were conducted in triumph into the great hall. Three days later, Louis XVI. came in procession from Versailles to the Hôtel de Ville under the protection of Bailly and other popular deputies, thus publicly testifying his submission to the will of the National Assembly. The king was accompanied by a dense mob, to whom he showed himself at the window of the Hôtel de Ville wearing the tri-coloured cockade, which Lafayette had just chosen as the cognisance of the new national guard. On 27th July, 1794 (9th Thermidor), when the *Commune*, the tool employed by Robespierre against the Convention, was holding one of its meetings here, Barras with five battalions forced his entrance in the name of the Convention, and Robespierre, to escape arrest, attempted to shoot himself, but only succeeded in shattering his jaw. Here was also celebrated the union of the July Monarchy with the bourgeoisie, when Louis Philippe presented himself at one of the windows, in August, 1830, and in view of the populace embraced Lafayette. From the steps of the Hôtel de Ville, on 24th Feb., 1848, Louis Blanc proclaimed the institution of the republic.

From 14th Sept., 1870, to 28th Feb., 1871, the Hôtel de Ville was the seat of the 'gouvernement de la défense nationale', and from 19th March to 22nd May, 1871, that of the Communists and their pretended 'comité du salut public'. In accordance with a secret resolution passed by the ringleaders of

these miscreants on 20th May, 1871 (comp. p. 150), heaps of combustibles steeped in petroleum, and barrels of gunpowder were placed in various parts of the building. At the same time they had strongly barricaded every approach to the building, which from the first had been the great centre of their operations, and where they had accumulated every possible means of defence. On the morning of 24th May a fearful struggle began in the Place de l'Hôtel de Ville, and was protracted without intermission until the following morning. As the insurgents were gradually driven back, they gave vent to their rage and despair by setting on fire many of the surrounding buildings and murdering the inhabitants, while two of their number, specially charged with the task by the commandant Pindy, ignited the combustibles in the Hôtel de Ville, although about 600 of their party were still within its precincts. The troops, now masters of the whole neighbourhood, directed an incessant fire against the devoted building and its unhappy occupants, all of whom perished. No quarter was given to those who attempted to escape from the blazing pile, while those who remained within its walls met with a still more appalling fate.

THE PLACE DE L'HÔTEL-DE-VILLE, formerly named *Place de Grève* ('bank of the river'), has also witnessed many a tragedy. Thus in 1572, after the massacre of St. Bartholomew, Catherine de Médicis doomed the Huguenot chiefs Briquemont and Cavagnes to perish ignominiously by the gallows in this Place; and in 1574 she ordered the Comte Montgomery, captain of the Scottish guard, to be executed here for having accidentally caused the death of her husband Henri II. at a tournament (p. 210). From that period down to 1789, the Place de Grève witnessed the execution of the numerous victims of a despotic government, as well as criminals; and in the July of that year, after the capture of the Bastille by the insurgents, Foulon, general comptroller of finance, and his son-in-law Bertier, the first victims of the Revolution, were hanged by the mob on the lamp-posts of this Place. Among the famous criminals who have here paid the penalty of their misdeeds are Ravallac, the assassin of Henri IV. (1610), the Marquise de Brinvilliers, the poisoner (1676), Cartouche, the highwayman (1741), and Damiens, who attempted to assassinate Louis XV. (1757).

The Place de l'Hôtel-de-Ville is connected with the Cité by the *Pont d'Arcole*, affording a view of the Hôtel-Dieu and Notre-Dame.

To the N. of the Hôtel de Ville begins the *Rue du Temple*, an old and busy street, which passes the Temple and joins the Rue de Turbigo near the Place de la République (p. 70).

II. FROM THE HÔTEL DE VILLE TO THE BASTILLE.

St. Gervais. St. Paul et St. Louis. Colonne de Juillet.

At the back of the Hôtel de Ville are the *Caserne Napoléon*, which can accommodate 2500 men, to the left, and the former *Caserne Lobau*, to the right, now used as an annexe of the Hôtel de Ville.

The Church of St. Gervais (Pl. R, 23; V), or *St. Gervais et St. Protais*, which stands at the end of the Place between the two barracks, was begun in 1212, but was completely remodelled in the 14th cent.; it now presents a combination of the Flamboyant and Renaissance styles. The rococo portal was added by *Debrosse* in 1616. If the chief entrance is closed, admission is obtained by a small door at the N. end of the choir.

The INTERIOR is remarkable for its height and the pendentives of its vaulting. The chapels are embellished with good modern frescoes by *Gigoux, Delorme, Heim, Jobbé-Duval*, and other masters, representing scenes from the Bible and the Acta Sanctorum. In the left transept is a *Passion*, painted on wood, in ten sections, a work of the Flemish school (attributed to Dürer). The candelabra and a bronze crucifix on the high-altar are good works of the 18th century. The church formerly contained a number of fine old stained-glass windows, of which only two, both restored, now remain: one, by *Jean Cousin* (1500-1584), in the Chapelle de la Vierge; the other, representing the Judgment of Solomon, by *R. Pinaigrier* (1531), in the seventh chapel on the right.

To the N. of St. Gervais, behind the Caserne Napoléon, is the small *Place Baudoyer*, with the *Mairie* of the fourth Arrondissement, an edifice in the style prevalent at the end of the 16th century. The Salle des Mariages and Salle des Fêtes are embellished with paintings by Cormon and Comerre.

We here regain the Rue de Rivoli, which is succeeded a little farther on by the *Rue St. Antoine*. In the latter, on the right, is the former Jesuit church of *St. Paul et St. Louis* (Pl. R, 25, 26; V), erected in 1627-41, by *Derrand*. The handsome Renaissance portal was added by *Marcel Ange*. The best of the numerous paintings in the interior is a Christ in the Garden, an early work of *Eug. Delacroix*, in the left arm of the transept. — The building to the right, formerly a Jesuit college, is now the *Lycée Charlemagne*.

A short distance from this church, to the N. of the Rue St. Antoine, is the Rue du Roi de Sicile (Pl. R, 23; V), once containing the famous *Prison de la Force*, in which the 'Septembriseurs' committed their assassinations in 1792.

In the Rue Sévigné, which begins opposite the church of St. Paul, is situated the Hôtel Carnavalet (p. 208).

On the left in the Rue St. Antoine, No. 142, is the old *Hôtel de Béthune*, built in the 16th cent. by Maximilien de Béthune, better known as the Duc de Sully and minister of Henri IV. The vaulted roof of the 'porte cochère' is interesting, and the façades in the court are adorned with elaborate sculptures.

There are numerous other mediæval buildings in this part of Paris, such as those in the Place des Vosges (p. 209; reached by the Rue de Birague, a little farther on, to the left), the *Hôtel d'Ormesson*, Rue St. Antoine 212, and those mentioned below; but most of them are hidden from view by modern edifices.

Farther on in the Rue St. Antoine, to the right, is the *Eglise de la Visitation* or *Temple Ste. Marie*, constructed in the 17th cent. by Fr. Mansart for a convent of Visitandine nuns. — The Rue St. Antoine terminates in the Place de la Bastille.

The *Place de la Bastille* (Pl. R, 25; V), or simply *La Bastille*, as it is usually called, was formerly the site of the *Bastille St. Antoine*, a castle which was left standing when the boulevards were levelled in 1670 (p. 68). This stronghold, which was erected in 1371-83 by Kings Charles V. and VI., was afterwards used as a state-prison, chiefly for the confinement of persons of rank who had fallen victims to the intrigues of the court or the caprice of the government, and

attained a world-wide celebrity in consequence of its destruction on 14th July, 1789, at the beginning of the French Revolution.

'With its massive walls, 10 ft. in thickness, and its eight heavy, sombre towers, it rose just at the entrance of the city; and the cannon on its battlements commanded the adjoining suburb of St. Antoine, the quarter occupied by the artisan classes. It formed the standing cognisance of despotic power under the old monarchy, and presented a formidable barrier to the advancing tide of the Revolution. Ere long, therefore, the popular desire for independence, coinciding with the designs of the demagogues, raised the cry, which speedily resounded throughout the whole of Paris, — Down with the Bastille! Notwithstanding the moats, the walls, and the gns with which the castle was defended, the execution of the scheme presented no great difficulty. The garrison consisted of 138 men, one-third of whom were Invalides; their provisions consisted of a couple of sacks of flour; they were unable to prevent the stoppage of their supply of water; and all hope of aid from without was cut off. From the suburbs an interminable multitude of armed men converged towards the entrance; and from the city came several companies of the regiments which had gone over to the Revolution, headed by the French guards. De Launay, the commandant, however, refused to capitulate, and the struggle began. A number of the citizens, with reckless bravery, succeeded in cutting the chains of the drawbridge, and the first court of the castle was speedily taken; but to the excessive exasperation of the assailants their attack on the second court was repulsed with great loss. The courage of the garrison was now exhausted. The Invalides desired to capitulate, and De Launay, who had been prevented by his officers from blowing up the castle and its inmates, let down the second bridge on being promised a free retreat. The victorious crowd immediately poured into the ancient building, some of them enthusiastic in the cause of Liberty, others bent on murder and destruction. The lives of the garrison were now in great jeopardy. The French guards succeeded with difficulty in saving the common soldiers; but De Launay and his officers, in spite of the long and heroic attempts of the leaders of the populace to protect them, were slain, and their heads cut off as trophies'. — *H. v. Sybel, Period of the Revolution.*

A reproduction of the Bastille and its environs may be seen near the Champ de Mars, p. 284. — A line drawn on the ground in 1880 between the Boulevard Henri IV. and the Rue St. Antoine, indicates the exact site of the fortress so far as it is not now built over.

Some of the stones of the Bastille were afterwards employed in the construction of the Pont de la Concorde. The *Place* is also a noted spot in the annals of two subsequent revolutions. In June, 1848, the insurgents erected their strongest barricade at the entrance to the Rue du Faubourg St. Antoine, to the E. of the *Place*, and it was only with the aid of heavy artillery that this barrier was demolished. On 25th June, the third day of the contest, *Archbishop Affre* (p. 223), while exhorting the people to peace, was killed by an insurgent's ball. In May, 1871, the site of the Bastille was one of the last strongholds of the Communists, by whom every egress of the *Place* had been formidably barricaded, but it was captured after a desperate struggle by the Versailles troops on the 25th of the month.

A monument similar to that which now adorns the *Place* was first projected in May, 1789, when the 'tiers état' demanded the demolition of the Bastille and the erection on its site of a column bearing the inscription — 'A Louis XVI. restaurateur de la liberté publique'. Napoleon I. intended to have erected an elephant in bronze, 78 ft. in height, on this spot, but his plan was never carried out. After the Revolution of July, 1830, the original scheme was revived, and decrees were passed sanctioning the erection of a

monument in honour of the heroes who fell on that occasion. The **Colonne de Juillet**, as the monument was named, was designed by *Alavoine* (d. 1834), after whose death the work was superintended by *Duc* (d. 1879), and was solemnly inaugurated on 28th July, 1840.

The total height of the monument is 154 ft., and it rests on a massive round substructure of white marble, originally intended for Napoleon's elephant. On this rises a square basement, on each side of which are six bronze medallions symbolical of Justice, the Constitution, Strength, and Freedom, and on the basement is placed the pedestal of the column. On the W. side of the pedestal is represented a lion in relief (the astronomical symbol of July), by *Barye* (d. 1875), under which is the inscription — 'A la gloire des citoyens français qui s'armèrent et combattirent pour la défense des libertés publiques dans les mémorables journées des 27, 28 et 29 juillet 1830'; on the E. side are the armorial bearings of the city and the dates of the decrees mentioned above; on the N. and S. sides are the dates of the conflicts in which the 'July heroes' fell. At each of the four corners is seen the Gallic cock holding garlands. The column itself is of bronze, 13 ft. in thickness, and fluted. It is divided by four bands into five sections, on which the names of the fallen (615) are emblazoned in gilded letters. The capital is surmounted by a kind of lantern, crowned with the Genius of Liberty standing on a globe, by *J. Dumont* (d. 1884).

The INTERIOR (adm. gratis), which receives light and air through the open lions' jaws in the bands above mentioned, contains an excellent staircase of 212 steps leading to the top, where a fine view is enjoyed, particularly of the neighbouring cemetery of Père Lachaise (p. 176).

The VAULTS (20 c.), to which a visit may also be paid, consist of two chambers, each containing a sarcophagus, 45 ft. in length and 7 ft. in width, with the remains of the fallen. In the same receptacles were afterwards placed the victims of the Revolution of February, 1848. In May, 1871, during the Communist reign of terror, these vaults, and boats on the canal beneath, were filled with gunpowder and combustibles by the insurgents for the purpose of blowing up the column and converting the whole neighbourhood into a heap of ruins. Fortunately the attempt was unsuccessful. The custodian opens a small door in one of the vaults to show the massive arches above the canal.

To the N. of the Place de la Bastille is the wide *Boulevard Richard-Lenoir*, running above the *Canal St. Martin* (p. 186), which communicates by means of a tunnel with the basin of the *Gare de l'Arsenal* and the Seine on the S., and with the *Bassin de la Villette*, on the W. The canal being navigable for barges and small tug-steamers, smoke is occasionally seen issuing from air-holes concealed among the shrubberies in the boulevard. To the left of this boulevard are the *Boulevard Beaumarchais*, which we follow, and the *Rue St. Antoine*, leading to the Rue de Rivoli (p. 58). To the S.W., at the end of the *Boulevard Henri IV.*, in the distance, rises the fine dome of the Panthéon (p. 236). The *Rue du Faubourg St. Antoine*, well known from the Revolution of 1848, leads E. from the Bastille to the Place de la Nation and to Vincennes (p. 210). —

To the S.E. is the *Gare de Vincennes* (p. 24), adjoining which is one of the busiest omnibus and tramway stations in Paris (comp. Plans in the Appx.). Restaurants, see p. 13.

To the left of the Boulevard Henri IV. rises the *Caserne des Célestins*, on the site of a celebrated convent, which is to be rebuilt. To the left diverges the Rue de Sully, in which is situated the valuable *Bibliothèque de l'Arsenal* (Pl. R, 25; V), occupying part of the old arsenal of Paris, which extended from the Seine to the Bastille. The Library is open daily 9-6, except on Sundays and holidays and during the vacation (15th Aug. to 1st Sept.). Its founder was the *Marquis Paulmy d'Argenson*, who sold it in 1785 to the Comte d'Artois. The latter added the Duc de la Vallière's library to it in 1787. During the Revolution it became government property and was thrown open for general use. In 1815, after the Restoration, it was restored to the Comte d'Artois, and under the name of *Bibliothèque de Monsieur* was still left accessible to the public. At the July Revolution it fell once more into the hands of the state, and received its present name. After the *Bibliothèque Nationale* it is the finest library in Paris. It is especially rich in theatrical literature.

The Boulevard Henri IV. crosses the two arms of the Seine and the E. end of the Ile St. Louis by means of the *Pont Sully*. On the island is the Hôtel Lambert (p. 224).

On the Quai Henri IV. is the old *Hôtel la Valette*, now the *Ecole Massillon*, a handsome building of the 16th cent., recently restored. On the Quai des Célestins, at the corner of the Rue Figuier, rises the old *Hôtel de Sens*, or palace of the archbishops of Sens when they were metropolitans of Paris. It is a Gothic building of the 15th cent., with turrets and a *donjon* in the court.

III. THE BOULEVARDS FROM THE BASTILLE TO THE MADELEINE.

Place de la République. Portes St. Martin and St. Denis. The Bourse.
The Opéra.

The omnibus may, in case of fatigue, be taken from the Bastille as far as the Place de la République, or the whole way. Best view from the top, on the right side.

The **Boulevards** of Paris are divided into four classes: the Old or Inner Boulevards, the External Boulevards, the New Boulevards, and the Boulevards of the Enceinte or Lines.

(1) The *Old* or *Inner Boulevards* derived their name from having been constructed in the reign of Louis XIV. on the site of the ancient boulevards ('bulwarks') or fortifications, which formerly surrounded the city. They are divided by the Seine into a northern and a southern half. The northern half, the 'Boulevards Intérieurs du Nord', or '**Great Boulevards**', commonly known *par excellence* as '*The Boulevards*', extend in a semicircle from the Bastille (Pl. R, 25; V) to the Madeleine (Pl. R, 18; II), a distance of $2\frac{3}{4}$ M., and are never less than 33 yds. in width. These Boulevards consist of the following 11 subdivisions: Boulevard Beaumarchais, B. des Filles-du-Calvaire, B. du Temple, B. St. Martin, B. St. Denis, B. Bonne-Nouvelle, B. Poissonnière, B. Montmartre, B. des Italiens, B. des Capucines, B. de la Madeleine. These imposing streets are nowhere surpassed in the handsomeness of their architecture, the briskness of their traffic, and the attractiveness of their shops. The Great Boulevards are continued on the left bank by the Boulevard St. Germain. — The 'Boulevards Intérieurs du Sud', forming the southern half, extend

in another semicircle ($4\frac{1}{2}$ M. long) on the left bank of the Seine, from the Pont d'Austerlitz to the Pont des Invalides, and consist of the B. de l'Hôpital, B. d'Italie (formerly des Gobelins), B. St. Jacques, B. Raspail, B. du Mont-Parnasse, and B. des Invalides. These Boulevards are now scarcely distinguished from the following.

(2) The *Outer Boulevards* ('B. Extérieurs'), laid out on the site of the octroi wall of Louis XVI., still retain their name, though it has been less appropriate since 1860, when the suburban districts (*banlieue*) were annexed to Paris. The northern line of these, beginning at the Pont de Bercy, is $9\frac{3}{4}$ M. long, while the southern half, also beginning at the Pont de Bercy, but uniting at places with the old Boulevards Intérieurs, is $5\frac{1}{2}$ M. in length.

(3) The *New Boulevards* ('B. Nouveaux') have been laid out since 1852. Of these the most important are the following: — B. de Strasbourg, B. de Sébastopol, B. du Palais, B. St. Michel, B. Malesherbes, B. Haussmann, B. de Magenta, B. des Amandiers, B. Voltaire, B. Richard-Lenoir, and B. St. Germain. With this class of Boulevards, which have no connection with 'bulwarks' or fortifications either ancient or modern, may be ranked numerous *Avenues*, such as the Avenues de l'Opéra, des Champs-Élysées, de Friedland, Hoche, Victor Hugo, de l'Alma, du Trocadéro, etc.

(4) The *Boulevards d'Enceinte* form a military road skirting the inside of the present wall of Paris, and consist of 19 sections.

The Boulevards were formerly paved, but as the stones had frequently been used in the construction of barricades they were replaced in 1850 by a macadamised roadway, which has more recently given way to one of wood. The side-walks for foot-passengers are of asphalte. The trees with which the boulevards and many of the most important thoroughfares are flanked are a source of constant trouble to the municipal authorities, being frequently killed by the gas. When dead they are replaced by full-grown substitutes, transplanted at great expense from a more healthy atmosphere.

The traffic on the Grands-Boulevards is immense, especially at the ends of the Boulevard Montmartre, the Place de l'Opéra, and other points where the streets intersect (comp. p. 73). At most of the crossings 'refuges' have been erected for pedestrians.

Cafés in the Boulevards, see p. 18; *Restaurants*, p. 13; *Theatres*, pp. 29, 30; *Shops*, p. 35.

The small glass stalls where newspapers are sold, and which are also covered with advertisements, are called '*Kiosques*'. Besides these there are '*Trinkhalles*' (a word borrowed from the German) for the sale of soda-water, lemonade, and other beverages. Chairs are placed for hire (*chaises* 10, *fauteuils* 20c.) in the broadest parts of the boulevards; there are also numerous benches for the use of the public. The principal *cafés* (p. 18) place chairs outside their doors in summer. The most frequented part is afforded by the

Boul. des Italiens and the *Boul. des Capucines*, with the adjoining *Avenue de l'Opéra* and *Avenue de la Paix*, where the scene on fine evenings is of indescribable animation and brilliancy. The E. boulevards, with which the following description begins, are less frequented. When the traffic reaches its climax, in the afternoon, the top of an omnibus is a good point of observation.

The **Boulevard Beaumarchais** (Pl. R, 26; *III*, V), called after the author of that name (d. 1799), who owned a considerable part of the E. side of the street, is the longest of the Great Boulevards, being 770 yds. in length. It was the scene of the most obstinate struggles during the insurrection of 1848. No. 25, on the left, is the small *Théâtre Beaumarchais*, or *Fantaisies-Parisiennes*. Farther on, also to the left, diverges the Rue des Vosges, leading to the *Place* of that name (p. 209).

The Rue St. Claude, also diverging from the Boulevard to the left, leads to the church of St. Denis du Saint-Sacrement, built in 1830 and containing paintings by Pujol, Court, Picot, Decaisne, and Eug. Delacroix, the best of which is the *Pietà* by the last, in the chapel to the right of the entrance.

The **Boulevard des Filles-du-Calvaire** (Pl. R, 26; *III*), which adjoins the Boulevard Beaumarchais, is 330 yds. long. It derives its name from a nunnery founded in 1633 and suppressed in 1790. At its N. end, to the right, is the *Cirque d'Hiver* (p. 31).

Beyond the Rue des Filles-du-Calvaire begins the **Boulevard du Temple** (Pl. R, 27; *III*), 550 yds. in length, once known as the *Boulevard du Crime*, a nickname given to it on account of the numerous melodramatic theatres formerly situated here. It was at that time the fashionable promenade of the citizens, when the centre of Paris lay more to the E. No. 42, situated at a bend of the street, occupies the site of the house from which Fieschi on 28th July, 1835, discharged his infernal machine at Louis Philippe. The king escaped unhurt, but Marshal Mortier and fourteen other persons were killed. Farther on, to the left, is the *Théâtre Déjazet* (p. 31).

The Boulevard du Temple terminates in the ***Place de la République**, formerly called the *Place du Château-d'Eau* (Pl. R, 27; *III*), one of the finest squares in Paris (300 yds. long). The centre is embellished with a bronze *Statue of the Republic*, by the brothers Morice, erected in 1883, which is 32 ft. high to the top of the olive-branch. The stone pedestal, 50 ft. in height, is surrounded with seated bronze figures of Liberty, Equality, and Fraternity, and adorned with 12 bas-reliefs in bronze, by Dalou: Capture of the Bastille; Taking the oath in the Jeu de Paume; Renunciation of privileges; Festival of the Federation; Meeting of the Constituent Assembly; Volunteers enrolling; Battle of Valmy; Combat of the 'Vengeur'; Resumption of the tricolor in 1830; Provisional Government of 1848; September 4th, 1870; National Fête, July 14th, 1880. In front is a brazen lion with the urn of 'suffrage universel'. On each side are two rows of handsome plane-trees, planted in 1880, among

which are distributed several small fountains and Venetian masts. — To the N.E. are the *Hôtel Moderne* (opened in 1889) and the *Caserne du Prince Eugène*, which is capable of accommodating 3235 men.

Streets diverge from the Place de la République in every direction. To the S.E. is the *Boulevard Voltaire* (p. 175); to the E. runs the *Avenue de la République*, which is being prolonged to the Père-Lachaise (p. 176); to the N.E. the *Rue du Faubourg du Temple* leads to Belleville (p. 46), and is traversed by a cable-tramway (10 c.). To the N.W. diverges the *Boulevard de Magenta*, which leads past the Gare de l'Est and the Gare du Nord (p. 24) to Montmartre; to the left, near this end, is the *Bourse du Travail*, built in 1889-90 by Bouvard. To the S.W. are the old *Rue du Temple*, leading to the Hôtel de Ville, and the wide *Rue de Turbigo*, more to the right, descending to the Halles Centrales (p. 170).

A short distance down the Rue du Temple, to the left, rises the *Marché du Temple* (Pl. R, 27; *III*), erected in 1863-65 on the site of a number of unsightly wooden sheds that formed the old market. The same spot was once occupied by the *Temple*, a stronghold erected by the Knights Templar in 1212, and after the suppression of the order (1312) used for a long period by the kings of France as a treasury. During the Revolution (in 1792 and 1793) part of this building, the *Tour du Temple*, attained notoriety as the prison of the royal family, and in 1811 it was taken down. The market-hall covers an area of 16,940 sq. yds., and contains 2400 stalls. The *Square du Temple* is embellished with four bronze statues: Béranger (1780-1857), by Doublemard; the 'Retiarius', by Noël; 'This age is pitiless', by Schœnewerk; and the Harpooner, by J. Richard. The handsome modern building at the E. end is the *Mairie of the Third Arrondissement* (du Temple).

To the right, between the Rue du Temple and the Rue de Turbigo, is the church of *Ste. Elisabeth*, dating from the 17th cent. but enlarged in 1826. The fonts in white marble, to the right of the door, were erected in 1654. The small cupola of the choir is adorned with an Apotheosis of St. Elisabeth, by Alaux, and there are paintings by Biennoury, Hesse, Roger, and Lafon, in a chapel to the left of the entrance. The fine wood-carvings of Biblical scenes (16th cent), were brought from a church at Arras.

Beyond the Place de la République we next reach the *Boulevard St. Martin* (Pl. R, 27, 24; *III*), 710 yds. long, the houses of which stand on a slight eminence. The carriage-way was levelled in 1845, to facilitate traffic, while the foot-pavements retain their original height. Several theatres (see p. 31) are situated on the right side of this boulevard.

The *Porte St. Martin*, a triumphal arch, 57 ft. in height, 57 ft. in breadth, and 14 ft. in thickness, designed by *Pierre Bellet*, was erected by the city in honour of Louis XIV. in 1674. The inscriptions and reliefs commemorate the victories of that monarch; on the S. side are represented the capture of Besançon, and the Triple Alliance, by *Dujardin* and *G. Marsy*; on the N. the taking of Limbourg, and the defeat of the Germans, by *Le Hongre* and *Le-gros the Elder*. On 31st March, 1814, the German and Russian armies entered Paris by the Barrière de Pantin and the Rue du Faubourg St. Martin, and passed through the *Porte St. Martin* and the Boulevards to the Place de la Concorde (p. 81).

Beyond the *Porte St. Martin* begins the short **Boulevard St. Denis** (Pl. R, 24; *III*), 270 yds. in length. The handsome streets which diverge here to the right and left, intersecting Paris from N. to S., are the *Boulevards de Sébastopol* and *de Strasbourg*. At the end of the *Boulevard de Strasbourg*, to the right, is the *Gare de l'Est*. To the left, at the end of the *Boulevard de Sébastopol*, rises the dome of the *Tribunal de Commerce* (p. 219). About 200 yds. to the left of this boulevard is the *Square des Arts et Métiers*, in front of the *Conservatoire* of that name (p. 173).

We now reach the **Porte St. Denis**, another triumphal arch, designed by *Blondel*, with sculptures by the brothers *Anguier*, and erected two years before the *Porte St. Martin*, to commemorate the victories of Louis XIV. in Holland and the district of the Lower Rhine. It is 81 ft. high, 82 ft. wide, and only 16 ft. thick. The single archway is 50 ft. in height and 26 ft. in width. The piers are adorned with two obelisks in relief covered with military trophies. At the bases of the piers are represented, on the left, vanquished Batavia (Holland) with a dead lion, and on the right the river-god of the Rhine. Nearly all the sculptures were restored in 1886-87.

Both these triumphal arches were the scene of sanguinary conflicts in July 1830, June 1848, and May 1871.

The *Porte St. Denis* stands between the *Rue St. Denis* and the *Rue du Faubourg St. Denis*, together forming one of the most ancient, and still one of the most important lines of streets in Paris.

As we proceed westwards the traffic becomes brisker, and the shops more handsomely built and richly stocked.

The continuation of the *Boulevard St. Denis* is the **Boulevard Bonne-Nouvelle** (Pl. R, 24; *III*), which is 380 yds. in length. On the right, No. 20, is the 'Ménagère Bazaar' (p. 38), and farther on, also to the right, are the *Rue d'Hauteville*, at the end of which the church of *St. Vincent-de-Paul* (p. 188) is seen in the distance, and the *Théâtre du Gymnase* (p. 29).

At the point where the *Rue du Faubourg-Poissonnière* diverges to the right, and the *Rue Poissonnière* to the left, begins the **Boulevard Poissonnière** (Pl. R, 21; *III*), which is also 380 yds. long.

In the *Rue du Faubourg-Poissonnière*, No. 15, is the *Conservatoire de Musique et de Déclamation* (Pl. B, 21, 24; *III*), founded in 1784 for the purpose of training singers and actors for the national stage. The staff of teachers numbers 73, and there are about 600 enrolled pupils, besides 200 'hearers'. Pupils are admitted by competition and receive their training gratuitously. Winners of the *Grand Prix* are awarded an annual allowance of 3000 fr. for four years, during which they visit Italy and Germany for the purpose of perfecting themselves in their art. The *Conservatoire* possesses a valuable *Collection of Musical Instruments*, open to visitors on Thurs., 12-4; and an extensive *Musical Library*. Concerts, see p. 32.

A little farther on, at the corner of the short *Rue Ste. Cécile* and the *Rue du Conservatoire*, is the church of *St. Eugène*, a Gothic edifice, built in 1854-55 from the design of M. Boileau. The interior is supported by cast-iron columns and is embellished with paintings and stained glass in the style of the 13th century.

Farther on, to the right of the Boulevard, diverges the small *Rue de Rougemont*, at the end of which is seen the *Comptoir d'Escompte*, rebuilt in 1882-83. Its façade, surmounted by a dome with a small spire, has a fine doorway in the form of a triumphal arch, decorated with symbolic statues by A. Millet.

On the right of the Boulevard Poissonnière, No. 30, is the attractive shop of *Barbedienne & Co.*, dealers in bronzes (p. 36).

At the point where the *Rue Montmartre* diverges to the left, and the *Rue du Faubourg-Montmartre* to the right, we reach the **Boulevard Montmartre** (Pl. R, 21; *III*), which is 270 yds. in length. The point where these three streets intersect, called the *Carrefour Montmartre*, is perhaps the busiest in Paris; over 100,000 vehicles a day pass through it. — On 24th Febr., 1848, and in May, 1871, the end of the Rue du Faubourg-Montmartre next to the Boulevards was closed by a strong barricade.

Not far off, to the right of the Rue Montmartre, is the Rue Notre-Dame-des-Victoires, which passes behind the Exchange (see below). Farther down, Rue Montmartre 144, is the *Office of 'La France'*, a fine building erected in 1882-83 by Bal. The newspaper is printed upon three rotatory Marinoni presses, each producing 20,000 copies per hour, printed, folded, and counted. Visitors admitted, 4-6 p.m. — The street ends at the Halles Centrales.

The cafés become more numerous, and the shops more attractive. On the left stands the *Théâtre des Variétés* (p. 30). On the same side is the *Passage des Panoramas*, and opposite to it the *Passage Jouffroy*. These two arcades, with their handsome shops, are generally thronged with foot-passengers, especially towards evening. (Restaurants and cafés, see pp. 13, 18.) In the Passage Jouffroy are the *Musée Grévin* (p. 32) and the bazaar named the *Galerie Orientale*. On the left, farther on, the *Rue Vivienne* diverges to the (3min.) Bourse (see below) and the Palais-Royal (p. 56).

The Boul. Montmartre ends at the *Rue de Richelieu* and the *Rue Drouot*.

A few hundred paces to the S. of the Boulevard Montmartre is the small *Place de la Bourse*, in the centre of which rises the ***Bourse**, or *Exchange* (Pl. R, 21; *III*), a handsome building in the Græco-Roman style, surrounded by a series of 66 Corinthian columns, being an imitation of the Temple of Vespasian in the Forum at Rome. It was begun in 1808 by *Brongniart* (d. 1813), and completed in 1826 by *Labarre* (d. 1833). Length 75 yds., width 45 yds., height 100 ft.; columns 33 ft. high, and 31½ ft. thick. The edifice is enclosed by a railing, and approached by a flight of sixteen steps at each end. At the corners in front are allegorical statues of Commerce by *J. Dumont* (d. 1844), and Consular Justice by *Duret* (d. 1865); at the back, Industry by *Pradier* (d. 1852), and Agriculture by *Seurre* (d. 1858).

The hall of the Bourse, which is 35 yds. in length, and 19 yds. in width, is opened for business daily, except on Sundays and holi-

days, at 12 o'clock. A few minutes before that hour the *Place* begins to present a busy scene. Numerous vehicles, chiefly private carriages, drive up, and the money-seeking throng hurries into the building. Business, however, does not fairly begin till about half past twelve. The *parquet*, at the end of the hall, is a railed-off space which the sworn brokers, or *agents de change*, alone are privileged to enter. In the centre of this part of the hall is the *corbeille*, a circular, railed-off space, round which they congregate, making their offers in loud tones. Various groups in different parts of the hall, but especially near the *parquet*, are occupied in taking notes, or concluding sales or purchases, the prices being regulated by the transactions going on in the *parquet*, while other persons are seen handing instructions to the brokers within the *parquet*.

The tumultuous scene is best surveyed from the gallery, reached from the vestibule by two staircases ascending to the right and left of the large hall. The deafening noise, the vociferations, and the excited gestures of speculators, produce a most unpleasant impression. Amidst the Babel of tongues are heard the constantly recurring words, '*J'ai . . . ; qui est-ce qui a . . . ? ; je prends ; je vends !*'

The visitor should not omit to observe the 'grisailles' on the vaulting, by *Abel de Pujol* (d. 1861) and *Meynier*. They represent the Inauguration of the Bourse by Charles X., France receiving tribute from every part of the globe, the Union of commerce with the arts and the sciences, and the Principal Cities of France. The paintings in imitation of reliefs are very skilfully executed.

At 3 o'clock the business of the stock-exchange terminates, the brokers assemble and note the prices realised in their transactions, and in accordance with these they adjust the share-list for the day, which is then immediately printed and issued. The hall remains open till 5 o'clock for the transaction of other mercantile business. The annual amount of business transacted in the Bourse has been calculated at 50 milliards of francs or 2,000,000,000*l.* Telegraph and telephone office, see p. 26.

The handsome *Rue du Quatre-Septembre* leads to the W. from the *Place* du Bourse to the *Avenue de l'Opéra* (p. 76); the *Rue de la Banque* (p. 169) leads to the S. to the *Bank of France* (p. 169).

The ***Boulevard des Italiens** (Pl. R, 24; *III, II*), 600 yds. in length, beginning beyond the *Rue de Richelieu* (on the left, with a painted bust of the cardinal) and the *Rue Drouot* (on the right), to which the *Boulevard Haussmann* is to be continued, is the most frequented and fashionable of the boulevards, consisting almost exclusively of handsome hotels and cafés (on the right, No. 16, *Café Riche*; No. 20, *Maison Dorée*; and several others on the left), and the choicest and most expensive shops. The boulevard derives its name from the old *Théâtre des Italiens*.

In the *Rue Drouot*, to the right, No. 6, is the *Mairie of the IXth Arrondissement* (de l'*Opéra*), occupying the old *Hôtel Aguado*. To the left,

farther on, No. 9, is the *Hôtel des Ventes Mobilières*; a large public auction-room, the 'Christie and Manson's' of Paris, where extensive sales of works of art take place in winter at 2 p.m. The best works generally come to the hammer about 4 p.m. Considerable experience is, however, necessary to make purchases here with advantage, and the stranger is warned against entering into a useless or expensive competition with the brokers, who are always ready to unite against the 'common enemy'.

Near the beginning of the Boulevard des Italiens, on the right (N.), is the *Passage de l'Opéra* (so named from the old opera-house, burned down in October, 1873, which stood at the N. end of it), with the *Galleries de l'Horloge* and *du Baromètre*. It is now almost entirely deserted.

On the right, farther on, is the *Rue Le Peletier*, where Orsini attempted to assassinate Napoleon III. on 14th Jan., 1858. The following streets, the *Rue Laffitte*, the *Rue Taitbout*, and the *Rue de la Chaussée d'Antin*, are chiefly inhabited by wealthy bankers and moneyed men. At the corner of the Rue Laffitte is the *Maison Dorée* restaurant, with interesting sculptures; No. 21 in this street is the Rothschilds' office; and at the end is the church of Notre-Dame-de-Lorette (p. 194), beyond which rises the Butte Montmartre (p. 189), with the Church of the Sacré-Cœur, and the new reservoir. No. 28 in the boulevard is the *Théâtre des Nouveautés* (p. 30).

At the Rue Taitbout begins the handsome *Boulevard Haussmann* (Pl. B, 21, 18, 15), so called in honour of the Prefect of the Seine (d. 1891) under whom were effected the great transformations in the Paris of the Second Empire. It leads behind the Opéra (p. 76) to the Chapelle Expiatoire (p. 204), and is thence prolonged to the ($1\frac{3}{4}$ M.) Arc de Triomphe de l'Etoile by the Avenue de Friedland. If continued in the other direction to the Boulevard Montmartre, a distance of 300 yds., it would form the most direct route from that neighbourhood to the Bois de Boulogne. The expense of removing buildings, etc., would, however, amount to 25-30 million francs.

On the left of the Boulevard des Italiens, opposite the Passage de l'Opéra, is the *Passage des Princes*, leading to the Rue de Richelieu. Farther on are the Rue Favart and the Rue Marivaux, between which was the *Opéra Comique* (p. 29), burned in May, 1887. Beyond are the Rue Grammont and the imposing building of the *Crédit Lyonnais*, at the corner of the Rue de Choiseul. On the S. side of the boulevard we next observe the *Pavillon de Hanovre*, No. 33, built by Marshal de Richelieu in 1760 (partially rebuilt in 1888), and containing the principal dépôt of the 'Orfèvrerie Christoffe' (p. 37).

The Rue de la Michodière, on this side of the Pavillon de Hanovre, leads to the pretty *Fontaine Gaillon* (Pl. R, 21; II), which consists of two richly-sculptured basins, surmounted by a Genius striking the head of a dolphin with a trident.

Beyond the Rue de la Chaussée d'Antin (on the right), at the end of which rises the church of La Trinité (p. 200), begins the handsome **Boulevard des Capucines* (Pl. R, 18; II), 550 yds. in length. On the right are the *Théâtre du Vaudeville* (p. 29), the *Café Américain*, the *Grande Maison de Blanc* (linen, etc.; p. 37), and the handsome shop of A. Klein, the dealer in Viennese leather and fancy goods (p. 38).

We next reach the *PLACE DE L'OPÉRA (Pl. R, 18; II), which is intersected by the Boulevard des Capucines, and where five other broad streets converge. To the S. run the *Rue de la Paix*, with its tempting shops and the Vendôme Column in the background (p. 84), the handsome **Avenue de l'Opéra*, leading to the Place du Théâtre-Français (p. 58), with the dome of the Pavillon de Marsan (Tuileries) rising at the other end, and the *Rue du Quatre-Septembre*, leading to the Bourse (p. 73). To the N., on the left and right of the Opera, are the *Rue Halévy* and the *Rue Auber*, the latter leading to the Gare St. Lazare (p. 204). To obtain space for this *Place* between four and five hundred houses had to be removed, and that from the quarter where house-property is most valuable. Continuation of the Boulevard, p. 79. On the N. side of the *Place* rises the —

***Opera House**, a most sumptuous edifice bearing the inscription '*Académie Nationale de Musique*', designed by *Garnier*, begun in 1861, and completed in 1874. It is now the largest theatre in the world, covering an area of 13,596 sq. yds. (nearly three acres); but it contains seats for 2156 persons only, being less than the number accommodated by the opera-house at Vienna or the vast theatres of La Scala at Milan and San Carlo at Naples. Nothing can surpass the magnificence of the materials with which the building is lavishly decorated, and for which the whole of Europe has been laid under contribution. Sweden and Scotland have yielded a supply of green and red granite, from Italy have been brought the yellow and white marbles, from Finland red porphyry, from Spain 'brocatello', and from different parts of France other marbles of various colours. In 1860 competitive plans for the New Opera were sent in by the most eminent architects in France, and it was resolved that the edifice should in every respect be the most magnificent of the kind in the world. Begun under the auspices of the Second Empire, the work has been most successfully completed by the Republic. In many respects, however, the building is open to criticism. The façade in particular, notwithstanding the richness of its ornamentation, has a somewhat heavy and depressed appearance. The magnificent interior, on the other hand, with its staircase, corridors, saloons, and other details, is exceedingly effective and is altogether an unrivalled work of the kind. The cost of the site of the Opera amounted to 10½ million francs (420,000*l.*), and that of the building to 36,500,000 fr. (1,460,000*l.*).

The PRINCIPAL FAÇADE, which is approached by a broad flight of steps, consists of three stories. On the ground-floor is the *Portico* with its seven arches, of which the two outer ones, on the right and left respectively, form the principal entrances. Flanking each of these are two large groups of statuary, and the piers of the intervening arches are embellished with four statues. These groups and statues are, beginning on the left, Lyric Poetry by *Jouffroy*, Music

by *Guillaume*, Idyllic Poetry by *Aizelin*, Declamation by *Chapu*, Song by *Dubois* and *Vatrinelle*, Drama by *Falguière*, Dance by *Carpeaux* (d. 1875), and Lyric Drama by *Perraud*. The group by *Carpeaux* though admirably executed, has been severely and justly criticised for the sensuality of its style. Above the statues are medallions of Bach, Pergolese, Haydn, and Cimarosa. Above the portico is the *Loggia*, a gallery with square windows corresponding with the doors, with marble parapets, and each flanked with two Corinthian monolithic columns, 33 ft. in height. Fourteen smaller Corinthian columns of red marble, with gilded bronze capitals, form a kind of frame to the windows. In niches above the windows are medallion busts, in gilded bronze, of Mozart, Beethoven, Spontini, Auber, Rossini, Meyerbeer, and Halévy. Above the loggia the façade terminates in an attic, richly embellished with mosaics and gilded masks, and with colossal gilded groups by *Gumery*, one on each side, representing Music and Poetry, attended by the Muses and goddesses of victory. In the centre of the building rises a low dome (visible from a distance only), and behind it a huge triangular pediment, above the stage, crowned with an Apollo with a golden lyre in the middle, by *Millet*, and flanked with two Pegasi by *Lequesne*. — There is also a pavilion in the centre of each of the LATERAL FAÇADES, that on the left side of the grand façade having a double carriage-approach ('pavillon d'honneur'). The pavilion on the other side, in the Rue Halévy, is the entrance for regular subscribers. The lateral façades are adorned like the principal one with busts of composers and allegorical figures.

In order to obtain an accurate idea of the vast dimensions and lavish ornamentation of the edifice, the traveller should walk round the whole of it, inspecting each façade in turn.

****INTERIOR.** Passing through the gilded gates, we first enter the VESTIBULE, containing the ticket-offices, and adorned with statues of Lully, Rameau, Gluck, and Händel. Opposite to us is the ****Grand Staircase** ('*Escalier d'Honneur*'), ascending to the first floor. As far as the first landing, where the entrance to the amphitheatre and orchestra is situated, the staircase is single, being about 32 ft. in width, but beyond that it divides into two flights of steps. The steps are of white marble, and the balustrades of *rosso antico*, with a hand-rail formed of Algerian onyx. Each landing of this magnificent staircase is furnished with boxes or balconies from which the visitor may conveniently survey the interesting scene presented by the passing throng. The 24 coloured marble columns which separate these balconies, grouped in pairs, rise to the height of the third floor. The ceiling-frescoes by *Pils* (d. 1875), beginning on the right, represent the Gods of Olympus, the Triumph of Harmony, the Instructiveness of the Opera, and Apollo in his Chariot. The handsome door on the first landing, flanked by caryatide figures of Tragedy and Comedy, and the bronze groups supporting the lamps should also

be noticed. Below the grand staircase, in a room reached from the subscribers' entrance (p. 77), are the *Bassin de la Pythie*, a fountain with a priestess of Apollo in bronze, seated on a tripod, by *Marcello* (a pseudonym of the Duchess of Colonna di Castiglione), and a marble statue of Music, by *Delaplanche*. — Visitors who take their tickets at the door have to ascend to their places by side-staircases, but may inspect the Grand Staircase during the 'entr'actes'.

The *SALLE, or theatre itself, fitted up in the most elaborate style, is rather overladen with decoration, which, however, has already begun to fade. The boxes, of which there are four tiers, all equally well fitted up, are divided into seven bays by eight huge columns. The gallery forms a fifth story. The 'Avant-scènes', which are rather narrow, are adorned with Caryatides in coloured marble and bronze. Above is a handsome frieze, and numerous small windows in the shape of lyres. The magnificent and curiously shaped lustre contains 340 burners, and seen from below presents the appearance of a crown of pearls. The ceiling-paintings, by *Lenepveu*, represent the different hours of the day and night, allegorised.

The STAGE is 196 ft. in height, 178 ft. in width, and 74 ft. in depth. At the back of the stage, and communicating with it, is the *Foyer de la Danse*, or ball-room, with portraits of 20 celebrated 'danseuses' and other paintings by Boulanger (not open to the public).

The *Grand Foyer, the most striking feature of the Opera House, extends throughout the whole length of the building. It is entered by the 'Avant-Foyer', the vaulting of which is adorned with mosaics designed by *Curzon*, and executed by Salviati, representing Diana and Endymion, Orpheus and Eurydice, Aurora and Cephalus, and Psyche and Mercury. The Foyer itself is 175 ft. long, 42 ft. wide, and 59 ft. in height. It is lighted by ten gilded lustres and several huge candelabra. Five windows and two doors lead from the Foyer to the Loggia. Opposite the windows are huge mirrors, 23 ft. high, separated by twenty columns bearing statues emblematical of the qualities required by an artist. At the ends are also two monumental chimney-pieces with Caryatides of coloured marble, by *Thomas* and *Cordier*. The chief embellishment of the hall, however, consists of the paintings by *Baudry*, on the walls, ceiling, and over the doors and mirrors. On the ceiling, are Melody and Harmony in the centre, with Tragedy and Comedy at the sides. Over the chimney-pieces are Mount Parnassus and the Poets of Antiquity. The other paintings represent the Muses, with the exception of Polyhymnia (Philosophy), the Music of different nations, and Dancing. All the paintings have suffered sadly from the gas. — To the left, as we quit the hall, is a buffet, decorated with tapestry designed by *Maserolle*. — Beyond the chimney-pieces mentioned above are several smaller rooms.

In the Pavillon d'Honneur (p. 77), Rue Auber, are a *Library* belonging to the Opera and a small *Musée de l'Opéra*. The latter, open on week-days 11-4, contains models of scenery, busts and portraits of stage celebrities, MSS. of well-known composers, old play-bills, and the like.

The *Eden Theatre* (Pl. R, 18; II; p. 31), in the Rue Boudreau, near the Opéra, is a fantastic building in the Indian style, erected in 1882, for ballets, etc. The interior, a close imitation of a pagoda, with ceiling-paintings by *Clairin*, is worth a visit.

In the Boulevard des Capucines we next observe on the right (N.) the *Grand-Hôtel* (p. 3), with the *Café de la Paix*; beyond which is the Rue Scribe.

We now reach the **Boulevard de la Madeleine** (Pl. R, 18; II), which is 220 yds. in length, and leads hence to the Place de la Madeleine. Part of the N. side is called Rue Basse-du-Rempart.

The *Place de la Madeleine*, which is planted with trees, forms the W. extremity of the Old or Great Boulevards. On Tuesdays and Fridays it is converted into a large flower-market. In the centre of the *Place*, entirely detached from other buildings, rises the imposing, though unecclesiastical —

***Madeline**, or *Church of St. Mary Magdalene* (Pl. R, 18; II). The foundation was laid by Louis XV. in 1764, but the edifice in its present form, designed by *Couture*, was not begun till 1777. The Revolution found the edifice unfinished, and Napoleon I. ordered the building to be completed as a 'Temple of Glory', entrusting the execution of this scheme to the architect *Pierre Vignon*. Louis XVIII., however, returned to the original intention of making it a church. After Vignon's death (1828) *Huvé* was appointed the architect. The works were again stopped by the Revolution of July, 1830, but the edifice was at length completed by *Huvé* in 1842, having cost upwards of 13 million francs (520,000*l.*).

The church is built in the style of a late-Roman adaptation of a Greek temple, 354 ft. in length, 141 ft. in breadth, and 100 ft. in height. It stands on a basement about 23 ft. in height, and is surrounded by massive Corinthian columns, eighteen of which are ranged along each side, while sixteen form the S. portico, and eight are placed at the N. end. The building, which is destitute of windows, is constructed exclusively of stone, as is the case with the Bourse, which the Madeleine much resembles externally. The niches in the colonnade contain thirty-four modern statues of saints.

The tympanum of the Principal Façade (S.) contains a high relief of vast dimensions, by *Lemaire* (d. 1880), 126 ft. in length, and in the centre 23 ft. in height, representing Christ as the Judge of the world. The figure of the Saviour is 17 ft. high. On his right are the angel of salvation and the elect; on his left the angel of justice and the damned, with Mary Magdalene interceding for them.

The church is approached by a flight of 28 steps. The bronze **Doors*, 34½ ft. in height and 16 ft. in breadth, are adorned with illustrations of the Ten Commandments by *Triqueti*.

The *Interior (not open to visitors till after 1 o'clock, when the morning services are over; entrance by the side-doors when the principal door is closed), the walls and floor of which are of marble, forms a single spacious hall, with a ceiling in three dome-shaped sections, through the gilded and painted lacunars of which the light is introduced. Under the organ are the *CHAPELLE DES MARIAGES*, to the right of the entrance, with a group in marble by *Pradier*, representing the nuptials of the Virgin; and the *CHAPELLE DES FONTS*, or Baptistery, to the left, with a group by *Rude* (d. 1855), representing the Baptism of Christ. These sculptures are insufficiently lighted. The statues of the Apostles in the spandrels of the vaulting are by the same sculptors and by *Foyatier*.

The walls of the nave are divided by buttresses into six chapels, three on each side, and each containing a statue of its patron saint. The paintings in the semicircular spaces above the chapels represent scenes from the life of Mary Magdalene. — *Right Side*. 1st Chapel: Ste. Amélie, by *Bra* (d. 1863); Mary Magdalene's conversion, by *Schnetz* (d. 1870). — On a pillar here is a tablet to the memory of Abbé Deguerrey, curé of the Madeleine, who was shot by the Communists on 24th May, 1871, at the prison of La Roquette (p. 176). His tomb is in the crypt. — 2nd Chapel: The Saviour, by *Duret*; *Mary Magdalene at the foot of the cross, by *Bou-chot*. — 3rd Chapel: Ste. Clotilde, by *Barye* (d. 1875); Mary Magdalene in the wilderness praying with angels, by *Abel de Pujol* (d. 1861). — *Left Side*. 1st Chapel: St. Vincent-de-Paul, by *Raggi* (d. 1862); Christ in the house of Simon the Pharisee, and Magdalene washing the feet of Christ, by *Coudet*. — 2nd Chapel: The Virgin, by *Seurre*; Angel announcing the Resurrection to Mary Magdalene, by *Coignet*. — 3rd Chapel: St. Augustine, by *Eter*; Death of Mary Magdalene, by *Signol*.

The *HIGH ALTAR consists of a fine group in marble by *Marochetti* (d. 1867), representing Mary Magdalene being borne into Paradise by two angels. — At the back of the altar, on the vaulted ceiling of the choir, is a large fresco by *Ziegler*, representing the History of Christianity in numerous groups. In the centre is Christ, and before him Mary Magdalene, kneeling. On the right there is an illustration of the spread of Christianity in the East in the early centuries of the Christian era, during the Crusades, and in modern times (Expedition to the Morea, 1829). Among other figures may be mentioned St. Louis adjoining the Magdalene, Godfrey de Bouillon with the oriflamme, Richard Cœur-de-Lion, and the Doge Dandolo. To the left is exhibited the progress of Christianity in the West. Among the chief characters are the Martyrs, the Wandering Jew, Charlemagne, Pope Alexander III. laying the first stone of Notre-Dame (1163), the Maid of Orleans, Raphael, Michael Angelo, and Dante. In the centre is Henri IV., entering the pale of the Roman Catholic church; then Louis XIII., Richelieu, and lastly Napoleon I. crowned by Pope Pius VII.

The Madeleine is famed for its sacred music and orchestral performances on great festivals and during Passion Week.

For a description of the Boulevards Malesherbes, St. Augustin, etc., to the N.W. of the Madeleine, see p. 203.

IV. FROM THE MADELEINE TO THE PALAIS-ROYAL BY THE PLACE DE LA CONCORDE.

Colonne Vendôme. St. Roch.

The broad *Rue Royale* leads from the Madeleine to the Place de la Concorde, beyond which, on the opposite bank of the Seine, rises the Palais de la Chambre des Députés (p. 272).

The Rue Royale was the scene of some of the most violent outrages of the Communists in May, 1871. Six houses here were deliberately set on fire, together with several neighbouring houses in the Rue du Faubourg St. Honoré, and 27 persons perished in the flames. Some firemen, bribed by the Commune, even went so far as to replace the water in their pumps by petroleum.

Palais de l'Elysée, in the Rue du Faubourg St. Honoré, see p. 153; Rue St. Honoré, see p. 85.

The ****Place de la Concorde** (Pl. R, 15, 18; II), the most beautiful and extensive *place* in Paris, and one of the finest in the world, covers an area 390 yds. in length, by 235 yds. in width, bounded on the S. by the Seine, on the W. by the Champs-Elysées, on the N. by the Rue de Rivoli, and on the E. by the garden of the Tuileries. It received its present form in 1854, from designs by *Hittorff* (d. 1876). From the centre of the square a view is obtained of the Madeleine (p. 79), the Palais de la Chambre des Députés, the Louvre, and the Arc de Triomphe de l'Etoile. When viewed by gas-light, the scene is scarcely less striking, the lamps ascending the Champs-Elysées as far as the Triumphal Arch ($1\frac{1}{3}$ M.) forming an apparently interminable avenue. The two imposing edifices of nearly uniform exterior on the N. side of the square, separated from each other by the Rue Royale (see above), were erected in 1762-1770, from *Gabriel's* plans, for the reception of ambassadors and other distinguished personages. That to the right is now occupied by the *Ministère de la Marine*, that to the left by private tenants.

Numerous historical associations, mostly of a sombre character, are connected with the Place de la Concorde. In 1763 it received the name of *Place Louis XV.* and was adorned by the municipality with an equestrian statue of that prince, surrounded by figures emblematical of Strength, Wisdom, Justice, and Peace. Soon after the erection of the statue the following pasquinade appeared on the pedestal: —

'Grotesque monument, infâme piédestal!

Les vertus sont à pied, le vice est à cheval.'

A few days later was added the sarcasm: —

'Il est ici comme à Versailles,

Il est sans coeur et sans entrailles.'

A third scribbler called the monument a '*statua statuae*'.

On 30th May, 1770, during an exhibition of fireworks in honour of the marriage of the Dauphin (afterwards Louis XVI.) with the Archduchess Marie Antoinette, the Place was the scene of a terrible calamity; such a panic was occasioned by the accidental discharge of some rockets, that no fewer than 1200 persons were crushed to death, or killed by being thrown into the ditches then surrounding the Place, and 2000 more severely injured.

On 11th August, 1792, the day after the capture of the Tuileries, the statue of the king was removed by order of the Legislative Assembly, melted down, and converted into pieces of two sous. A terracotta figure of the 'Goddess of Liberty' was then placed on the pedestal, and derisively styled '*La Liberté de Boué*', while the Place was named *Place de la Révolution*.

On 21st Jan., 1793, the guillotine began its bloody work here with the execution of Louis XVI. On 17th July Charlotte Corday was beheaded; on 2nd October Brissot, chief of the Gironde, with twenty-one of his adherents; on 16th Oct. the ill-fated queen Marie Antoinette; on 14th Nov. Philippe Egalité, Duke of Orléans, father of King Louis Philippe; on 12th May, 1794, Madame Elisabeth, sister of Louis XVI. On 14th March, through the influence of Danton and Robespierre, Hébert, the most determined opponent of all social rule, together with his partizans, also terminated his career on the scaffold here. The next victims were the adherents of Marat and the Orleanists; then on 8th April Danton himself and his party, among whom was Camille Desmoulins; and on 16th April the atheists Chaumette and Anacharsis Cloots, and the wives of Camille Desmoulins, Hébert, and others. On 28th July, 1794,

Robespierre and his associates, his brother, Dumas, St. Just, and other members of the '*comité du salut public*' met a retributive end here; next day the same fate overtook 70 members of the *Commune*, whom Robespierre had employed as his tools, and on 30th July twelve other members of the same body.

Lasource, one of the Girondists, said to his judges: '*Je meurs dans un moment où le peuple a perdu sa raison; vous, vous mourrez le jour où il la retrouvera*'. Of St. Just, Camille Desmoulins had said: '*Il s'estime tant, qu'il porte avec respect sa tête sur ses épaules comme un saint-sacrement*'. St. Just replied: '*Et moi, je lui ferai porter la sienne comme un St. Denis*'. (St. Denis, it is well known, is usually represented as a martyr, bearing his head in his hands.) St. Just kept his word, but a few months later he himself was also executed.

Between 21st Jan., 1793, and 3rd May, 1795, upwards of 2800 persons perished here by the guillotine. A proposal afterwards made to erect a large fountain on the spot where the scaffold of Louis XVI. had stood was strenuously opposed by Châteaubriand, who aptly observed that all the water in the world would not suffice to remove the blood-stains which sullied the Place. In 1799 the square was named *Place de la Concorde*.

On 10th April, 1814, a solemn service was performed in the Place, then again called the *Place Louis XV.*, in presence of the Emperors Francis and Alexander, and King Frederick William III., in memory of Louis XVI., after which a *Te Deum* was sung as a thanksgiving for their victory. Prussian and Russian troops were on that occasion bivouacked in the Champs-Élysées, and English soldiers the following year. In March, 1871, Prussian troops again bivouacked in the Champs-Élysées and the Place de la Concorde, and in the following May the latter was the scene of a desperate struggle between the troops of Versailles and the Communists. The troops had entered Paris on the 21st, and next day encountered a most formidable obstacle in the barricade of the Rue Royale (p. 80), which effectually commanded the Place.

After 1830 the name of *Place de la Concorde* was revived, and it was resolved to adorn the square with some monument bearing no reference to political events. An opportunity of doing this was soon afforded by the presentation to Louis Philippe by Mohammed Ali, Viceroy of Egypt, of the ***Obelisk of Luxor**. The obelisk is a monolith, or single block, of reddish granite or syenite, from the quarries of *Syene* (the modern *Assuan*) in Upper Egypt. It is 76 ft. in height, and weighs 240 tons. The pedestal of Breton granite is 13 ft. high, and also consists of a single block, while the steps by which it is approached raise the whole 3½ ft. above the ground. Cleopatra's Needle in London is only 70 ft. in height, but the Obelisk in the Piazza di S. Giovanni in Laterano at Rome is 104 ft. high.

Ramses II., King of Egypt, better known by his Greek title of Sesostris the Great, who reigned in the 14th cent. before Christ, erected a huge 'pylon' gate and a colonnade before a temple which his great ancestor *Amenhotep III.* (*Amenophis* or *Memnon* of the Greeks) had built in the E. suburb of Thebes, the site now occupied by the poor village of *Luxor*. In front of this gate stood two beautiful obelisks, and it is one of these that now embellishes the Place de la Concorde. Each of the four sides of the obelisk is inscribed with three vertical rows of hieroglyphics, the middle row in each case referring to Ramses II., while the others were added by Ramses III., a monarch of the succeeding dynasty. The inscriptions of Ramses II. are in the early Egyptian monumental style, and record with self-satisfied repetition how Ramses II., the 'Lord of the Earth', the 'Sun', the 'annihilator of the enemy', erected the pylons and the obelisks in honour of *Ammon Ra* (the chief Egyptian deity) in return for the victorious

might with which the god had endowed him. The fact that the faces of the obelisk are slightly convex seems to prove that the priestly architects of Egypt were aware that a flat surface was apt to appear concave in a strong light. — A vessel was despatched to Egypt in 1831 for the purpose of bringing home the pasha's gift. The task, however, proved so difficult that the vessel did not return with its costly freight till August, 1833, and the erection of the obelisk in its present position was not accomplished till 1836, under the direction of *Lebas*. The expense of the whole undertaking amounted to two million francs.

The ***Fountains** form another striking ornament of the Place. Each of them consists of a round basin, 53 ft. in diameter, above which rise two smaller basins, surmounted by a spout from which a jet of water rises to a height of 28 ft. The lower basin is surrounded by Tritons and Nereids, holding dolphins which spout water into the second basin.

The fountain on the S. side is dedicated to the *Seas*. The figures supporting the second basin represent the Pacific Ocean and the Mediterranean; the genii are emblematical of the four kinds of fishery. The fountain on the N. side is dedicated to the *Rivers*. The principal figures represent the Rhine and the Rhone; and the genii of Corn, Wine, Fruit, and Flowers are symbols of the chief products of France. The figures and the upper basins are of bronzed iron, the lower basins of granite.

Around the Place rise eight stone figures representing the chief towns of France: Lille and Strasbourg by *Pradier*, Bordeaux and Nantes by *Calhouet*, Rouen and Brest by *Cortot*, and Marseilles and Lyons by *Petitot*. The square is lighted at night by twenty bronzed rostral columns on the surrounding balustrades, each bearing two gas-lamps, and by upwards of 100 candelabra.

The **Pont de la Concorde** (Pl. R, 15, 14; II), which crosses the Seine from the Place to the Palais de la Chambre des Députés, was built in 1787-90, the material for the upper part being furnished by the stones of the Bastille. The buttresses are in the form of half-columns, the cornice resting on which is the parapet of the bridge. Napoleon adorned the parapet with statues of famous generals, but these were replaced at the Restoration by the statues of great men now in the Cour d'Honneur at Versailles (see p. 290). Fine view up and down stream.

Chambre des Députés, see p. 272; Boulevard St. Germain, p. 226; Garden of the Tuileries, p. 151; Champs-Élysées, p. 153.

We finish our circular walk by re-entering the *Rue de Rivoli* (p. 58), at the N.E. corner of the Place de la Concorde, and following it to the E., skirting the Tuileries Garden and the wing of the palace still existing on this side.

On the left once stood the Ministère des Finances, destroyed by the Communists in 1871. The site is now occupied by the *Hôtel Continental* (comp. p. 3) and other buildings. A tablet on the railing of the Garden of the Tuileries, nearly opposite this spot, records that here was situated the famous riding-school (*Manège*)

used as a place of meeting by the Constitutional Assembly, the Legislative Assembly, and the National Convention.

The Rue Castiglione, at the corner of which the Hôtel Continental stands, leads to the **Place Vendôme** (Pl. R, 18; II), an octagonal Place in an imposing, but somewhat cold and monotonous style of architecture, partly constructed by the celebrated architect *J. H. Mansart* (the Younger, d. 1708). The Place was once embellished with an equestrian statue of Louis XIV. by Girardon, and was named *Place des Conquêtes*. The statue was removed during the Revolution, and the name changed to *Place des Piques*. Napoleon I., disliking this reminiscence of the Revolution, altered the name to *Place Vendôme*, a palace having once been erected here by Henri IV. for his son, the Duc de Vendôme. In the centre of the Place, and named after it, rises the —

***Colonne Vendôme**, an imitation of Trajan's column at Rome, 142 ft. in height and 13 ft. in diameter. It was erected by the architects *Denon*, *Gondouin*, and *Lepère*, by order of Napoleon I. in 1806-10, to commemorate his victories over the Russians and Austrians in 1805.

The column is constructed of masonry, encrusted with plates of bronze (designed by *Bergeret*) forming a spiral band nearly 300 yds. in length, on which are represented memorable scenes of the campaign of 1805, from the breaking up of the camp at Boulogne down to the Battle of Austerlitz. The figures are 3 ft. in height, and many of them are portraits. The metal was obtained by melting down 1200 Russian and Austrian cannons. At the top is a statue of Napoleon in his imperial robes, by *Dumont* (d. 1884), replacing the original one by *Chaudet*. Visitors are no longer permitted to ascend. A small model of the reliefs is shown at the Hôtel des Monnaies (p. 246).

The vicissitudes of the Vendôme Column reflect the political history of France. In 1814 the statue of Napoleon was taken down by the Royalists, and was replaced by a monster fleur-de-lis surmounted by a white flag. The metal was used in casting the equestrian statue of Henri IV. (p. 220). In 1831 Louis Philippe caused a new statue of the emperor, in a greatcoat and three-cornered hat, to be placed on the summit, but Napoleon III. caused this to be replaced in 1863 by one resembling the original figure. The Column was overthrown by the Communists in May, 1871, at the instigation of the painter Courbet (d. 1878); but as the fragments were preserved, it was re-erected in 1875. Dumont's statue of Napoleon was also restored to its position at the top.

On the W. side of the Place is the *Ministère de Justice*. The *Hôtel du Rhin* (p. 5), on the S. side of the Place, was the residence of Napoleon III. when deputy to the National Assembly in 1848. On 23rd May, 1871, the Versailles troops captured a barricade in the Rue de Castiglione by passing through this hotel and attacking the insurgents in the rear. M. Maréchal, the proprietor of the house, is said to have offered the Communists 500,000 fr. if they would spare the Vendôme Column. The reply was, 'Donnez un million, et l'on verra!' M. Maréchal, it

need hardly be said, was dissatisfied with this answer, and kept his money.

The street prolonging the Rue Castiglione on the W. side of the Place is the Rue de la Paix, mentioned at p. 76. — We, however, retrace our steps along the Rue Castiglione to the *Rue St. Honoré*, the first cross-street. Here, in the section of the street between the Rue Castiglione and the Rue Royale (p. 80), are the *Nouveau Cirque*, and, beyond it, the *Church of the Assumption*, a copy of the Pantheon at Rome. We now recross the Rue Castiglione and follow the Rue St. Honoré on the other side to the church of —

St. Roch (Pl. R, 18; II), the best rococo edifice in Paris, erected in 1653-1740 from designs by *Lemercier*. The façade, with its two rows of columns, one above the other, was designed by *Robert de Cotte*, and executed by his nephew *Jules de Cotte*. The interior is by *Lemercier*.

INTERIOR. Each of the two aisles is flanked with five chapels. The choir contains eight side-chapels and three large chapels in the centre, two of the latter being roofed with spherical vaulting, while the third adjoins the semicircular end of the second. By the left pillar of the principal portal is a medallion-portrait to *Corneille* (d. 1684), who is buried in the church. The pulpit, with its quaint allegorical decorations, is of the 18th century.

LEFT AISLE. *1st Chapel*: St. Francis Xavier among the Indians; opposite, St. Philip baptising the Ethiopian eunuch, painted by *Chassériau*. — *2nd Chapel*: St. John pointing out the Saviour, and the risen Christ appearing to the disciples, by *Dureau*; "Baptism of Christ, a group in marble by *Lemoine*. — *3rd Chapel*: St. Nicholas, by *Collin* and an inscription in memory of Bossuet, who died in the parish of St. Roch. — *4th Chapel*: Mater Dolorosa, a marble group: the Virgin mourning over Christ taken from the cross, by *Cornu*. — *5th Chapel*: over the altar, the Chaste Susanna, a painting by *Herbstroffer*, and two figures of the same, by *Norblin*; below the window, monument of the *Abbé de l'Épée* (1712-1789), the celebrated teacher of the deaf and dumb, and founder of the Deaf and Dumb Asylum (p. 241), by *Préault*.

CHAPEL OF THE LEFT TRANSEPT: St. Denis preaching, by *Vien* (d. 1809), a celebrated picture.

CHOIR AMBULATORY. The Chapels on both sides of the Ambulatory contain large reliefs representing scenes from the history of the Passion, and a number of paintings. *Chapels on the Left*: (1st) St. Vincent de Paul, by *Porion*; (2nd) St. Joseph, by *Tissier* and *Biennoury*; (3rd) St. François de Paule, by *Scheffer*; (4th) St. Carlo Borromeo, by *Raymond Balze*. — *Chapels on the Right*: (1st) Ste. Clotilde, by *Devéria*; (2nd) St. Theresa, by *Bohn*; (3rd) St. Catharine, by *Brune*; (4th) Mary Magdalene, by *Briset*.

CHAPELS IN THE RETRO-CHOIR. The *1st Chapel*, dedicated to the Virgin, and constructed in 1753, was remodelled by *Saint-Père* in 1845. The dome is embellished with a large fresco of the Assumption, by *Pierre*. Among the modern paintings are the following fine works: Christ blessing children, by *Schnetz*; Christ driving out the money-changers, by *Thomas*; Raising of the daughter of Jairus, by *Delorme*; Triumph of Mordecai, by *Jouvenet*; St. John preaching in the wilderness, by *Legendre*. Upon the altar: "Nativity, a group in marble by *Michel Anguier*. — The *Chapelle du Calvaire* (the 3rd), which is separate from the other two, contains three well-executed groups: the Crucifixion, Christ on the Cross, and the Entombment. The central group, by *Mich. Anguier*, occupies a niche and is lighted from above.

RIGHT TRANSEPT. In the Chapel: Healing of the Leper, a somewhat theatrical composition, by *Doyen* (d. 1806).

RIGHT AISLE. *1st Chapel* (5th from the entrance): St. Peter, by *Dureau*. — *2nd Chapel*: Purgatory, by *Boulanger*. — *3rd Chapel*: St. Stephen, by *Roux*; monument of *Marshal Duc de Créquy* (d. 1687), by *Coyzevox* and *Coustou*. — *4th Chapel*: The Holy Women and the Risen Saviour, by *Charpentier*; monuments of *Cardinal Dubois* (d. 1729), by *G. Coustou*, and of *Comte d'Harcourt* (d. 1686), by *Renard*; busts of the painter *Mignard* (d. 1695), by *Desjardins*, and of the landscape-gardener *Le Nôtre* (d. 1700), by *Coyzevox the Elder*. — *5th Chapel*: The Prodigal Son, by *Quantin*; monument of the learned chancellor *Maupertuis* (d. 1759), by *d'Huez*; bust of the *Duc de Lesdiguières* (d. 1626), by *Coustou*, and several medallions.

The church-festivals are celebrated at St. Roch with great pomp, and it is noted for its music (10 a.m. on Sun.).

It was in the Place in front of St. Roch, extending at that time as far as the Tuileries Garden, that the Royalists who attacked the Convention on 5th Oct., 1795, placed their best battalions; whilst others advanced on the side of the river. Napoleon Bonaparte, however, brought the latter under a cross-fire from his batteries, which he had hastily summoned, while by a vigorous attack he overwhelmed the soldiers of St. Roch, thus stifling the counter-revolution in its birth.

The *Rue des Pyramides*, to the right of St. Roch, leads to the Rue de Rivoli, passing the small *Place de Rivoli*, with a mediocre statue of *Joan of Arc*, in bronze, by *Frémiet*.

Following the Rue de Rivoli to the left we now soon reach the Nouveau Louvre, and the Place du Palais-Royal (p. 55).

2. Palace and Galleries of the Louvre. The Tuileries.

I. THE PALACE OF THE LOUVRE.

The **** Louvre** (Pl. R, 17, 20; II), the most important public building at Paris, both architecturally and on account of its treasures of art, is a palace of vast extent, rising between the Rue de Rivoli and the Seine, and is said to derive its name from an ancient hunting château once situated here in the midst of a forest infested by wolves, and called the *Lupara*, or *Louverie*. On the same site, close to the city-wall of that period, *Philip Augustus* (d. 1223) erected a castle, consisting of four wings enclosing a quadrangular court, with a strong keep or *donjon*, the position of which is indicated by a white line on the ground in the S.W. corner of the Cour du Louvre. This château was afterwards handsomely fitted up as a royal residence by *Charles V.* (d. 1380), but no trace of these buildings now remains.

The old château was removed, and the foundation of the present palace laid, in 1541, by *Francis I.* (d. 1547), an indefatigable builder, who intended the court of the new building to be of the same extent as that of the old. In 1546 he appointed as his architect *Pierre Lescot* †, the most distinguished master of the earlier French Renaissance style, who continued to superintend the works during the reign of the splendour-loving *Henri II.* (1547-59),

† For details regarding the artists, see List at the end of the Handbook.

and under subsequent monarchs, down to his death in 1578. Of the *Vieux Louvre*, or large quadrangle formed by the buildings enclosing the *Cour du Louvre* (comp. the Plan), half of the western and half of the southern side next to the Seine were erected by Lescot. The *Façade of the W. wing, facing the court, rising in three stories, and decorated with sculptures by *Jean Goujon* and *Paolo Ponzio*, is justly admired as the richest and most perfect example of the early Renaissance architecture of that period.

After the death of *Henri II.* his widow *Catherine de Médicis* (d. 1589), during the reigns of her sons *Francis II.* (d. 1560), *Charles IX.* (d. 1574), and *Henri III.* (d. 1589), continued the erection of the S. wing, and in 1566 also proceeded to build the so-called 'Petite Galerie', a wing of one story over which the *Galerie d'Apollon* was afterwards constructed, forming a right angle with the other, and running towards the river. The corner-pavilion adjoining the *Galerie d'Apollon* was also erected by the same queen. These corner-pavilions and others in the centre of the façade, a lingering reminiscence of mediæval towers, form a genuine French peculiarity. Simultaneously with these buildings *Catherine de Médicis* began to erect the palace of the *Tuileries*, which was destined to be connected with the Louvre by means of a long gallery on the bank of the Seine. The latter was probably also begun by Lescot.

This older part of the Louvre has been the scene of many memorable historical events. On 19th Aug., 1572, the marriage of *Princess Margaret of Valois* with the King of Navarre, afterwards *Henri IV.* of France, was solemnised here, most of the Huguenot chiefs being present on the occasion. Five days later, on the night of 24th Aug., the signal was given here for the massacre of the Huguenots. The guards immediately issued from the palace-court where they had been assembled, and proceeded first to the residence of *Admiral de Coligny*, who became the first victim of the fearful Night of St. Bartholomew. According to a tradition, repeated by Mirabeau and other orators of the Revolution, *Charles IX.* himself on this occasion fired on his subjects from one of the S. windows of the palace, where the inscription, 'C'est de cette fenêtre que l'infâme Charles IX., d'exécration mémoire, a tiré sur le peuple avec une carabine', was accordingly engraved in 1795. Six years later, however, the words were erased, as it was discovered that that part of the palace was not built till the reign of *Henri IV.*

Like his predecessors, *Henri IV.* (1589-1610) devoted much attention to the continuation of the Louvre. He constructed the 'Galerie d'Apollon', which forms the second floor of the 'Petite Galerie', and completed the S. gallery leading to the *Tuileries* which had been begun by *Catherine de Médicis*, as well as a short connecting wing, now destroyed. His architects, and Lescot's successors, were *Thibaut Métzeau* and his son *Louis Métzeau*, besides whom *Baptiste Androuet du Cerceau* and his brother *Jacques* were also employed. *Pierre Chambiges*, or *Chambiche*, is also mentioned as one of the architects. The annexed plan of the palace shows the parts usually attributed to these different masters during the reign of *Henri IV.*; but the entire W. portion of the *Galerie du Bord de l'Eau* was rebuilt under *Napoleon III.* (see next page).

Under *Louis XIII.* (1610-43) the works were suspended for a considerable time, but in 1624 he entrusted *Jacques Lemercier* with the completion of the buildings begun by Lescot. The extent of Lescot's design was quadrupled, and what had formerly been the N. pavilion (Pavillon Sully, or de l'Horloge) was now made the centre of the W. wing. The pavilion was raised, and embellished with eight Caryatides by *J. Sarazin*. The construction of the N., S., and E. sides, begun by Louis XIII., was continued by his successor *Louis XIV.* (d. 1715), *Leveau* being the architect who succeeded Lemercier in 1660; and the Galerie d'Apollon, which had been burned down, was restored. The principal E. Façade, opposite St. Germain l'Auxerrois, 190 yds. long and 90 ft. high, was erected (1665) by *Claude Perrault*, whose handsome colonnade, consisting of 28 Corinthian columns in pairs, has been somewhat overrated.

The building was neglected after the death of Louis XIV., as Louis XV. and Louis XVI. preferred St. Germain, Versailles, and the Tuileries to the Louvre. In 1805 *Napoleon I.* at length caused the whole of the Louvre buildings to be thoroughly restored, and instructed his architects *Percier* and *Fontaine* to erect a connecting gallery between the Tuileries and the Louvre on the N. side.

The downfall of Napoleon caused the suspension of these works, the connecting gallery having been completed as far as the Pavillon de Rohan only. In 1852 the old plan of the French kings and the first emperor for the junction of the Louvre and the Tuileries was revived by *Napoleon III.*, who appointed *Visconti* (d. 1853) his architect, and after his death *Lefuel*, who were instructed to complete the N. connecting gallery. By the year 1857 this immense task was completed, at an estimated cost of 75 million francs. The heavy and showy façades of these new buildings, with their pavilions roofed with domes, their Corinthian half-columns, their Caryatides, their portico, colossal statues (representing 86 eminent Frenchmen), and groups of sculpture (63, of an allegorical character), harmonise in their general characteristics only with the architecture of the earlier parts of the palace. These remarks apply equally to that part of the S. connecting gallery (Galerie du Bord de l'Eau, see above) which was reconstructed and enlarged in 1863-68.

The Louvre and Tuileries together cover an area of about 48 acres, enclosing two, or rather three different courts, and forming one of the most magnificent palaces in the world. — To the W. of the square which occupies the centre of the court of the New Louvre is a *Monument to Gambetta* (p. 148).

Since 1793 the apartments of the Old Louvre have been used as a Museum. The E. half of the S. wing of the New Louvre also contains collections, while the N. wing is occupied by the offices of the minister of finance. On 24th May, 1871, the whole building with its immense treasures of art was seriously imperilled by the incendiarism of the Communists. The part of the connecting wing


MUSÉES DU LOUVRE.


0 10 20 30 40 50 Mètres

REZ-DE-CHAUSSEE

- | | |
|---|--|
| <p>A. <i>Entrée des salles des antiquités égyptiennes.</i></p> <p>B. <i>Entrée des salles des antiquités asiatiques.</i></p> <p>C. <i>Entrée du musée des marbres antiques, grecs et romains.</i></p> <p>D. <i>Entrée du musée des sculptures du Moyen-Age et de la Renaiss.</i></p> <p>E. <i>Entrée du musée des sculptures modernes.</i></p> <p>F. <i>Entrée de la Chalcographie ou musée de gravure.</i></p> | <p>G. <i>Entrée des musées du 1^{er} étage et des marbres antiques.</i></p> <p>H. <i>Escalier des musées d'antiquités égyptiennes et grecques, etc.</i></p> <p>I. <i>Escalier du musée du Moyen-Age et de la Renaissance, etc.</i></p> <p>J. <i>Escalier Henri II (collection la Caze, musée de peinture, etc.).</i></p> <p>K. <i>Escalier des galeries françaises et sortie de la Grande Galerie.</i></p> <p>L. <i>Direction des musées nationaux.</i></p> <p>M. <i>Bureaux de l'administration.</i></p> <p>N. <i>Escalier Henri IV, sortie quand il y a foule.</i></p> |
|---|--|

Place du Carrousel






MUSÉES DU LOUVRE.

0 10 20 30 40 50 Mètres


PREMIER ÉTAGE.

- A. Escalier du musée égyptien.
- B. Escalier du musée assyrien.
- C. Escalier Henri II.
- D. Entrées principales.
- E. Escalier des galeries françaises.
- F. Petits escaliers du 2^e étage.
- G. Grand escalier du 2^e étage et sortie quand il y a foule.

Place du Carrousel




Quai du Louvre



MUSÉES DU LOUVRE.

0 10 20 30 40 50 Mètres.

R u e d e R i v o l i



SECOND ÉTAGE.

A. C. *Petits escaliers.*

B. *Grand escalier.*

next to the Tuileries was much damaged by the fire, and the imperial library of 90,000 vols. and many precious MSS. was destroyed. The Versailles troops fortunately arrived in time to arrest the progress of the flames and prevent incalculably greater losses.

Those who wish to make use of their time before the Galleries are open, or after they are shut, may walk through the Jardin des Tuileries (p. 151) to the Place de la Concorde (p. 81), or along the quays on the Seine to the Pont-Neuf (p. 220), or even as far as the Palais de Justice (p. 217). The Galleries cannot be properly seen in one day. — Déjeuner may be taken at the Palais-Royal (see pp. 12, 14).

II. THE GALLERIES OF THE LOUVRE.

Most of the Louvre Collections are open gratis to the public daily, *except Mondays* and certain holidays, as Christmas Day, Shrove Tuesday, July 14th. In summer (1st Apr. to 30th Sept.) the collections of *Paintings* and *Ancient Sculptures* are open from 9 to 5 on week-days, and from 10 to 4 on Sundays and holidays; in winter the hours are 10-4. The other collections are not open till 11 a.m. The *Salle des Boites* (p. 148) is shown on Saturdays only, 2 to 4 or 5.

The best time for visiting the galleries is as early as possible in the morning, as they are often crowded in the afternoon, particularly on Sundays. — Overcoats, sticks, and umbrellas should if possible be left at the hotel, though they may, if necessary, be left in charge of the officials at the principal entrance, or at the entrance to the Henri II. staircase (p. 104).

The history of the *Louvre Collections* dates from the time of the French monarchs of the Renaissance of the 16th cent., who were not only intimately connected with Italy in their political relations, but paid enthusiastic homage to Italian culture. Foremost among patrons of art and collectors was *Francis I.*, who invited Leonardo da Vinci, Andrea del Sarto, Benvenuto Cellini, Primaticcio, and other artists to his court, and to whose favour gifts of works of art formed the surest passport. He endeavoured also to secure the services of Michael Angelo, and it was his intention to form a collection of casts from celebrated antiques. His efforts, however, were but partly successful; for the School of Fontainebleau, as the group of Italian masters employed by him and by *Henri II.* is usually called, exercised no permanent influence on the character of French art. In the reign of *Louis XIV.*, whose love of power and magnificence induced him to cultivate art, it again became the fashion to make collections of treasures of art, both with persons of the highest rank (such as Cardinal Mazarin) and members of the middle class (like Crozat). Thus in the 'Cabinet du Roi' of that period were collected a large number of very valuable paintings, while the collection of drawings and other works of art begun by Crozat in 1683 (but afterwards dispersed) was the most extensive and precious of the kind. To the Revolution, however, the collections of the Louvre are chiefly indebted for their great extent and magnificence. The principle of centralisation was then for the first time applied to art collections, and various treasures distributed throughout the royal palaces were united here. At length, when the French armies returned to Paris from their victorious campaigns in Italy, the Netherlands, and Germany, laden with treasures of art of every description, the Louvre Collection became not merely the most important of the kind in France, but *par excellence* the museum of Europe. On the conclusion of peace many of these treasures had to be restored to their former owners, but the collections can still boast of being the most extensive and valuable on the continent.

The rooms of the Louvre, most of which are connected with each other, are so numerous that it takes 2 hrs. to walk through them all without stopping, and it is indispensable for the visitor to be provided with a plan for his guidance.

Before entering, the visitor should particularly note that the —

GROUND FLOOR contains the *Sculptures*, ancient and modern, and the *Engravings*.

The FIRST FLOOR contains the *Pictures*, the *Smaller Antiquities*, the *Mediaeval and Renaissance Art Objects*, the *Drawings*, and various small collections.

The SECOND FLOOR contains the *Musée de Marine*, the *Musée Ethnographique*, the *Musée Chinois*, and the *Supplementary Saloons of Pictures and Drawings*.

Visitors who have only a short time to devote to the Galleries should begin with the *Antique Sculptures* (p. 95) and the *Pictures* (p. 111), which are the first to be opened in the morning (see above). They are also recommended to adhere closely to the following order of proceeding through the rooms, so as to avoid missing their way or losing time by going twice over the same ground. To find the description of any particular saloon, see the Index. The authorities caution visitors, by means of numerous notices, not to employ the guides who assail the public at the entrances to the Galleries.

ENTRANCES. Most of the Galleries have special entrances, which are marked on the plan. The *Principal Entrance*, leading to the Gallery of Antique Sculpture and to the First Floor, is in the *Pavillon Denon* (Pl. G, ground-floor), in the court of the New Louvre, on the side next the Seine. The descriptions at pp. 95, 111 begin here.

The *Catalogues* sold at the entrances of most of the collections not only enumerate the objects in each, but contain biographical notices of the artists and other valuable information. In several of the departments the objects are furnished with the names of the artists, and sometimes with explanatory notices. Our enumeration includes only the objects of the greatest interest.

A. GROUND FLOOR.

The **Egyptian Museum* (*Musée Egyptien*), the most important collection of the kind in Europe, affords, so far as is possible without the appropriate architectural surroundings, an almost complete survey of the religion, the customs, and the art life of the most ancient of civilised nations. The entrance is in the passage under the colonnade (p. 88), on the right side when approached from the court (A on the Ground-plan).

We first enter the *SALLE HENRI IV.*, which contains the largest and most important objects in the collection, many of them provided with detailed descriptions or translations of the hieroglyphics. Among these are the *Sphinxes*, fantastic figures with lions' bodies and men's or rams' heads, which were erected in pairs to serve as guardians of the entrances of temples. The most interesting of the sphinxes is one in granite (by the entrance) from Tanis, the capital of the Hyksos kings, the head of which is a portrait of one of the monarchs of the 12th Dynasty (B. C. 2400); the hieroglyphics

on the sides, added at a later period, record the names of King Menephtah (19th Dyn.), under whom the Exodus of the Children of Israel took place, and King Sheshonk I. (22nd Dyn.), the Shishak of the Bible and conqueror of Rehoboam. — Next, *Steles*, or votive stones erected to the memory of deceased persons, bearing inscriptions and representations of the infernal deities (Osiris), to whom, as well as to the deceased themselves, offerings were presented by the bereaved relatives. Thus No. 307, of rose-coloured granite, in the form of an ancient Egyptian temple-gate; 261, 291. (at the windows, under glass), with fine reliefs (12th Dyn.). — Then *Statues*, likewise chiefly from tombs: 207. Sekhet, Goddess with lion's head, of the 18th Dynasty (16th and 15th cent. B.C.); a warrior named Hor, in black granite, considered a masterpiece of the 26th Dynasty (7th and 6th cent. B.C.); 242. a colossal statue of king Sebekhotep, 13th Dynasty, 9 ft. in height; groups representing kings and gods; in the middle of the room, 203. Colossal statue of Seti II., son of the above-mentioned Menephtah, with the 'Pschent' or royal hat on his head, and inscriptions repeating the royal name thrice; 205. Four grotesque figures with dogs' heads, from the original base of the Obelisk of Luxor (p. 82); 153. Statue of Ramses II., supposed to have been originally a statue of a king of the old kingdom (12th or 13th Dyn.), usurped by Ramses. — Next, *Reliefs*. The best is *93. (by the left wall), taken from the tomb of Seti I. and the finest found in the Theban tombs of the kings, representing the king stretching out his hand to the goddess Hathor; the colouring is admirably preserved — *Sarcophagi*: 276. in rose-coloured granite, that of Ramses III., 20th Dynasty (13th-11th cent. B. C.), the decorations on which indicate the symbolical parallel between the course of the sun after its setting, 'in the mysterious paths of the west', and the wanderings of the soul after death; 102. Colossal sarcophagus in basalt, 4 ft. high, 9½ ft. long, and 4 ft. wide, brought to France by Champollion, the great French Egyptologist, a masterpiece of the Egyptian sculpture of the 26th Dynasty, with representations similar to those just mentioned; 117. Sarcophagus of a priest of the reign of Psammetichus I. (26th Dyn.); 217. Sarcophagus of an official named Horus; in the interior are the 42 infernal judges who assisted Osiris in judging the dead. To the left, by the exit: 344. Votive chapel in granite (monolith), formerly containing a statue of Osiris, and erected, according to the long inscription, by Ahmes, the Amasis of the Greeks.

A doorway at the back of this saloon leads to a short corridor, which terminates in a staircase ascending to the first floor. The adjoining saloon on the left is called the —

SALLE D'APIS, after the figure of the bull placed in the centre. The *Apis* was the animal sacred to Ptah, the great god of Memphis. The bull to be thus honoured required to be black in colour, to have a white triangle on his forehead, a white mark on his

back resembling an eagle, and an excrescence under his tongue in the shape of the sacred scarabæus beetle — peculiarities recognizable in the figure before us, a work of the 30th Dynasty (4th cent. B. C.). After his death the sacred bull was interred with great pomp in the vaults known to the Greeks as the 'Serapeum', a word derived from 'Osiris Apis', which the Egyptians applied to the dead Apis. At the side are several *Canopi*, or sepulchral vases with human heads. Around the walls are *Steles*, erected by devout persons in the tombs of the bulls, which give the dates of the deaths of these revered animals, with the king's reigns when they occurred, affording a valuable clue to Egyptian chronology. — The entrance to an adjacent apartment is formed by the gateway of the Serapeum (under glass), with inscriptions of the period of the Ptolemies.

We return through the Apis Saloon to the corridor, and ascend the STAIRCASE to the left (No. II. on the Ground-plan, p. 89), the walls of which are covered with papyrus writings (including some of the earliest Coptic and Greek MSS.) and inscriptions on stone. Among the last we observe, to the left, a fragment of the most valuable inscription discovered in the great temple at Karnak, recording the campaign of Thotmes II. (18th Dynasty, 16th cent. B.C.), the greatest of the Egyptian monarchs. On the landing, to the right, an admirable relief of the early empire (down to the end of the 6th Dynasty, B.C. 2500), most interesting on account of its fidelity to nature, especially when contrasted with the workmanship of a later period, when artists were hampered by the conventional rules known as the 'canon'.

The UPPER LANDING also contains sarcophagi in the shape of mummies and sculptures of the early empire. In the centre of the wall: 670-672. Two male and one female figure, with the hair painted black, dating from the period before the building of the Pyramids (about B. C. 4000), and probably the oldest portrait-figures in existence; the workmanship is simple but the effect vigorous and original. On the balcony of the staircase: 668. 698. 745. 723. Four fine painted statues; 721. Large alabaster statue of Ramses II. (Sesostris), the contemporary of Moses (upper half modern). — The door to the right leads to the E. wing of the Old Louvre (p. 144).

The glass-door in front leads to the collection of *Smaller Egyptian Antiquities* (comp. the Plan).

I. SALLE HISTORIQUE, with a ceiling-painting by Gros, representing the Genius of France encouraging the arts and protecting mankind (1827-31). The objects here are mainly of historical value. In the middle, under glass, Votive statuettes, with names inscribed. In other cases: Ivory casket of King Meri-en-Ra (6th Dyn.); Enamelled brooches; Mummy's mask in gold-foil. — To the left, beside the chimney-piece, in the middle of the wall-cabinet: Statuettes in gold of Osiris, Isis, and Horus (22nd Dyn.).

II. *SALLE CIVILE*, with a ceiling-painting by *Horace Vernet*, representing *Bramante*, *Raphael*, and *Michael Angelo* before *Pope Julius II.* (1827). In the middle of the room is an extensive collection of ornaments, household implements in carved wood, etc. Also a celebrated sitting *Statue of an Egyptian scribe (5th Dyn.), with life-like eyes of rock-crystal. The glass-cases at the sides contain finely woven garments, papyri, shoes, sandals, fruit, tools, musical instruments, articles of the toilet, trinkets, etc. On the chimney-piece: *Vigorously-executed portrait-bust.

III. *SALLE FUNÉRAIRE*, with a ceiling-painting by *Abel de Pujol*, Joseph as the saviour of Egypt (1827). The contents of this room afford an admirable insight into the worship of the dead, which, like the whole religious system of the ancient Egyptians, was closely connected with their doctrine of the immortality of the soul. It was owing to their peculiar form of belief that they used every endeavour to preserve the bodies of the dead by embalming and otherwise, and constructed the spacious and magnificent tombs with which Egyptian travellers are familiar. Our information regarding the Egyptian notions of the soul's condition after death is chiefly derived from the 'Book of the Dead', a collection of hymns, prayers, and instructions for the use of the deceased, and to enable him to answer the questions asked by the judges of the dead. The papyri hung on the walls contain a number of these passages, sometimes illustrated by paintings in wonderfully good preservation. Above the fire-place hangs a large picture in water-colours, of the Græco-Roman period, representing a departed soul, supported on the left by *Osiris* and received by *Anubis*. In the middle of the room are three wooden portrait-figures, dating from about B. C. 3000. Near the exit, to the right, are the earliest easel-paintings known, consisting of slightly-executed portraits of the Græco-Roman period. The remaining contents of the room include painted mummy-cases, masks, scarabæi, writing-implements, etc.

IV. *SALLE DES DIEUX*, with a ceiling-painting by *Picot*, representing Greece and Egypt. Statues of gods. In the glass-case: Scarabæi, symbols and attributes of Egyptian gods in various materials.

V. *SALLE DES COLONNES*, the last of the suite, divided by Corinthian columns into three sections, and adorned with an allegorical ceiling-painting by *Gros*, contains various objects for which a place could not be found in the preceding rooms. By the window is the so-called 'Royal Papyrus', an excellently-preserved copy of the 'Book of the Dead', in hieroglyphics; it is 25 ft. long.

The visitor may now proceed to the Smaller Greek Antiquities and the Musée Campana (p. 145), instead of adhering to the following order.

The **Asiatic Museum* (*Musée des Antiquités Asiatiques*) contains one-half of the yield of the excavations made on the site of the ancient *Assur* and *Nineveh* by M. Botta and Mr. Layard (the other half being in the British Museum), and also antiquities collected

by scientific missions and private individuals in other parts of Asia. — The entrance is from the E. passage under Perrault's Colonnade, opposite the Egyptian Museum (B on the Plan, p. 89).

Rooms I & II.: *Assyrian Antiquities*. The kingdom of Assyria or Assur, the land of the Nimrod of the Bible, lay on the left bank of the Tigris, its capital being Assur, and afterwards Nineveh. The Assyrians conquered the Babylonian empire about B.C. 1250, and afterwards extended their supremacy as far as Asia Minor. The excavations have brought to light remains of extensive palaces, the chambers of which were lined with alabaster slabs, bearing scenes from the lives of the Assyrian monarchs, similar to those on the Egyptian monuments, and still more lifelike. Hunting-scenes, battle-fields, and sieges alternate with others representing the king in his court or among his guards, and accompanied by figures of fantastic monsters. The inscriptions in cuneiform character, or wedge-shaped and angular signs placed horizontally and obliquely, have only recently been deciphered. Most of the objects exhibited here belonged to the palace of King Sargon (B.C. 722-705) at Khor-sabad or to that of Sardanapalus V. at Nineveh (7th cent.). Among the most noteworthy are: 19, King at the chase; the vigorous display of muscular power and the flowing hair are characteristic of Assyrian art. Four *Winged Bulls with portrait-heads, probably of kings (the third fore-foot is added to make the animal seem complete when viewed either from the front or the side). On the end-wall of the same room: 4, 5, Lion-tamers, the animals very lifelike. In the middle of the wall, Relief of a king with four wings. In the intervening spaces, Colossal bas-reliefs: 21-25. Royal train; 15, 16. King and priests; 6, 10. King sacrificing an antelope. In the centre of the room: Nine headless statues, two heads, and other Chaldean antiquities; finely-designed door-frame.

Visitors who are pressed for time may pass hence immediately to the following collection.

Rooms III & IV.: *Phœnician Sarcophagi*, in black and white marble. — In the middle: Basalt sarcophagus of King Esmunzar of Sidon, with a Phœnician inscription.

The Phœnicians, whose chief settlements were on the Syrian coast, possessed important colonies on every part of the Mediterranean, and were the earliest traders between the East and West. To them we are indebted for our modern system of writing, as they were the first to reject the cumbrous Egyptian style and to adopt a simple sign for each simple sound. They also exercised no small influence on the earlier stages of Greek art.

Room V., under the staircase, contains a small *Musée Judaïque*, consisting of Jewish antiquities from Palestine and the neighbouring countries, such as sarcophagi from the Tombs of the Kings, architectural fragments, reliefs, pottery, Moabite sculptures, and inscriptions. In the centre of this room is the famous basalt *Stele of King Mesa of Moab*, whose battles with the Jews in B.C. 896 are recorded by the inscription.

Room VI. contains Phœnician monuments, figures, and inscriptions from the earliest period to the time of Constantine the Great. To the right: Frieze and architrave from the temple of Gebeil (Byblos). In the middle: *Vase* of immense size from Amathus in Cyprus, perhaps for holding grain. Seven statues from Cyprus. By the second window to the right: Fragments of monuments from Palmyra, in Syria. By the exit-wall: Cyprian sculptures, the figures in excellent preservation. By the second window to the left: Fragments of monuments from Carthage, with Neo-Punic inscriptions.

Room VII. Greek sculptures from Miletus and Heraclea in Asia Minor, the yield of excavations carried on at the expense of Mr. E. Rothschild. To the right: *Fragments from the Temple of Apollo at Didyma*, specimens of primitive Ionian art. In the centre: Two colossal bases of columns from the same temple. At the back: Statues (headless) which adorned the theatre. Mutilated statues from the Necropolis, in the Assyrian style. By the windows, under glass: Bronze clamps used in building.

Room VIII. contains *Fragments of the Temple of Artemis Leucophryene* ('Diana of the white eyebrows') at Magnesia, on the Mæander. The *Frieze, one of the most extensive relief-compositions of ancient times, about 88 yds. in length, represents wild contests between Greeks and Amazons, the date of which, however, is matter of dispute. The unusual prominence of the reliefs and other peculiarities seem to point to a comparatively late, perhaps a Roman origin. We also observe a vase from Pergamus, with reliefs of young Greeks on horseback, presented by Sultan Mahmoud in 1838; and a statue of Diana from Phrygia, acquired in 1888.

From Room IV. a staircase (marked J on the Plan, p. 89) ascends to the first floor. On the landings are some ornamented Syrian sarcophagi, and on the wall is a decorated leaden coffin. The glass-door at the top, on the right, leads to the collection of small Objects of the Renaissance (p. 142) and to the Drawings. From the first room to the right a short staircase ascends to the Naval Museum on the second floor (p. 146).

The **Collection of Ancient Sculpture (*Musée des Marbres Antiques*), though inferior to the great Italian collections, boasts of a number of works of the highest rank. We begin our enumeration at the end next the *Pavillon Denon* (comp. p. 90).

In the VESTIBULE is a facsimile of the bronze figure of Victory at Brescia. To the right is the GALERIE MOLLIEN, which contains ancient statues, more or less mutilated and of inferior value. At the end is a staircase ascending to the French department of the Picture Gallery (Pl. K; see p. 131). — We turn to the left and enter the —

GALERIE DENON, where copies of bronzes from the antique, executed in the 16-18th cent. at Fontainebleau and Rome, and mutilated antiquities are exhibited.

Bronzes. To the right, Apollo Belvedere; to the left, Diana 'à la biche'; right and left, Centaurs, from the Capitol; right, Boy extracting a thorn from his foot (from the Capitol); left, Mercury (from Florence),

Cnidian Venus (from the Vatican), Ariadne (from the Vatican), Antinous (from the Capitol); right, Commodus as Hercules (from the Vatican), Laocoon (from the Vatican), Amazon (from the Vatican), the Arrotino or knife-grinder (from Florence); left, Faun (from Madrid), Young Athlete; to the right, Medicean Venus; at the end, Diana and Apollo.

We next reach the GRAND ESCALIER, or ESCALIER DARU, which ascends to the Picture Gallery (p. 111). This staircase has only lately been completed, and the ceiling is now being decorated with mosaics. Those in the centre refer to the Renaissance, which is represented by four large figures (by *Lenepveu*) of Italy, France, Flanders, and Germany, and by medallions of Raphael, Poussin, Rubens, and Dürer. — On the landing halfway up stands the *Nike of Samothrace*, one of the finest sculptures in the Louvre but not seen to advantage in its present position. The figure has been cleverly put together from a number of fragments found by a French vice-consul in the island of Samothrace in 1863. The huge pedestal, the form of which, representing the figure-head of a trireme, shows that the monument commemorated a naval victory, was discovered by a scientific expedition sent from Austria in 1875.

The presence of the same figure on the coins of Demetrios Poliorketes makes it probable that this statue was erected in memory of the naval victory won by that potentate off Salamis, in the island of Cyprus, in B.C. 306. The reconstruction of the figure has been performed with reference to the design on the coin, in which the goddess is represented with a staff in one hand, while with the other she holds a trumpet to her lips. If this surmise is correct, the statue is the most important relic of early-Hellenic art. The breadth of conception, the dignity of form, and the energy of movement reflect the creative spirit of the period immediately succeeding the great masters of the second Attic school, while the realistic treatment of the voluminous drapery and the exact reproduction of its texture indicate the influence of a more modern tendency.

To reach the sculpture-gallery we ascend eight steps to the first landing, then turn to the left, and descend the staircase. A new room, to the right of the staircase, is about to be opened as a museum of Tunisian antiquities (mosaics, etc.). On the walls, at the windows, and under the staircase are ancient inscriptions, bas-reliefs, statues of secondary importance, sarcophagus-reliefs, etc.

Below, by the window to the left: Recumbent Bacchus. Nearly opposite: Dionysus (Bacchus) and his train at a banquet of mortals (bas-reliefs); this scene, frequently repeated in ancient sculptures, probably represents a 'Theoxenion', or banquet participated in by the deity in whose honour it is held. By the second window: Recumbent figure, restored as a Naiad. In the window-recess: to the left, Relief of a Theoxenion, of a good Greek period; to the right, Colossal relief of a head (Helios?), an effective, decorative work. On the rear-wall: Statues of captive Barbarian princes, the drapery of porphyry and Egyptian breccia; One of the children of Niobe and the tutor; Sarcophagus from Salonica with a Battle of Amazons, and others with Apollo and Marsyas and scenes from the myth of Meleager. Below the staircase are architectural fragments, etc., including an early Greek column with Doric capital from a temple at Assos.

The door to the left leads to the —

ROTONDE, with decorations in stucco by *Michel Anquier* (1653) and ceiling-paintings by *Mauzaisse*, representing the Creation of

Man. In the centre, *2111.† So-called *Borghese Mars* (formerly called Achilles), a celebrated statue in which the 'dread god of war' is represented as sunk in dreams of love. In the recesses on the right, 2162, 2174. Lycian Apollo. To the left, 2130, Apollo; 2134. Athlete, restored as Pollux. — Turning to the right, we now enter a suite of apartments in the wing erected by Catherine de Médicis (p. 87; under the Galerie d'Apollon, p. 136). The archway leading to the first room is embellished with a relief by *Chaudet*, representing Painting, Sculpture, and Architecture.

SALLE DE MÉCÈNE, with ceiling-paintings by *Meynier* (the World receiving from Hadrian and Justinian laws dictated by Nature, Justice, and Wisdom); the arches by *Biennoury* ('Sculpture'). By the entrance: *2168. *Silenus with the Infant Bacchus* in his arms.

This is one of the most attractive of those representations from the satyr world which were so much in vogue during the later period of Greek art. The guardian seems to be pacifying the child by his looks and kindly gestures, while the child smiles to him and raises his left hand caressingly. An air of perfect repose and content pervades the whole group, and the effect is enhanced by the admirable ease and finish of the execution.

To the right, Roman sarcophagus reliefs, including 2180. Contest between Apollo and Marsyas, mutilated. In the centre, Antique fountain. By the first window, 2208. Colossal head of the Emp. Caracalla, found in Macedonia. By the second window, 2214. Colossal *Bust of Mæcenas*.

The next four rooms chiefly contain sculptures of the Roman imperial epoch.

SALLE DES SAISONS, with ceiling by *Romanelli* (Diana with Apollo, Actæon, or Endymion; Apollo and Marsyas or the Muses; the Seasons). In the centre: 2219 (131). Roman married couple (Hadrian and Sabina?) in the characters of Mars and Venus. To the right, 2229. Bust of Constantine the Great. On the wall near the entrance, above, 2225. Relief representing the fall of Phaëthon.

2231-1234. The god *Mithras* slaying a bull.

The worship of Mithras was brought from Asia to Rome, where the deity was identified with the 'unvanquished god of the sun'. In the later empire this mysterious cult, with its mass of allegory and symbol, in which sun and moon, the dog-star, the serpent, and the scorpion all play their parts, was disseminated throughout the whole of the Roman world. It comprised within its range the most diverse mythological characteristics of later paganism. This relief was long the only one of the kind known, but there are now numerous similar works both in the Louvre and other collections.

SALLE DE LA PAIX, with ceiling by *Romanelli* (Minerva surrounded by the Sciences, Arts, and Commerce). In the centre: 2262. *Statue of Minerva*, sitting on a rock, in porphyry, restored as Roma, the flesh parts in gilded bronze. — The eight granite columns, placed at the entrance and exit of the saloon, once adorned that part of the Cathedral of Aix-la-Chapelle which was built by Charlemagne.

† The numbers here given (blue on the labels) are those of the new catalogue, which is on the point of being published. The figures given in parentheses are those of the old catalogue (black on the labels).

SALLE DE SÉVÈRE, with ceiling by *Romanelli* (Poetry and History celebrating the warlike fame of Rome). Extensive collection of busts of Roman emperors and empresses from Marcus Aurelius to Caracalla, named with the help of coins and medals. In the middle, 2281. Statue of *Mammaea*, mother of Alex. Severus. To the right, 2289. Antinous, a fine bust; 2305. Pertinax, statue.

The SALLE DES ANTONINS is mainly occupied with busts and statues of Trajan, Hadrian, Antoninus Pius, Marcus Aurelius, Commodus, Ælius Verus, and Lucius Verus, some of them in several different styles. In the middle: 2334. Colossal statue of Marcus Aurelius (head modern). *2335. Sitting figure of Trajan. On one side, 2371. Colossal head of Lucilla, wife of Lucius Verus, found in 1847 at Carthage. — The ceiling-paintings, by *Romanelli*, represent Virtues and their Geniuses, and Heroines of the Bible. To the right is the —

SALLE D'AUGUSTE, the decorations of which were executed in the reign of Napoleon III.; ceiling-painting by *Matout* (Apollo and Minerva, the Muses and poets). Busts and statues of the early Roman emperors are exhibited here. In the centre: *2397. Colossal *Bust of Antinous*, from the Villa Mondragone. The expression is grave and pensive, and the elaborately-arranged hair is adorned with Bacchanalian attributes. — *2396. *Bust of Julius Caesar*; beyond, *2398. (184). *Roman Orator*, formerly called Germanicus (perhaps Julius Cæsar), conceived in the type of a Hermes and of fine and vigorous, though somewhat realistic execution. It is inscribed with the name of the sculptor *Cleomenes* of Athens, and belongs to the best period of the revival of Greek art under the early Roman emperors. — 2422. *Bust of Agrippa*; 2399. Colossal bust of Roma, with a she-wolf suckling one of the founders of Rome on each side of the helmet. In the centre of the end-wall: *2402. *Statue of Augustus*, with finely-executed draperies. To the right, *2435. *Tiberius*; to the left, 2467. *Augustus*; in front, 2400, 2401. *Two Young Romans with the Bulla*. Along the sides of the hall: Busts of the Julian emperors and their families, that of Nero especially interesting; some of the female heads are executed with great delicacy.

We now return to the Rotonde (p. 97), whence we enter the other rooms to the right.

The *SALLE GRECQUE, with good ceiling-paintings (Jupiter and Diana) by *Prud'hon*, and mural paintings by *Garnier* and *Mérimée*, contains works of the culminating period of Greek plastic art, and that immediately before and after it (5th cent. B.C.). Everything here is worthy of careful inspection, though sadly mutilated.

To the right, below, by the wall next to the Rotonde: *1993. Three *Reliefs from the Island of Thasos*, found in 1867.

These three reliefs originally formed one whole, which, as we learn from the ancient inscriptions, belonged to a sanctuary sacred to Apollo, the Charities (Graces), and the Nymphs. The inscription in larger letters at

the top is of later origin, and refers to the use of the reliefs in adorning a tomb in the Roman period. From each side of the central niche step four goddesses, holding garlands and blossoms in their hands; those on the left are accompanied by Apollo, those on the right by Hermes. In form and movement the stiffness and angularity of the archaic school are still visible, but the vitality and variety of the motives, as well as the fine arrangement and execution of the drapery, betoken the period of transition to a more perfect style. The work thus probably dates from the end of the 6th or the beginning of the 5th cent. B.C.

Above: *2107. *Fragment of the Frieze of the Parthenon*, the celebrated temple of Athena on the Acropolis at Athens, executed under the superintendence of Phidias.

The frieze, which ran round the walls of the temple within the colonnade, represents the festive procession which ascended to the Acropolis after the Panathenæan games for the purpose of presenting the goddess with the peplus, or robe woven and embroidered by Athenian virgins. The rest of the reliefs are in London and Athens. The fragment preserved here represents young Athenian girls with vessels, and two priests, advancing in solemn procession.

Still higher: *2106. *Metope* from the Parthenon, representing a Centaur carrying off a woman, a group of great vigour.

As it would have been impossible for Phidias to execute with his own hands all the sculptural ornamentation of the Parthenon, as well as the chryselephantine statue in the interior, we may take it for granted that most of the frieze and metopes was entrusted to his pupils. It is indeed very evident that different hands have been at work in the production of these sculptures.

Adjacent, to the right, *2096. Hercules subduing the Cretan Bull, and to the left, *2097. Athena sitting on a rock, two metopes from the Temple of Zeus at Olympia, excavated by the French in 1829, and in tolerable preservation. Compared with Attic sculptures these works, dating from about 460 B.C., are somewhat deficient in grace, but they are full of freshness and vigour.

Below, to the left: *2105. Attic relief of **Hermes, Orpheus, and Eurydice*, an admirable example of the simple and yet majestic style of the best period of Greek art.

'Orpheus was permitted to bring back his wife Eurydice from the infernal regions to the light of day on condition that he should not look at her on the way; but he failed to fulfil the condition. Hermes, the leader of the dead, gently, but firmly grasps the hand of Eurydice to conduct her back to the empire of shades. In this simple and beautiful composition are traceable a whole series of different phases of hope and pain. The advance of the procession, the turning round of Orpheus, the confidential communing of the pair, the halt, and the impending return of Eurydice are all distinctly portrayed'. *Kékulé*. — There are replicas of the work at Rome and Naples. The inscription 'Zetus, Antiope, Amphion' over the figures is doubtless comparatively modern.

In the first window-recess, on the side next the Seine: Glass-case containing fragments from the temple at Olympia. To the left, 2076. Apollo. — Between the windows: 2035 (488). Alexander the Great, formerly called Inopus, found in the island of Delos. — By the second window: in front, 2008. Head of one of the Lapithæ from a metope in the Parthenon, lately found in the sea at the Piræus; behind, 2041. Tablets with Athenian decrees; on the walls, votive bas-reliefs. — By the third window: Funeral bas-reliefs; 2039.

2040. The *Nointel Tablets*, with lists of the Athenians who fell in the war of B. C. 457. By the wall at the end of the room, Funeral monuments, including several fine large bas-reliefs. In front, a sepulchral couch. — In the middle of the hall: 1976-1978. Three mutilated statues in the archaic style: *Juno, from Samos (probably 6th cent.) and two Apollos, from Actium.

On the side next the court, to the left of the window: 2003. Bust of a veiled woman; 1332. Minerva from Athens. By the window: Inscriptions, including 2079 (124). Marble stele, brought from Athens by Choiseul-Gouffier, with inscriptions, recording the sums spent by the treasurers of the Parthenon in the 3rd and 4th years of the 92nd Olympiad (B.C. 410 and 409). Above it, a relief of Athene, the olive-tree, and the Archon Glaucippus. — To the right of the window: 2018. Bust of Theseus (?); 1391. Daughter of Niobe; 1393. Lion of Plataea; architectural fragments from Macedonia. To the left of the entrance to the following room, 2001. Torso of Juno, probably of the Phidian school.

We proceed in a straight direction, leaving the Salle des Caritides (p. 103) to the left.

CORRIDOR DE PAN. To the right: Demosthenes, one of the most artistic and best-preserved heads now extant of this orator. Then behind two columns, 1596. Sitting figure of *Pan*.

SALLE DU SARCOPHAGE DE MÉDÉE. In the middle: 1604. Venus in a stooping attitude, a life-size, somewhat coarse figure, unfortunately headless, with the remains of a small hand on the back, found at Vienne in the S. of France, and acquired for the Louvre in 1878. To the right: *1611 (282). Sarcophagus adorned with a representation of the myth of Medea. 1615. The Graces (heads modern); 1613. Hunting satyr (bas-relief); 251. Silenus; 1631 (407). Hygieia (? head from another statue).

SALLE DE L'HERMAPHRODITE DE VELLETRI. To the right: 1649. Farnese Cupid, found in 1862 in the excavations carried on by Napoleon III. in the imperial palace on the Palatine; the torso alone is ancient. 1650, 1651, 1644. Athena. In the window-recess: 1642. Hermaphrodite, from Velletri (see p. 103). To the left, 1637 (260). Young satyr and boy.

SALLE DU SARCOPHAGE D'ADONIS. In the middle: 1709. Stooping Venus, like the figure in the Salle du Sarcophage de Médée. To the right and left: 1657, 1673. Youthful Bacchus. 1664 (438). Roman sarcophagus with Tritons and Nereids. On the wall above: *1666 (172). Front of a sarcophagus, with reliefs in three scenes, representing Adonis starting for the hunt, being wounded by the boar, and dying in presence of the mourning Aphrodite.

In the entry to the next room stand four figures of Aphrodite.

SALLE DE LA PSYCHÉ. In the middle: 1715. Atalanta. To the right: 1698 (271). *Psyche*; at the sides, 1694, 1701. (426, 240). Sarcophagi from Bordeaux, with reliefs of Selene and Endymion,

and of Bacchus and Ariadne; on the second, 1705. Sitting figure of *Euripides* (head modern) with a list of his dramas at the back. Several bas-reliefs from sarcophagi. 1706, 1719. Dancing Satyrs. 1718, 1713. Two fine marble chairs. 1711. Athlete anointing himself with oil. — At the entry to the next room: 1722, 1723. Aphrodite.

SALLE DE LA VÉNUS DE MILO, dedicated to the *Venus of Milo* (No. 1724), the most celebrated of the treasures of the Louvre. 'This is the only statue of Aphrodite handed down to us which represents her not merely as a beautiful woman, but as a goddess. The form is powerful and majestic, and yet instinct with an indescribable charm of youth and beauty, while the pure and noble expression of the head denotes the goddess's independence of all human requirements and the calm self-sufficiency of her divine character. The fact that this beautiful work, notwithstanding its great excellence, is not one of those which have been specially extolled by ancient authors, affords us an approximate idea of the beauty of those lost masterpieces which formed the great marvel of antiquity' (*Lübke*).

The statue was found in 1820 by a peasant in the island of *Melos*, now *Milo*, at the entrance to the Greek Archipelago, and sold for 6000 fr. to the French government. It is the work of a school which forms a transition from the school of *Phidias* to that of *Praxiteles*, and is very similar to the Florentine group of the Children of Niobe, which was probably executed by *Scopas*, a contemporary of Philip of Macedon, so that this Venus is not unreasonably ascribed to a pupil of that master. On the ancient monuments Aphrodite and Nike, in attitudes similar to that of this work, are each represented singly, holding a shield; and the same attitude is observed in groups of Aphrodite with Ares. The weight of evidence in the present case is in favour of the view that the goddess stood alone, holding a shield as a symbol of victory in her hand. Among various fragments found along with the statue were part of a left arm and a left hand, the closed fingers of which hold an apple (now preserved in a glass case by the first window to the left); and this has naturally led some of the French savants to suppose that this Aphrodite held an apple in her uplifted left hand and her drapery with the right. The hand is, however, of inferior workmanship to the torso, so that it is probably either altogether unconnected with it, or belonged to an ancient attempt to restore the work.

To the right and left are statues in the same attitude as the Venus of Milo, but differing from it in various points.

SALLE DE LA MELPOMÈNE, so named from No. *1741 (386). *Melpomene*, one of the largest ancient statues in existence (13 ft. in height), occupying the wall at the back, hewn out of a single block of Pentelic marble, and admirably draped. — The large mosaic on the pavement, by *François Belloni*, represents the genius of Napoleon I. (in the character of Minerva) gaining victories that she may inaugurate peace and plenty. — To the right, by the window at the back: *1750 (164). Head of Aphrodite, of the Cnidian Venus type, probably of the school of Praxiteles. To the right and left of Melpomene: 1749 (380), 1743 (379). Statues restored as Euterpe.

SALLE DE LA PALLAS DE VELLETRI. In the centre, 1761. Large marble cratera with masks of satyrs. 1762. Sleeping Cupid; 1763.

Bust of Alexander the Great; 1764. Venus leaving the bath, an antique reproduction of the Venus of the Capitol; ancient bath of porphyry. — *1766. *Venus of Arles*, a Greek work found in 1651 at Arles in Provence. — *1767. Head of Homer (upper part of a herma), of the well-known type; the sunken features, sightless eye-balls, and slightly-opened mouth are all characteristic of the ancient conception of the inspired singer in his old age. — *1768. *Apollo Saurroctonus*, 'the lizard-slayer', a copy of a work by Praxiteles; the right hand originally held a dart, with which he was about to transfix the reptile. — *1769. Vase with a curious representation of a festive dance round a sacrificial altar. The altar is approached by Diana, Apollo, Hermes, and other gods, while Satyrs and Mænads are dancing around. *Sosibios* of Athens, the name of the master, is inscribed in relief on the pedestal of the altar (now scarcely legible).

To the right, in retracing our steps: 1828. Rustic usurer; 1822. Urn; 1815. Bacchic candelabrum; 1810. Seat from a bath; 1806. Bacchus and Silenus; 1802. Juno (?) restored as Providentia. — On the other side: 1771. Statue restored as Urania; 1780. Sarcophagus with reliefs of Actæon torn to pieces by his dogs. — *1784. *Pallas of Velletri*, whence the saloon derives its name, found in 1797 at Velletri near Rome. In the right hand was a spear, in the left perhaps a small Nike (Victoria). The statue is a Roman copy of a work of the best Greek period. — 1791. Polyhymnia, the upper part of the body modern, in front, *1793. *Sarcophagus of the Muses*, on which are represented the Nine Muses in the following order, from left to right: Clio, Thalia, Terpsichore, Euterpe, Polyhymnia, Calliope, Erato, Urania, and Melpomene. On the right side are Plato and Calliope; on the left, Socrates and a woman; on the top, a festival.

SALLE DU HÉROS COMBATTANT. In the centre: 1833. *Venus Genetrix*, as the traditional ancestress of the Julian family. — *1835. *Fighting Hero* or *Borghese Gladiator*, found at Antium near Rome, in one of the imperial palaces. The inscription records that it was executed by 'Agasias, son of Dositheos of Ephesus', who seems to have flourished in the last years of the Republic or the first of the Empire.

'The statue is rather to be regarded as that of a hero fighting. The right arm is modern, while the left arm and the strap of the shield are preserved. Opposite the hero we must suppose an Amazon on horseback or standing on a rock above, against whom the hero is defending himself with his shield by a movement of his left arm, while with his right he is directing the stroke of his sword with eager look. The mouth is open, as if the hero, like Homer's warriors, were shouting to his adversary. The expression of the face is indicative of a supreme and yet controlled effort of strength. The distinctness with which the simultaneous acts of defence and attack are expressed in this master-work has led to the belief that the figure did not originally stand alone, but was placed opposite some antagonist, without whom the hero's attitude would be comparatively meaningless.' *Welcker*.

1837. Young satyr, known as 'Le Faune à la tâche'; *1838. So-called *Diana of Gabii*, a charming work, probably of the time of

Alexander the Great, and simply a genre-figure of a girl. To the right, in retracing our steps: 1883. Mercury (the 'Richelieu Mercury'); 1864. Wounded Amazon. On the other side: 1839. Minerva; 1846. Cupid and Psyche; *1854. Marsyas, bound to the trunk of a tree, awaiting the execution of the sentence of Apollo that he should be flayed alive; in front, 1849. Sarcophagus of Meleager, on which lies (No. 1850) a celebrated Græco-Egyptian map of the stars, named after Fr. Bianchini (d. 1729), an astronomer of Verona; 1857. Cupid; 1860. Cupid as Hercules; 1862. Mercury.

In the entry to the next room: *1885 (299). Centaur subdued by the Genius of Bacchus, from the Borghese collection, resembling the Capitoline Centaur, which, however, is without the Genius.

SALLE DU TIBRE. In the centre: 1894. Unknown Greek poet. — *1895. *The Huntress Diana*, or *Diana of Versailles*, probably executed at Rome by a Greek sculptor during the last century of the Republic. It is similar to the Belvedere Apollo, but inferior in execution.

The goddess, walking fast, seizes an arrow. She is looking round as if in search of fresh game. The expression of face is grave, the forehead high and severe, the eyes eager. The fawn running beside her heightens the impression of the rapid strides of the goddess.

*1892. *Colossal River-god of the Tiber*, recumbent, with Romulus and Remus and the she-wolf by his side, probably a work of the early Roman empire, an admirable companion to the celebrated group of the Nile in the Vatican. On the left and right: 1900, 1901. Flute-playing Fauns, after Praxiteles. — Behind, 1903-1906. Four colossal Fauns bearing a frieze, a happy combination of the dignified and the humorous, from the Theatre of Dionysus at Athens (3rd cent. B. C.).

In front of the windows: 1923. Bacchus of Versailles; 1934. Æsculapius.

By the second window: *1961. *Base of the Borghese Candelabrum*, also known as the Altar of the Twelve Gods.

Each of the three sides is divided into two equal parts, the upper part containing four figures, the lower, three. First side: Jupiter, Juno, Neptune, Ceres; the Three Graces. Second side (left): Mars, Venus, Mercury, Vesta; the Three Fates. Third side: Apollo, Diana, Vulcan, Minerva; three Hours or Seasons.

To the left, by the first window: 1954. So-called astrological altar of Gabii, with the heads of the twelve Olympian gods and the signs of the Zodiac.

SALLE DES CARIATIDES. The vestibule contains, by the farther wall, a chimney-piece executed by *Percier* and *Fontaine*, and many other decorations by the same masters, by whom this room was thoroughly restored in 1806. In front of the chimney-piece: *1375. *Hercules*, with his son *Telephus* and the hind by which the latter was suckled. — To the left, by the window: *1562. The *Borghese Hermaphrodite*, of the latest Greek period, and too sensuous in style. The pedestal is an unhappy idea of Bernini (17th cent.).

The saloon itself was originally an ante-chamber of the apartments of Catherine de Médicis, and was therefore named the 'Salle des Gardes'. Here Henri IV. celebrated his marriage with Margaret of Valois, and here his body was placed after his assassination. It was in this saloon that the Ligue held its meetings in 1593, and that the Duc de Guise caused four of its most zealous members to be hanged the following year. In 1659 the room was used as a theatre by Molière, who acted here in his own inimitable plays.

In the middle, between two pillars: *1378. *Jupiter of Versailles*, or Zeus as the conqueror of the Giants, restored as a herma. To the right, 1380. Statue of a Greek philosopher (*Poseidonius?*). To the left, *1379. *Demosthenes* in a sitting posture; the compressed lower lip suggests the effort made by the great orator to overcome his stammering; his features express the utmost intelligence and great self-reliance. In the centre: no number, Polyhymnia, much mutilated. *1383 (183). Young Greek in the act of fastening his sandals, formerly called Jason, Cincinnatus, or Hermes. 1385. Sleeping Bacchus; *1386 (235). *Borghese Vase*, in Parian marble, with admirable Bacchanalian representations, found in the 16th cent. near the gardens of Sallust at Rome. Then, *1387 (217). Young Dionysus (the 'Richelieu Bacchus'); 1389. Discobolus; *1996 (112). 'Minerva au collier', in the ancient Greek style.

Round the walls, from right to left: 1416 (221). Intoxicated Bacchus; 1457, 1486 (383, 380). Statues restored as Thalia; 1460. Large candelabrum reconstructed in the 18th cent. from ancient fragments; 1524. Youthful Hercules; 1537. Lion of green Egyptian basalt. — 1354 (147). *Venus in the Bath*, stooping so as to allow a nymph to pour water over her back (freely restored); 1347. Alexander the Great, head and torso of different statues; 1342. Boy with a goose; 1334, 1326 (33, 34). Jupiter; 1320. Nymph of Diana (*Vénus à la coquille*); 1315 (32). Jupiter; 1305 (148). Venus in a stooping posture (head modern).

At each end of the Salle is a large antique shallow vase. The acoustic properties of the room are such that the faintest whisper uttered at the edge of one vase is distinctly audible to an ear at the edge of the other.

The saloon derives its name from the four *Caryatides bearing the gallery at the egress, executed by *Jean Goujon*. Above it is a cast of Cellini's Nymph of Fontainebleau (p. 107).

Antique Bronzes, see p. 141; *Terracottas, Vases* etc., p. 145.

The *Escalier Henri II*, in the Pavillon de l'Horloge, adjoining the Salle des Caryatides, ascends to the principal collections on the first floor (see plans, pp. 88, 89; Collection La Caze, p. 140). It is, however, better to ascend by the grand staircase, reached by returning through the Salle des Caryatides, and turning to the right.

Visitors who have time to spare should pass out, by the side of the Escalier Henri II., into the Court of the Old Louvre, in order

to inspect the Mediæval Collection of Renaissance Sculptures, which are well worth a visit.

The *Collection of Mediæval and Renaissance Sculptures (*Musée des Sculptures du Moyen-Age et de la Renaissance*), in connection with the collection of modern sculptures, affords an excellent opportunity of tracing the progress of the plastic art in France, and also contains some admirable Renaissance work in the Italian department, which has recently been much enriched. — Entrance in the S. wing of the inner Court of the Louvre, E. side (admission daily except Mon., 11 to 4 or 5; see p. 89).

To the right of the vestibule is the MUSÉE CHRÉTIEN, containing sarcophagi, reliefs, a mosaic, and inscriptions, chiefly of the 4th and 5th centuries, from S. France, Italy, Algeria, etc. — The adjoining room is at present (spring 1891) empty, but will possibly be used for some of the works removed temporarily from the following rooms.

On the other side of the vestibule is situated the SALLE DE LA CHEMINÉE DE BRUGES, containing a cast of the beautiful chimney-piece in the Palais de Justice at Bruges and casts from the tombs of Marie of Burgundy and Charles the Bold, also at Bruges. Among the original works is a bronze recumbent figure of Duchess Blanche (d. 1283), the heroine of Brittany. — Another room is to be opened on this side, communicating with the Salle du Moyen Age (see below).

SALLE BEAUNEVEU or ROOM I., at the end to the left, communicating with the Egyptian Museum (p. 90), contains statues from tombs and statuettes of the French school of the 14-15th centuries. The chief work is the *Monument of Philippe Pot, grand-seneschal of Burgundy and favourite of Philip the Good, who was buried at the Abbey of Cîteaux. The recumbent statue reposes on a slab supported by eight mourning figures. By the window towards the Seine, a Flemish *Calvary, in wood (16th cent.). In the middle, a tomb-statue in beaten copper.

SALLE DU MOYEN AGE (II). This room contains similar statues of the 14th century; Virgin, Christ, and bas-reliefs of that date. Statue of Childebert, king of France (13th cent.). Capitals, sculptured fragments, etc. of the 11-13th centuries. Gothic *Portal from a house in Valentia in Spain (15th cent.); sepulchral bronze of a Catalan merchant (d. 1400). — A room to the side, not yet arranged, communicates with the Salle de la Cheminée de Bruges (see above).

SALLE DE MICHEL COLOMBE (III), the works in which show the French school of sculpture uninfluenced by Italian art. By *M. Colombe* or *Michault Columb* (1431-1514), from whom the room takes its name: opposite the entrance, St. George and the Dragon, a large relief. To the right, *Virgin, of the same school. In the middle: *Mercury and Psyche, bronze, by *R. de Vries*. At the first window: Mercury, a replica of the bronze statue in Florence, by *Giov. da Bologna*, an imitator of Michael Angelo, and a native of Douai in

Flanders. Behind, bronze head of Henri IV., and two bas-reliefs. The second, also in bronze, is a portrait of André Blondel de Roquencourt (d. 1558), general comptroller of finance under Henri II., attributed to *Paolo Ponzio*. Bronze bust of Francis I. Tombs of the 16th century. *Tomb of Jean de Cromois, abbot of St. Jacques, at Liège (d. 1525); Passage of the Red Sea (bas-relief). Tomb of Alberto Pio of Savoy, Prince of Carpi (1535, bronze): Monument of the historian Phil. de Commynes and his wife; Death of the Virgin (alto-relief); recumbent statue of Dead Christ, attributed to *G. Pilon*, etc. By the second window, 'La Mort St. Innocent', a skeleton from the former Cemetery des Innocents; fine bas-reliefs, including Judas's Kiss (French school) and a Holy Family, after Dürer, attributed to *Hans Daucher*.

SALLE DE JEAN GOUJON (IV), named after the most distinguished French sculptor of the 16th century, who executed, under Henri II., a great part of the decorations of the Louvre. His best-known work is the large group of *Diana with the hind in the middle of this saloon, which affords an excellent example of the gracefulness of form and other attributes characteristic of French taste. (The visitor will find it interesting to compare this Diana with Benvenuto Cellini's Nymph of Fontainebleau, p. 107.) In the middle of the room are also placed a marble group of the Three Graces (the urn on whose heads was once destined to contain the heart of Henri II.), and wooden statues representing the four cardinal virtues (destined as the supporters of a reliquary), works by *Germain Pilon* (d. 1590), showing the same style as the Diana, and one which the French painters soon afterwards adopted. — Round the room from right to left: *G. Pilon*, Small bust; *Barth. Prieur*, Statue of Anne de Montmorency; *Frémyn Roussel*, Genius of history; *G. Pilon*, Statue and figures from the tomb of the wife of the chancellor De Birague; three bas-reliefs; *J. Goujon*, *Five bas-reliefs; *B. Prieur*, Column, three statues, and symbols from the tomb of the Constable Anne de Montmorency; *G. Pilon*, Chimney-piece, with bust of Henri II. attributed to *J. Goujon*; *Le Hongre*, Mausoleum of the Cossé-Brissac family; *G. Pilon*, Busts of Henri III. and Charles IX.; bronze statue of Cardinal de Birague; *B. Prieur*, Bronze geniuses, from a tomb; *G. Pilon*, Testimony on oath (bronze reliefs); *J. Goujon*, Fountain-nymphs from the Fontaine des Innocents. At the third window: *Richier*, *Daniel come to judgment (relief); Infant Jesus and two angels (statuettes); Pietà, by an unknown artist of the 17th cent.; *Fr. Roussel*, Nymphs awakened; *G. Pilon*, Faith and Strength (bas-relief). At the second window: *B. Prieur*, Statue from a tomb; *School of J. Goujon*, Nymphs and Venus (bas-relief). At the first window: *G. Pilon*, Fragments of a pulpit.

The chief attraction of this collection is the *MICHAEL ANGELO SALOON (V), containing Italian sculptures of the 15-17th cent., and

named from the marble statues of the two ^{**}Fettered Slaves, by the great Florentine sculptor *Michael Angelo Buonarroti*.

These figures were intended to form part of a magnificent monument to Pope Julius II., and to represent, along with several others of a similar character, the virtues fettered and doomed to death in consequence of the decease of that pontiff. Michael Angelo executed them in 1513-16, and in 1544, when the original ambitious design of the monument was abandoned, presented them to Roberto Strozzi, by whom they were sent to France. The younger dying slave, with the pained expression of countenance, is of great beauty; the other figure is in a somewhat constrained and unpleasing attitude.

These statues stand on the right and left of the entrance to the next room, consisting of a ^{*}Portal of the end of the 15th cent., removed from the Palazzo Stanga in Cremona, and purchased in 1875 for 80,000 fr., a perfect gem of decorative sculpture, attributed to the brothers *Rodari*. The reliefs represent scenes from the life of Hercules, the mythical founder of Cremona, and from that of Perseus. In front of this portal are two busts, one of ^{*}Filippo Strozzi by *Benedetto da Majano*. In the middle of the room is a marble fountain from Château Gaillon (p. 364), an Italian work of the 16th century.

Beside the entrance: Bust of John the Baptist as a child, by *Mino da Fiesole*; Virgins, by unknown artists of the 15-16th cent.; Bust of Ferdinand I. of Aragon, king of Naples (1458-1494) and other busts; Circumcision (Venetian school); etc. High up: ^{*}*Benvvenuto Cellini*, the 'Nymph of Fontainebleau', a large relief in bronze executed for an archway in the Palace at Fontainebleau, and mentioned in the master's autobiography.

By the back-wall: Jason, and Hercules slaying the Hydra, two bronze statues of the 16th cent.; equestrian figure in high-relief of Rob. Malatesta, captain-general of the papal forces (end of 15th cent.); Virgin and the angel Gabriel (Florentine school of the end of the 14th cent.); Bust of John the Baptist, by *Donatello*. By the first window: Romulus and Remus suckled by the wolf, another Italian work of the 16th cent., in white marble and rosso antico. — The collection of early-Renaissance bronzes by the windows forms the most beautiful collection of the kind on this side of the Alps. The finest are eight bronze reliefs by *Andrea Briosco*, surnamed *Riccio*, of Padua (1480-1532).

Originally belonging to the tomb of Marcantonio della Torre, these reliefs illustrate the life and death of that celebrated physician in a thoroughly antique style, as follows: Della Torre lecturing under the superintendence of Apollo and Hygieia and in front of a statue of Minerva; His death-bed, surrounded by Apollo and the Fates; His relatives sacrifice to the gods to induce them to spare the sick man; His death; His burial; His soul at the portals of the infernal regions; His arrival in Elysium, where he is awaited by the Graces; The goddess of fame placing an honorary chaplet on his body.

SALLE DE LA RENAISSANCE ITALIENNE (VI). Statues and reliefs of religious subjects of the 14-15th centuries. On the wall opposite the entrance: Statue of Louis XII. by *Lor. da Mugiano*; Bust

of John the Baptist by *Donatello*. At the windows: Ornamental sculptures, etc. — The next room (empty) adjoins the Salle des Antiquités Chrétiennes (p. 105).

WORKS NOT YET ARRANGED: *François Anguier*: Monument of the Dukes of Longueville, a pyramid with graceful allegorical figures and reliefs; Marble monument of Jacques de Souvré (d. 1670), Knight of St. John, in a theatrical style; in better style, Marble statue of De Thou (d. 1617), president of the Parliament. — *Simon Guillain*: Statues of Louis XIV. at the age of ten, and his parents, Louis XIII. and Anne of Austria; Marble statue from the tomb of Charlotte de le Trémouille, Princess of Condé. — Fame, a bronze by *Berthelot*; Fragments from the monument of Henri IV., on the Pont-Neuf, which was destroyed in 1792. Four slaves in bronze from the pedestal of the monument, by *P. Francheville* or *Franqueville*, a pupil of Giov. da Bologna. *Bust of Henri IV., by *Barth. Prieur*. Four bronze dogs from Fontainebleau (17th cent.). Virgin attributed to *G. Pilon*, formerly in the Château d'Ecouen, and latterly at Notre Dame de Versailles.

The Collection of Modern Sculptures (*Musée des Sculptures Modernes*) forms a continuation of the Renaissance collection. Entrance on the W. side of the Cour du Louvre, second door to the right of the Pavillon d'Horloge (open daily, except Monday, 11-4; comp. Plan, E). This door leads us at once into the —

SALLE DE PUGET, named after *Pierre Puget* of Marseilles (1622-94), the most famous and the most exaggerating of the French followers of the theatrical school of Bernini, which aimed exclusively at effect. Among his works are, in the middle: 204. Perseus and Andromeda (1684); 201. Hercules reposing, executed in Genoa about 1660; to the left, *203. Milo of Croton fighting with a lion, the best-known and most admired of his works, executed in 1682 for the park of Versailles; to the left, 205. Diogenes requesting Alexander the Great to stand out of his light, an alto-relief (the vulgar types of the king's followers very cleverly represented). — By the first window: 206. *Puget*, Alexander the Great triumphing over his enemies (the original design had Louis XIV. instead of Alexander). — By the central window: *213. Antique head of Alexander in porphyry, placed on a bust in green breccia and gilded copper by *Girardon*. — By the window to the right: 209. *Girardon*, Bronze model of the equestrian statue erected to Louis XIV. in the Place Vendôme in 1699. — Adjacent: *Théodon*, 244^{ter}. Phaetusa converted into a reed, 244^{bis}. Atlas.

The door on the left of the entrance leads to the —

SALLE DE COYZEVOX, named after *Charles Antoine Coyzevox*, one of the ablest masters of the same school, especially happy in his portrait-busts. His works here include: in the centre, 234. Shepherd playing on the flute, Small satyr; opposite (no number), the Rhone;

to the left, Venus; on the other side, Monument of Cardinal Mazarin; the Cardinal kneels on the sarcophagus, while behind him is a Genius with a bundle of staves, the chief cognisance in his armorial bearings; below are bronze statues of Prudence (left), Peace, and Fidelity (right). The marble figures of Love and Religion also belong to the Cardinal's monument. Round the room, also by Coyzevox: Busts of Richelieu, Bossuet, Lebrun, the painter, Coyzevox himself, Mignard, the painter, and Marie Serre, mother of the painter Rigaud.

We return to the Salle de Puget and pass through it to the —

SALLE DES COUSTOU, in which are assembled the plastic masterpieces of the pleasure-loving age of Louis XV. The brothers *Nicolas Coustou* and *Guillaume Coustou*, and the son of the latter, another *Guillaume Coustou*, were artists of the 17th and 18th cent. who exaggerated the tendencies of their predecessors. In the centre: 250^{bis}. *Nicolas Coustou*, Adonis resting from the fatigues of the chase (1710). Behind (no number), *Cupid with his dart, by *Antoine Tassaert* (below is the inscription: 'Qui que tu sois, voici ton maître, il l'est, le fut, ou le doit être'). 303. *Julien*, The nymph Amalthea and the goat, the *chef d'oeuvre* of the master. To the right of the entrance: *255. *Guillaume Coustou the Elder*, Maria Lesczinska of Poland, consort of Louis XV. (1731). Facing this: **Falconet*, Music. Between the windows: 270^{bis}. *J.-B. Pigalle*, Mercury fastening his sandals, one of the artist's best works (1763). Above, on the wall: 221-226. *Martin Desjardins*, Six bas-reliefs in bronze from the statue of Louis XIV. which used to stand on the Place des Victoires, now replaced by another. — Three doors lead into the adjoining —

SALLE DE HOUDON, dedicated chiefly to *Antoine Houdon* (Versailles, 1741-1828), a sculptor who lived and worked in Rome, Paris, and America. By *Houdon*, in the centre of the room: 296. Bronze statue of Diana (1783), executed first in marble for the Empress of Russia (1781). — In front of the pillar to the right: *Pajou*, 287. Psyche (1790), with the inscription: 'Psyche perdit l'amour en voulant le connaître'; 284^{bis}. Bacchante. In a niche, 272. *Bouchardon*, Cupid carving a bow out of the club of Hercules. — The following busts are also by *Houdon*: The Abbé Aubert (d. 1814). Rousseau (bronze), *Washington, *Franklin, *Diderot, Mirabeau, and Voltaire (bronze). *Pajou*, Busts of Mme Dubarry, Buffon, etc. — Opposite the window: 310. *Delaistre*, Cupid and Psyche (1782); *Bouchardon*, Model of the statue of Louis XV., which was destroyed in 1792, in terracotta.

The SALLE DE CHAUDET is mainly occupied with works of the end of the 18th and beginning of the 19th cent., when the ancient classical style was revived. To the left: 314. *Chaudet*, Cupid with the butterfly. In the centre: 326. *F. J. Bosio*, Aristæus, the god of gardens (1817); *383. *Canova*, Cupid and Psyche; 313. *Chaudet*,

The young Œdipus rescued by the shepherd Phorbas. Round the hall, beginning at the end: 338. *Cortot*, Daphnis and Chloe; 339. *Roman*, Nisus and Euryalus; 324. *Ruxtiel*, Psyche borne by Zephyr (1814); 327, 328. *Bosio*, Hyacinthus, the Nymph Salmacis; 320. *Dupaty*, Biblis changed into a fountain; *384. *Canova*, Cupid and Psyche with the butterfly. Central range: no number, *Cortot*, Soldier of Marathon; 355. Statue of Cato of Utica, begun by *Roman*, and finished by *Rude* in 1840.

The *SALLE DE RUDE*, the last, named after the sculptor *François Rude* (1784-1855), contains the most modern works admitted to the Louvre (comp. p. 255). From right to left: no number, *Foyatier*, Spartacus; 354. *Rude*, Christ; no number, *Barye*, Bronze animals; **Carpeaux*, Four quarters of the globe supporting the sphere, model of the group on the Fontaine du Luxembourg (p. 260); 353. *Rude*, Mercury, in bronze; no number, *Perraud*, Despair (male figure in a sitting posture); *Rude*, 353^{bis}, 353^{ter}. Young Neapolitan Fisher, Joan of Arc; no number, *Perraud*, Les Adieux, a bas-relief; *382. *David d'Angers*, Philopœmen wounded with a spear; 349^{bis}, 348^{bis}. *Pradier*, Sappho, Psyche; no number, **Durel*, Young Fisherman dancing the tarantella; *Ramey*, Theseus and the Minotaur; *Nanteuil*, Eurydice; **Duret*, Neapolitan Improvisatore, in bronze; **Perraud*, Childhood of Bacchus; **Carpeaux*, Dance, model of the group at the Opéra (p. 77); *Dumont*, Genius of Liberty, a model of that on the July Column (p. 67); 348, 349. *Pradier*, Child of Niobe, a restoration of the well-known Florentine antique, *Atlanta's toilet*. On the walls; Several medallions by *David d'Angers*.

The *Musée de Chalcographie*, where a large collection of engravings is on view and on sale, resembling the *Calcografia* at Rome, was founded by Louis XIV. in 1660. Engravings of most of the great Parisian works of art, in the provinces of painting, sculpture, and architecture are exhibited and sold here. The catalogue enumerates about 5000. The exhibition is on the left side of the entrance (rear the Musée of modern sculpture, Pl. F; admission daily), the sale-room on the right side. — *Photographs*, see p. 111.

B. FIRST FLOOR.

The most important collection on the first floor of the Louvre is the *Picture Gallery*, which occupies more than half of the S. connecting gallery between the Old Louvre and the Tuileries (*Galerie du Bord de l'Eau*), together with the whole of the inner gallery of the New Louvre parallel to it, and also several saloons in the Old Louvre. — The first floor of the Old Louvre also contains the *Ancient Bronzes* (p. 141), the *Drawings* (p. 141), the *Medieval and Renaissance Antiquities* (p. 142), the *Ancient Vases* (*Musée Campana*, p. 145), the *Smaller Antiquities* (p. 144), the *Jewels* (p. 138), the *Gems*, *Enamels*, and *Gold Ornaments* (p. 137), and various recent acquisitions.

The *PRINCIPAL ENTRANCE* to the first floor is by the *Pavillon Denon* (where sticks etc. may be left) whence the *Escalier Daru*

ascends to the picture-gallery. — Those who wish may ascend the *Escalier Henri II.* (comp. p. 104), whence they proceed to the right to the Collection La Caze (p. 140), the Salle Henri II. (p. 140), the Salle des Sept-Cheminées (p. 139), the Salle des Bijoux (p. 138), the Rotonde d'Apollon (p. 136), and the Galerie d'Apollon (p. 136), which leads to the Salon Carré (p. 116). — There are separate entrances to the special collections on the first floor.

Photographs of the pictures, drawings, and sculptures, by Braun, are sold in the vestibule just mentioned. The photographs of the large pictures, 20 in. long and 16 in. broad, cost 12 fr., but there are also cheap copies ('épreuves d'artistes au nitrate') at 3 fr. The smaller cost 3-10 fr. The prices are marked on the specimens in the albums for public use.

**Picture Gallery.

The numbers on the pictures were altered in 1889, and a new catalogue is being prepared, of which an abridgement (1 fr.), for the entire musée, has already appeared. The old catalogue, in several sections, is still on sale in the galleries, and most of the pictures also bear the old numbers (below, to the left). Labels, with the names of the artists and the subjects of the paintings, have also been placed on the frames. The former are the painters' family names, and not of the names by which they are commonly known; thus, *Sanzio* (more correctly *Santi*), and not *Raphael*, and *Vecellio* instead of *Titian*.

Persons desiring to copy in the Louvre or Luxembourg apply to the *Administration des Musées*, the office of which is in the S.W. corner of the Cour du Louvre. — Conveniences for the use of visitors are to be found off the Galerie des Sept-Mètres (p. 120); key kept by the custodian.

The *Picture Gallery* of the Louvre, the saloons of which have an aggregate length of five furlongs, comprises upwards of 2000 select works, almost every school being represented by numerous masterpieces. There are indeed some masters whose acquaintance can be satisfactorily made in the Louvre alone. For the following general review of the most important works, arranged in schools, we are indebted to the pen of *Prof. Anthony Springer*, the eminent German historian of art; and we recommend his sketch, as well as the various incidental notices of particular pictures by Mr. Crowe and other distinguished authorities, to the perusal of the visitor before proceeding to view the gallery itself.

Most visitors to the Louvre will of course be chiefly interested in the ITALIAN PAINTERS. Among the EARLY MASTERS, those of the Florentine School first attract our notice. An excellent example of the tender and saintly style of *Fra Angelico da Fiesole* is his Coronation of Mary (No. 1290; p. 121), while *Benozzo Gozzoli's* Glory of St. Thomas Aquinas (No. 1319; p. 120) affords an instance of the inveteracy with which the artists of that age clung to mediæval ideas. *Fra Filippo Lippi* is admirably represented by a Madonna among angels and archangels (No. 1344; p. 120); but *Domenico Ghirlandajo's* Visitation, of the year 1491 (No. 1321; p. 117) is not one of his best works. — To the earliest period of *Perugino*, the chief master of the Umbrian school, belongs a round picture of the Madonna with SS. Rose and Catharine, and to his culminating

period (1505) the Conflict between Cupid and Chastity (Nos. 1564, 1567; pp. 116, 121). — The Louvre also possesses several important creations of *Andrea Mantegna*, a master of Upper Italy: Mt. Parnassus and the Victory of Minerva (Nos. 1375, 1376; p. 120) mark the transition from mythological to allegorical scenes; then the Madonna della Vittoria, a votive picture in memory of the Battle of the Taro (No. 1374; p. 120).

THE GREAT MASTERS of the Italian School, *Leonardo da Vinci*, *Raphael*, and *Titian*, demand the most careful attention. The most celebrated work of LEONARDO in the Louvre is his *Mona Lisa* (No. 1601; p. 117), the portrait of a Florentine lady, the wife of Francesco Giocondo. Leonardo was engaged on this work for four years, and at last left it unfinished. 'Any one desirous of seeing how far Art can succeed in imitating Nature should examine this beautiful head', said Vasari; but the work is so faded that its original effect is not easily imagined. A better-preserved work by Leonardo is another portrait of a lady in a red dress with a band on her forehead, supposed to be a portrait of Lucretia Crivelli, the mistress of Lodovico Moro (No. 1600; p. 123).

No gallery in Europe is so amply supplied with works of RA-
PHAEL as the Louvre. Even when the doubtful pictures (No. 1508. Raphael and his fencing-master; 1644, The handsome youth leaning on his hand) are deducted, there remains so complete a series of his works that with their help the student will have no difficulty in tracing the various stages of the master's development. To his earlier period, before he had shaken off the influence of Perugino's school, belong the small pictures of St. George and St. Michael, which he is said to have painted for the Duke of Urbino (Nos. 1503, 1502, p. 118). A gem of his Florentine period is the 'Belle Jardinière', painted in 1507 (No. 1496; p. 118), in which pure maternal joy, a favourite motive in Raphael's Madonnas, is expressed with the most lifelike fidelity. The Apollo and Marsyas (No. 1509; p. 116), a masterpiece of a different style, was also painted in this period. To his early Roman period belongs the 'Vierge au Voile' (No. 1497; p. 117). His progress in dramatic effect and in depth and contrast of colouring are exemplified by his large Holy Family and his St. Michael conquering Satan (Nos. 1498, 1504; pp. 118, 119), two works painted with the aid of his pupils in 1518, by order of Leo X., as a gift for the king and queen of France. The touch of inferior hands, and the haste with which the work was probably executed, serve to account for the displeasing effect produced by the blackened shadows and the coldness of the lights. A specimen of his best period (1515) is the portrait of Castiglione (No. 1505; p. 123), in which we are struck with his consummate skill in modelling, in blending a warm yellow tint with a delicate green, in giving roundness without sudden contrasts, and in lighting without the slightest glare. The portrait of the beautiful Johanna of

Aragon, wife of Ascanio Colonna, Constable of Naples (No. 1507; p. 122), which has also been much extolled, appears to have been chiefly executed by other hands. By desire of Cardinal Bibbiena, the papal legate in France, the picture was drawn at Naples by *Giulio Romano*, Raphael's pupil, and afterwards painted from memory in the master's studio. The fact of its having been painted without the living model accounts for the hardness of the outlines and the coldness of the colouring. The fresco of God the Father with angels (No. 1512; p. 121), removed from the Villa Magliana near Rome, is now universally attributed to Lo Spagna.

Correggio is fairly well represented in the Louvre by the Marriage of St. Catherine (No. 1117; p. 119) and Jupiter and Antiope (No. 1118; p. 116; formerly called Venus and a Satyr).

With specimens of *TITIAN*'s works in all his various styles the gallery is admirably provided. His Entombment (No. 1584; p. 116) is a work of the most touching pathos and most magic colouring. The Christ at Emmaus (No. 1581; p. 123), a favourite scene with the Venetian school, and one which gradually led to the delineation of great and ceremonious banquets, rather approaches the genre style, but is lifelike and pleasing. Very imposing as a study of character is the Christ crowned with thorns, between the executioners (No. 1583; p. 123). Among the pictures of the Virgin we may mention the Madonna with the rabbit (No. 1578; p. 123), painted in 1530 for the Duke of Mantua. To this beautiful idyll the Holy Family (No. 1580; p. 122) forms a companion picture of almost equal excellence. A work over which the master has shed a radiant poetic halo is the Sleeping Antiope approached by Jupiter in the form of a Satyr, while fauns are couching on the outskirts of the wood, a hunter quiets a dog, and in the background the signal of victory is being blown on the horn (No. 1587; p. 122). The picture was formerly known as the Venus del Pardo, from a palace at Madrid. In all these works the landscape in the background is worthy of examination. In order fully to appreciate Titian's merits as an artist the visitor must not overlook his portraits, painted either for the purpose of embodying his ideal of female beauty, or for that of displaying his skill in psychological delineation. To the former class belongs the picture known as Titian and his Mistress (No. 1590; p. 117), representing a girl arranging her hair in presence of her lover, who is holding the mirror. Most interesting as a study of character is the Portrait of Francis I. (No. 1588; p. 122), which is all the more remarkable as the king never sat to the master for it. An admirable portrait of Titian's middle period is the Young man in black, holding a glove in his left hand (No. 1591, p. 122; 'L'homme au gant'). Half portrait, half allegory, is the likeness of Alphonso Davalos, Marchese del Vasto, the famous general of Charles V. (No. 1589; p. 124). Equipped for departure, he stands beside his wife, a sister of Johanna of Aragon, who sits with a

crystal globe in her lap, mourning over his departure, while emblematic figures of Victory, Cupid, and Hymen appear to console her. — By these fine compositions the other Venetian works are almost entirely eclipsed. The most attractive of them is the Rustic Festival (No. 1136; p. 119), attributed to *Giorgione*. The banqueting scenes by *Paolo Veronese*, in a rich, but somewhat materialistic style, are too large to be easily overlooked (thus No. 1192; p. 119).

After having feasted his eyes with the ideal and richly-coloured pictures of the South, the visitor will at first be disposed to do but scant justice to the specimens of NORTHERN ART, with which the Louvre is also richly stocked. To the EARLY GERMAN SCHOOL, which is not very fully represented, belongs a table with four scenes from the life of David, painted by *Sebald Beham* for Archbishop Albert of Mayence (No. 2701; p. 129). The portraits of Erasmus of Rotterdam, Archbishop Warham of Canterbury, and Nicholas Kratzer, the astronomer, by the younger *Holbein* (Nos. 2715, 2714, 2713; pp. 118, 128) should also be noticed. — By far the most noteworthy work of the EARLY FLEMISH SCHOOL is *Jan van Eyck's* Madonna revered by the Chancellor Rollin (No. 1986; p. 118). To an important altar-piece by *Memling* belong the St. Magdalene and John the Baptist with rich landscape in the background (Nos. 2024, 2025; p. 118).

THE LATE FLEMISH, or BRABANT SCHOOL is magnificently represented by *Rubens*, by whose brush the gallery possesses 21 large scenes from the life of Marie de Médicis (Nos. 2085-2105; pp. 128, 129). However objectionable it may be from a strictly æsthetical point of view to combine portraits with allegory, the spectator will be unable to refrain from admiring these pictures for the freshness of their composition, richness of colouring, and the lifelike vigour of the numerous characters they contain, although their meaning is not always distinctly intelligible. As a painter of ecclesiastical works and of dignified mythological and historical scenes, Rubens may be studied elsewhere as well as in the Louvre, but his Flemish Fair (No. 2115; p. 130) in this collection exhibits him to us in an entirely new light. Of the broad humour and exuberant merriment which characterise his countrymen he was by no means destitute, and no painter has shown himself better acquainted with national customs except *Teniers* alone, who is rather to be regarded as a follower of Rubens in this sphere than the originator of the genre style. So successful, however, were the labours of Teniers, though Louis XIV. utterly despised him, that the fine collection of his works in the Louvre forms one of the chief boasts of the gallery.

THE DUTCH MASTERS of the 17th cent. can be thoroughly appreciated only on their native soil, but the Louvre gallery possesses good specimens of the handiwork of all the most celebrated. Among these are *Rembrandt's* Angel of Tobias, Holy Family at Nazareth, known as the 'Carpenter's Family', Christ at Emmaus, his own por-

trait with the gold chain (Nos. 2536, 2542, 2554, 2555), besides his Bathsheba, or woman bathing (No. 2549) added by the La Caze collection (p. 140). To that collection the Louvre is also indebted for the Laughing Girl (No. 2384; 'La Bohémienne') by *Frans Hals*. The latter is well calculated to exhibit the broad humour of the master, while his portrait of a woman, (No. 2385) presents him to us as a most brilliant colourist. The collection originally possessed only one canvas by Hals, the portrait of Descartes (No. 2383; p. 131), but has lately been enriched by three other portraits by him (Nos. 2386, 2387, 2388). *Van der Helst* is also well represented by his Distributors of Prizes (No. 2394; p. 127). — The most famous of the genre pictures are: *Terburg's* Officer and Girl (No. 2587), *Douw's* Woman selling spices, and particularly his Dropsical Woman (Nos. 2350, 2348), *Metsu's* Vegetable Market (No. 2458), *Jan Steen's* Tavern Festival (No. 2578), *Adrian van Ostade's* Schoolmaster (No. 2496), and an Interior by *P. de Hooch* (No. 2415). — Of the numerous excellent landscapes of the Dutch School it is unnecessary to make any special mention, as the visitor will have no difficulty in making a selection to suit his own taste.

The renown of the SPANISH pictures in the Louvre had its origin in a time when Spain was seldom visited by travellers, and when the treasures which Madrid and Seville possessed in the masterpieces of *Velazquez* and *Murillo* were known only in limited circles. Since that period the study of Spanish art has become both wider and more profound, and it is now admitted that it can be perfectly estimated in Spain alone. This is especially true with regard to *Velazquez*, of whose works the Louvre possesses only one eminently good example, the portrait of Philip IV. (No. 1732; p. 125). The most famous of *Murillo's* works in this collection is the 'Conception' (No. 1709; p. 117), while the 'Nativity of the Virgin' (No. 1710), and the 'Cuisine des Anges' (No. 1716; p. 124) are also admirable specimens of his power.

THE FRENCH SCHOOL is naturally more numerous represented in the Louvre than any other, though to obtain a complete idea of it the collections at Versailles and the Luxembourg and some provincial galleries must also be visited. Comp. Introduction, p. xxix.

We now proceed to enumerate the most important works in the order in which they are distributed throughout the various saloons. Our list is necessarily limited to the more interesting and celebrated pictures, to which the traveller who only pays a few short visits to the gallery should specially direct his attention; but it need hardly be said that there are many other works of high merit, which the discriminating visitor, with command of sufficient leisure, will easily discover for himself. The explanatory and critical remarks are from the pens of several of the most eminent historians of art. In each room, unless stated to the contrary, we begin to the right of the entrance.

The ****Salon Carré** or Room IV., like the Tribuna in the Uffizi at Florence, contains the gems of the collection. It is reached from the Pavillon Denon and by the Daru Staircase (p. 111), or from the Pavillon Sully and the Salle La Caze, through the Rotonde and the Galerie d'Apollon (p. 136).

*1564. *Perugino*, Madonna and Child with angels, St. Rose, and St. Catharine.

'An early work, remarkable for clearness of outline, pure and rich brilliancy of colour, and soft, pale yellow flesh tone.'

Crowe & Cavalcaselle.

*1198. *Paolo Veronese*, Jupiter hurling thunderbolts against criminals, once a ceiling-painting in the assembly-hall of the Council of Ten in the Doges' Palace at Venice. — 1515. *Andrea del Sarto*, Holy Family.

****1584. Titian**, Entombment of Christ, painted for the Duke of Mantua about 1523.

'It would be true to say that none of the persons perform all that they seem to promise, and that there is more of symbolism than of absolute reality in the action of every one of them; and yet the impression produced by the picture as a whole is probably much greater than that which we receive on looking at the Borghese altar-piece; and this arises no doubt from a surprising variety in type and expression, a subtle display of light surfaces upon a ground studded with diverse shades of gloom, and a richness of colouring which throws over the whole canvas a mysterious weirdness.'

Crowe & Cavalcaselle, Titian.

*1706. *Herrera*, St. Basil expounding his doctrines.

*2542. *Rembrandt*, Holy Family at Nazareth, known as the 'Carpenter's Family', signed 1640.

This family scene is one of those idyllic pieces by means of which Rembrandt and other Dutch masters endeavoured to familiarise the spectator with incidents from the Old and New Testament by transplanting them to the present. The simplicity and depth of sentiment which pervade the picture may be regarded as the badge of the Protestant spirit of the 16th and 17th centuries, which viewed the Bible as a standard of life in a very different sense from the mediæval church.

*1118. *Correggio*, Antiope and Jupiter disguised as a satyr, executed about 1518, for the Duchess of Mantua; the atmosphere is full of magical charm, and the conception is naïve and unaffected.

— *2946. *Adrian van Ostade*, The Schoolmaster, dated 1662, the dramatic force and warm golden tone of which are characteristic of the master's most finished style. — 2709. *Dürer*, Head of an old man (tempera, under glass). — 325. *Guido Reni*, Dejanira carried off by the Centaur Nessus. — *1509. *Raphael*, Apollo and Marsyas, purchased in 1883 for 200,000 fr.; its authenticity is vouched for by a drawing by Raphael in the Academy at Venice.

1048. *Jean Perreéal* or *J. de Paris*, Madonna and donors. — 723. *Nic. Poussin*, St. Francis Xavier resuscitating a dead woman in Japan, painted in 1641.

*2547. *Rembrandt*, Portrait, painted, according to Vosmaer, in 1654. — 1179. *Paris Bordone*, Portrait.

*2587. *Ger. Terburg*, A handsome officer sitting in a room with

an elegantly-dressed girl, to whom he offers money: the heads full of life, admirably drawn, and of a delicately-blended silvery tone; one of his finest works. — *2459. *Gabriel Metsu*, Officer saluting a young lady, a gracefully-conceived and delicately-coloured work.

1352. *Sebastian del Piombo*, The Salutation, signed Rome, 1521 a most impressive picture.

*2348. *Gerard Dou*, The dropsical woman, his greatest work: a successful composition, in which the grief of the daughter is touchingly portrayed; most elaborately finished, although unusually large for this master. — 1184. *Bronzino*, Portrait of a sculptor.

**1709. *Murillo*, The Immaculate Conception, one of his greatest works (1678), pervaded with an intense sentiment of religious enthusiasm. As usual in the Spanish School, the master has drawn his inspiration from the 'woman clothed with the sun, and the moon under her feet, and upon her head a crown of twelve stars' (Rev. xii. 1). The picture was bought from Marshal Soult for 615,000 fr.

*1590. *Titian*, 'La Maîtresse du Titien', a girl at a toilet-table, with a man behind her with two mirrors, perhaps Laura Dianti and Duke Alphonso of Ferrara, painted shortly after 1520.

'The light is concentrated with unusual force upon the face and bust of the girl, whilst the form and features of the man are lost in darkness. We pass with surprising rapidity from the most delicate silvery gradations of sunlit flesh and drapery, to the mysterious depth of an almost unfathomable gloom, and we stand before a modelled balance of light and shade that recalls Da Vinci, entranced by a chord of tonic harmony as sweet and as thrilling as was ever struck by any artist of the Venetian school.'

C. & C.

*2555. *Rembrandt*, Portrait of the artist at an advanced age (1660). — *1644. *Italian School of the 16th cent.* (? *Franciabigio*), Portrait of a young man.

*1497. *Raphael*, Madonna with the veil, also called the Virgin with the diadem (p. 112).

*1321. *Dom. Ghirlandajo*, The Visitation, dated 1491.

**1601. *Leonardo da Vinci*, Portrait of Mona (Madonna) Lisa, wife of the painter's friend Fr. del Giocondo of Florence, known as 'La Gioconda'.

'The eyes', says *Vasari* (d. 1574), the painter and biographer of artists, 'have the moist radiance which we observe in living persons; the mouth, the lips, the redness of which blends at the corners with the rose tint of the cheeks — this is not colour, but actual living flesh'. These excellences are now concealed by the darkened shades, but the face still delights us with the wonderful charm of its smile.

1977. *Van Dyck*, Portrait. — *1193. *Paolo Veronese*, Christ in the house of Simon the Pharisee, painted in 1570-75.

1967. *Ant. van Dyck*, Portrait of Charles I. of England, a work of the most pleasing delicacy of execution and fidelity to nature. — 1219. *Annibale Carracci*, The Madonna appearing to St. Luke and St. Catharine. — *1530. *Andrea Solario*, 'Madonna with the green cushion', rich and radiant in colouring, with a beautiful

landscape. — 1355. *Luini*, Salome with the head of John the Baptist, painted under the influence of Leonardo da Vinci.

*1503. *Raphael*, St. George and the dragon, painted in 1506.

**1498. *Raphael*, 'Great Holy Family of Francis I.', Rome, 1518.

'This picture is one of the richest and most dramatic compositions of Raphael. In care and uniformity of execution, in fulness and grandeur of the nude, in breadth and delicacy of the drapery, in lightness and freedom of the motions, and in powerful effects of colour, this work approaches most nearly to the Transfiguration in the Vatican'. — *Waagen*.

1502. *Raphael*, St. Michael (1504; a youthful work). — 1499. *Raphael* (?), Holy Family, school-piece; the original, according to F. Notté, is at the château of Isle-Adam (p. 344). — 1221. *Carracci*, Virgin with Dead Christ. — *741. *Poussin*, Diogenes throwing away his bowl. — 1731. *Velasquez*, Infanta Mary Margaret, daughter of Philip IV. — *Claude Lorrain*, 319. Sea-piece, 320. Landscape.

**1496. *Raphael*, Madonna and Child with St. John, usually called 'La Belle Jardinière'; Florence, 1507.

'With the Madonna and Infant Christ, who are represented alone in the simpler and earlier representations of the Madonna, is associated the young St. John. This addition has not only given rise to more varied gestures of infant life, but has enabled the master to form a more regular group. Standing or kneeling at the Madonna's feet are the two children, forming a broad pedestal for the composition, which is easily and naturally completed by the Madonna. This idea was first expressed by sculptors, and afterwards eagerly adopted by Florentine painters, including Raphael, who within two years painted the 'Madonna in the Garden' three times, one of the replicas being now at Vienna'. (*Springer*: '*Raphael & Michael Angelo*'). — The original drawings for this work have lately been bequeathed to the Louvre.

1932. *Phil. de Champaigne*, Pieta, resembling Holbein's Pieta at Bale. *1986. *Jan van Eyck*, The Chancellor Rollin revering the Virgin, with a beautifully-executed landscape.

The strong and the weak points of Van Eyck's art are combined in this picture. The figure of the chancellor is admirably faithful to life, contrasting strongly with the commonplace Madonna and the wooden form of the Child.

437. *Jouvenet*, Descent from the Cross.

783. *Rigaud*, Portrait of Bossuet, the celebrated preacher. —

2013. *Jordaens*, Infancy of Jupiter.

2024, 2025. *Memling*, Mary Magdalene with the box of ointment, and John the Baptist, two delicately-finished panels (school-pieces according to Mr. Weale). — *2715. *Holbein the Younger*, Erasmus of Rotterdam, exceedingly lifelike and admirably executed.

*1598. *Leonardo da Vinci*, Madonna and Infant Christ with St. Anne; one of the gems of the gallery, with beautiful heads and most expressive features, but somewhat careless in the details. (There are several sketches for this picture at Windsor.)

*1134. *Antonello da Messina*, Portrait of a man, known as the Condottiere, 1475. — 1143. *Guercino*, Patron saints of Modena. — 722. *Nic. Poussin*, Vision of St. Paul. — 562. *Lesueur*, St.

Scholastica appearing to St. Benedict. — 2084. *Rubens*, Tomyris, Queen of the Scythians, causes the head of Cyrus to be dipped in a vessel full of blood.

**1192. *Paolo Veronese*, Marriage at Cana, finished in 1563, the largest picture in the collection, 32 ft. long and 21 ft. high, occupying nearly the whole S. wall, a perfect 'symphony in colours'.

Among the figures are numerous portraits. The bride is Eleanor of Austria, the young Queen of France; behind her the court-jester; at her side Francis I., with a curious head-dress; then Mary of England in a yellow robe, Sultan Soliman near a negro prince; at the corner of the table the Emperor Charles V., with the Golden Fleece. The musicians are portraits of Venetian painters of the day. *Paolo Veronese* himself, in white, plays on the viol, behind him *Tintoretto* with a similar instrument, on the other side *Titian* with a bass-viol, and the elder *Bassano* with a flute.

**1117. *Correggio*, Betrothal of St. Catharine, 'with a celestial expression in the faces', says *Vasari*. — *1136. *Giorgione*, Rustic festival: very charming from the depth and warmth of the colouring, the golden glow of the flesh tones, and the rich treatment of the landscape, in spite of its having been freely retouched.

*1713. *Murillo*, Holy Family; the light and harmonious colouring are of great beauty. — 1464. *Tintoretto*, Susanna at the bath. — *2195. *Rogier van der Weyden*, Virgin and Child. — *1383. *Simone di Martino* (?), Christ bearing the Cross.

*1504. *Raphael*, St. Michael the conqueror of Satan, painted in 1518 for Francis I. of France, a work of sublime poetical character and strikingly sudden in its action, painted partly by *Giulio Romano* and other pupils (comp. p. 112). — 1139. *Guercino*, Raising of Lazarus. — 2028. *Memling*, Madonna with saints. — 1435. *Francesco Francia*, Nativity, a beautiful and lovingly-executed miniature. — 129. *Clouet*, Elizabeth of Austria, wife of Charles IX. — *2718. *Holbein the Younger*, Anne of Cleves, fourth wife of Henry VIII. of England, a work of the master's later period. — 1938. *Ph. de Champaigne*, Portrait of Richelieu. — 1538. *Lionello Spada*, Concert.

The **Salle Duchâtel** or Room V., nearly opposite the Marriage at Cana, connecting the Salon Carré with the Escalier Daru (pp. 96, 111), contains several frescoes, transferred to canvas, of the Milanese School, which reflected the influence of *Leonardo da Vinci*. — 1359, *1360, *1361. *Bern. Luini*, Nativity, Adoration of the Shepherds, and Christ pronouncing a blessing, from Milan. — 1357, 1358. *Bern. Luini*, Two boys with vine-foliage, from the Villa Pallucca near Monza.

This room also contains the following works: to the left, *2026. *Memling*, Madonna and Child, with SS. James and Dominic, and the donors, a work of solemn dignity and appropriate colouring; to the right, 2480, 2481. *Ant. Moro*, Portraits, probably Louis del Rio, an official of Brabant, and his wife. Then, *422. *Ingres*, The

Spring, painted in 1856 and perhaps the most perfect specimen of the treatment of the nude among modern paintings; 421. *Ingres*, Œdipus solving the riddle of the Sphinx, with a view of Thebes in the background, painted in 1808, when the master was still swayed by his admiration of the plastic features of antique art.

We may now leave the Salon Carré by the door at the end opposite the Galerie d'Apollon, and enter the Grande Galerie (p. 121); but in order to obtain a better chronological survey of the Italian School, it is advisable first to visit the so-called Galerie des Sept Mètres, the first saloon on the right.

The *Galerie des Sept Mètres* (or *des Primitifs*) or Room VII contains an admirable collection of pictures of the earlier Italian School, particularly by Tuscan masters of the 15th century. The series begins at the farther end of the room.

On the right: 1372. *Manni*, Holy Family. — 1668. *Bolognese School*, Judgment of Paris. — 1174. *Bononi*, Madonna and Child. — *1375. *Andrea Mantegna*, Mount Parnassus. — 1284. *Lor. di Pavia*, Family of the Virgin. — *1263. *Lorenzo di Credi*, Madonna and saints. — *1376. *A. Mantegna*, The vices banished by wisdom, companion to No. 1375. — 1169. *Giov. Ant. Boltraffio*, The Madonna of the Casio family, with the poet of that name on the right: the painter's masterpiece according to Vasari. — 1211. *Vitt. Carpaccio*, Preaching of St. Stephen, painted about 1515, unfortunately injured. — 1374. *Mantegna*, Madonna della Vittoria, one of his last works, painted about 1495 for Giov. Franc. di Gonzaga, Duke of Mantua. — *1158. *Giov. Bellini* (?), Madonna and saints. — *1373. *Mantegna*, Crucifixion of Christ, from the predella of the altar-piece of S. Zeno at Verona, a grand composition; the holy women full of dramatic life. — *1565. *Perugino*, Holy Family. — 1175, 1176. *Moretto*, Four saints. — 1182. *Borgognone*, St. Peter of Padua and a kneeling woman. — *1344. *Fra Filippo Lippi*, Madonna with angels and saints; an early work of the master's. — 1400. *Palmezzano*, Pietà. — 1527. *Luca Signorelli*, Seven male figures. — *1436. *Franc. Francia*, Christ on the Cross, with Mary, John, and (at the foot of the Cross) Job. — 1264. *Lor. di Credi*, Christ and Mary Magdalene. — 1417. *Pinturicchio*, Madonna. — *1312. *Giotto*, St. Francis of Assisi receiving the stigmata; below, Vision of Innocent III., the same pope confirming the statutes of the order of St. Francis, and St. Francis preaching to the birds: a genuine, signed picture, painted for the Pisans.

[The door at the back of this hall leads to a landing of the Daru Staircase (comp. p. 96), on which there are two frescoes by *Botticelli* and one by *Fra Angelico*. French school, see pp. 131-137.]

To the left, beginning from the posterior wall: 1260. *Cimabue*, Virgin and angels, a strange composition resembling a Russian icon. — *1319. *Benozzo Gozzoli*, Triumph of St. Thomas Aquinas.

Above is Christ, with Paul, Moses, and the Evangelists. In the centre of the glory is the celebrated theologian between Aristotle and Plato; at

his feet, overwhelmed by his eloquence, is Guillaume de St. Amour, a professor of the Sorbonne; below, an ecclesiastical assembly with Pope Alexander IV.

1279. *Gentile da Fabriano*, Madonna with the Holy Child, in the act of blessing Pandolfo Malatesta, Lord of Rimini. — *1343. *Fra Filippo Lippi*, Nativity; the Virgin is said to be a portrait of Lucrezia Buti. — 1394. *B. Montagna*, Angelic musicians. — 1367. *Mainardi*, Madonna, Child, and angel with lilies. — 1322. *D. Ghirlandajo*, Portraits of a man and boy. — *1290. *Fra Angelico da Fiesole*, Coronation of Mary, with accessories, extolled by Vasari, the faces of the saints full of holy aspiration. — 1296. *Botticelli* (school-piece), Madonna with the Child and John the Baptist. — 1481. *Borgognone*, Presentation in the Temple. — 1488. *Sacchi*, The Four Doctors of the church. — *1532. *A. Solario*, Crucifixion of Christ, dated 1503, full of expression and very skilfully composed. — 1382. *Marco d'Oggionno*, Holy Family. — 1416. *Piero di Cosimo*, Coronation of the Virgin. — 1539. *Lo Spagna*, Nativity of Christ. — *1261. *Lor. Costa*, Court of the Muses held by Isabella d'Este, Duchess of Mantua, an attractive allegory. — *1259. *Cima da Conegliano*, Madonna and Child, with St. John and Mary Magdalene, richly coloured. — *1567. *Perugino*, Conflict between Cupid and Chastity; the visitor should compare this work with the similar scenes by Lorenzo Costa (No. 1261) and Mantegna (opposite). — 1323. *Ghirlandajo*, Christ bearing the Cross. — 1526. *Signorelli*, Adoration of the Magi. — 1167. *Fr. Bianchi*, Madonna enthroned, between SS. Benedict and Quentin. — Above the door: 1512. *Lo Spagna* (not Raphael), God the Father and two angels, frescoes removed from the Villa Magliana near Rome, purchased in 1873 for the extravagant price of 206,500 fr. (8260*l.*).

The ***Grande Galerie**, or Room VI. is divided into six bays, marked A, B, C, D, E, F. — It contains nearly all the remaining pictures of the Italian, Spanish, German, and Netherlandish Schools (p. 146).

BAY A. HIGH RENAISSANCE ITALIAN MASTERS.

On the right: *1114. *Albertinelli*, Madonna and Child with SS. Jerome and Zenobius, dated 1507, a fine work. — *Garofalo*, 1153. The Child Jesus sleeping, 1154. Madonna and Child, a reduced replica of a picture at Dresden. — 1115. *Albertinelli*, Christ appearing to Mary Magdalene. — *1420. *Giulio Romano*, Triumph of Titus and Vespasian, composed in the style of the ancient reliefs on the Arch of Titus at Rome. — *1353. *Luini*, Holy Family. — 1513. *After Raphael*, Madonna of Loreto (original lost). — 1603. *Marco d'Oggionno*, Copy of Leon. da Vinci's Last Supper (the Milan fresco). — *1350. *Lor. Lotto*, St. Jerome in the desert, dated 1500; the landscape breathes the poetry of solitude, of which the saint is the living counterpart. — 1551. *Garofalo*, Holy Family. — *1514. *Andrea del Sarto*, Caritas, signed 1518, somewhat recalling

Michael Angelo's style of composition, injured in the colouring. — *1399. *Palma Vecchio*, Adoration of the Shepherds: the figures resembling portraits, exuberantly natural (C.). — *1465. *Tintoretto*, Paradise. — 1602. *Leonardo da Vinci* (school-piece?), Bacchus, originally composed as John the Baptist in the desert. — *1580. *Titian*, Holy Family. — 1354. *Luini*, The Child Jesus sleeping. — *1507. *Raphael* and *Giulio Romano*, Portrait of Johanna of Aragon, painted in 1518, the head only, according to Vasari, having been painted by Raphael (comp. p. 112). — *P. Veronese*, 1190. Holy Family, *1197. St. Mark and the three cardinal Virtues (Faith, Hope, and Charity), a ceiling-painting from the palace of the doges at Venice. — 1597. *Leonardo da Vinci*, John the Baptist, with an enthusiastic, ecstatic expression of countenance (retouched). — *1501. *Raphael*, St. Margaret, painted, according to Vasari, almost entirely by *Giulio Romano*.

1199. *Paolo Veronese*, Portrait of a young mother. — *1588. *Titian*, Portrait of Francis I. of France, painted about the year 1530 from a medal, and yet reproducing the characteristically quaint features and royal bearing of that monarch. — *1170. *Bonifazio* (Venetian School), Raising of Lazarus. — 1500. *Raphael*, John the Baptist in the wilderness, probably genuine, but completely ruined. — 1575. *Giorgio Vasari*, Annunciation. — *Paolo Veronese*, 1195. Golgotha; 1187. Lot's daughters fleeing from Sodom; 1188. Susanna in the bath. — *1577. *Titian*, Madonna and Child, with saints. — 1438. *Bagnacavallo*, Circumcision of Christ. — 1149. *Barocci*, Circumcision of Christ, 1580.

Left wall, beginning again from the entrance: —

*1171. *Bonifazio the Elder*, Holy Family and saints. — *1508. *Raphael*, Two male portraits, described as Raphael and his fencing-master. — *1604. *School of Leon. da Vinci*, perhaps *Cesare da Sesto*, Madonna with the scales. — 1285. *Gaudenzio Ferrari*, St. Paul, dated 1543.

*1592. *Titian*, Young man in black with gloves or 'L'homme au gant', an admirable portrait of his middle period. Comp. p. 113. — 1135. *Giorgione*, Holy Family.

*1591. *Titian*, Portrait of a man in black, resembling No. 1592, and painted at the same period.

**1587. *Titian*, Jupiter and Antiope, known as the 'Venus del Pardo', painted in 1574. Comp. p. 113.

'Though injured by fire, travels, cleaning, and restoring, the masterpiece still exhibits Titian in possession of all the energy of his youth, and leads us back involuntarily to the days when he composed the Bacchanals. The same beauties of arrangement, form, light, and shade, and some of the earlier charms of colour are here united to a new scale of effectiveness due to experience and a magic readiness of hand. . . . The shape of Antiope is modelled with a purity of colour and softness of rounding hardly surpassed in the Parian marble of the ancients.'

C. & C.

*1154. *Fra Bartolommeo*, Madonna enthroned, with saints (1511).

'Christ gives the ring to the kneeling Catherine of Siena. This charming idea, rendered with Leonardesque elegance, conveys a sense of great affection and veneration towards Christ on the part of his mother, expressed chiefly by movements emulating those of the *Bella Giardiniera* in softness.'

C. & C.

*1351. *Lor. Lotto*, Holy Family. — **1581. *Titian*, Christ and the two disciples at the Supper of Emmaus, painted about 1547.

'A genre picture in monumental setting, a mixture of the commonplace and the sublime, forming a kind of precursor to that naive and piquant mode of rendering the sacred narrative which was afterwards rendered almost classical by Paolo Veronese.'

C. & C.

*1418. *Giulio Romano*, Nativity of Christ, painted as an altarpiece for S. Andrea at Mantua.

*1599. *Leonardo da Vinci*, Holy Family, known as 'La Vierge aux Rochers', a work of the highest merit; the light on the flesh-tints is still brilliant, but the shadows have become very dark. — 1172. *Bonifazio*, Madonna, St. Agnes, and St. Catharine; *1196. *Paolo Veronese*, Christ and the disciples at Emmaus; the subsidiary figures the most attractive. — 1579. *Titian*, Holy Family, perhaps executed in part by a pupil.

**1583. *Titian*, Christ crowned with thorns, painted about 1560.

'The pictures of this period show various allusions to antiquity. Titian seems to have been specially interested in the Laocoon. The impression produced on him by that work is most worthily utilised in the chief figure in his 'Crowning with thorns', although the master's efforts to attain fidelity to nature have led him into exaggerations foreign to antiquity. — Strangely enough, though warm and golden in general tone, the picture has less variety and more uniformity of colour than usual.'

C. & C.

*1505. *Raphael*, Portrait of Count Castiglione, a poem regarding which still exists, painted about 1516, with masterly management of the different shades of colour. Comp. p. 112.

*1153. *Fra Bartolommeo*, Annunciation, with six saints, dated 1515. — *1506. *Raphael*, Portrait of a young man, painted after 1515. — 1194. *Paolo Veronese*, The route to Golgotha, unfinished.

*1578. *Titian*, 'La Madonna del Coniglio', or the Virgin with the rabbit, painted in 1530.

'A masterpiece in which Titian substitutes for the wilds of Bethlehem the lovely scenery of the Isonzo and Tagliamento. He represents the Virgin seated on the grass with her hand on a white rabbit, and St. Catherine by her side stooping with the infant Christ: a charming group in the corner of a landscape, — a group on which all the light of the picture is concentrated, whilst the broad expanse behind with the wooded farmstead in its right, the distant village, the chain of hills, and the far-off mountains lost in blue haze, lies dormant under the shade of a summer cloud. St. Catherine and the Virgin are both portraits.' — C. & C.

*1600. *Leonardo da Vinci* (?), Female portrait.

'It was formerly, without any authority, called *La Belle Féronnière* (a mistress of Francis I.), but is probably the portrait of *Lucrezia Crivelli*, the mistress of Ludovico Sforza, and must therefore have been painted at Milan. The figure is remarkable for its graceful and noble bearing, and attractive owing to the gentle tinge of melancholy which pervades the features.'

Kugler.

1189. *Paolo Veronese*, Esther before the wrathful Ahasuerus, very lifelike and dramatic.

*1589. *Titian*, Allegory, painted for Alphonso Davalos, Marchese del Vasto, representing that general taking leave of his wife when summoned by the emperor to Vienna in 1532 to fight against the Turks (see also p. 113).

'As an allegorical creation and as a work of a potent master of colour, Titian's canvas is one of the most entrancing that was ever created. There is such perfect sweetness of tone, such a rich strain of harmony in tints, such a solemn technical mastery — that we can do no more than look on and wonder.' C. & C.

1593. *Titian* (?), Portrait. — 1185. *John of Calcar*, Portrait, dated 1540. — 1150. *Barocci*, Coronation of the Virgin, with SS. Lucia and Anthony.

In the middle, 1462. *Dan. da Volterra*, David beheading Goliath, forced and exaggerated (painted on both sides).

BAY B. ITALIAN ACADEMIC SCHOOL OF BOLOGNA (Eclectics) AND NATURALISTIC SCHOOL OF NAPLES. — SPANISH SCHOOL.

On the right: 1164. *Pietro da Cortona*, Madonna and Child, with St. Martina. — 1228. *Annibale Carracci*, St. Sebastian. — 1441. *Guido Reni*, Purification of the Virgin. — 1124. *Caravaggio*, Alof de Vignacourt, grand-master of the Maltese Order. — 1111. *Albani*, Diana and Actæon. — 1450. *Guido Reni*, St. Sebastian. — 1257. *Cesari*, Diana and Actæon. — 1449. *Guido Reni*, Mary Magdalene. — 1555. *Trevisani*, Child Jesus sleeping. — 1490. *Sassoferrato*, Assumption of Mary. — 1163. *Pietro da Cortona*, Virgin and Child. — 1456. *Guido Reni*, Rape of Helen, theatrical. — *Albani*, 1110. Venus and Adonis, 1109. Cupids disarmed. — 1408. *Panini*, St. Peter's at Rome. — 1392. *P. Mola*, Vision of St. Bruno. — 1287. *Feti*, Open-air life. — 1495. *Sassoferrato*, Annunciation. — 1235. *L. Carracci*, The Deluge.

1739. *Zurbaran*, Funeral of a bishop. — *1716. *Murillo*, Miracle of St. Diego, known as the 'Cuisine des Anges', representing a poor monastery in Spain being provided with food by angels. — *1738. *Zurbaran*, Conference of St. Peter of Nola and St. Raymond of Pennafort. — 1329, 1328. *Guardi*, Church of La Salute at Venice, with the doge embarking on the Bucintoro. — *Marillo*, 1714, 1715. Christ in Gethsemane, and Christ scourged, painted on marble; *1708. Immaculate Conception of the Virgin. — 1721. *Spagnoletto*, Adoration of the Shepherds.

The adjoining room contains the pictures of the French school described at p. 135. Beyond it is the Salle du Pavillon Denon, between the two French Galleries mentioned at pp. 131 and 133.

Left wall, beginning from the entrance: 1133. *Anselmi*, Madonna, with St. Stephen and John the Baptist. — *1217. *Ann. Carracci*, Mary and the Child, to whom St. Joseph is giving cherries, or 'La Vierge aux Cerises'. — 1210. *Cigoli*, St. Francis of Assisi. — *1445. *G. Reni*, Peter receiving the keys of heaven. 1617. *Domenichino*, Rinaldo and Armida, from Tasso. — 2382. *P. da Cortona*, Nativity of the Virgin. — 1379. *Maratta*, Portrait

of Marie Madeleine Rospigliosi. — 1121. *Caravaggio*, Death of Mary, painted for a church in Rome, which declined to receive it. — 1390. *Mola*, John the Baptist preaching. — 1166. *P. Cortona*, Meeting of Dido and Æneas. — *G. Reni*, 1447. *Ecce Homo*; 1448. The Magdalen. — 1489. *Sassoferrato*, Infant Jesus asleep. — *1203. *Canaletto*, The Grand Canal with the church of S. Maria della Salute at Venice. — *1479. *Salv. Rosa*, Cavalry battle. — *1613. *Domenichino*, St. Cecilia. — 1288. *Dom. Feti*, Melancholy. 1480. *Salv. Rosa*, Landscape in the Abruzzi, with soldiers. — 1239. *Lod. Carracci*, The Virgin appearing to St. Hyacinthe.

*1732. *Velazquez*, Philip IV. of Spain, in a simple but majestic style. — **1710. *Murillo*, Nativity of the Virgin, with exquisitely-blended colours. — 1734. *Velazquez*, Thirteen portrait-figures. — *1723. *Spagnoletto*, St. Paul the hermit. — *1717. *Murillo*, Beggar-boy 'cherchant à détruire ce qui l'incommode': the intent expression is full of life and the light admirable. — 1334. *Guardi*, Coronation of the doge of Venice. — *1737. *Velazquez*, Portrait of an ecclesiastic of Toledo (1633). — 1722. *Spagnoletto*, Entombment. — 1712. *Murillo*, Madonna with the rosary, of his earlier period. — 1333. *Guardi*, Sala del Collegio, in the doges' palace at Venice. — 1704. *Goya*, Guillemardet, ambassador of the French Republic at Madrid, 1798.

BAY C. EARLY FRENCH SCHOOL.

On the right: Portraits, by *Clouet* and his school, etc. — 1013. *School of Fontainebleau* (15th cent.), Diana. — 155. *Jean Cousin*, Last Judgment (one of the only two pictures of this artist). — 304. *Fréminet*, Mercury bidding Æneas abandon Dido. — 1035. *Unknown artist of the 16th cent.*, Ball at the court of Henri III. — 1014. *School of Fontainebleau* (16th cent.), Moderation of Scipio.

On the left: 126. *Clouet* (?), Francis I. — 1007. *French School of the 16th cent.*, Francis I. — 998. *French School of the 15th cent.*, Descent from the Cross. — 995. *French School of the 14-15th cent.*, Last communion and death of St. Denis. — *J. Fouquet*, *288. Guillaume Juvénal des Ursins, *289. Charles VII. — Several other interesting portraits of the old French school.

BAY D. GERMAN AND NETHERLANDISH SCHOOLS.

On the right: *2202, *2198. *Flemish School of the 15th cent.*, Annunciation, Pastoral Instruction. — *Mabuse*, 1998. Virgin and Child; 1997. Carondelet, chancellor of the Netherlands. — *Flemish School of the 15th cent.*, 2200. Christ, 2201 Mater dolorosa. — 2738. *Flemish School of the 16th cent.*, Last Supper, Preparation for the Entombment, and St. Francis receiving the 'stigmata'. — *2029. *Q. Matsys*, Banker and his wife, of very delicate workmanship; replicas, with slight variations, are to be seen at Valenciennes, Nantes, etc. — *2739. *German School of the 16th cent.*,

Adoration of the Magi. — *2716. *Holbein the Younger*, Portrait of a man. — *2196. *Rogier van der Weyden*, Descent from the Cross. — 2717. *Holbein*, Portrait of Sir Thomas More, the English chancellor, a small and spirited picture, probably painted soon after the painter's arrival in England (1526). — 2703. *Lucas Cranach*, Venus, dated 1529. — 2433. *Karel Dujardin*, Landscape. — *2346. *Alb. Cuyp*, Thunder-storm at sea. — 2106. *Rubens*, Portrait of the Grand Duke Francis of Tuscany, father of Marie de Médicis. Opposite: 2107. *Rubens*, Johanna of Austria, wife of the preceding, at the beginning of the series by Rubens, mentioned below. — *1975. *Ant. van Dyck*, Portrait of the Duke of Richmond. — *2378. *Jan van Goyen*, River-scene, dated 1647. — 2340. *Craesbeke*, The artist painting a portrait; his best work. — 2144. *Frans Snyders*, Wild-boar hunt. — 1993. *Jan Fyt*, Dead game. — 2304. *Ludolf Bakhuizen*, Dutch ships of war. — 2164. *David Teniers the Elder*, Heron-hawking, with Archduke Leopold on horseback on the right (erroneously ascribed to the younger Teniers). — 2465. *Mierevelt*, Portrait. — 2022. *Jan van der Meer of Haarlem*, Scene at a tavern-door, dated 1652. — 2483. *A. van der Neer*, Canal at sunset. — 2369. *Lely* (?), Portrait. — 2011. *Jac. Jordaens*, Christ driving the money-changers out of the Temple, somewhat trivial in composition, but masterly in its realistic vigour. — 2305. *L. Backhuysen*, Harbour of Amsterdam. — 2072. *F. Pourbus the Younger*, Marie de Médicis. [The adjoining door leads to the French galleries, see p. 131.] — 2160. *Teniers the Younger*, Tavern by a brook.

*2108. *Rubens*, Marie de Médicis. — The large pictures by Rubens higher up will be noticed afterwards in a single group.

2039. *Van der Meulen*, Louis XIV. and his troops crossing the Rhine at Emmerich. — 2500. *Adr. van Ostade*, The smoker. — *2568. *Pieter Stingelandt*, The family, one of the finest works of the master, who is said to have worked at the collars and cuffs of the boy for a whole month. — 2361. *Jan le Ducq*, The marauders.

*1968. *A. van Dyck*, Children of Charles I. of England. — *2360. *Jan le Ducq*, Interior of a guard-house, his principal work. — 2320. *Nicolas Berchem*, Landscape with cattle. — 2137. *Ryckaert*, Interior of a studio. — 2561. *Jac. van Ruysdael*, Landscape. — 2706. *Denner*, Portrait of an old woman; of rare delicacy of workmanship. — 2509. *Isaac van Ostade*, Vehicle in a village-street. — 2033. *Van der Meulen*, Louis XIV. entering Douai, 1667. — *2389. *D. Hals*, Open-air festival. — *Teniers*, 2166. Miller, 2165. Smoker. — *2356. *Ger. Dou*, Reading the Bible, a very attractive, peaceful, domestic scene. — *2430, *2429. *Dujardin*, Cattle pasturing, Landscape with cattle. — 2351. *Dou*, Trumpeter.

Farther on, to the left, and turning in the opposite direction: — 2414. *Pieter de Hooch*, Court-yard and porch by sunset. — *2596. *Adr. van de Velde*, Cattle on the bank of a canal, by evening-light. — *2330. *Ferd. Bol*, Portrait of a mathematician. — *2391.

Jan Dav. de Heem, Fruit and pottery. — *2589. *G. Terburg*, The concert, a little piece of delicate workmanship. — *2484. *Aart van der Neer*, Village scene by moonrise. — 2471. *Fr. van Mieris*, Tea. — 2482. *Moucheron*, Starting for the hunt. — *2116. *Rubens*, Tournament in front of a fortress by sunset, a spirited sketch. — 1972. *Van Dyck*, Portrait of François de Moncade. — *1912. *A. Brouwer*, Interior of a tavern. — *2158. *Teniers the Younger*, Temptation of St. Anthony. — 2158. *Dekker*, Landscape. — *Teniers the Younger*, *2155, Peter's Denial; among the soldiers at the table is the artist himself; *2346. The works of mercy. — 2074. *Pourbus the Younger*, Guillaume de Vair, Keeper of the Seals of France. — *2403. *Hobbema*, Forest-landscape.

*2536. *Rembrandt*, Family of Tobias revering the departing angel, painted in 1637; very characteristic of the master's easy and genial mode of rendering Bible scenes, and admirable for its warm and harmonious colouring and its poetry of chiaroscuro. — *2058. *Isaac van Ostade*, Vehicle in a village-street. — 2047, 2048. *Van der Meulen*, Battles, resembling miniatures in delicacy of detail. — *2559. *Jac. van Ruysdael*, Autumnal landscape. — *J. van Huysum*, 2422. Flowers and fruit; 2421 (after 2601), Basket of flowers. — 2061. *Adr. van der Venne*, 'Fête champêtre', with allegorical allusions to the peace in 1609 between Archduke Albert and the Dutch.

*2373. *Govaert Flinck*, Portrait of a girl. — 2623. *Phil. Wouverman*, Starting for the hunt. — *2501. *Adr. van Ostade*, A drinker. — *2545. *Rembrandt*, Portrait of a young man, dated 1658. — 2600. *Will. van de Velde*, Harbour. — *2350. *Ger. Dou*, Woman selling spices behind a counter. — *2394. *Bart. van der Helst*, Four directors of a guild of archers awarding the prize to the victor. — *2352. *Ger. Dou*, Cook. — *2593. *Adr. van de Velde*, Prince of Orange on the beach at Scheveningen. — 2353. *Ger. Dou*, Girl with a cock at a window. — 2625. *Phil. Wouverman*, Stag-hunt. — *2415. *Pieter de Hooch*, Two ladies and cavaliers in a room, with admirable rendering of sunshine. — 2315. *Nic. Berchem*, Cattle wading through a ford, of the master's happiest period. — 2359. *Ger. Dou*, Portrait of himself. — *2355. *Ger. Dou*, The dentist.

*2114. *Rubens*, Portrait of a lady of the Boonen family. — 2070, 2071 (beyond 2495), *Fr. Pourbus the Younger*, Two portraits of Henri IV. of France. — *2495. *Adr. or Isaac van Ostade*, Domestic scene, supposed to be the two Ostades and their families. — *J. van Huysum*, 2424. Vase of flowers; 2423 (beyond 2075), Flowers and fruit. — *2075. *Rubens*, Lot's flight, dated 1625. — *Teniers the Younger*, 2162. Tavern with card-players; 2156 (beyond 2539), The Prodigal Son. — *2539. *Rembrandt*, The Supper at Emmaus, dated 1648, from the collection of his friend the Burgomaster Six. As in the picture of Tobias, a subdued red is here the predominating colour, and the whole work is pervaded with a warm and hazy

glow. (Vosmaer.) — *2554. *Rembrandt*, Portrait of himself, dated 1637. — *2111. *Rubens*, Portrait of Baron de Vicq, ambassador of the Netherlands at the French court. — 1921. *Jan Brueghel*, nicknamed *Velvet Brueghel*, Battle of Arbela. — 1961. *Van Dyck*, Madonna and Child with SS. Magdalene, David, and John the Baptist. — *2714. *Holbein*, Portrait of William Warham, Archbishop of Canterbury, at the age of seventy, dated 1528. — 2732. *Rottenhammer*, Death of Adonis, in the style of Tintoretto. — *2713. *Holbein*, Portrait of Nic. Kratzer of Munich, astronomer to Henry VIII. of England, dated 1528, the finest Holbein in the Louvre. — 2705. *Lucas Cranach*, Portrait. — 2028. *School of Memling*, Resurrection of Christ, Ascension, and St. Sebastian. — 2719. *Holbein*, Portrait of Sir Richard Southwell, a replica, or perhaps a skilful copy of the picture at Florence. — *2737. *School of Cologne* (15th cent.), Descent from the Cross. — *1957. *Gér. David* (?), Marriage at Cana, with a view of the Hôtel de Ville of Bruges on the left. — *2030. *Quentin Matsys*, Christ imparting a blessing.

We now proceed to examine the series of large **Paintings by *Rubens* (Nos. 2085-2105), beginning on the same side, a little higher up. Marie de Médicis, widow of Henri IV., for a time regent for her son Louis XIII., and afterwards exiled, returned to France in 1620, and resolved to embellish her Luxembourg Palace with paintings on a very extensive scale. Rubens, to whom the task was entrusted, came to Paris in 1621, where he painted the sketches (eighteen of which are now at Munich), after which he returned to Antwerp and executed the pictures there with the aid of his pupils. In 1625 the completed works were brought to Paris, where they received a few final touches from Rubens himself. The scenes are as follows: — 2085. The three Fates spin the fortunes of Marie de Médicis. — 2086. Birth of Marie (1575, at Florence); Lucina, the goddess of births, is present with her torch; Florentia, the goddess of the city, holds the new-born infant; on the right is the river-god of the Arno. — 2087. Her education, conducted by Minerva, Apollo, and Mercury; on the right are the Graces. — *2088. Amor shows the princess the portrait of Henri IV.; above are Jupiter and Juno; beside the king appears Gallia. — 2089. The nuptials; the Grand Duke Ferdinand of Tuscany acts as proxy for his niece's husband. — 2090. The queen lands at Marseilles. — 2091. Wedding festival at Lyons; Henri IV. in the character of Jupiter, and Marie de Médicis in that of Juno; in the chariot in front the patron-goddess of Lyons. — 2092. Birth of Louis XIII.; behind the queen is Fortuna; the infant is in the arms of the genius of Health. — 2093. Henri IV., starting on his campaign against Germany (1610), entrusts the queen with the regency. — *2094. Coronation of the queen by Cardinal de Joyeuse at St. Denis; the king is observed in a gallery above. — *2095. Apotheosis of Henri IV.; below are Victoria, in a yellow robe, and Bellona with a trophy; on the right

is enthroned the mourning queen between Minerva and Wisdom; at her feet are Gallia and noblemen. — *2096. Regency of the queen under the protection of Olympus; Mars, Apollo (a copy of the antique Belvedere), and Minerva drive away the hostile powers; Juno and Jupiter cause the chariot of France to be drawn by gentle doves. — 2097. The queen in the field during the civil war; she is crowned by Victoria. — 2098. Treaty between France (on the right) and Spain (left); princesses of the allied courts are mutually destined to marry the heirs to the two thrones. — *2099. Prosperity prevails during the regency; the queen enthroned bears the scales of justice; on the right are Minerva, Fortuna, and Abundantia; on the left Gallia and Time; below are Envy, Hatred, and Stupidity. — *2100. The queen commits the rudder of the ship of the state, rowed by the virtues, to Louis XIII. on his majority. — 2101. Flight of the queen (1619). — 2102. Mercury presents himself to the queen as a messenger of peace. — 2103. The queen is conducted into the temple of peace. — *2104. Marie de Médicis and Louis XIII. in Olympus; below is the dragon of rebellion. — *2105. The god of time brings the truth to light; above is the king giving his mother a chaplet of peace.

In the centre, between this bay and the following: 2701. *Hans Sebald Beham*, History of David, dated 1534, with the armorial bearings of Albert of Brandenburg, Archbishop of Mayence: Siege of Rabba; David seeing Bathsheba; Saul and David returning in triumph from a battle with the Philistines; David and Nathan. The figures all wear the Nuremberg costume of the period.

BAY E. NETHERLANDISH SCHOOLS.

On the right: *2527. *Paul Potter*, Cows pasturing, very highly finished. — 2548. *Rembrandt*, Flayed ox. — *2159. *Teniers*, Village festival. — 2142. *Snyders*, The animals of Noah's ark. — 2544. *Rembrandt*, Portrait of an old man, dated 1638. — *2588. *Terburg*, The music-lesson, a charming work. — *2553. *Rembrandt*, Portrait of himself, dated 1634. — 1934. *Phil. de Champaigne*, Two nuns of Port-Royal (p. xxx). — 2314. *Berchem*, Landscape. — 1954. *Caspar de Crayer*, Equestrian portrait of Archduke Ferdinand of Austria, governor of the Netherlands. — 2606. *Ary de Voys*, Portrait. — *2497. *Adr. van Ostade*, Fish-dealer. — 1966. *Van Dyck*, Rinaldo and Armida (a copy?). — *2611. *Jan Weenin*, Dead game, one of his principal works. — 2543. *Rembrandt*, Venus and Cupid, a portrait-picture, of his earlier period. — 2083. *Rubens*, Triumph of Religion; opposite, 2076. *Rubens*, Elijah in the desert fed by an angel, both painted in Spain as patterns for tapestry. — *2392. *Jan Davidz de Heem*, Fruit and plate on a table. — 2016. *Jordaens*, Portrait of the Dutch admiral De Ruyter. — *J. Fictoor*, 2370. Isaac blessing Jacob, 2371. Girl at a window. — *Metsu*, 2462. Woman with a pitcher, 2463. Woman peeling apples. — 2332. *Both*, Land-

scape. — *1971. *A. van Dyck*, Portrait of the Marquis d'Aytona, the Spanish commander-in-chief in the Netherlands. — *2112. *Rubens*, Portrait of Elizabeth of France, Queen of Spain and daughter of Henri IV. — *2388. *Fr. Hals*, The Van Beresteyn family of Haarlem. — *1970. *A. van Dyck*, Elizabeth of Austria, Regent of the Netherlands, as a Clarissine nun. — *2323. *Berchem*, Italian landscape. — 2331. *Ferd. Bol*, Portrait. — 1927. *Phil. de Champaigne*, Repast at the house of Simon, the Pharisee.

On the left, beginning from the other end: *2458. *Metsu*, Vegetable-market at Amsterdam, one of his chief works. — 2538. *Rembrandt*, St. Matthew, dated 1661. — *2404. *Meindert Hobbema*, The mill. — *Snyders*, 2141. The earthly paradise, 2145. Fish-market. — 2044. *Van der Meulen*, Louis XIV. hunting the stag, with Fontainebleau in the background. — *2341. *A. Cuyp*, Landscape. — 2604. *Lievens*, Visitation. — *1974. *Van Dyck*, Portrait of a lady and her daughter. — *2343. *A. Cuyp*, The ride. — 1928. *Phil. de Champaigne*, Last Supper. — 2015. *Jordaens*, Music after the repast. — 2076. *Rubens*, Elijah. (p. 129). — *2342. *A. Cuyp*, Two riders. — 2372. *G. Flinck*, The angels appearing to the shepherds. — 2014. *Jordaens*, Feast of Epiphany. — 1973. *Van Dyck*, Portrait of a man and a girl. — *2557. *J. van Ruysdael*, River in a wood, with figures by *Berchem*, an important work of the master's best period. — 2035. *Van der Meulen*, View of Arras, in the foreground Maria Theresa in a carriage, behind which are Louis XIV. and his train on horseback. — 2130. *Rubens* (?), Diogenes with his lantern (school-piece). — 1985. *Van Dyck* or *Rubens*, Portrait of President Richardot of Brussels and his son. — 2498. *Adrian van Ostade*, Interior of a cottage, with admirable chiaroscuro. — 2546. *Rembrandt*, Portrait of a man. — *Rubens*, 2078. Madonna surrounded by angels, *2113. Helena Fourment, his second wife, with two of her children (unfinished). — 2068. *Pourbus the Younger*, Last Supper.

At the windows, two Sèvres vases of the Restoration period.

BAY F. NETHERLANDISH SCHOOLS.

On the right: *2115. *Rubens*, Rustic merry-making (comp. p. 114). — 2636. *Wynants*, Outskirts of a forest, with cattle and figures by *Adr. van de Velde*, one of the master's chief works. — 2395, 2396. *Van der Helst*, Portraits. — *2117. *Rubens*, Landscape, partly veiled in mist, with a bird-snarer to the left in the foreground. — *2487, 2486. *Caspar Netscher*, Lesson on the bass-viol, Singing lesson. — *2560. *J. van Ruysdael*, Mountain-landscape, with a sunbeam shining through the parting clouds; figures by *Ph. Wouwerman*: poetically rendered, and masterly in its silvery, greenish-grey tone. — 2163. *Teniers the Younger*, Tavern. — 2427. *Dujardin*, Quacks, with a Roman landscape. — 2528. *Potter*, Grey horse (1653). — *1969. *Van Dyck*, Duke Charles Louis I. of Bavaria (full face) and his brother Robert, Duke of Cumberland. — 2576.

G. Sprong, Portrait. — *2383. *Frans Hals*, Descartes. — 2410, 2411. *Honthorst*, Portraits of the same persons as No. 1969. — 2609. *Weenix*, Marauders repulsed. — 1953. *De Crayer*, St. Augustine in an ecstatic trance.

To the left, beginning at the other end : *1962. *Van Dyck*, Madonna and donors. — *2637. *Wynants*, Landscape with figures by *Adr. van de Velde*. — *2541, *2540. *Rembrandt*, Two philosophers in profound meditation, dated 1633. — *2578. *Jan Steen*, Roystersers, dated 1674; a most humorous and joyful scene, full of happy motives. — 2510. *Isaac van Ostade*, Frozen canal. — 2595. *A. van de Velde*, Landscape with cattle. — *2558. *J. van Ruysdael*, Stormy sea on the Dutch coast; a work of marvellous poetry, striking effect, and masterly treatment. — 2082. *Rubens*, Crucifixion. — 1964. *Van Dyck*, St. Sebastian with angels. — *2537. *Rembrandt*, The good Samaritan, dated 1648. — *2386, *2387. *Fr. Hals*, Portraits of Nic. de Beresteyn and his wife. — 2313. *Berchem*, Environs of Nice (?). — 1929. *Phil. de Champaigne*, Last Supper (variation of No. 1928). — 2460. *Metsu*, Music-lesson. — 2580. *Jan Steen*, End of an orgy. — *2475. *Mieris the Elder*, The cook.

Supplementary Room of the German and Netherlandish Schools, see p. 146; *Recent Acquisitions*, p. 144.

We now return to the nearest door, and on the left enter the — **French School** (*Salles Françaises*), the works of which are arranged in chronological order (comp. Intro., p. xxix). The first five rooms contain works of secondary importance.

IX. Room. 71. *Bourdon*, Descent from the Cross; 585. *Valentin*, The Tribute-money; *Le Nain*, 539. Nativity, 541. Rustic repast; etc.

X. Room. Twenty-two pictures by *Eustache Lesueur* illustrating the life of St. Bruno, the founder of the Order of Carthusians, painted on wood in 1645-48 for the Carthusian Monastery at Paris, but freely retouched. The best is 584. Death of St. Bruno.

XI. Room. Works by *Lesueur*: 591-596. Birth of Cupid and scenes in his life; 598-602. The Muses, brought from the Hôtel Lambert (p. 224).

XII. Room. Fifteen views of French sea-ports by *Joseph Vernet*, painted for Louis XV., with good light-effects.

XIII. Room. Sea-pieces by *Jos. Vernet*, and a few paintings by British artists (Constable, Lawrence, Morland, etc.).

Crossing the vestibule of the staircase (Pl. E; leading to the exit in the Pavillon Denon), we next reach a long hall chiefly containing French works of the 17th cent., many of which deserve notice.

SALLE MOLLIER or ROOM XIV. On the right: 730. *N. Poussin*, Bacchanal. — *Valentin*, 57. Judgment of Solomon; 56. Judgment of Daniel. — 742. *Poussin*, Apollo and Daphne, unfinished. —

513. *Chas. Lebrun*, Alexander entering Babylon, a large picture, painted (like Nos. 509-512, see below) as a design for Gobelins tapestry. — *Lesueur*, 558. Christ appearing to Mary Magdalene; *554. The young Tobias departing on his journey with the blessing of his father. — 504. *Lebrun*, Martyrdom of St. Stephen. — 718. *N. Poussin*, Assumption. — *556. *Lesueur*, Bearing of the Cross. — 494. *Lebrun*, Adoration of the Shepherds. — *Nicolas Poussin*, 713. Holy Family; 710. The Philistines struck with the pestilence, painted at Rome about 1630; 709. The Israelites gathering manna in the wilderness (Rome, 1639); 704. Landscape, with Orpheus and Eurydice; 706. Moses in the ark of bulrushes. — *167. *Ant. Coypel*, Athalia thrust out of the temple. — 502. *Lebrun*, Pietà. — *434. *J. Jouvenet*, Raising of Lazarus, one of the best and most characteristic works of this artist (1706). — *560. *Lesueur*, Preaching of St. Paul at Ephesus (1649), the chief figures after Raphael. — 511. *Lebrun*, The tent of Darius, one of the Gobelins series mentioned above. — 715. *Poussin*, The blind beggars of Jericho. — *Claude Lorrain* (unsurpassed in rendering soft and vaporous atmosphere), *313. Harbour at sunset, an ideal landscape; 312. Landscape with village-festival, both painted in 1639; the figures, as in most pictures by this artist, are by another hand. — *Poussin*, 726. The young Pyrrhus, son of the king of Molossus, rescued from the pursuit of his rebellious subjects by two faithful followers of his father; 712. Adoration of the Magi. — 59. *Valentin*, Concert. — 433. *Jouvenet*, The miraculous draught of fishes, 1706. — 724. *Poussin*, Rape of the Sabine women. — *Lebrun*, 497. Christ in the desert, waited on by angels; 501. Crucifixion. — 728. *Poussin*, Mars and Rhea Sylvia. — 529. *Lefèvre*, Master and scholar. — 707. *Poussin*, The infant Moses spurning the crown of Pharaoh with his feet. — 456. *Lahire*, Pope Nicholas V. opening the burial-vault of St. Francis of Assisi. — *317. *Claude Lorrain*, Harbour, of great vigour and depth of colouring. — 708. *Poussin*, Moses changing the rod of Aaron into a serpent. — 790. *Rigaud*, Robt. de Cotte, the architect. — *557. *Lesueur*, Descent from the Cross, one of the painter's master-pieces. — *510. *Lebrun*, Battle of Arbela, another of the Gobelins series mentioned above. — 322. *Claude Lorrain*, The ford.

On the exit-wall: 52. *Bon Boulogne*, St. Benedict resuscitating a child; 555. *Lesueur*, The Annunciation, painted under the influence of Guido Reni.

318. *Claude Lorrain*, Sea-port. — 780. *Rigaud*, Presentation in the Temple. — *Poussin*, 737. Summer, or Ruth and Boaz; 738. Autumn, or the spies returning with grapes from the Promised Land; 729. Bacchanal; 727. Mars and Venus; 721. John the Baptist; 739. Winter, or the Deluge; 731. Echo and Narcissus; 720. Death of Sapphira. — 512. *Lebrun*, Alexander and Porus. — 544. *Le Nain* (?), Procession in a church. — *Poussin*, 716. The Woman

taken in adultery; 714. Holy Family. — 515. *Lebrun*, Death of Meleager. — 782. *Rigaud*, Philip V. of Spain, at the age of 17, painted in 1700. — 314. *Claude Lorrain*, Cleopatra received by Antony at Tarsus. — 735. *Poussin*, Time delivering Truth from the attacks of Envy and Discord, executed as a ceiling-painting for Card. Richelieu in 1641. — 24, 23. *Blain de Fontenay*, Flowers and Fruit. — 316. *Claude Lorrain*, Ulysses restoring Chryseis to her father (figures by *Fil. Lauri*). — *734. *Poussin*, Three Arcadian shepherds and a maiden surrounding an old tombstone which they have found and which bears the inscription 'Et in Arcadia ego': a simple, harmonious, and much admired composition (comp. p. xxx). — *Poussin*, *711. Judgment of Solomon; 705. Moses in the ark of bulrushes. — *628. *Mignard*, The Virgin with a bunch of grapes ('la Vierge à la grappe'). — *781. *Rigaud*, Louis XIV., painted from life (1701). — 452. *Lahire*, Virgin and Child. — 514. *Lebrun*, Meleager and Atalanta. — 498. *Lebrun*, Christ entering Jerusalem. — 971. *Vouet*, Presentation in the Temple. — 505. *Lebrun*, Repentant Magdalene, perhaps a portrait of Mlle. de la Vallière, mistress of Louis XIV. — 540. *Le Nain*, Forge. — 530. *Lefèvre*, Portrait. — 500. *Lebrun*, Crucifixion. — *Claude Lorrain*, *310. Sea-port at sunrise; 311. Campo Vaccino. — 732. *Poussin*, Triumph of Flora. — *Mignard*, 634. St. Cecilia; 630. Bearing of the Cross. — 509. *Lebrun*, Crossing of the Granicus. — 483. *Largillière*, Count de la Châtre. — *704. *Poussin*, Eleazar and Rebecca. — 499. *Lebrun*, Bearing of the Cross.

We now enter a lofty saloon with vaulted ceiling, called the —

SALON DENON or ROOM XV, which contains a collection of portraits of artists, formed in 1887 on the model of the collection at Florence. Some of the canvases have been brought from the other rooms of the Louvre, but the majority come from the Ecole des Beaux Arts and from Versailles, and are of historical value only. The most interesting are as follows, from right to left:

373. *Et. Jeaurat*, by Greuze; 640. *P. Mignard*, by himself; 525. *Jos. Vernet*, by Mme. Lebrun; *1983. *Van Dyck*, by himself; 743. *N. Poussin*, *2552. *Rembrandt*, 1148. *Guercino*, by themselves; 1944. *F. Mansart* and *Cl. Perrault*, by Phil. de Champaigne; 1380. *Maratta*, 482. *Lebrun*, by themselves; 492. *Nic. Coustou*, by Largillière; 760. *P. Puget*, by Fr. Puget; 147. *Courbet*, *521. *Mme. Lebrun*, 183. *Coyvet*, by themselves; 524. *Hub. Robert*, by Mme. Lebrun; 265. *Rob. le Lorrain*, by H. Drouais; 333. *Canova*, by Fr. Gérard; 796. *H. Rigaud*, 214. *Eug. Delacroix*, 1947. *Phil. de Champaigne*, by themselves; 476. *J. L. David*, by Langlois; 786. *Lebrun* and *Mignard*, by Rigaud.

The lunettes of the ceiling are embellished with paintings by *Charles Müller* illustrative of the history of art in France: St. Louis and the Sainte Chapelle, Francis I. in the studio of one of his artists, Louis XIV. beginning the Louvre, Napoleon I. ordering its completion.

We now repass the large side-hall, in which the more recent works are hung, and inspect first the —

SALLE DARU or ROOM XVI, containing French works of the 18th

and 19th centuries. On the right: 670. *Oudry*, The farm. — 411. *Huet*, Dog and geese. — 902. *L. Mich. Vanloo*, Portrait of Soufflot, the architect. — 42. *Boucher*, The goat. — 671. *Oudry*, Dog. — 465-462. *Lancret*, The seasons. — 275. *J. Dumont* (called *Le Romain*), Madame Mercier, nurse to Louis XV., and her family. — 234. *Desportes*, Dog and partridges. — *Hub. Robert*, 798. View of Nîmes, 808. Ruins of a temple. — *J. Vernet*, 935. Castello S. Angelo, 936. (farther on) Ponte Rotto, at Rome. — 375, 374. *Greuze*, Studies of girls' heads. — 896. *J. B. Vanloo*, Diana and Endymion. — 900. *C. Vanloo*, Maria Leszczinska, queen of France. — *Boucher*, 33. The bagpipe, 30. Diana quitting the bath, 31. Venus demanding arms for Æneas from Vulcan, 32. Sleeping shepherdess. — 2722. *Angelica Kaufmann*, Baroness Krüdener and her daughter. — 99. *Chardin*, The Procuree. — 173. *A. Coypel*, Flora and Zephyr. — *H. Robert*, 809. Landscape, 797. View of Orange. — 666. *Oudry*, Dog. — 170. *A. Coypel*, Esther before Ahasuerus. — 920. *J. Vernet*, The torrent. — *Chardin*, 97. The antiquarian monkey; 94. Weapons of the chase. — 863. *Taraval*, Triumph of Amphitrite. — 668. *Oudry*, Dog and game. — 913. *J. Vernet*, Moonlight. — 658. *Nattier*, Mme. Adelaïde, fourth daughter of Louis XV. — 222. *De Marne*, Fair. — 261. *Drolling*, Kitchen interior. — 520. *Mme. Lebrun*, Abundance lead back by Peace. — 766. *Raoux*, Pygmalion and Galatea — 223. *De Marne*, Start for the wedding.

End wall: 194. *David*, Paris and Helen. — *Greuze*, 370. The father's curse; 372. The repentant son. These are characteristic examples of the 'bourgeois' dramas with a 'moral', which Greuze was so fond of painting. — 448. *Lagrenée*, Rape of Dejanira.

Left side, returning: 381. *Greuze*, Portrait of the artist. — 922. *J. Vernet*, Return from fishing. — 135. *Cochereau*, David's studio. — 35. *Boucher*, Pastoral scene. — 925. *J. Vernet*, Moonlight effect. — 884. *Fr. de Troy*, Esther's toilet. — *369. *Greuze*, The Marriage Contract, marked by skilful discrimination of individual character at a moment of great excitement. This is considered his masterpiece. — 698. *Perronneau*, Oudry, the painter. — 678. *J. Parrocel*, Passage of the Rhine by Louis XIV.'s army. — 102-100. *Chardin*, Still-life. — 969. *Voiriot*, Nattier, the painter. — *H. Robert*, 799. Interior of the temple of Diana at Nîmes, 807. Ruined portico. — 820. *Roslin*, Girl decking the statue of Cupid. — 96, 95. *Chardin*, Feasting and Fasting. — 899. *C. Vanloo*, Huntsmen resting. — *J. Vernet*, 933, 929, 930, 934. Sea-pieces (neighbourhood of Marseilles). — 867. *Tocqué*, Maria Leszczinska. — 803. *H. Robert*, Porticus of Octavia. — *92. *Chardin*, Grace before meat, his best work. — *982. *Ant. Watteau*, Embarking for Cythera, an admirable study for the picture at the Palace in Berlin. — 91. *Chardin*, The industrious mother. — *H. Robert*, 802. Porticus of Marcus Aurelius; 810. Park; 800. Pont du Gard. — *372. *Greuze*, The broken pitcher, the most popular of his works. — 638. *Mignard*, The Grand Dau-

phin, son of Louis XIV., and his family. — 923, 921. *J. Vernet*, Landscapes. — *Boucher*, 45. Pastoral scene; 36. Vulcan presenting Venus with arms for Æneas. — *Desportes*, 245. Fruit; 237. Game; 227. Still-life; 229. Hunt; 230. Dogs. — *Chardin*, 90. Fruit and Animals; 89. Cat in a larder. — 249. *Desportes*, Portrait of the artist. — 869. *Tocqué*, Portrait of a lady.

Between the doors: 835. *Santerre*, Susannah at the bath.

Visitors who wish to adhere to the chronological order in studying the paintings of the French school should omit the next gallery for the present, and proceed to the Salon des Sept Cheminées (p. 139). Those whose time is limited may return through the Salon Denon to the Salle des Etats (see Plan, p. 88).

THE NEW FRENCH GALLERY, or ROOM VIII, formerly the *Salle des Etats*, where the Chambers used to be formally opened by Napoleon III., has now been completely transformed in order to serve as an additional gallery for pictures of the French school; and the upper part has been lavishly decorated, though in a style open to criticism. As mentioned at p. 126, the farther end communicates with the Grande Galerie. We begin to the right, on entering from the Salon Denon (p. 133). — 140, 139. *Corot*, Views in Rome. — 251. *Diaz*, Views in the Pyrenees. — 832. *Th. Rousseau*, Effects of the storm. — *250. *Eug. Devéria*, Birth of Henri IV. — *207. *Eug. Delacroix*, The barque of Dante. The cracking of this and other paintings in the gallery is attributed to the inferior quality of modern pigments, and to the necessity under which artists are brought by the exigencies of exhibition of varnishing too soon. — *Ingres*, 415. Peter receiving the keys of heaven; 419. Roger delivering Angelica. — 147. *Courbet*, Deer in cover. — 702. *Pils*, Rouget de l'Isle singing the Marseillaise. — 363. *Gleyre*, Lost illusions. — No number, **Couture*, Romans of the decadence. — 615. *Marrilhat*, Ruins of the mosque of Sultan Hakem. — 841. *Ary Scheffer*, St. Augustine and his mother Monica. — 410. *Ingres*, Portraits of Cherubini. — 390. *Gros*, Francis I. and Charles V. visiting the tombs at St. Denis; an unhappy composition. — 138. *Corot*, Morning. — *417. *Ingres*, Apotheosis of Homer, an old ceiling-painting (p. 145). The figure of the 'Iliad', clad in red, is perhaps the best in this calm and dignified composition. — 145. *Courbet*, Stags fighting. — 744. *Prud'hon*, Crucifixion. — 426, 427. *Ingres*, Portrait of M. and Mme. Rivière. — 643. *Millet*, Spring. — 956. *H. Vernet*, The Barrière de Clichy in 1814. — *889. *Troyon*, Bullocks going to their work. — 829. *Th. Rousseau*, The Dormoir of Bas Bréau. — 305. *Fromentin*, Hawking in Algiers. — 610. *Lethière*, Death of Virginia. — 817. *L. Robert*, Return from the pilgrimage to La Madonna dell' Arco at Naples. — 748. *Prud'hon*, Meeting of Francis II. and Napoleon after the battle of Austerlitz. — *847. *Th. Rousseau*, Forest of Fontainebleau. — 14. *Belly*, Arab pilgrims. — 958. *H. Vernet*, Raphael at the Vatican. — 339. *Géricault*, Officer of the Chasseurs-à-cheval.

Beyond the door to the Grande Galerie, to the right coming from the latter: *17. *Benouville*, St. Francis of Assisi blessing his native town. — *216. *P. Delaroche*, Death of Queen Elizabeth of England. — *816. *L. Robert*, Reapers in the Pontine Marshes. This and No. 817 (p. 135) are two works characterized by skilful grouping, energetic, and cheerful. — 840. *Ary Scheffer*, The Temptation in the wilderness. — 83. *Brascassat*, Landscape with cattle. — 847. *Sigolon*, The young courtesan. — *890. *Troyon*, Return to the farm. — 211. *Delacroix*, Jewish wedding. — 416. *Ingres*, 'Madonna à la hostie'. — 609. *Lethière*, Brutus condemning his sons. — 210. *Delacroix*, Algerian women. — No number, *Bouchot*, Fall of the Directoire (Nov. 9th, 1799). — *213. *Delacroix*, Crusaders entering Constantinople. — 843. *Schnetz*, The vow to the Madonna. — 141. *Corot*, Landscape. — 146. *Courbet*, Wood with deer. — No number, *Delacroix*, The Barricade, July 28th, 1830. — 408. *Heim*, Capture of Jerusalem by the Romans. — 199. *David*, Mme. Récamier, unfinished. — 409. *Heim*, Charles X. distributing prizes to the artists at the close of the exhibition of 1824. — 217. *Delaroche*, The Princes in the Tower of London. — *389. *Gros*, Napoleon after the battle of Eylau. — 212. *Delacroix*, Boat of the 'Don Juan', a wrecked vessel. — 957. *H. Vernet*, Judith and Holofernes. — 641. *Millet*, Church of Gréville; No number, *Gleaners*. — 830. *Th. Rousseau*, Marsh in the 'Landes'. — *208. *Delacroix*, Massacre at Scio. — 770. *Regnault*, General Prim.

We now again pass through the second French gallery, descend the great staircase, and re-ascend on the left side to the —

Rotonde d'Apollon, a kind of vestibule, adorned with ceiling-paintings of the Fall of Icarus and the four Elements, by *Blondel*, *Mauzaisse*, and *Couder*. In the centre is a handsome marble vase, imitated from an antique vase of the Vatican, and surrounded with a beautiful modern mosaic by *F. Belloni*. The door opposite leads to the Salle des Bijoux (p. 138). The fine wrought-iron door of the 17th cent. on the right leads to the —

***Galerie d'Apollon**. This saloon, which is about 70 yds. in length, was constructed in the reign of Henri IV., burned down in 1661, and rebuilt under Louis XIV. from designs by *Charles Lebrun*, who left the decoration unfinished. It was then entirely neglected for a century and a half, but was at length completed in 1848-51. It is the most beautiful hall in the Louvre, and is considered one of the finest in the world. It derives its name from the central ceiling-painting by *Delacroix*, representing 'Apollo's Victory over the Python', a fine work both in composition and colouring (1849). The subjects of the other ceiling-paintings, beginning with the side next the Seine, are as follows: Triumph of the Waters (Neptune and Amphitrite), by *Ch. Lebrun* (about 1665); to the left, Summer (Ceres and her attendants beseeching the aid of the Sun God), by *Durameau*, 1775; in the middle, Castor as the

morning-star, by *A. Renou*, 1781; to the right, Autumn (Triumph of Bacchus), by *H. Taraval*, 1769. Corresponding to these last three scenes, on the other side of the central picture: to the left, Winter (*Æolus* and the winds), by *Lagrenée the Younger*, 1775; in the middle, Diana as the Goddess of night, by *Lebrun*, about 1665; to the right, Spring (Flora and Zephyr crowning Cybele, the Goddess of the Earth, with flowers), by *Callet*, 1781. On the vaulting above the entrance is the Triumph of Cybele, with Bacchantes, by *J. Guichard*, after Lebrun, 1849. The panels of the walls are adorned with *Portraits of twenty-eight celebrated French artists, and of St. Louis, Francis I., and Louis XV., in Gobelins tapestry.

The beautiful tables and other furniture in this room date chiefly from the reign of Louis XIV. The glass-cases contain **Objects of art, gems, etc. The collection of enamels is the most extensive and valuable in the world.

TABLE I. **Reliquary of St. Pothenthin*, a German work of the 12th century.

CASE I. chiefly contains ecclesiastical vessels of the Gothic period, and others in enamelled gold and rock-crystal. At the top: at each end, enamelled Venetian basins; Casket of the 14th cent.; *Ornament with enamelled statuettes, etc. from the Chapel of the Order of the Holy Ghost in the Louvre, dating from the reign of Henri III. (1579); Moorish cup, known as the *Baptistère de St. Louis*, used at the christening of French princes; Double cross, a mediæval enamel, with statuettes and gems; Reliquary (12th cent.), with an arm of Charlemagne. — In the middle: 12 Busts of the Caesars, the heads of crystal or precious stones; objects from the Chapel of the Holy Ghost in the Louvre (16th cent.); in the centre, Monstrance of the 13th cent.; Oriental cup of crystal (10th cent.); Italian pax (14th cent.). — Below: Cylindrical monstrance (15th cent.); objects from the Chapel of the Holy Ghost; Reliquary of the 13th cent.; etc.

CASE II. Chiefly objects of the 16th century. *Pax, with enamels and rubies; *Monstrance of crystal, with silver-gilt base and cover, adorned with chasing, cameos, and gems; *Rings; *Ornaments; Cup of sardonyx; Vessel of rock-crystal, shaped like a chimæra; Urns formerly in the possession of Cardinal Mazarin.

CASE III. Similar objects. At the top: **Epergne* of the time of Louis XV., consisting of a boat in lapis lazuli mounted in gold and enamel; **Goblets* in rock-crystal and **Vessels*, beautifully chased (translucent, best seen from the other side); the handle of the first cup is set with enamels and rubies; Casket of Hungarian jade. — In the middle, returning: *Vessel of sardonyx, with enamelled mounting; Platter of agate, with cameos; Platter of green jasper, richly mounted; *Scourging of Christ*, a statuette in dark jasper, with red flecks skilfully made to represent the wounds, at the base figures in gold; all these of the 16th century. — Below: Vase of jasper, with dragons as handles, by *Benvenuto Cellini*, the only specimen of his skill in the collection; *Vessel of Oriental agate and cup of sardonyx, adorned with enamels; Incense vessels of green jasper; antique *Vase, with very fine mountings; *Cup of sardonyx, the handle in the shape of a dragon studded with diamonds, rubies, and opals (16-17th cent.).

CASE IV. contains the Crown Jewels retained when the rest were sold in 1887. — Among these are: the **Regent*, perhaps the finest diamond in the world, weighing 136 carats and worth 12-15 million francs; to the right, the **Mazarin*, a rose-diamond of immense value, and a large ruby in the shape of a dragon. — Behind, to the right: *Crown of Louis XV.* (false jewels); *Crown of Napoleon I.*, in imitation of Charlemagne's; between these, *Sceptre of St. Louis*, of great value but doubtful authenticity. In front, Watch presented to Louis XIV. by the Dey of Algiers; pearl dragon-brooch and elephant of the Danish order of the Elephant. — Be-

low: Ring of St. Louis; *Sword ('épée militaire'), made at the order of Napoleon I., and set with gems, valued at 2 million francs; **Sceptre of Charles V.* (14th cent.); *Sceptre* of the Capetan kings; *Sword and Spurs of Charlemagne*, with early Germanic ornamentation. *Waillet of Catherine de Médicis*, set with diamonds.

CASE V. Objects of the 16-17th centuries. — At the top: Articles of rock-crystal; silver-gilt group of a Centaur carrying off a woman; *Female equestrian statuette, also in silver-gilt. — In the middle: Vessels of sardonyx; Vessel of agate (16th cent.); green jasper dish in Italian work of the 16th century. — Below: Dishes of Oriental cornelian and green jasper, vessels in agate, etc.

CASE VI. — Behind, to the left, **Enamelled Reliquary*, with the Virgin and Child (early 14th cent.). — *Casket of St. Louis* (13th cent.); *Reliquary for an arm of St. Louis of Toulouse, enamelled, on the hand a sapphire ring (14th cent.); *Vase of Eleanor of Aquitaine*, wife of Louis VII. of France and afterwards of Henry II. of England (12th cent.). *Vase and Sacrament-Platter of the Abbot Suger* of St. Denis; the latter, of antique porphyry, was remodelled in the 12th cent.; Byzantine reliefs in beaten work.

CASE VII. Behind, to the left: **Helmet* and **Shield of Charles IX.* (d. 1574), in gold and enamel; on the shield is represented a cavalry-engagement, with features borrowed from Leon. da Vinci's famous cartoon, and probably of French workmanship. **Shield of Henri II.* (d. 1559). **Casket of Anne of Austria.*

The cabinets along the wall opposite the windows, and the glass-cases in front of the windows, chiefly contain **Enamels*. Like majolica-painting in Italy, the enameller's art was practised in France at a very early date. Its culminating period was coeval with that of the School of Fontainebleau (second half of the 16th cent.), and Limoges was its headquarters. The most famous artists in enamel were *Nardon Pénicaud*, *Léonard Limousin*, *Jean* and *Pierre Courteys*, and *Pierre Reymond*. The practice of the art died out in the 18th cent., but has recently been revived with some success.

CABINET I. (at the end of the room next the Salon Carré). Enamels by *P. Courteys* and *P. Reymond*: Niobe and her children, by the former, after Giulio Romano. — CABINET II. *Plaques of enamel by *F. Courteys*, and other enamels; Silver-gilt *Ever*, with reliefs and chasings representing episodes in the capture of Tunis by Charles V. in 1535. — CABINET III. *Plaques of enamel by *Léonard Limousin*. — CABINET IV. Enamels. Dish in silver-gilt, embossed, a French work of the 16th century. — CABINET V. Enamels by artists of Limoges.

By the FIRST WINDOW, near the entrance: Transparent enamels of the 14-15th cent.; **Binding of a Prayer-book*, with filigree ornamentation, enamels (symbols of the Gospels), and embossed gold reliefs (Crucifixion), a Byzantine work. — SECOND WINDOW: *Champlevé Enamels* of the 12th cent., from the Rhine; *Limoges Enamels* of the 13th century. — THIRD WINDOW: **Enamels* ('Emaux Peints') by *Nardon Pénicaud* and *P. Reymond*. — FOURTH WINDOW: Enamels by *Léonard Limousin*. — FIFTH WINDOW: **Basin*, silver-gilt and enamelled, adorned in the centre with a large cameo representing Ferdinand III., Emperor of Germany (d. 1659), and on the margin with three concentric rows of cameos, each 48 in number, representing princes of the house of Austria from Rudolph of Hapsburg downwards, with their armorial bearings (a German work). — SIXTH WINDOW: Enamels by *Léonard Limousin*, including several portraits. — SEVENTH WINDOW: **Mirror* and **Candlestick*, adorned with emeralds and cameos, presented by the Republic of Venice to Marie de Médicis. — The cases at the remaining windows contain enamels by *P. and J. Courteys*, *Jacques Nouailler*, *P. Pénicaud*, *J. Court*, etc.

The door on the right at the end of this gallery leads to the Salon Carré (p. 116). — We return to the Salle Ronde, and turn to the rooms of the Old Louvre on the right, first entering the —

Salle des Bijoux, which is adorned with a ceiling-painting by *Mauzaisse*, representing Time amid the ruins of an ancient build-

ing. The room contains an extremely valuable collection of ancient ornaments, jewels, and enamels, among which the Etruscan works are conspicuous for the perfection of their execution.

Central Case. Gold crowns, including a Græco-Etruscan *Diadem (unique). Gilded iron helmet with enamel ornamentation (found in the Seine near Rouen); Etruscan helmet, with golden circlet; golden quiver. Above are necklaces of gold, silver, enamel, and pietra dura, some with artistic pendants of the finest filigree work. *198. Golden Etruscan necklace adorned with a head of Bacchus with the horns and ears of a bull; amulets; buckles; hair-pins of the precious and other metals; crosses. — *Wall Case.* Silver objects, *Ceres with movable arms; silver-plate found in Notre-Dame-d'Alençon near Brissac in 1836; Etruscan earrings; rings of Greek and Roman workmanship. — Side next the Seine. *1st Window Case.* Gold and bronze buckles, with reliefs; necklaces of stone and gold; rings, earrings, bracelets. — *2nd Window Case.* Golden rings with and without precious stones; golden necklaces and earrings; bronze clasps. — *3rd Window Case.* Articles belonging to the treasure-trove of Notre-Dame-d'Alençon (see above). — Side next the court. *Window Case:* Buckles; gold and bronze bracelets; earrings (of ancient Greek workmanship, from Megara); two gold signet-rings (one with a head of one of the Ptolemies).

Proceeding in a straight direction, we next enter the —

Salle des Sept Cheminées or Room III., containing a number of the finest pictures of *French Masters of the 19th Century*, or of the Empire and the Restoration.

Beginning on the left: *188. *David*, The Sabine women interposing between the Romans and the Sabines; in front Romulus about to hurl his spear at Titus Tatius; the artist's masterpiece, painted on the model of an antique medallion (1799). *187. *David*, Leonidas at Thermopylæ, finished in 1814 as the Allies entered Paris. — 360. *Girodet-Trioson*, The Deluge (1814). — *Prud'hon*, 751. Empress Josephine; *747. Crime pursued by Justice and Divine Vengeance, a work of tragic earnestness, painted in 1808 for the Criminal Court. — *338. *Géricault*, Wreck of the Medusa, a French frigate which went down with 400 men on board, of whom only five were saved on a raft (1819; this painting created a great sensation, comp. p. xxxiii). — 392. *Gros*, General Fournier-Sarlovèze. — 398. *Guérin*, Clytemnestra and Ægistheus waiting for Agamemnon. — *746. *Prud'hon*, Assumption. — No number, **David*, Coronation of Napoleon I. — *522. *Mme. Lebrun*, Portrait of the artist and her daughter. — *198. *David*, Portrait of Pope Pius VII. (1805). — *526. *Mme. Lebrun*, Mme. Molé-Raymond, of the Comédie Française (1786). — 343. *Géricault*, Carabinier. — *337. *Gérard*, Portrait of the Marchesa Visconti. — 395. *Guérin*, Hippolytus repelling the accusations of Phædra, by whose side is Theseus (1802). — *328. *Gérard*, Cupid and Psyche (1796). — 393. *Guérin*, Return of Marcus Sextus (an imaginary incident). — 756. *Prud'hon*, Rape of Psyche. — *362. *Girodet-Trioson*, Attala's burial, from Châteaubriand (1808). — *388. *Gros*, Bonaparte in the plague-hospital at Jaffa (1804). — 332. *Gérard*, Portraits of Isabey, the painter, and his daughter (1795). — 396. *Guérin*, Pyrrhus taking Andromache and her children under his protection (1810).

Passing through the door to the left of the entrance (or to the right if we face the entrance), we reach the **Salle Henri II.** or Room II., a badly-lighted room, with a ceiling-painting by *Blondel*, representing the strife of Pallas and Poseidon before Zeus and Hera.

To the left: 123. *Chintreuil*, Space. — To the right: 384. *St. Jean*, Fruit. — 185. *Daubigny*, Spring. — 125. *Chintreuil*, Rain and sunshine. — 143. *Courbet*, Burial at Ornans. — 833. *St. Jean*, Flowers. — 420. *Ingres*, Joan of Arc at the coronation of Charles VII. — 82. *Brascasset*, Bull. — 361. *Girodet-Trioson*, Endymion. — 120. *Chassériau*, Tepidarium, one of the finest canvases ever inspired by the revival of the antique. — 359. *Giraud*, Slavedealer.

Collection La Caze (Room I.). This collection, which was presented to the museum in 1869, and remains distinct from the others by desire of the donor, forms in several respects a valuable complement to the Louvre galleries. It comprises several French paintings of the rococo period and Dutch masters not otherwise represented.

Beginning on the left: 2208. *Dutch School*, Old woman. — *2454. *Nic. Maes*, Grace. — 2515. *Is. van Ostade*, Winter landscape. — 2175. *Teniers the Younger*, Smokers. — 659. *Nattier*, Portrait of Mlle. de Lambesc, with the young Count de Brionne. — 1468. *Tintoretto*, Susannah at the bath. — *Teniers*, 2177. The smoker; *2170. Rustic festival. — 471. *Lanceret*, Boldness rebuked, from Lafontaine. — *491. *Largillière*, Portrait of the painter and his wife and daughter. — 2176. *Teniers*, Temptation of St. Anthony. — *Chardin*, 106. Still-life; 103. The house of cards (1737). — 1914. *Adr. Brouwer*, The writer. — *1925. *J. Brueghel* ('Velvet Brueghel'), The bridge of Talavera. — 2179. *Teniers*, The collector. — *2385. *Fr. Hals*, Portrait of a lady. — *792. *Rigaud*, Portrait of J. F. P. de Créqui, Duke de Lesdiguières, as a child. — *983. *Watteau*, Gilles (p. xxxi). — *1041. *French School* (18th cent.), Portrait. — 2337. *Brekelenkamp*, The consultation. — 2174. *Teniers*, Village fête. — 292. *Fragonard*, Pastoral scene. — 2550. *Rembrandt*, Woman bathing. — 2017. *Jordaens*, Mythological banquet. — 548. *Le Nain*, Rustic meal (1642). — 1995. *J. Fyt*, Game and implements of the chase. — 1945. *Phil. de Champaigne*, The Provost of the Merchants and the Sheriffs of Paris. — 1311. *L. Giordano*, Death of Seneca. — 376. *Greuze*, Head of a girl. — 488. *Largillière*, Portrait of the President De Laage. — 115. *Chardin*, Grapes. — 991. *Watteau*, Jupiter and Antiope.

105. *Chardin*, Still-life (other examples farther on). — 1979. *A. van Dyck*, Study of a head. — 2402. *J. van der Heyden*, Landscape. — *1915. *Adr. Brouwer*, The smoker. — 2707. *Denner*, Portrait of a lady, executed with great delicacy. — 2573. *Zorg*, Tavern interior. — 2435. *Karel Dujardin*, Landscape. — 791. *Rigaud*, Portrait of Cardinal de Polignac. — *2384. *Fr. Hals*, Gypsy. — 46. *Boucher*, Venus and Vulcan. — 1469. *Tintoretto*, Madonna and Child, with saints. — 986. *Watteau*, Gay company in a park. —

2132. *School of Rubens*, Portrait of a woman playing the mandoline. — 987. *Watteau*, Conjurer. — 2634. *Wouverman*, Pilgrims. — *2551. *Rembrandt*, Portrait (1651). — 2109. *Rubens*, Portrait of Marie de Médicis in the character of Gallia. — 1735. *Velazquez*, The Infanta Maria Theresa, afterwards queen of France. — 2504, *2505. (farther on), *Adr. van Ostade*, Reading, The newspaper. — 2178. *Teniers*, Guitar-player. — *2549. *Rembrandt*, Woman after the bath (1654). — 2406. *Hondecoeter*, The white turkey. — 2171. *Teniers the Younger*, The duet. — 1946. *Phil. de Champaigne*, Portrait. — 2172. *Teniers the Younger*, The smokers. — 2503, *2502. *Adr. van Ostade*, The reader, The drinker. — *1725. *Spagnoletto*, Man with a club-foot (1642). — *2579. *J. Steen*, The repast. — 2393. *Heemskerck*, Interior.

The exit leads to the staircase (Escalier Henri II., p. 111), of the *Pa-villon de l'Horloge* or *Pavillon Sully*, through which we may quit the Louvre.

Opposite the door of the Collection La Caze is another leading to the —

Saloon of the Ancient Bronzes, formerly the chapel of the palace, containing a valuable collection of implements, weapons, statuettes, etc. In the centre-cabinet are preserved bronze statuettes of the Roman period (of no great artistic value) and also mirrors, buckles, keys, seals, bracelets, etc. By the central window is a life-size gilded bronze statue of Apollo, in good preservation, found near Lillebonne, in Normandy; on the left an archaic Apollo, of great historical interest. — In the window-recesses: Busts of emperors, etc., of the Roman period, over lifesize. — The glass-case to the left of the entrance also contains busts, of which No. 636 is the best. — Then *Roman weapons, candelabra, etc. — Among the smaller statuettes in the middle glass case to the right are a few divinities of Greek workmanship.

The flight of steps to the left beyond this hall leads to the second floor (Musée de Marine, see p. 146). We next enter the —

Collection of Drawings (*Musée des Dessins*), rivalling the great Florentine collection in the Uffizi, and numbering 37,000 in all, among which are 18,200 by Italian masters (358 by Ann. Carracci), 87 by Spanish, 800 by German, 3150 by Flemish and Brabant, 1070 by Dutch, and 11,800 by French (2389 by Lebrun). Many of these drawings are exhibited under glass.

I. Room. Old Italian masters: *Mantegna*, *Lorenzo di Credi*, etc. — Ceiling by *Blondel*: France victorious at Bouvines. The walls of this and the following rooms are covered with large coloured cartoons by *Giulio Romano*.

II. Room. Italian. Drawings by the most celebrated masters: *Leonardo da Vinci*, *Michael Angelo*, *Raphael*, *Titian*, and *Andrea del Sarto*. — Ceiling-painting by *Blondel*: France receiving the 'Charte' from Louis XVIII.

III. Room. Italian. Drawings, two of them in chalks, by **Correggio*. — Ceiling-painting by *Drolling*: Law descends to earth.

IV. Room. Bolognese School. — Ceiling-painting by *Mauzaisse*: Divine Wisdom giving laws to Kings and Lawgivers.

V. Room. Netherlandish and German: *Dürer*, *Holbein*, *Rubens*, *Rembrandt*, *Teniers*, etc. On the wall to the left, *565. Battle of knights, by

Rubens, after the celebrated cartoon painted by *Leonardo da Vinci* in 1504 in competition with Michael Angelo (not extant). The ceiling painting, by Carolus Duran, represents the Triumph of Marie de Médicis. [From the passage between this and the next rooms a small staircase ascends to the left to the Musée de Marine and Musée Ethnographique (p. 147), on the second floor.]

VI. Room (corridor). Chalk drawings, chiefly portraits, by *Vivien Mme. Gujard*, etc.

VII. Room. *Claude Lorrain, N. Poussin, E. Lesueur*.

VIII. Room. *E. Lesueur*, Designs for the 'Life of St. Bruno' (p. 131). Above: *Ingres*, Coloured cartoons for the stained glass in the Chapel of St. Ferdinand (p. 156).

IX. Room. French School. *Charles Lebrun, Van der Meulen*.

X. Room. French School. **Watteau, Fragonard*.

XI. Room. Modern French School. A large unfinished oil-painting by *David* (d. 1825) preserved here represents the Revolutionary meeting at the Jeu de Paume (p. 289). One of the four finished heads is that of Mirabeau. The painting was ordered by the National Convention in 1790.

XII. Room. Miniatures, paintings on porcelain, **Enamels* by *Petitot*, etc.

XIII. Room. Drawings of the early French School. Opposite the window a large drawing upon silk, presented as an altar-cloth to the cathedral of Narbonne by Charles V. of France (d. 1380); fine furniture.

XIV. Room. Crayons, chiefly portraits, by *Perronceau, Chardin*, etc. In the centre stands a valuable writing-table in the style of Louis XV.

A supplementary saloon containing drawings (*Salle des Boîtes*), on the second floor, is open daily except Sun. and Mon., after 2 o'clock (see p. 148).

The Collection Thiers, a collection of works of art bequeathed to the Museum by the ex-president of the Republic, occupies two rooms adjoining the last of the Collection of Drawings. Of the 1470 very miscellaneous objects (catalogues) the majority are small, and few are of much importance. They include *Antiquities*, *Terracottas* (33-35, in the glass-case to the left), *Bronzes* (113, 110. Busts; 109. Alto-relief; 12. Equestrian statuette; 126. *Perseus*), *Marbles*, *Carved Ivory* (153. Loving-cup; 15. St. Sebastian) and *Wood* (169. *Ecce Homo*; 170. Charles V.), *Marquetry* (door), *Carvings*, *Venetian Glass* (209), *Copies of Pictures*, *Chinese and Japanese Articles*, *Porcelain*, *Snuff-boxes*, *Enamels*, and *Miniatures*. In the first room is a *Portrait of Thiers, by *Bonnat*.

Adjoining is the *Donation His de la Salle*, a valuable collection of upwards of 300 drawings by old masters. This gallery leads to the end of the following collection.

Adjoining the Collection of Drawings is the ***Collection of Smaller Mediæval and Renaissance Antiquities** (*Musée des objets d'art du Moyen-Age et de la Renaissance*), which may also be reached by a staircase ascending from R. IV. of the Asiatic Museum (p. 95).

I. Room. *Venetian and German Glass* of the 15-18th centuries. To the left, on the wall, is a *Glass Mosaic*, representing the lion of Venice, executed by *Antonio Fasolo* at Murano in the 16th century. — On the rear wall: Ebony cabinet. Tapestry from Beauvais and designs for tapestry by Boucher (40, 48) and Coypel (176).

II. Room. *Ivory Carving* of the 14-18th cent., some of it very valuable. Opposite the window is an **Altar-Piece* from Poissy, about 7 ft. in height, executed at the end of the 14th cent.: in the centre is the history of Christ, on the left that of John the Baptist, on the right that of St. John the Evangelist, in 71 different reliefs; below are the Apostles. Magnificent Renaissance furniture. Fine tapestries from the Collection Davillier, notably a Coronation of the Virgin, perhaps after Memling.

III. Room. Flemish and German Earthenware, of the 16-17th centuries.

IV. Room, formerly containing metal-work, is at present empty. On the rear wall is fine tapestry, with the History of St. Stephen (15th cent.).

V. Room. *French Faïence*, including specimens of the famous work of *Bernard Palissy* (d. 1589), which chiefly consists of dishes adorned with snakes, frogs, lizards, fish, and plants moulded from nature. The finest antique French pottery is known as '*Faïences Henri Deux*' (specimens by the 1st window); it was manufactured in the 16th cent. at Oiron in Poitou. In the middle of the room, Child with a cage, a small marble sculpture by *Pigalle*. At the end, the '*Tapisserie du Louvre*', representing a miracle of St. Quentin, by which a robber who had stolen the priest's horse, escaped the gallows.

VI. and VII. Rooms. *Hispano-Moorish* and *Italian Faïence*. The former, chiefly in R. VII., is recognized by its Oriental designs, yellow metallic background, and blue patterns; it dates from the 14th and 15th centuries. Blue also prevails in the Italian faïence, but the metallic yellow is absent. Italian majolica painting attained its zenith in the reign of Duke Guidobaldo II. of Urbino (1538-74), who took a special interest in this branch of art. The chief manufactories were at Urbino, Pesaro, and Gubbio. The designs were frequently drawn by Raphael and his school, and widely circulated in the form of engravings. The finest pieces are two large dishes on the wall at the back, numbered G, 347 and G, 348. — The furniture in these rooms also deserves notice.

VIII. Room. Painted terracotta reliefs by *Luca della Robbia* and his school, Florence, 15th century, the best of which is G, 719 (to the left), a Madonna and Child. Some also in Room VII.

From this room a staircase ascends to the 2nd floor (p. 146).

Leaving Room VIII. by the door at the end we reach the top of the staircase leading to the Asiatic Museum (p. 95). We turn to the right and enter the rooms of the East Wing.

The two first rooms are occupied by the *Collection Dieulafoy* and the *Collection de Sarzec*. The former, by far the more important, consists of antiquities brought from Susistan (Persia) by M. and Mme. Dieulafoy, the latter of antiquities from Chaldæa.

I. Room. Græco-Babylonian statuettes and other sculptures; inscriptions; cylinders of great delicacy; glazed tiles from Babylon; fragments of bronzes; Chaldæan antiquities, inscriptions, and votive bronzes; fine Assyrian bronze lion, with a ring in its back.

II. Room. 1st Section: in the middle, plans of the tumuli in Susistan and Chaldæa where the antiquities were found; on the entrance-wall, magnificent frieze of enamelled clay, 40 ft. long and 13 ft. high, representing the archers of the 'immortal guard' of Darius; to the left, stair-railing from the palace of Artaxerxes Mnemon, also in burned clay; on the partition-wall, the crowning-ornaments of the pylons of this palace, with lions in the same material; on the right side, fragments of a bath and terracotta

vases. — 2nd Section: At the back, *Capital of one of the 36 columns (each 68 ft. high), which supported the roof of Artaxerxes's throne-room; in the other cases, glass, small terracottas, cut stones; cylinders from Susistan, Chaldæa, and Assyria; rings, medals, including a magnificent silver tetradrachma of Eucratides, etc.

III. Room. Continuation of the above collection, not yet arranged.

IV. Room or *Salle du Dôme*. Miscellaneous objects, placed here provisionally. In the glass-cases to the left, small bronzes; farther back, dishes and platters in zinc by Fr. Briot, and clocks of the 16-17th centuries. Beside the last two windows, magnificent weapons, shields, cuirasses, and armour. At the middle window, fine locksmiths' work; medals and metal bas-reliefs; knives and similar implements, watches, etc.

V. Room, with the *Don Lenoir, bequeathed to the Museum in 1877, and consisting chiefly of small objects of art of the 18th century. Interesting collection of 204 snuff and bonbon boxes, with porcelain-paintings by or after the first French masters: *Augustin, Blarenbergh, Boucher, Dumont, Aubry, Greuze, Hall, Petitot*. — At the 1st window, magnificent terracottas by *Clodion*. — At the 2nd window, articles from the Collection Sauvageot, formerly in the Musée de la Renaissance; medallions in coloured wax; bas-relief in lithographic stone by *Aldegrevier*; excellent wood-carvings, chiefly German workmanship of the 16-17th centuries.

VI. Room. Portrait of Henri II.; silk tapestry of the 16th cent., with scenes from the history of the Judges; fine wood-carving; German, Swiss, and French stained glass, of the 16th and 17th centuries. — Recently acquired paintings, provisionally placed here: Portraits, etc. of the *French School*, including General Bertrand by *Delaroche*; alleged portrait of Edward IV. of England, ascribed to *Ant. Mor.*; fine triptych of the *Flemish School*, Virgin and Child, with the donors and their patron-saints. — At the windows are two glass-cases, belonging to the Don Lenoir.

VII. Room, with alcove, in which Henri IV. breathed his last. The wood-carving is from the rooms of Henri II. in the Louvre, and was restored in the reign of Louis XIV. The stained glass is Swiss and French, of the 16th and 17th centuries. — Recent acquisitions: Venetian bed of state (15th cent.); bronze bust of Michael Angelo and wooden altar-screen of the Milanese school of the 16th cent.; Head of St. Elizabeth by *Raphael*; Italian folding-chair (16th cent.); inlaid woodwork (15th cent.); statue of St. Christopher, ascribed to *Verrocchio* (15th cent.); Virgin adoring the Child, terracotta bas-relief by *Donatello*.

VIII. Room. Portraits of Louis XIII. and his queen Anne of Austria, by *Phil. de Champaigne*; five large vases of Sèvres porcelain; silver statue of Peace, by *Chaudet*; small bronze group (18th cent.), Jupiter destroying the Titans; four Moorish saddles, ornamented with gold, coral, and turquoises.

On leaving this room we find ourselves at the top of the staircase of the Musée Egyptien, opposite the room containing the smaller antiquities. The staircase descends to the collection of Egyptian statues, and to the exit in the Place du Louvre (p. 92).

We re-traverse the rooms of the Egyptian Museum, until we reach the last, the *Salle des Colonnes*, whence we enter the —

Collection of Greek Antiquities (*Musée des Antiquités Grecques*), formerly the *Musée Charles X.* This collection, the Musée Campana (p. 145), and the Collection of Mediæval Antiquities (p. 142), together afford an almost complete survey of the progress of the potter's art. If we enter by the *Salle des Sept-Cheminées* (p. 139) it is better to inspect the Musée Campana before the Grecian antiquities.

I. Room. Vases with black and violet painting, including some Panathænean amphoræ. In the central glass-case: terracottas from Tarsus in Cilicia, brought thence by Langlois. Entrance-wall: to the right, Vase with execution of Cræsus; to the left, Hercules fettering Cerberus. In the middle, archaic amphora by Andocides, with warriors and a cithar-player. Exit-

wall: Vase with Argonauts, The birth of Athena. — Ceiling-painting by *Picot*: Cybele saving Pompeii and Herculaneum from total destruction.

II. Room. In the wall-cabinets: Small Greek terracotta articles from Tanagra in Boeotia. The best are a *Group of dancing Cupids and *Female figures with painted hair, in the cabinet to the right of the exit. The round central case contains pottery from the necropolis of Athens and from Liha (the Roman province of Cyrenaica); upon it is placed an *Amphora with the contest of the gods with the giants. — Ceiling-painting by *Meynier*: The Nymphs of Parthenope (Naples) arriving at the Seine.

III. Room. Vases with red figures, some of large size. In the window-cases: Roman lamps, cameos, and several *phaleræ*, the distinctive breast-ornament of the Roman warriors. — Ceiling-painting by *Heim*: Jupiter delivering to Vulcan the fire for the destruction of Herculaneum and Pompeii.

IV. Room. Small sculptures and fragments of others. In the central cases: Antique ivory carvings; Greek terracottas and wood-carvings, etc. — In the first window-case; *Phaleræ*; cameos, etc. — Ceiling-painting after *Ingres*: Apotheosis of Homer (original, see p. 135).

The door of exit leads into the *Salle des Sept-Cheminées* (p. 139), whence we proceed to the left into the —

Musée Campana, consisting of the valuable Campana collection purchased from the papal government in 1861, and subsequently much extended. The principal divisions are indicated by labels; and some of the most interesting objects have descriptions and explanations attached. The ceiling-paintings were executed when the pictures of French artists were exhibited here.

I. Room. *Asiatic Antiquities*. Large archaic craters and amphora put together from fragments. In the glass-cases in the centre: Golden ornaments, terracottas, and vases. In the other cases, from left to right: Terracottas, statuettes, heads of statues, pottery from Rhodes, etc. — Ceiling-painting by *Alaux*: Poussin being presented to Louis XIII. by Cardinal Richelieu; to the left Truth, to the right Philosophy.

II. Room. *Greek Terracottas*, from Athens, Magna Graecia (Lower Italy), and from the necropolis of Myrina, near Smyrna: Statuettes and bas-reliefs; Cists, ornamented with statuettes and bas-reliefs; Vases adorned with figures. — Ceiling-painting by *Steuben*: Battle of Ivry, with Henri IV. as a magnanimous victor.

III. Room. *Etruscan Pottery*, beginning with vases of the rudest type, black, with engraved designs; also the earliest attempts at reliefs (found in tombs). — Ceiling-painting by *Eug. Devéria*: Louis XIV. inspecting Puget's marble group of the Milo of Croton (p. 108).

IV. Room. *Etruscan Antiquities*. In the centre: *Sarcophagus, on which are two painted lifesize figures of a man and woman on a couch, clumsy in execution, but not without a certain naïve humour. Most of the terracottas were found at Cervetri, the Cære of the ancient Etruscans. In the glass-cases, small 'funereal couches', bas-reliefs, vases, and paintings found in a grave. — Ceiling-painting by *Fragonard*: Francis I. receiving pictures and statues brought by Primaticcio from Italy.

In the adjoining passages are antefixæ, heads, and vases.

V. Room. *Vases in the Corinthian Style* from the Grecian Archipelago and Italy. Greek vases formed an article of export from an early period. Similar vases also in the Collection of Greek Antiquities (see above). — Ceiling-painting by *Heim*: The Renaissance in France.

There is no difficulty in distinguishing the Greek vases from those manufactured in Etruria, which are inferior in form and workmanship, and display designs of a different style. Among the *Greek Vases* themselves there are also many differences. The *earlier* are those with black figures on a red ground, the *later* those with red figures on a black ground. They have of course no pretension to rank as works of art, being mere manufactures. And yet these vase-painters have depicted mythological and everyday scenes with such spirit and poetry, and produced such pleasing scenes with the humble means at their disposal, that their vases

(though sometimes despised by the ignorant) bear striking testimony to the flourishing condition of the Attic handicrafts, and thus afford us an idea of the great Athenian works of art which these simple artificers must have had before their eyes.' *Kekulé.*

Traversing another short passage, with archaic Greek vases, we next enter the —

VI. Room. *Older Greek Vases.* In the centre of the room, vases bearing the name of *Nicosithenes*. Vases with white background; above, black vase with white figures. Most of the scenes are from the myths relating to Hercules and Theseus. At the first window, to the left, Goblet of *Nicosithenes*, with the ship of Ulysses passing the sirens. — Ceiling-painting by *Fragonard*: Francis I. knighted by Bayard.

VII. Room. *Later Greek Vases*, many of which bear the name of the maker. In the glass-case in the centre: Amazons arming, on an amphora bearing the name of Andocides; two large bowls (*Crateræ*), with the combat between Hercules and Antæus, and Apollo slaying Tityus when in the act of carrying off Latona. — At the window: several beautiful Greek goblets. — Ceiling-painting by *Schnetz*: Charlemagne and Alcuin, the founder of the university of Paris.

VIII. Room. *Graeco-Italian Vases.* In the centre are Rhyta or goblets in the form of horns, with heads and other ornaments, and other vases of curious shapes. Round the room are black vases, with a greenish glaze, to imitate bronze. — *Ceiling-painting by *Drolling*: Louis XII. hailed as father of the people by the Estates at Tours.

IX. Room. *Mural Paintings from Herculaneum and Pompeii.* In the glass-case in the centre: Antique glass objects from Pompeii. — Ceiling-painting by *Léon Cogniet*: Bonaparte in Egypt.

The exit-door leads to the staircase of the Musée Egyptien (p. 92), whence we reach the nearest staircase to the second floor by re-traversing the rooms in which the small Egyptian antiquities are exhibited (p. 144).

C. SECOND FLOOR.

The second floor of the Louvre, which contains the Marine and the Ethnographical Museums, some pictures not yet removed to the first floor, and a collection of drawings, is open to the public after 11 a.m. (comp. p. 89). There are three staircases ascending to the second floor: — (1) From the 8th room of the collection of smaller Mediæval and Renaissance objects (p. 143), which is reached from the ground-floor by a staircase near the Assyrian Museum; (2) From the 5th room of the drawings (p. 142); and (3) From the corridor which is reached by the staircase in the Pavillon de l'Horloge or Pavillon Sully (see p. 141).

On ascending the first of the above-mentioned staircases we see in front of us two new rooms of the *Musée de la Marine*, containing water-colours of vessels, drawings of ornaments from ancient vessels, models of steam-engines, and a relief-plan of the Panama Canal. Adjoining is a *Salle Supplémentaire du Musée de Peinture*, containing the remaining pictures of the French, Flemish, and Dutch schools (Snyders, Champaigne, Van der Werff, Bakhuizen, Everdingen, Wouwerman, etc.).

We then return to the main part of the Marine Museum.

The **Musée de la Marine* is a very valuable collection of various objects connected with ship-building and navigation, such as models of vessels and machines, plans of harbours in relief, drawings,

and relics of historical interest. Most of the models of ships are one-fortieth of the actual size.

I. CORRIDOR, adjoining the staircase, models of merchant-vessels, etc.

I. ROOM. The French navy 1786-1824. Model representing the taking down and embarkation of the obelisk of Luxor (p. 82); Erection of the obelisk in the Place de la Concorde.

II. ROOM. Models of various kinds. Machine for adjusting the masts of a ship. Relief-plan of the town and harbour of Brest.

III. ROOM. Models of pumps and machines; Ship in the stocks about to be launched; Relief-plan of the town and harbour of Lorient; Model of the 'Valmy', a ship of the line of the first class.

IV. ROOM. Large model of a ship of the line (120 guns); Armour-plates; Saw-mills; Pumps; Rigging.

V. ROOM. The 'Rivoli' (3rd class warship) leaving the harbour of Venice with the aid of 'chameaux' or rafts to aid it over shallows; Breach-loading cannon; Drags.

VI. ROOM. Large obelisk composed of relics of the frigates 'Bonsole' and 'Astrolabe', which had been sent on a voyage of discovery under *Captain de Lapérouse* in 1788, and foundered at sea. Traces of the ill-fated expedition having been discovered by the English Captain Dillon in the island of Ticopia in 1828, with the aid of an inhabitant who had once been a Prussian sailor, a French vessel was despatched for the purpose of bringing home the relics. Letter written by Lapérouse. Busts of celebrated French navigators and naval heroes; among them, one of Lapérouse. Model of a monument erected to the memory of Lapérouse at Port Jackson, with English and French inscriptions.

VII. ROOM. Large model of the 'Océan', a man-of-war of the 18th cent., with 120 guns. Numerous interesting models of iron-clads, turret-ships, torpedoes, etc.

VIII. ROOM. Models of ships. Model of apparatus used in excavating a dry-dock at Toulon in 1776-78.

IX. ROOM. Two relief-plans of Toulon dating from 1790 and 1850. Representation of the interior of the turret-ship 'Marengo' (1867). Compasses; rudders; cables; rigging.

X. ROOM. Fire-arms of various calibres. 'Orgues' with five and seven barrels.

XI. ROOM. Mathematical Instruments. Large geographical globe. Key of the fortress of Sfax (1881).

XII. ROOM. Models of galleys. Model of 'La Réale', an admiral's ship built near the end of the 17th cent. and artistically adorned by the sculptor *Puget* (p. 108). The original carving in gilded wood hangs on the wall. Relief-plan of the town and harbour of Rochefort.

XIII. ROOM. Models of the dwellings of the natives of New Guinea, New Zealand, and the Tonga Islands. Model of Cherbourg breakwater. Ethnographical collection.

XIV. ROOM. Careening a frigate. Pirogues and masks from New Caledonia.

II. CORRIDOR, the *Galerie des Pirogues*, connecting ROOM VII. with the Ethnographical Museum (see below), contains models of Arab, Indian, Chinese, Australasian, and American ships and boats.

The **Ethnographical Museum** (*Musée Ethnographique*) is devoted almost exclusively to curiosities brought home by French navigators and the spoil captured in the course of military expeditions in India, China, and Japan. Vessels and utensils in gold and silver, Indian idols, pictures, statuettes, trophies, stuffs; musical clock of the dey of Algiers (made in London); model of the pagoda of Juggernaut in India, surmounted by an image of Vishnu, the principal deity of the Hindoo triad, to whose shrine every believer must make a pilgrimage once at least in his life.

The **Chinese Museum** (to the left on leaving the Marine Museum) occupies three rooms, and part of a fourth called the 'Salle de Lesseps'.

I. Room. Paintings, drawings, beds, furniture, screens decorated with carving, arms, musical instruments, statues of porcelain, ship elaborately carved in ivory, books, albums, etc.

II. Room (to the right of the first). Arms, musical instruments, porcelain, enamels, statues, chest gilded and varnished, with numerous statuettes; furniture of all kinds; books and albums; trays with figures carved in coloured ivory; coloured drawings.

III. Room (adjoining the first). *1st Glass-Case*: objects in ivory, including a ball containing six or seven others, exquisitely cut, chessmen, statuettes in wood, enamels, bamboo boxes, caskets, etc. — *2nd Case*: enamelled vases and other objects; bronzes, including two hand-bells, a buffalo bearing a vase, and a tray inlaid with silver; vases and small figures in precious stones. — *3rd Case*: lacquered articles, objects in bamboo, rock crystal, etc., women's shoes. — In the centre: "Three ancient enamelled tables and antique enamelled bronze perfume-burners.

IV. Room (*Salle du Canal de Suez, or Salle de Lesseps*). Against the wall, by the entrance, the god Sei-jin, the dispenser of wealth; the god Wen-chan, in wood, seated on a gilded throne; Buddha on a throne; the whole placed on a large cabinet of gilded wood, carved and varnished, with numerous figures. The glass-cases contain articles of dress and objects in porcelain. In the centre is a relief-plan of the Suez Canal, on a scale of 6 centim. to the kilomètre (6:100,000). On the window-wall are hung views connected with the canal. Beyond the plan are placed models of the apparatus used in excavating the canal. — On the farther side of the room are a cannon from Cochin China in the form of a monster, and the ill-favoured goddess Kouanyin, in gilded copper, in a large niche of carved wood.

Leaving the Salle de Lesseps, we enter a corridor, which is adjoined by the **Salle des Boites** on the right. This saloon and the corridor contain the most valuable drawings by *Raphael, Michael Angelo, Leonardo da Vinci, Titian, Poussin, Albert Dürer, and Holbein*, preserved in wooden cases (whence the room derives its name). Admission on Sat. only, 2 to 4 or 5 o'clock. The direct approach to this collection is by the staircase called the *Escalier Henri II.* in the Pavillon de l'Horloge (p. 88), by which we leave the museum.

III. THE TUILERIES.

Arc de Triomphe du Carrousel.

The vast open space between the Louvre and the Tuileries was occupied at the time of the first Revolution, and down to nearly the middle of the present century, by a labyrinth of narrow streets, which Louis Philippe, the first monarch who projected extensive city improvements, began to remove. The work of demolition was completed by Napoleon III., and the space thus cleared was divided into three parts (comp. ground-plan, p. 88): the *Square du Carrousel*; the *Place du Carrousel*, which adjoins it on the W.; and the *Cour des Tuileries*.

The **Monument of Gambetta**, in front of the square, consists of a lofty stone pyramid with a group in high relief representing Gambetta (1838-1883) as organiser of the national defence, in bronze by *Aubé*. At the sides are decorative statues of less impor-

tance representing Truth and Strength, and on the top is Democracy (a maiden seated on a winged lion), also in bronze, by Aubé. The numerous inscriptions are chiefly passages from Gambetta's political speeches.

The **PLACE DU CARROUSEL** (Pl. R, 17, 20; II), formerly much smaller than now, derives its name from a kind of equestrian ball given here by Louis XIV. in 1662. Although lying between the two palaces it is open to general traffic, and generally presents a lively and bustling appearance. On this site Napoleon I. directed his architects *Fontaine* and *Percier* to erect the ***Arc de Triomphe du Carrousel**, in imitation of the Arch of Severus at Rome, to commemorate his victories of 1805 and 1806. The structure, which was formerly the principal entrance to the Tuileries, is 48 ft. in height, 63½ ft. in width, and 21 ft. in thickness, but in consequence of the immense clearance that has taken place since its erection it is now too small to harmonise with its surroundings. (The Arch of Severus is 75 ft. in height and 82 ft. in width.)

The arch is perforated by three arcades and embellished with Corinthian columns of red marble with bases and capitals in bronze supporting marble statues representing the soldiers of the empire.

The *Marble Reliefs* on the sides commemorate the achievements of the Emperor and the French army. In front: on the right, the Battle of Austerlitz; on the left, the capitulation of the Austrian general Mack at Ulm. At the back: on the right, the conclusion of peace at Tilsit; on the left, entry into Munich. On the N. end, the entry into Vienna; on the S. end, conclusion of peace at Pressburg.

The arch was originally crowned with the celebrated ancient Quadriga from the portal of St. Mark's in Venice, brought thence as a trophy, but sent back to Venice by Emperor Francis in 1814. It was afterwards replaced by order of Louis XVIII. by a **QUADRIGA** designed by *Bosio*, and intended to represent the 'Restoration'.

The **Palais des Tuileries**, begun in 1564 by Catherine de Médicis, widow of Henri II., and the constant residence of the French rulers from the time of Napoleon I., exists no longer. The original plan, by *Philibert Delorme*, was on a very extensive scale, but little of it was ever carried out. The wings were added by Henri IV. and Louis XIV. In 1871 the palace was set on fire by the Communists, and the ruins, after standing untouched for 12 years, were finally removed in 1883. The only parts of the building still extant are the wings which connected it with the Louvre. That on the side next the river, containing the *Pavillon de Flore*, was restored in 1863-68 and again after the fire of 1871, in which it sustained little damage. The right wing, in the Rue de Rivoli, with the *Pavillon de Marsan*, was entirely burned down in 1871 and was rebuilt in 1875-78; but the interior is still unfinished and unoccupied.

The palace derived its name from the tile-kilns (*tuileries*), which originally occupied its site. It presented no great architectural interest, but was rich in historical associations, especially those connected with the overthrow of the French monarchy in 1791-92. Before the Revolution the Tuileries formed only an occasional residence of the French sovereigns. On 5th. Oct., 1789, *Louis XVI.* was brought by the 'Dames de la Halle' from Versailles to the Tuileries, and in June, 1791, he was again forcibly

installed in this palace after the arrest of his flight at Varennes. On 20th July, 1792, the anniversary of the meeting in the Jeu de Paume (p. 289), the palace of the Tuileries was attacked by a mob of about thirty thousand rioters armed with pikes, but on that occasion they contented themselves with threatening and insulting the king. On 10th August the storm at length burst forth in all its fury. At midnight alarm-bells began to ring in the suburbs. Thousands of armed men marched to the palace. The fidelity of the national guard posted in the palace-yard and garden began to waver, and they were deprived of their commanding officer by stratagem. They might, however, in conjunction with the Swiss guard of 1950 men commanded by Colonel Pfyffer, have successfully defended the palace, had not the king, yielding to solicitations which were in some cases treacherous, quitted the palace with his family. Passing through the garden of the Tuileries, he repaired to the *Manège*, or riding-school (see p. 83), where the legislative assembly held its meetings. The national guard then dispersed, but the Swiss guard and about 120 noblemen who were faithful to the king occupied the palace and refused to surrender it. As the mob pressed forward more vehemently, the colonel commanded his men to fire, and the palace-yard and Place du Carrousel were speedily cleared. The Swiss guard now believed that victory was assured, but the king sent orders to them to discontinue firing and to surrender the palace. Finding that the guard ceased to fire, the assailants renewed their attack and reopened their fire with redoubled vigour. Within a few seconds they inundated the palace, killed every man they encountered, wrecked the furniture and fittings, and stole or carried to the Hôtel de Ville numerous objects of value. The retreating-Swiss guard were almost all shot down in the garden, and the rest by order of Louis gave up their arms to the national guard in the hall of the national assembly. The Revolution was victorious. Of the hitherto existing state-structure not one stone was left on another. Royalty lay prostrate in the dust, and the legislative assembly continued to exist merely in name. — The king and his family spent the night in a small room in the *Manège*, and on 13th Aug. he was conveyed as a prisoner to the Temple Tower (p. 71), whence he was only released to be led to the scaffold.

From 10th May, 1793, to 4th Nov., 1796, the *Convent*, and afterwards the *Council of Elders* down to 1799, held their meetings in the N. wing. On Feb. 1st, 1800, Napoleon, as 'First Consul', took up his quarters here, and the palace also became the official residence of the Restoration and July monarchies. On 24th Feb., 1848, *Louis Philippe* abandoned the palace to the mob without resistance. Napoleon III. resided here from 1852 to 23rd July, 1870, when he quitted Paris to take the command of the army of the Rhine. The history of the Tuileries as a royal residence closes with the departure of the Empress Eugénie after the battle of Sedan.

On 20th May, 1871, the Communists, aware of their desperate position and the impending capture of the city by the government troops, determined at one of their secret meetings to wreak their revenge by setting all the principal public buildings on fire. The orders which they issued for this purpose, signed by Delescluze, Dombrowski, Eudes, and other ringleaders, professed to emanate from the '*Comité du Salut Public!*' Several of these documents still extant show the fearfully comprehensive and systematic character of this diabolical scheme, which also embraced numerous private dwellings, as being 'maisons suspectes'. A beginning was made with the Tuileries, which was prepared for destruction by placing combustibles steeped in petroleum and barrels of gunpowder in the various rooms. It was set on fire at a number of different places on 22nd and 23rd May, after the Versailles troops had forced an entrance into the city, but before they had gained possession of the palace. The conflagration soon assumed the most terrible dimensions, and all attempts to extinguish it were fruitless. The whole of the W. side of the palace was speedily reduced to a gigantic heap of smouldering ruins. All thoughts of rebuilding the palace were soon given up, and its site is now laid out in gardens.

On the pillars outside the large archways leading from the Place du Carrousel towards the Seine, are statues of Naval and Merchant Shipping. At the top is a bronze relief, by *Mercié*, representing the Genius of the Arts. — Pont du Carrousel, see p. 262. — The next bridge is the Pont des Arts (p. 244), whence the sculptures on the S. façade of the Pavillon de Flore, especially those by Carpeaux, are best seen.

The **Jardin des Tuileries* (Pl. R., 18; II), the most popular promenade in Paris and the especial paradise of nursemaids and children, was enlarged in 1889 by the addition of the gardens occupying the actual site of the former palace. The older portion retains the same general features as when first laid out by the celebrated landscape-gardener *Le Nôtre* in the reign of Louis XIV.; but the parts between the palace-site and the central basin, formerly the 'Jardin Reservé', are of later origin and the *Rue des Tuileries* here was made in 1871. At the S. end of the last are two marble sphinxes from Sebastopol.

The greater part of the Jardin des Tuileries is always open; but the reserved portion closes between 6 and 9 p.m., according to the season, the signal being given by a bell. The gardens may be entered from the Rue des Tuileries, the Rue de Rivoli, the quays, or from the Place de la Concorde at the W. end. At the W. end, beyond the flower-beds is a shady grove of large trees. On the N. and S. sides the garden is enclosed by terraces, called the *Terrasse des Feuillants* and the *Terrasse du Bord de l'Eau*. The first derives its name from a Monastery of the Feuillant Order (reformed Cistercians), founded here in 1587 (nine years after the establishment of the order at Feuillant near Toulouse), and still existing at the time of the Revolution. The club of the moderate party, founded in July, 1791, by Lameth, Lafayette, and their partizans, in opposition to the more violent Jacobins, used to meet in the monastery, whence they became known as '*Les Feuillants*'. The *Allée des Orangers*, which skirts the terrace, is adorned in fine weather with two rows of orange-trees in tubs, forty-one of which date from the time of Francis I. (1494-1547). The S. terrace, formerly the playground of various youthful princes, commands an excellent view of the Seine.

Entering the garden from the Rue des Tuileries by the broad central walk, we obtain a fine view of the whole garden, with the Obelisk in the Place de la Concorde and the Arc de l'Etoile in the background. On the right and left are grass-plots with two circular basins of water, embellished with marble statues and vases.

On the right: Omphale, by *Eude*; Æneas carrying his father Anchises from the flames of Troy, by *P. Lepautre*; a Bacchante, by *Carrier-Belleuse*; behind, Venus with the dove, and Nymph with the quiver, by *Guill. Coustou*; Lion and crocodile, bronze by *Cain*. In the allée beyond the rondel: Diana and the Nymph of Fontainebleau, by *E. Lévêque*. On the left: a Corybante, by *Cugnot*; Lucretia and Collatinus, by *Lepautre*; New Year's Day, by *Beaumeval*; behind, Flora and Zephyr, by *Coyzeux*; on the lawn, Death of Lais, by *Meunier*, and a bronze lion and peacock, by *Cain*. Around

the central basin are the following statues, enumerated from right to left: Orithyia carried off by Boreas, by *Duquesnoy* and *De Marsy*; Themistocles, by *Lemaire*; Alexander the Great, by *Dieudonné*; Prometheus, by *Pradier*; Soldier tilling the ground (from Virgil), by *Lemaire*; the Oath of Spartacus, by *Barrias*; Cincinnatus, by *Foyatier*; Alexander fighting with a lion, by *Lemaire*; Fraternal Love, by *Conny*; Pericles, by *Debay*; Cybele carried off by Saturn, by *Regnaudin*. In the transverse walk to the left: Comedy, by *Roux*; Aristotle, by *Desgeorge*; the Grinder, after the Florentine antique; Phidias, by *Pradier*. In the walk to the right: Masque, by *Cristophle*; Aurora, bronze figure by *Magnier*; Ugolino, in bronze, by *Carpeaux*; Silence, by *Legros*. — At the beginning of the Allée des Orangers: Return from the hunt, bronze, by *An'. Carlés* (1888); at the flight of steps opposite the street leading to the Vendôme Column (p. 84), two groups of animals, by *Cain*; at the end, Hercules subduing the Hydra, in bronze, by *Bostio*. Other sculptures are placed in the grove, etc. On the Terrasse du Bord de l'Eau, near the Orangerie, bronze lion and serpent, by *Barye*.

Under the trees of the small grove, on the right and left of the broad central walk, are two marble semicircular platforms called the *Carrés d'Atalante*, constructed in 1793, in accordance with the instructions of Robespierre, for the accommodation of the council of old men who were to preside over the floral games in the month of Germinal (21st March to 19th April). On that to the right is a group of Atalanta and Hippomenes by *G. Coustou*, and on that to the left, Apollo and Daphne by *Théodon*. — In summer a military band plays near this spot on Sun., Tues., and Thurs. from 4 to 5 or 5 to 6 p.m. Chair 10 c., arm-chair 20 c.

At the W. end of the grove is an octagonal basin, 200 yds. in circumference, with a fountain in the centre. On the E. side are marble statues of the four seasons: on the right, Summer and Winter; on the left, Spring and Autumn. On the W. side are four groups of river-gods: on the left, the Nile, by *Bourdier*, and the Rhine and Moselle, by *Van Cleve*; on the right, the Rhone and Saône, by *G. Coustou*, and the Tiber by *Van Cleve*. The Nile is from an antique in the Vatican, the Tiber from one in the Louvre (p. 103). The temporary building to the left contains the *Panorama of the History of the Century* (1789-1889), by Stevens and Gervex (adm. see p. 32). At the ends of the terraces are, to the right a *Tennis Court* (ball-room), to the left, an *Orangery*.

The pillars at the entrance to the garden from the Place de la Concorde are crowned with two handsome groups of Mercury and Fame on winged steeds, by *Coyzevox*. — Description of the *Place de la Concorde*, see p. 81.

3. From the Place de la Concorde to the Bois de Boulogne, and back by the Trocadéro.

This excursion is arranged on the assumption that the visitor starts in the morning. If, however, he is later in setting out, he should go first from the Place de la Concorde or the Champs-Élysées to the Trocadéro, after which he will have an opportunity of seeing the Bois and the Champs-Élysées under their most animated aspect. On Mon. both the museums at

the Trôcadéro are closed, on Sun. and Thurs. both are open. They may, however, also be visited in combination with the excursion to the Invalides, which absorbs less time.

Those who wish to go direct to the Bois de Boulogne may proceed by the Chemin de Fer de Ceinture, with stations at the Porte Maillot (p. 157), at the Avenue du Bois de Boulogne (p. 157), at Passy (p. 162), at the Avenue Henri Martin (Trôcadéro, p. 162), and at Auteuil (p. 162). Or they may take the tramway or omnibus (see Appx.). On days, however, when races or reviews are held, and even on fine Sundays, it is impossible to secure a place in the omnibuses and tramway-cars bound for the Bois without much waiting. — Luncheon may be taken in the Champs-Élysées or at the Bois (see pp. 13, 15).

I. FROM THE PLACE DE LA CONCORDE TO THE PLACE DE L'ÉTOILE.

Place de la Concorde, see p. 81. On the W. side of this Place begin the ***Champs-Élysées** (Pl. R, 15; II), under which name is now included not only the small park adjoining the Place, about 750 yds. long by 400 yds. wide (the Champs-Élysées proper), but also the whole of the avenue, extending from the Place de la Concorde to the Arc de l'Étoile, $1\frac{1}{3}$ M. in length, by which these grounds are traversed. The grounds were originally laid out and planted with elms and lime-trees at the end of the 17th century.

This magnificent avenue, which is flanked with handsome buildings, is one of the most fashionable promenades in Paris, especially between 3 and 6 or 7 o'clock, when numerous carriages, riders, and pedestrians are on their way to and from the Bois de Boulogne. The end next the town abounds with the attractions of cafés-chantants (p. 33), jugglers, marionettes (or *Théâtres de Guignol*), shows, cake-stalls, restaurants, etc. These various entertainments are most popular towards evening, by gas-light, and are in great request till nearly midnight. The traveller will have an opportunity here of witnessing one of the characteristic phases of Parisian life. The less frequented parts are better avoided after dusk.

At the entrance to the Champs-Élysées are placed two figures of *Horse-tamers*, by *Coustou*. They were removed in 1794 from the palace at Marly (p. 311) to their present position, where they form a suitable counterpart to the winged steeds at the exit of the Jardin des Tuileries (p. 152). The small and tasteful drinking-fountains, which we notice in the Champs-Élysées, and many others of the same kind throughout the city, were erected by the well-known philanthropist *Sir Richard Wallace* (d. 1890).

To the right, separated from the Champs-Élysées by a large garden, is the **Palais de l'Élysée** (Pl. R, 15; II), erected by *Molet* in 1718 for the Comte d'Evreux, and now the official residence of the President of the Republic (no admission).

During the reign of Louis XV. this mansion was the residence of *Madame de Pompadour*, from whose heirs it was purchased by the king to form a residence for the foreign ambassadors. Under Louis XVI. the palace acquired the name of *Élysée Bourbon* from its prolonged occupation by the *Duchesse de Bourbon*. During the Revolution the palace was offered for

sale, but, no purchaser offering, it was converted into a government printing-office. At the time of the Directory the rooms were let to keepers of public ball-rooms and gaming-tables. The palace was afterwards occupied in turn by Murat, Napoleon I., Louis Bonaparte, king of Holland, and his queen Hortense, Emperor Alexander I., of Russia, and the Duc de Berry. The building was left uninhabited after the Revolution of 1830, until Napoleon III. took possession of it as President of the French Republic, enlarging and improving it considerably.

On the S. side, the Champs-Élysées have been compelled to yield a considerable space to the **Palais de l'Industrie** (Pl. R, 15; II), a large building, erected in 1855 for the first Great Exhibition at Paris. The building is rectangular in form, 270 yds. in length, 118 yds. in width, and 114 ft. in height. The handsomest part is the pavilion in front, towards the avenue occupying nearly one-third of the whole length. An arcade 48 ft. in width and 98 ft. in height here forms the principal entrance, which is flanked with Corinthian columns and surmounted by an attic with a bas-relief by *Desbœuf*, representing Industry and the Arts bringing their products to the exhibition. On the summit is a fine colossal group by *Regnault*, representing France awarding laurel-wreaths to Art and Manufacture. The frieze which separates the ground-floor from the one above it bears numerous names and medallion-portraits of persons who have acquired distinction in the pursuit of art, science, commerce, or agriculture. In the centre is a large glass-covered hall, 210 yds. in length and 51 ft. in height.

The Palais de l'Industrie is now used for different exhibitions, the chief of which is the annual exhibition of modern paintings and sculptures, so well known under the name of the **Salon** (derived from the former exhibition-room in the Louvre), lasting from 1st May to 20th or 30th June. It is open daily from 8 a.m. (Mon. from 12 o'clock) to 6 p.m. (on Sun. to 5 p.m.). Admission in the forenoon 2 fr., in the afternoon or evening 1 fr.; on the opening day and on Frid. 5 fr.; on Sun. forenoon 1 fr., on Sun. afternoon free. The entrance is by the large door facing the avenue, and the exit is at the end looking towards the Place de la Concorde. The pictures are exhibited on the first floor, and the sculptures on the ground-floor. Refreshment room on the ground-floor.

An *Agricultural Show* (animals; implements; produce) is also held here for 10-12 days every spring; followed by a *Horse Show* in the first fortnight in April.

The first floor of the S.E. wing of the Palais is now occupied by the **Musée des Arts Décoratifs**, which, however, is to be removed to the Palais des Beaux-Arts erected in the Champ de Mars for the exhibition of 1889 (p. 283). This Museum, founded in 1877 on the model of South Kensington Museum and opened to the public in 1880, contains a large number of interesting objects, many of which are lent to the museum by their owners for longer or shorter periods, so that the contents are constantly changing. The museum is open daily from 10 to 4, 5, or 6; adm. 1 fr., Sun. and holidays 50 c. The entrance is on the side next the Place de la Concorde, door No. 7.

The Palais de l'Industrie also contains a *Musée des Colonies*, i. e. an exhibition of colonial produce and of Parisian goods suitable for export to the colonies. It is open daily, except Mon. and Frid., from 12 to 5,

gratis (entrance by door No. 8, in the middle of the S. side). — The *Pavillon de la Ville de Paris*, an iron and brick structure from the Exhibition of 1878, has been re-erected to the S. of the Palais. — In the neighbouring *Jardin de Paris* concerts and balls are given (p. 33).

To the N.W. of the Palais de l'Industrie is the *Old Panorama*, containing at present the Siege of Paris in 1870-71, by *Philippoteaux* (open from 10 a.m.; adm. 2 fr., on Sun. 1 fr.). On the other side of the avenue is the *Cirque d'Été* (p. 34). A little to the E., opposite the Palais de l'Industrie, is the *Panorama Marigny*, an elegant structure by Ch. Garnier. It contains at present a panorama of ancient Jerusalem (Door A.; 1 fr.) and a diorama of Paris 'à travers les âges' (Door B.; 1 or 2 fr.).

The park or *Carré des Champs-Élysées* extends as far as the *Rond-Point des Champs-Élysées* (Pl. R, 15; II), a circular space adorned with beds of flowers and six fountains, situated about halfway between the Place de la Concorde and the Arc de l'Etoile. Two avenues descend hence to the Seine: the *Avenue d'Antin*, leading to the Pont des Invalides (p. 168), and the *Avenue Montaigne*, leading towards the Pont de l'Alma (p. 168).

To the N. of the Rond-Point the Avenue d'Antin is prolonged to the church of St. Philippe du Roule (Pl. B, 15; II), in the Rue du Faubourg St. Honoré, an edifice in a Greek style, by *Chalgrin* (1769-84). The cupola is adorned with a Descent from the Cross, by *Chassériau*.

Farther on, to the left of the Champs-Élysées, extends the modern quarter of *Marbeuf*, consisting of handsome private residences. The Trocadéro, about $\frac{3}{4}$ M. from this point, may be reached by an omnibus traversing the Rue Pierre Charron. — Farther up, to the right, diverges the Rue de Berry, containing the *Panorama National*, with the battle of Champigny (1870), by *Detaille* and *De Neuville*.

The Avenue des Champs-Élysées ends at the *PLACE DE L'ETOILE (Pl. B, 12; I), so named from the star formed by the twelve different boulevards or avenues which radiate from it (see p. 156). This Place occupies a slight eminence, on the summit of which rises the —

***Arc de Triomphe de l'Etoile**, the largest triumphal arch in existence, and visible from almost every part of the environs of Paris. Begun by Napoleon I. in 1806, it was completed by Louis Philippe in 1836, from designs by *Chalgrin* (d. 1811). It consists of a vast arch, 67 ft. high and 46 ft. wide, intersected by a lower transversal arch. The whole structure is 160 ft. in height, 146 ft. in width, and 72 ft. in depth. The arch conveys a somewhat heavy impression when approached. The huge pillars of masonry on which it rests are adorned only with colossal trophies, 36 ft. high, with figures 16 ft. high. The final top member is still wanting.

The following groups adorn the E. façade: on the right, Departure of the troops to the frontier in 1792, by *Rude*, the finest of the four groups; above it, the Obsequies of General Marceau, by *Lemaire*. On the left, Triumph of Napoleon after the Austrian campaign, and the Peace of Vienna (1810), by *Cortot* (d. 1843); above it, the Pasha Mustapha surrendering to Murat at the battle of Aboukir (1799), by *Seurre* the Elder. — The bas-reliefs on the frieze surrounding the monument represent the departure and the return of the troops, by *Brun*, *Jacquot*, *Seurre*, and *Rude*.

On the W. façade: on the right, Resistance of the French to the invading armies in 1814, by *Etez*; above it, Passage of the bridge of Arcola (1796; death of Muiron, Bonaparte's adjutant), by *Feuchères*. On the left, the Blessings of Peace (1815), by *Etez*; above it, the Taking of Alexandria (1798; Kléber, who has received a wound on the head, points out the enemy to his troops), by *Chaponnrière*.

The reliefs on the N. side, by *Gechter*, represent the battle of Austerlitz (1805). On the S. side is the Battle of Jemappes (1792), by *Marochetti*.

The figures of Victory on each side of the upper part of the arch are by *Pradier*. A series of 30 shields on the cornice above the entablature are inscribed with the names of different victories, while the names of 142 other battles appear on the vaulting of the principal arch. On the vaulting of the transversal arch are recorded the names of officers of the Republic and of the Empire, the names of generals who fell in battle being underlined (656 in all). The figures of Victory in relief under these names relate to successes gained in the east, north, and south.

The *Platform*, to which a spiral staircase of 261 steps ascends, commands a noble prospect (adm. 25 c.).

The following are the twelve avenues, named in consecutive order, which radiate from the Place de l'Etoile: the *Avenue des Champs-Élysées*, above described; then, to the left, *Avenue de Friedland*, a prolongation of the Boulevard Haussmann (p. 204); the *Avenue Hoche*, leading to the Park Monceaux (770 yds.; see p. 202); the *Avenue de Wagram*; the *Avenue Macmahon*; the *Avenue Carnot*; the *Avenue de la Grande-Armée* (p. 157), opposite the Avenue des Champs-Élysées; the *Avenue du Bois de Boulogne* (p. 157); the *Avenue Victor-Hugo*, which also leads to the Bois de Boulogne, passing the Place d'Eylau with the *Artesian Well of Passy* (p. 162); the *Avenue Kléber*, leading straight to the Trocadéro (tramway) and passing the pretty *Hôtel de Castille* (No. 19), the property of Queen Isabella of Spain; the *Avenue d'Iéna*, which ends at the Parc du Trocadéro; and, lastly, the *Avenue Marceau*.

Neuilly, which lies to the N. of the Bois de Boulogne (Jardin d'Acclimatation; p. 160), and is traversed by the wide Avenue of the same name, forming a prolongation of the Avenue de la Grande-Armée, is now a suburb with 26,600 inhabitants. The château of Neuilly, once the favourite residence of Louis Philippe, was totally destroyed by the mob on 25th Feb., 1848, and the park was afterwards parcelled out into building sites, on which numerous tasteful villas have been erected.

In Neuilly, near the line of fortifications, on the right side of the Route de la Révolte, is the Chapel of St. Ferdinand (Pl. B, 9), a cruciform mausoleum in the Romanesque style, erected on the spot where Ferdinand, Duke of Orleans, the eldest son of Louis XIV. and father of the Comte de Paris, breathed his last on 13th July, 1842, in consequence of a fall from his carriage. Admission daily; visitors ring at No. 13, nearly opposite the chapel (fee). Over the high-altar is a Descent from the Cross, in marble, by *Triqueti*. To the left is the Monument of the Duke, also by *Triqueti*, from a design by *Ary Scheffer*, with a fine praying angel by the prince's sister, Marie d'Orléans (d. 1839). The windows are filled with good stained glass designed by *Ingres* (p. 142). The sacristy contains a picture by *Jacquand* representing the death of the prince.

In the N. of the town is a handsome *Mairie* (Pl. B, 5), built in 1882-1885, in front of which is a bronze *Statue of Parmentier* (1737-1813), who made his first experiments in the cultivation of the potato at Neuilly. From Neuilly a handsome bridge crosses the Seine to the N.E., 2 M. from the Arc de Triomphe (p. 155). On the opposite side of the river, to the right, is *Courbevoie*, and on the hill is the *Monument de la Défense de Paris*, a bronze group by Barrias.





II. FROM THE PLACE DE L'ETOILE TO THE BOIS DE BOULOGNE.

Jardin d'Acclimatation.

Visitors who wish to see the Bois de Boulogne with the least possible expenditure of time should engage a cab by the hour (see p. 19). The principal points may thus be visited in 2-3 hrs. Those who do not wish to keep the cab waiting for the return-journey should finish their drive in the Bois before visiting the Jardin d'Acclimatation. — Stations on the Chemin de Fer de Ceinture and tramways, see p. 153.

The *Avenue de la Grande-Armée*, prolonging the *Avenue des Champs-Élysées* beyond the Arc de l'Etoile (p. 155), leads to the *Porte Maillot*, at the beginning of Neuilly (p. 156) and near the Jardin d'Acclimatation, the nearest, though not the most frequented entrance to the Bois de Boulogne. 'Tramway Miniature' from this gate (which is named from the 'Jeu de Mail' formerly played here), see p. 160. A little to the left is the large circular *Plaza de Toros* (p. 32).

The *Avenue du Bois de Boulogne* (Pl. B, R, 9, 6), leading from the Arc de l'Etoile to the W., is the usual route followed by the fashionable crowds in carriages, on horseback, or on foot proceeding from the Champs-Élysées to the Bois de Boulogne. The avenue is about 140 yds. in breadth (including the side-alleys) and is $\frac{3}{4}$ M. long to the *Porte Dauphine* (Pl. R, 6). It consists of a carriage-way in the centre, flanked on one side by a riding-path and on the other by an alley for pedestrians. On both sides are plots of grass and trees. In the distance, the Mont Valérien (p. 286) is seen rising above the Bois. To the left of the entrance is a station of the Chemin de Fer de Ceinture.

The ***Bois de Boulogne** is a beautiful park covering an area of 2250 acres, bounded by the fortifications of Paris on the E. (see p. 158), the Seine on the W., Boulogne (p. 309) and the Boulevard d'Auteuil on the S., and Neuilly (p. 156) on the N. It is a fragment of the extensive old *Fôret de Rouvray* (from Lat. '*roveretum*', the chêne rouvre, i.e. holm-oak), which also comprised the Park of St. Ouen (p. 201). This forest was long in evil odour, being the resort of duellists, suicides, and robbers. Down to 1848 it belonged to the crown-domains and received little attention. In 1852 it was presented to the municipality, on condition that a sum of two million francs should be expended on it within four years, and that it should be maintained in future at the municipal expense. The authorities accordingly converted it into a park, and it has become a favourite promenade of the Parisians. The Bois is still somewhat formal and monotonous in spite of the care that has lately been taken to introduce variety into its grouping. Few large trees now remain, a great part of the forest having been cut down by the Allies in 1814-15, while the portion adjoining the fortifications was destroyed during the two sieges of 1870-71.

The annexed plan will enable the visitor to find his way without difficulty.

The Bois de Boulogne is most frequented in the afternoon between 3 and 5 o'clock, the favourite routes being those leading from the Avenue du Bois de Boulogne to the lakes, where the handsomest carriages and most elegant toilettes are to be seen.

The Bois de Boulogne is considered part of Paris, but as already indicated it lies outside the *Enceinte*, or lines of fortifications. The ramparts here, however, are almost completely disguised.

The Fortifications of Paris were constructed in consequence of a decree of 1840, and were completed within five years at an expense of 140 million francs (5,600,000*l.*). The *Enceinte*, with its 94 bastions, is 21 M. in length. The ramparts, 32 ft. in height, with a parapet 19 ft. in width, are environed by a moat 48 ft. in width, and a glacis. The approaches to the city are also commanded by seventeen *Forts Détachés*, at different distances from the city, up to a maximum of 2 M. On the N. side, near St. Denis, are the *Forts de la Briche, Double Couronne du Nord, and de l'Est*; on the E., *Fort d'Aubervilliers*, near Le Bonnet, *Forts de Romainville, de Noisy, de Rosny, de Nogent, and de Vincennes*, and the redoubts *de la Faisanderie and de Gravelle*; on the left bank of the Marne lies *Fort de Charenton*; to the S., on the left bank of the Seine, *Forts d'Ivry, de Bicêtre, de Montrouge, de Vanves, and d'Issy*; on the W., the *Forteresse du Mont Valérien*. Most of these were entirely destroyed in 1870-71, but have since been rebuilt. A second line of forts, at a greater distance from the ramparts, has also been constructed on the heights commanding the valley of the Seine. On the right bank of the Seine: the *Forts de Courmeilles, de Montlignon, de Domon, de Montmorency, d'Ecouen, de Stains, de Vaujours, de Chelles, de Villiers, and de Villeneuve-St. Georges*; on the left bank: the *Forts de Châtillon, de la Butte-Chaumont, de Palaiseau, de Villeras, de Haut-Buc, de Saint-Cyr, de Marly, de Sainte-Jamme, and d'Aigremont*. The area included within this elaborate system of fortifications is 400 sq. M. in extent, and besides the capital itself embraces the seven towns of Versailles, Sceaux, Villeneuve-St. Georges, St. Denis, Argenteuil, Enghien, and St. Germain-en-Laye.

We enter the Bois by the *Porte Dauphine* (p. 157), near which are the *Chinese Pavilions* from the Exhibition of 1878, now used as a café. The broad *Route de Suresnes or du Lac*, which diverges to the left, leads in about 10 min. to the *Carrefour du Bout des Lacs* (see below). The *Route de la Porte des Sablons*, to the right, leads to ($\frac{1}{3}$ M.) the *Jardin d'Acclimatation* (p. 160), crossing the large *Allée de Longchamp or des Acacias*, which leads to the left to the race-course (p. 159). This allée has been the chief scene, during the last few years, of the *Fête des Fleurs*, held for a benevolent object at the time of the 'Grand Prix de Longchamp' (p. 159).

The *Carrefour du Bout des Lacs* is one of the finest points in the Bois de Boulogne. It lies at the lower end of two artificial lakes, the *Lac Inférieur* ($\frac{2}{3}$ M. in length and 100 yds. in width), and the *Lac Supérieur* ($\frac{1}{4}$ M. in length and 60 yds. in width), which are fed by the Canal de l'Ourcq (p. 186) and the Artesian Well of Passy (p. 162). Two brooks issue from the *Lac Inférieur*, one of which flows to the *Jardin d'Acclimatation*, the other, or 'Rivière de Longchamp', to the cascade (see below). We walk round the lakes, beginning at the left side.

In the *Lac Inférieur* are two islands (ferry there and back 10 c.; boat on the lake 2-3 fr.), on one of which is a café-restaurant in

the form of a Swiss *Chalet*. As cafés are one of the chief characteristics of every Parisian resort, the wayfarer will find other places of refreshment in various parts of the park, especially at the *Carrefour du Bout du Lac* and near the *Grande Cascade* (see below).

Between the two lakes is the *Carrefour des Cascades*, and at the S. end of the *Lac Supérieur* is the *Butte Mortemart*, whence there is a fine view of St. Cloud and Meudon. As the fine old trees on this side of the park were cut down in 1870, the vacant space has been converted into the *Champ de Courses d'Auteuil*, an extensive race-course. Races and steeple-chases take place here in spring and autumn, the most important being those of Whit-Monday. The *Grand Steeplechase* (value 4800*l.*) is run at the beginning of June. — *Auteuil*, see p. 162.

On arriving at the upper extremity of the *Lac Supérieur* we turn to the right and walk along the margin of the lake to the *Carrefour des Cascades* (see above). Hence we follow the *Avenue de l'Hippodrome* to the left or, if on foot, the walk at the side (see Plan), both of which cross the wide *Allée de la Reine Marguerite* and lead in 15-20 min. to the **Grande Cascade*, an artificial waterfall issuing from a grotto. After viewing the waterfall, we may ascend the eminence a little before it, which affords a fine view of the valley of the Seine; to the left on the opposite bank lies St. Cloud with its modern church; nearer is the Hippodrome de Longchamp (see below); opposite us are the *Moulin de la Galette* and the remains of the ancient *Abbey of Longchamp*, with the village of *Suresnes* beyond them; to the right, a little farther off, is *Mont Valérien* (p. 286). A path cut in the rock descends the hill and passes behind the fall, through the spray of which Mont Valérien is again visible. To the left, under the trees, is the *Restaurant de la Cascade*.

The *Hippodrome de Longchamp* is the principal race-course in the neighbourhood of Paris (see p. 34). The races (*courses* or *réunions*) at Longchamp take place in spring, summer, and autumn, the days being advertised in the newspapers and handbills. The races attract vast crowds and are worth seeing. The 'Première de Longchamp', at the beginning of April, opens the spring-season, and the new spring fashions then appear in all their glory. The principal race at this meeting is the 'Cádran', worth 1200*l.* The *Grand Prix*, of 100,000 fr., is competed for at the beginning of June, and may be styled the 'French Derby'. It may also be said to inaugurate the summer season, as immediately after it the fashionable world of Paris prepares for its annual migration to the country or the sea-side. Charges for admission to the hippodrome: pavilion 5 fr.; weighing-place 20 fr.; for a carriage with one horse 1*5*, with two horses 20 fr.; each rider 5 fr.; pedestrian 1 fr. — Reviews take place here occasionally.

The *Route de Neuilly* (p. 156), at the opposite end from the race-course, passes between the *Champ d'Entraînement* and the park of the little château of *Bagatelle*, constructed in one month by the Comte d'Artois (Charles X.) in consequence of a wager with Marie Antoinette; it is now the property of the heirs of Sir Richard Wallace (d. 1890). The pretty park and the valuable collections of art may be visited only by permission. — The part of Neuilly adjoining this side of the Bois de Boulogne is known as *Madrid*, a name derived from a château which once stood in this neighbourhood, built by Francis I. after the Battle of Pavia, and thus named as a remi-

niscence of his captivity in Spain. The château, which was destroyed after the Revolution, was remarkable for the external decorations of the walls, consisting of terracottas by Girolamo della Robbia, and works in enamel; the former no longer exist, but the latter are still to be seen in the Musée de Cluny (p. 230). At the Porte de Madrid is a *Restaurant. To the left lie the *Mare de St. James* and, a little farther on, the Jardin d'Acclimatation (see below).

The wide *Allée de Longchamp* leads straight from the Hippodrome, passing the Cascade on the right, to the (2 M.) Porte Maillot (p. 157). To the right, a little way on, is the *Pré Catelan*, an enclosed space where fêtes used to be given in summer, but now a 'dépendance' of the Jardin d'Acclimatation, containing a *Dairy*, a *Café-restaurant*, *Velocipede Track*, etc. Farther on, to the left, is the *Cercle des Patineurs*, a pond and pigeon-shooting grounds belonging to the Skating Club. Near the end of the Allée a path to the Jardin d'Acclimatation diverges to the left.

The ***Jardin d'Acclimatation** is an enclosed part of the Bois de Boulogne adjoining the Boulevard de Maillot, situated to the S. of the Avenue de Neuilly, and between the Porte des Sablons and the Porte de Madrid, and affords one of the most attractive promenades in the environs of Paris. It was founded by a company 'in order to introduce into France and acclimatise foreign plants and animals suitable for domestic or ornamental purposes', and covers an area of 50 acres. It suffered severely during the second siege of Paris in May, 1871.

Visitors who hire a cab in Paris may dismiss it at the Porte Maillot, before the line of the fortifications is crossed; otherwise, the fare to the Jardin is higher, and 1 fr. additional must be paid as 'indemnité de retour' (see p. 20). Tramway from the Porte Maillot to the entrance of the Jardin 20 c., to different points in the interior of the Jardin 25-35 c. On concert-days (see below) special omnibuses run to the garden from No. 8, Boulevard des Italiens (there and back 1 fr.).

The Jardin d'Acclimatation is open the whole day. Admission 1 fr. (greenhouses included); on Sundays and holidays $1\frac{1}{2}$ fr.; carriage 3 fr., in addition to the charge for each person in it; no charge for coachman. Children under seven enter free. Concert in the garden in summer on Sundays and Thursdays at 3 p.m., for which no additional charge is made.

The principal entrance is on the E. side, near the Porte des Sablons, but there is another at the opposite end, near the Porte de Neuilly.

On entering, we find ourselves in a handsome walk, 11 yds. wide, which runs round the whole garden. On the right are the *Offices* (Pl. 1) of the company, to which purchasers address their orders. On the left is the large hothouse (Pl. 14), which we shall again have occasion to mention. Farther on, to the right, is a *Permanent Exhibition* (Pl. 2) of articles connected with gardening and other industrial objects. Adjacent is an *Artificial Mineral Spring*, formed by rain-water passing over a mass of carbonates of lime and iron. To the right is the *Singerie*, or monkey-house (Pl. 3), which is

entered from the rear. To the left are the *Ostriches*, the *Cranes*, and the pigeon-house (see below). Then, to the right, the *Faisanderie* (Pl. 4), in front of which are a statue in white marble of the naturalist *Daubenton* (d. 1799), by *Godin*, and the *Poulerie* (Pl. 5), a semicircular building. Farther on, to the left, are the *Camels* and the *Dromedaries*; to the right, the *Antelopes*, the *Llamas*, and the *Kangaroo Chalet*, near which diverges the walk leading to the entrance on the side next the *Porte de Neuilly*.

A little farther on are the *Ecuries* (Pl. 6), or stables, and enclosures connected with them, containing quadrupeds trained for the purposes of the garden or the amusement of visitors. A great source of delight to children here is a ride on the back of an elephant or dromedary, or a drive in a carriage drawn by ostriches, llamas, etc. (Charges fixed by tariff: dromedary 50 c., elephant 25 c., ostrich-carriage 50 c., small carriage 25 c., pony 50 c.) During summer the adjoining lawn is generally occupied by encampments of natives of various savage tribes. Beyond the *Quagga*, *Zebra* and *Giraffe Houses*, to the right, is the *Panorama du Monde Antédiluvien* (adm. 50 c.), by *Castellani*, and beyond that again the *Alpacas*, to the left, and the *Cattle-Shed*, to the right.

Farther on, to the left is the basin of the *Ottaries* or sea-lions (Pl. 8), which are fed at 10 a.m., 2 and 5 p.m.; and on the same side is a rocky enclosure for chamois, mountain-goats, and other climbing animals. Behind are *Antelopes* and *Chamois* (Pl. 9). To the right of the circular walk is the *Laiterie*, or dairy (cup of milk 40 c.). The *Aquarium* (Pl. 10), consisting of ten glass reservoirs of sea-water and four of fresh, is inferior to that at the *Trocadéro* (p. 165), but it claims to be the oldest in Europe (1860). Behind are *Fishponds*, *Penguins*, and *Water Rats*.

Farther on is the *Buffet* (Pl. 11), opposite which is the *Kiosque des Concerts*, where the band plays. Then come the *Chalet des Cerfs* (Pl. 12) and the *Chenil* (Pl. 13), containing thorough-bred dogs, whose pedigrees are carefully recorded. Facing the latter is a *Book-stall*, with a reading-room. Beyond this, to the right, are an *Aviary* and the *Grande Serre* (Pl. 14), or winter-garden, which contains a very fine collection of camellias (shut in winter at 5 and in summer at 6 p.m., on Sun. $\frac{1}{2}$ hr. earlier).

The brook issuing from the artificial lakes in the Bois de Boulogne flows through the Jardin d'Acclimatation, and in the centre forms a pond containing *Aquatic Birds*. On the bank of this brook is the *Pigeonnier*, for rearing carrier-pigeons.

We may return to the town by the same route to view the crowd etc. in the Bois and the Champs Elysées, but if the day be unfavourable for this we may take the *Chemin de Fer de Ceinture* (p. 24), or we may return via the *Trocadéro* (p. 163).

III. FROM THE BOIS DE BOULOGNE TO THE TROCADÉRO AND THE PLACE DE LA CONGORDE.

Returning to the Lac Inférieur (p. 158), either by the Route de Madrid or direct from the Hippodrome (p. 159) by the Route de Longchamp (comp. Plan), we next follow the Route de la Muette (Pl. R, 3) or the Route de Passy, and re-enter Paris viâ *Passy*, one of the communes annexed to Paris in 1860, now forming, with Auteuil (see below), the 16th arrondissement and containing the Trocadéro. Its lofty and healthy situation has long made it a favourite place of residence, and it contains numerous handsome private mansions. To the S.E. is the *Ranelagh*, a triangular grass-plot occupying the site of the public establishment of that name, which, like its London namesake, was famous at the end of last century for its banquets, masquerades, and fêtes. It is adorned with a statue of Cain by *Caillé*, a Cupid by *Damé*, and a Fisherman, with the head and the lyre of Orpheus, by *Longepied*. Adjacent are the station of the Chemin de Fer de Ceinture and the office of the tramways (lines N & J) which pass the Trocadéro.

The beautiful *Parc de la Muette* (Pl. R, 5), a little to the N., is now private property. In the 18th cent. a royal château stood here, of which nothing now remains. — Beyond La Muette, at No. 145 Avenue Henri Martin, are the *Serres de la Ville* (public hot-houses; Pl. R, 5), not usually shown to visitors without a permission from the prefecture (office of public works), but open from 1 to 6 for a fortnight in April, when the magnificent azaleas are in bloom.

There is another station of the Chemin de Fer de Ceinture here, at the junction of the Avenues Henri-Martin and Victor-Hugo. A little to the E., between the two avenues, is a square with the copious *Artesian Well of Passy*, adjoining which is a *Statue of Lamar-tine* (1792-1869), in bronze, by Vasselot.

Auteuil, like Passy a quiet suburban district with numerous villas, lies to the S.E., between the Seine and the Bois de Boulogne. Race-course see p. 159. From the station of Auteuil, near the Bois (Pl. R, 1), a tramway runs to Boulogne (p. 309) and the omnibus lines A and AK to the Madeleine and St. Sulpice. At this point also begins the immense **Viaduct* of the Chemin de Fer de Ceinture, 1¼ M. long, constructed throughout of masonry, with several galleries for foot-passengers beneath the line, and 234 cross-arches. It ends with the **Pont-Viaduc du Point du Jour*, where the viaduct proper rises between two carriage-roads.

In the Rue d'Auteuil rises the Romanesque church of *Notre Dame d'Auteuil*, restored in 1877-81 by Vaudremer, in front of which is the modest monument of the *Chancelier d'Aguesseau* (1668-1751). To the right is the *Maison Chardon-Lagache*, and behind is the handsome *Institution Ste. Péline* and the *Maison Rossini*, three charitable houses.

At No. 9 Rue La Fontaine, not far from the Pont de Grenelle (Pl. R, 4), is the *Musée de Ville* (adm. only with permission of the Bureau des Beaux-Arts, in the Hôtel de Ville), containing models of the statues acquired by the town since 1871, competitive plans and designs, some paintings, and a collection of textile fabrics, some very old. — At the lower end of the *Ile des Cygnes*, at the *Pont de Grenelle* (Pl. R, 4, 7), is a reduced copy in bronze of the statue of *Liberty enlightening the World*, by Bartholdi, which stands at the entrance of New York harbour.

The *Avenue Henri-Martin* leads straight from the Bois to the ($\frac{3}{4}$ M.) Trocadéro, passing the *Mairie of the 16th Arrondissement* on the right and near the *Lycée Janson de Sailly* on the right. Just beyond the *Cimetière de Passy*, on a height to the left, it ends at the *Place du Trocadéro* (Pl. R, 8, 9; I; tramways D and J, omnibus-lines A and B), behind the palace. Here also converge the *Avenue Kléber*, leading to the Arc de l'Etoile (p. 156), the *Avenue du Trocadéro*, leading to the Place de l'Alma (p. 168), and the *Avenue Malakoff*, leading to the Avenue du Bois de Boulogne (p. 157).

The **Trocadéro* (Pl. R, 8; I), which bears the name of one of the forts of Cadiz, captured by the French in 1823, was down to 1866 a piece of waste ground descending rapidly to the Seine. Napoleon I. entertained the idea of building a marble palace here for the King of Rome, but nothing came of it. In 1867, when the Great Exhibition was held in the Champ-de-Mars, the undulating ground of the Trocadéro was laid out in terraces as a place for large popular festivals. This attempt, however, met with little success. In 1878 the heights of the Trocadéro were added to the exhibition-grounds of that year, and the present park and palace were constructed.

The *Palais du Trocadéro* (Pl. R, 8; I), which occupies the summit of the plateau, is a huge building in the Oriental style, designed by *Davioud* and *Bourdais*. The central portion consists of a circular edifice 63 yds. in diameter and 180 ft. in height, surmounted by a dome, and flanked with two minarets 270 ft. high. On each side is a wing in the form of a curve, 220 yds. in length, so that the whole edifice presents the appearance of an imposing crescent. On a level with the spring of the dome is a gallery adorned with thirty statues representing the arts, sciences, and various industries. The dome itself is surmounted by a colossal statue of Fame, by *A. Mercié*. The balcony in front of the central building is embellished with a large group in white stone and six figures in gilded bronze: Europe, by *Schoenewerk*, Asia by *Falguière*, Africa by *Delaplanche*, N. America by *Holle*, S. America by *Millet*, and Australia by *Moreau*. Below the balcony gushes forth a large CASCADE, which descends to a huge basin, 196 ft. in diameter, surrounded by a bull, a horse, an elephant, and a rhinoceros in gilded bronze, by *Cain*, *Rouillart*, *Frémiet*, and *Jacquemart*. Under the arches flanking the cascade are allegorical figures of Water, by *Cavelier*, and Air, by *Thomas*. At the upper basin is a group, by *Falguière*, of the Seine and its tributaries, the Yonne and the Marne. Concerts are often given in the elaborately-decorated *Salle des Fêtes*, which contains an immense organ by *Cavaillé-Coll* and has seats for 6000 persons (adm. by order from the secretary of the Beaux-Arts, Rue de Valois 3, or on application to the keeper of the Ethnographical Museum, p. 165). The galleries and balconies command an admirable *View of Paris (best at sunset). Visitors may ascend by a lift (50 c., on Sun. 25 c.).

The Palais du Trocadéro contains important collections of plaster casts and of ethnographical curiosities and also the Musée Cambodgien.

The MUSÉE DE SCULPTURE COMPARÉE, or *Musée des Moulages*, occupies the right wing and part of the left wing of the building and is open daily, except Mon., from 11 to 4 or 5. The casts are mainly illustrative of the chief types of monumental sculpture since the middle ages, but, for the sake of comparison, there are a few casts of ancient and other works of a different class. The sculptures are arranged chronologically. Explanatory labels are attached to each cast.

Rooms I & II. French sculptures of the 11-13th cent., chiefly from the portals and façades of churches. Among the ancient sculptures is the statue of Mausolus from Halicarnassus (4th cent. B.C.). — R. III. Photographs of monuments and sculptures, of which no casts have yet been made. St. George, from the cathedral of Bâle. — R. IV. Sculptures from the cathedrals of Strassburg and Naumburg; pediment from the cathedral of Bourges; tomb of St. Stephen, from the abbey-church of Aubazine, in the department of Corrèze; portal of the cathedral of Bordeaux. — R. V. Portals of St. Maclou at Rouen; gate of the ducal château at Nancy. In the middle: St. George, by Donatello; tombs of Charles the Bold and his daughter, Mary of Burgundy, from Bruges; fountain with figure of Moses at Dijon, by Claus Sluter; tomb of the children of Charles VIII. at Tours; tomb of Francis II. of Brittany; statues from the tombs of Henri II. and Catherine de Médicis at St. Denis. At the end of the room, screen from the cathedral of Limoges. To the right, in returning: Bas-reliefs from the Fontaine des Innocents (p. 171), by Jean Goujon; Tomb of Duke Louis de Brézé (cathedral of Rouen); statues, by Sluter, from the Carthusian convent at Dijon; bas-reliefs from the château at Ecouen; stall from the cathedral of Coimbra (Portugal); monks from the tomb of the duke of Burgundy at Dijon, by Sluter; reliefs from St. Nicholas, at Troyes; group of children with musical instruments, by Luca della Robbia (Florence); SS. Anna and Mary from the cathedral of Bordeaux; high-reliefs from the cathedral of Siena, by Nic. Pisano. — In the front row: Female figure from the Rathaus at Nuremberg; Madonna from Notre Dame at Bruges. — On the other side: Numerous Italian busts; reliefs by Mino da Fiesole, from the tomb of Paul II. at Rome; door-panels of the Baptistery at Florence, by A. Pisano. Visitation, by Andrea della Robbia, from Pistoja; choir-stalls from the cathedral of Amiens; Visitation, from St. Jean at Troyes; bas-reliefs from the Hôtel du Bourghéroulde at Rouen. In front: Tombs of Soccino, at Florence, and Gaston de Foix, at Milan. Then, on the wall, bas-reliefs from the tomb of Cardinal Duprat, at Sens; other statues from tombs; portal of the cathedral of Beauvais, etc. — R. VI. Italian and French sculptures of the 15-16th centuries. Fountain of the 16th cent., from the tomb of St. Just, at Narbonne; bas-reliefs from the Hôtel du Bourghéroulde, at Rouen; Hermes with the child Bacchus, by Praxiteles, from the temple of Juno at Olympia; dying Adonis, by Michael Angelo. — R. VII. Statues, busts, groups, and bas-reliefs from Versailles; St. Bruno by Houdon, at Rome; portal of the town-hall of Toulon, by Puget. — R. VIII. Pinnacle from St. Pierre at Caen; portal of Ste. Marie-des-Dames, at Saintes (12th cent.). Photographs of sculptures.

The rest of the collection, not yet finally arranged, is in the other wing of the palace beyond the Rotunda. — Room I. Inside the entrance, Portal from the château of La Ferté-Milon; to the right and left, and behind, portals from the churches of Carennac (Lot), Aulnay (Charente-Infér.), and St. Pierre de Moissac (Tarn), and fragments from the churches of St. Trophime at Arles, Souvigny, and Souillac. — R. II. Photographs. Portal of the abbey-church of Charlieu (Loire). — R. III. Photographs. Church-portal from St. Gilles (Gard). — R. IV. Photographs. Doors of the sacristy of the cathedral of Bourges; vaulting of the bell-tower at Rouen. — R. V.

Photographs. Portions of the Hôtel d'Escouville (Exchange) at Caen; door of the Lyceum at Toulouse. — R. VI. Models of the interiors of St. Denis (tombs), Notre-Dame at Paris, and the abbey-church of Mont St. Michel. — R. VII. Fountain from the bell-tower at Rouen. Casts of modern sculptures. Drawings and plans of historic monuments.

The MUSÉE CAMBODGIEN or *Musée Khmer*, which occupies the three following rooms (adm. daily, except Mon., 11 to 4 or 5), consists of very interesting sculptures found in Cambodia, a Chinese district under the protectorate of France, situated to the E. of Cochin China. These once belonged to huge buildings erected by the Khmers, a people now almost entirely consigned to oblivion. Some of these edifices have been rediscovered in the depths of pathless forests from accounts given by travellers of the 18th century. This collection may be transferred to the Musée Guimet (p. 166).

Room I. Huge temple-entrance; curious bas-reliefs and ornaments; mask and figure of Buddha; figure of a bonze. — To the right of the staircase: End of a gallery from the temple of Vishnu at Angkor; to the left: other curious bas-reliefs and ornamental sculptures. — R. II. Fragments from the temple at Angkor; figures of gods and animals, steles, etc. — R. III. At the foot of the staircase, parapet of a bridge in the form of a huge serpent borne by giants; architectonic sculptures. On the staircase, water-colours and photographs of edifices in Cambodia.

The ETHNOGRAPHICAL MUSEUM is on the first floor, behind the rotunda of the Salle des Fêtes. To reach it we ascend the staircase nearly opposite the entrance to the Museum of Casts. It is open free on Sun. and Thurs., from 12 to 4 or 5; but strangers will probably find little difficulty in gaining admittance on other days.

The STAIRCASE is embellished with fine paintings on glass. At the foot, canoes from Tierra del Fuego, S. Australia, etc. — VESTIBULE I. Figures and other objects from various parts of *Oceania*; model of a hut in the Malay Archipelago. — GALLERIES. Figures, curiosities, and domestic objects from *America*. Hut of a native of Tierra del Fuego. The gallery on the left contains the sculptures and other large works. The main gallery to the right is divided into 9 sections. Sec. 1: Figures, arms, utensils, and ornaments of the natives of Guiana. Sec. 2, 3, 4: Mummies, vessels, and ornaments from Peru; Peruvian cloth; Mexican sculptures. Sec. 5: Objects from New Granada, South America, and Mexico. Sec. 6: Curious Mexican idol. Sec. 7: Mexican antiquities. Sec. 8: Californian flint implements. Sec. 9: Indian objects from the United States and Canada. — VESTIBULE II. Exhibits from the *Polar Regions*, with figures of Esquimaux, Laplanders, and Samoyedes. Here also several Chinese objects are temporarily placed. — At the end of the vestibule, to the right, is a room devoted to *European Exhibits*, including many curious costumes. Two glass-cases on the staircase also contain objects from China.

The *Parc du Trocadéro* is not large, but it is tastefully laid out and well kept up. It contains, to the left in descending from the palace, beyond the broad walk below the Cascade, a subterranean *Aquarium*, stocked with fresh-water fish (adm. 9-11 and 1 to 5 or 6). The two buildings a little higher and a little lower are respectively a *Restaurant* and the former *Pavillon des Travaux Publics*, both dating from the exhibition of 1889.

Beyond the park, towards Passy, in the Boulevard Delessert, is a reproduction of the *Tour du Temple*, in which Louis XVI. was imprisoned (p. 71), provisionally placed here (like the Bastille near the Ecole Militaire, p. 284), with historical groups (adm. 1 fr.).

Below the middle of the park the Seine is crossed by the **Pont d'Iéna** (Pl. R, 8; I), constructed in 1806-13 to commemorate the victory of that name. It is adorned with eagles and with four colossal horse-tamers. Beyond the bridge is the Champ-de-Mars (p. 280), with the famous *Eiffel Tower* and other buildings erected for the exhibition of 1889.

The Avenue du Trocadéro leads to the E. from the Place du Trocadéro to the *Place d'Iéna*, passing the buildings of the *Dépôt des Phares*. In the Place d'Iéna rises the **Musée Guimet** (Pl. R, 12; I), a handsome classical building, with a rotunda at the angle, surmounted by a colonnade and cupola. It contains the extensive and valuable collections presented to the state in 1886 by M. Em. Guimet of Lyons, relating chiefly to the religions of India and Eastern Asia, but including also a *Library* and collections of *Oriental Pottery* and of *Antiquities*. The museum is open daily, except Mon., from 11 to 4 or 5, only one wing, however, being shown each day (the Galerie d'Iéna and Galerie Boissière alternately). The chief objects only are noticed here. Explanatory labels are attached to the exhibits. Short illustrated catalogue, 1 fr.

GROUND FLOOR. The ROTUNDA contains a few Roman sculptures. GALERIE D'IÉNA, to the right: *Chinese Pottery*. The inscriptions above the glass-cases refer to the sections. — 1st Section: Modern ware from Nankin (right) and Canton (left); Chinese enamels, turquoise-blue, violet, etc.; pale-green from Nankin (15th cent.). — 2nd Section: to the right, porcelain with European patterns, 'East India Company's ware'; earthenware ('boccaros'), white Chinese porcelain, old blue porcelain; to the left, as we return, blue, red, green, yellow, and pink varieties. — 3rd Section, from right to left: Faience and porcelain from the 10th cent. to the present day; the finest dating from the time of Khien-Long (1736-1769).

GALERIE BOISSIÈRE. **Japanese Pottery* and **Bronzes*, for which there is no room on the first floor. 1st Section: modern faience, porcelain, and stone-ware from Yokohama; bronze temple-lamp; faience and porcelain from various sources; large lacquered vase in faience. — 2nd Section (continuation of the same): 'dagoba' or bronze reliquary of the 16th cent.; lamps of the same period; large modern vases in Avata faience. — 3rd Section: various kinds of porcelain, ancient and modern; large lacquered vase in faience. — 4th Section: modern ware from Kioto; Bozen stone-ware in imitation of bronze. — 5th Section: faience made by ladies and other amateurs; Kioto ware and works by the potter Ninsei (18th cent.); bronze lamp.

FIRST FLOOR. In the Rotunda is the *Library*. At the entrance are statues of Mondshu and Fughen, the two chief disciples of Budoha, upon a lion and an elephant; and two reliquaries. The *Paintings* in the Rotunda and following galleries, by Regamey, represent Oriental scenes, religious ceremonies, priests, etc.

A small room to the left of the entrance to the gallery to the right contains additional porcelain, less important objects of the kind already noticed, a large model in aloe-pith of an Indian temple, paintings of American scenes, etc.

GALERIE D'IÉNA, to the right, towards the staircase: **Religions of India and China*. — Room I., Cult of Brahma, Vishnu, and Siva, the triad representing the creating, preserving, and destroying principles. Wood-carvings from chariots of Brahma; articles used in religious services; representations of temples. In the centre is a bronze figure of Lakshmi, the Indian Venus (16th cent.), etc. — Room II. Buddhism, the worship of Sakya-Mooni or Buddha, the 'perfect sage', a cult with four

sects. 1st Section: Six glass-cases, devoted to India and Java (to the left), Cambodia, the kingdom of Siam, Burma (2), and Tibet. Statues and statuettes, vases, etc., some notable as works of art; sacred books; bronze bell. — 2nd Section: from left to right, Buddhism continued. Buddha in his three states: birth, penitence, transfiguration; transformations and cult of Kouanyn, goddess of charity; drawings extending back to the 11th cent.; statuettes and portraits of the propagators of Buddhism in China. To the left: Taoism, or Chinese pantheistic idolatry; statuettes, MSS., coloured drawings, geomantic compasses (for soothsaying), votive sabres from Cochin China. In the centre, large model of a Buddhist temple. — 3rd Section: Taoism continued; idols of various kinds; MSS. In the centre, large bronze gong. To the left, Eleven fine boxwood statuettes (18th cent.), representing celestial deities; paintings on silk; Chinese coins, the most ancient, in the shape of bells, dating from 2000 B.C. On the wall: Dharma, the apostle of Buddhism in China. In the glass-cases at the end: Confucianism, the imperial religion in China, involving ancestor-worship; here represented by statuettes, sepulchral urns, etc. — Room III., *"Salle de Jade or Gem Room"*, with numerous articles of jade, a stone highly prized in China, many of which come from the imperial Summer Palace in Peking. The glass-cases at the back contain sceptres of mandarins, etc.

GALERIE BOISSIÈRE: *"Religions of Japan"*. — Room I., 1st and 2nd Sections: fine statue of Ida-Ten, god of the grace before meat; Shintoism (to the left), the national religion, which has no idols but only symbols of the Supreme Being, and the temples of which are always closed; Buddhism, six different sects; statuettes, tissues, priests' vestments; fine bronze statuettes. At the end of the 2nd section are two bronze statues of the god of travellers, and two bronze vases, with representations of the death and ascension of Buddha. — Room II: model of a *"Mandara"* or pantheon, with nineteen personages. The central group represents Dainiti, the highest perfection, and beings who have become 'buddhas', with the eye of wisdom in the centre of their foreheads; those to the right and left represent his transformation into beings, whose end is the salvation of souls by gentleness or by violence. Around are brasiers, fountains, gongs, other figures of deities, etc. — Room III., 1st Section: Japanese and Chinese legends; curious statuettes (in the glass-case to the right, in front, the devil grown old becomes a monk); gods of happiness in the transverse cases. — 2nd Section: bronze statue of Jiso, the guardian deity of children; historical articles, very interesting statuettes; lacquer work; weapons; two palanquins belonging to princes; Chimæras of the 12th century. — Room IV. Chapel in gilded wood; two warriors armed for the field (17th cent.); three statues of Amida, one of the immortal 'buddhas'; figure of the philosopher Dharma rising from his tomb. Behind, bronze groups illustrating Japanese legends; men with long arms and legs; sage whose soul wanders throughout the earth. To the left, temple-drum in antique cloisonné-work; figures of priests; bronze lamps.

Second Floor. The ROTUNDA, supported by caryatides, contains *Paintings* by Regamey.

GALERIE D'ÉNA: *Graeco-Roman Antiquities*. Statuettes of Æsculapius, Bacchus, Apollo, and Juno, and other sculptures; busts; terracottas; black Etruscan pottery; Greek vases; bronze statuettes and helmets; paintings; glass; jewels; votive statuettes; etc.

GALERIE BOISSIÈRE: *Egyptian Antiquities*. Coffins with mummies; objects found in graves; reproductions of sepulchral paintings (6th cent. B.C.); marble statue of Diana of Ephesus; small bronzes; historical articles; figures of kings, etc. with blue enamel; textile fabrics; statue of Isis; Assyrian cylinders and seals. To the right, sacrificial table; behind, Alexandrian deities; etc.

Farther on in the Avenue du Trocadéro, on the left, is the *Musée de Galliera* (Pl. R, 12; I), in the Italian Renaissance style, by *Ginain*, now building for the collections of the Duchesse de Galliera (d. 1888), and presented with these to the state. The chief

façade fronts the Rue Pierre-Charron. The sculptures are by A. *Thiébault*. — To the right, adjoining the *Quai Debilly*, stands the *Etablissement des Subsistances Militaires*. The avenue and the quay converge at the *Place de l'Alma*, near the bridge of this name. To the left rises the *Hippodrome* (p. 31). To the right is the *Pompe à Feu de Chaillot*, supplying the city-reservoirs from the Seine.

The *Pont de l'Alma* (Pl. R, 11, 12; I) was constructed in 1856 and named in memory of the Crimean campaign. The buttresses are embellished with handsome figures of a Zouave and a private of the line by *Dieboldt*, and an artilleryman and a chasseur by *Arnaud*.

From the Place de l'Alma the *Avenue Montaigne* leads N.W. to the Rond-Point des Champs-Élysées (p. 155). Near the middle of this avenue, on the right, No. 18, is the *Hôtel Pompéien* (Pl. R, 12; I), erected by *Normand* in the style of the 'Villa of Diomedes' at Pompeii. The interior may be inspected in the absence of the present owner (fee 1 fr.). The most interesting part is the atrium, with paintings after the antique. The other rooms contain some modern Italian sculptures, and paintings by Troyon, Daubigny, Verboeckhoven, etc. Adjacent is the *Hôtel du Prince Solikoff*, in the mediæval style (also accessible in the owner's absence).

Along the Seine, between the Place d'Alma and the Place de la Concorde (p. 81), extends the *QUAI DE LA CONFÉRENCE* (Pl. R, 15, 12; I, II), named after an old gate through which the Spanish ambassadors entered Paris in 1660, to confer with Mazarin on the betrothal of the Infanta Maria Theresia with Louis XIV. It is traversed from end to end by the *Cours-la-Reine*, a fine avenue formed by Marie de Médicis in 1610. — Near the middle of the quay the Seine is crossed by the *Pont des Invalides* (Pl. R, 14, 15; II), built in 1854-55 on the site of an older suspension-bridge, and to a great extent reconstructed in 1879-80. It is adorned with Victories by *Dieboldt* and *Vilain*. *Hôtel des Invalides*, see p. 274.

Near the Pont des Invalides, at the corner of the Cours-la-Reine and the Rue Bayard, is the house known as the **Maison de Francois I.*, a very pleasing example of the domestic architecture of the Renaissance. Francis I. caused this building to be erected at Moret, near Fontainebleau, in 1527, for the reception of Diane de Poitiers, or according to others for his sister Margaret of Navarre, and in 1826 it was transferred in fragments to Paris and re-erected on its present site. The façade, the style of which is quite unique and very unlike that of contemporary buildings, finds its closest parallel in the palaces of Venice. On the ground-floor are three large arched windows, to which the three square-headed windows of the upper floor correspond. The ornamentation on the pilasters between the windows and at the corners is singularly rich and elegant. Many of the medallion-portraits (including that of Margaret of Navarre, between the arms of France and Navarre) have been restored. The back is also worthy of inspection, but the sides have been modernised.

The Cours-la-Reine touches the Champs-Élysées at the Pont des Invalides, and $\frac{1}{3}$ M. farther on is the *Place de la Concorde* (p. 81).

4. From the Palais-Royal to Père-Lachaise.

With this walk a visit to the Conservatoire des Arts et Métiers is conveniently combined (adm. on Sun., Tues., and Thurs.). — Luncheon may be taken near the Conservatoire des Arts et Métiers, in the Boul. St. Denis or the Boul. St. Martin, or near the Place de la République, in the Boul. St. Martin or the Boul. du Temple (see pp. 13, 15).

I. FROM THE PALAIS-ROYAL TO THE HALLES CENTRALES.

ST. EUSTACHE.

The *Rue des Petits-Champs* (Pl. R, 18, 21; II, III), passing at the back of the Palais-Royal, leads eastwards past the Bibliothèque Nationale (p. 195), the Rue Vivienne (leading to the Bourse and the Boul. Montmartre), and the handsome *Passage Vivienne*, all on the left, and terminates at the *Rue de la Banque*. The latter street contains three handsome modern edifices: the *Mairie du IIe Arrondissement* (Bourse) and the *Caserne de la Banque* on the right, and the *Hôtel du Timbre* on the left.

In the Rue de la Vrillière, leading to the right, is the *Banque de France*, enclosed by four different streets. It was formerly a private mansion, and contains a handsome apartment of the 18th cent. called the *Galerie Dorée*, which may be visited on application at No. 1, Rue de la Vrillière.

The *Bank of France*, which has the sole right of issuing notes in France, transacts all ordinary banking business on a very extensive scale. The cellars contain bullion, diamonds, and other valuables, worth in all several milliards of francs. These repositories are constructed in a very massive style and are guarded with most elaborate precaution.

A narrow side-street leads from the Bank to the small circular **Place des Victoires** (Pl. R, 21; III), about 85 yds. in diameter, designed by *J. H. Mansart*, and constructed in 1685. It was originally called the 'Place Louis XIV.', and was embellished in 1686 with a gilded statue of that monarch, with the inscription, '*viro immortalis*'. The monument was destroyed in 1792, and replaced by a pyramid inscribed with a list of victories gained by the republican army, from which the Place derives its present name. The pyramid was in its turn displaced in 1806 by a statue of *General Desaix* (d. 1800), which in 1814 was melted down along with others to furnish materials for the statue of Henri IV. on the Pont-Neuf (p. 220). The present clumsy monument, an *Equestrian Statue of Louis XIV.*, in bronze, which is too large for the Place, was erected in 1822 by *Bosio*. The figure of the horse, in a rearing attitude, rests on the hind-legs and tail, and the rider is garbed as a Roman general. The reliefs on the pedestal represent the king's passage of the Rhine, and the distribution of military honours.

A few paces to the N.W. of this Place is the church of *Notre-Dame-des-Victoires*, erected in 1629-1740 to commemorate the taking of La Rochelle, the chief stronghold of the Huguenots. It is now the seat of a monastic fraternity. The altar of the Virgin to the right of the choir, which is the object of special veneration, was despoiled of its chief treasures by the Communists, but has been richly re-decorated. The walls of the chapels are covered with votive inscriptions on marble. The choir contains well-executed carved woodwork and two pictures by *Van Loo* (d. 1745): an Allegory of the capture of Rochelle, and scenes from the life of St. Augustine. The first chapel on the right contains a St. Peter in bronze, a copy of a statue in St. Peter's at Rome.

To the E. of the Place des Victoires the Rue des Petits-Champs is prolonged by the new *Rue Etienne-Marcel*, which skirts the central post office (p. 170) and is continued to the Boul. de Sébastopol.

The **Hôtel des Postes et Télégraphes** (Pl. R, 24; *III*), rebuilt in 1880-1884, cannot lay claim to great architectural importance. It is, however, of immense size, occupying the whole of the area enclosed by the Rue Etienne-Marcel on the N., the Rue du Louvre on the W., the new Rue Gutenberg on the S., and the old Rue Jean-Jacques-Rousseau on the E. The main public entrance is in the *Rue du Louvre*, opened in 1888, which connects the Rue St. Honoré and the Rue Coquillière, and is to be prolonged to the Rue Montmartre. The latter intersects the Rue Etienne-Marcel at the N.E. corner of the post-office. All the different offices in direct communication with the public are united in the same colonnade or hall. Behind is the loading-yard, used by the post-vehicles; the sunk floor accommodates the stamping offices, the apparatus for the pneumatic post, and the stables. On the first floor are the sorting and forwarding departments; on the second, the diligence offices and official dwellings; and on the third, the archives and stores. — The Poste Restante and enquiry offices are at the end of the main hall, to the right from the Rue du Louvre entrance. — A *Hôtel des Téléphones* is now being built in the adjacent Rue Gutenberg.

Farther to the S. in the Rue du Louvre, rises the **Bourse de Commerce** (Pl. R, 20; *III*), formerly the *Halle au Blé* or corn-exchange, converted to its present use in 1888-89 by *Blondel*. The nucleus is a rotunda, 46 yds. in diameter, 106 ft. high, with an iron roof, originally built in 1662, burnt down in 1802, and rebuilt in 1811. Fronting the Rue du Louvre is a new façade, with four Greek columns, 65 ft. high, above which is a pediment with sculptures, by *Croisy*, representing Paris, Trade, Industry, Art, and Architecture. The interior of the dome is embellished with frescoes of the East and West, by *Clairin* and *Luminais*, the North and South, by *Laugée* and *Lucas*. The exchange is open daily, except Sun., from 9 to 6 (to 7 on Wed.; business hours 1-3). — In front, on the other side of the street, is a fluted Doric column, 100 ft. high and 10 ft. in diameter, erected in 1872 by order of Catherine de Médicis, for the purpose, it is said, of astronomical observations. — Behind the Bourse de Commerce are the —

***Halles Centrales** (Pl. R, 20, 23; *III*), a vast structure, chiefly of iron, and covered with zinc, erected by the architect *Baltard* (d. 1874). These 'halls' consist of ten pavilions (to which two more are to be added), between which run covered streets, 48 ft. wide, and 48 ft. in height, and they are intersected by a boulevard 105 ft. in width, descending towards the Rue de Rivoli. The six pavilions on the E. side of the boulevard occupy a space of 182 by 136 yds., and the whole market when complete will cover an area of 22 acres. Each pavilion contains 250 stalls, the area of each of which is 40 sq. ft., and the rent 20 c. per day. Under the Halles there are 1200 cellars for the storage of goods, each 12 ft. high, and lighted with electricity.

The provisions for the daily market begin to arrive on the previous evening, and by daybreak the market is fully stocked. The sales by auction to wholesale dealers last till 8 or 9 a.m., after which the retail traffic begins. About 500,000 fr. per day are realised in the wholesale market alone. The supplies, many of which come from Algeria, include meat, fish, poultry, game, oysters, vegetables, fruit, butter, and cheese. The show of flowers, especially in summer, is a charming sight.

The produce annually brought to the Halles include 65,000,000 lbs. of fish, 250,000,000 oysters, 66,000,000 lbs. of meat, 55,000,000 lbs. of poultry and game, 27,000,000 lbs. of butter, 350,000,000 eggs, and 15,000,000 lbs. of cheese. This, however, represents but a fraction of the food consumed in Paris, as not only are there several other 'Halles', but many dealers import their own goods without the intervention of a market. According to the most recent calculations the average annual consumption per head of population amounts to 325 lbs. of bread, 186 quarts of wine etc., 187 lbs. of meat, and 23 lbs. of fish. Reckoning the population at 2,345,000, we find that this amounts in round numbers to 764,000,000 lbs. of bread, 437,000,000 quarts of wine, and 438,000,000 lbs. of meat, and 54,000,000 lbs. of fish, of the value of fully a milliard of francs. Thus the daily bill of Paris for meat, wine, and bread alone amounts to about 3 million francs or 120,000*l.*

The Halles occupy the old *Marché des Innocents*, which was once adorned with the *Fontaine des Innocents*, a tasteful Renaissance work by *Pierre Lescot*, but frequently altered. The fountain now occupies the centre of a square to the S.E. (Pl. R, 23; *III*), on the other side of the Halles. It originally stood with its back to the church of the Innocents (demolished in 1783), and had three arches only. It now presents the somewhat incongruous form of a square pavilion, a fourth arch having been added. The older figures of Naiads are by *Jean Goujon*.

The **Church of St. Eustache* (Pl. R, 21, 20; *III*), situated at the *Pointe St. Eustache*, to the N.W. of the Halles Centrales and at the end of the Rue Montmartre and Rue de Turbigo, is one of the most important though not the most interesting buildings in Paris. It was erected in 1532-1637, and presents a strange mixture of degenerate Gothic and Renaissance architecture. The disposition of the building is that of a Gothic church of the 15th cent., but the arches are round instead of pointed, the buttresses are in the form of composite pilasters, and the pillars consist of columns of different orders placed above one another. The ornamentation is in the Renaissance style. The chief portal is a mediocre work of the 18th century. The funeral rites of Mirabeau were solemnised in 1791 in this church, from which the body was conveyed to the Panthéon; and here was celebrated the Feast of Reason in 1793. In 1795 the church was handed over to the 'Theophilanthropists', who turned it into a temple of agriculture.

THE INTERIOR (entrance by the chief portal or by a side-door near the Rue Montmartre) consists of a graceful and lofty nave and double aisles, and is 348 ft. in length, 144 ft. in width, and 108 ft. in height. The chapels, entirely covered with painting, contain some fine *Frescoes, illustrating the history of the saints to whom they are dedicated. The paintings in the 4th and 5th chapels to the right are by *Gourlier* and *Magimel*. The former also contains a Marriage of the Virgin, carved by *Triqueti*, and the latter an Ecce Homo by *Elex* and a figure of Resignation by

Chartrousse. — In the S. transept are bas-reliefs by *Devers*, six statues of Apostles by *Debay*, and frescoes by *Signol*. — Farther on are five chapels adorned by *Larivière*, *Vaugetet*, *Lazerges*, *Cornu*, *Pils*, *Damery*, *Biennoury*, and *Signol*. — The *Chapelle de la Vierge*, which we next reach, was added at the beginning of the present century. Over the altar is a fine statue of the Virgin by *Pigalle* (d. 1785). The frescoes are by *Couture* (d. 1879). — The next chapel, with frescoes by *Bézar*, contains the monument of *Colbert* (d. 1683), the able minister of finance of Louis XIV., consisting of a sarcophagus of black marble, with a kneeling figure of Colbert in white marble, by *Coyzevox* (d. 1720). At one end is a statue of Abundance by *Coyzevox*, at the other end one of Religion by *Tuby* (d. 1700). — The five other chapels flanking the choir contain frescoes by *Delorme*, *Basset* (early frescoes restored), *Perruz*, *Pichon* (St. Geneviève), and *Félix Barrias* (St. Louis). — The short N. transept is also adorned with bas-reliefs and frescoes by the same masters as those in the S. transept, and statues of Apostles by *Crauk* and *Husson*. Above a bénitier is a fine group of Pope Alexander I., by whom the use of holy water was introduced. — Handsome N. portal, which faces a lane leading to the Rue Montmartre. Beyond the transept is the chapel of St. Eustache, who was a Roman general under the Emp. Titus, with frescoes by *Le Hénaff*. Lastly, four chapels with paintings by *Basset* (restorations), *Riesener*, *Marquis*, and *Glaize*.

The high-altar in white marble, the modern pulpit in carved wood by *Moisy* and *Pyenet*, the woodwork of the 'banc d'œuvre' (stalls), and the *Organ* (one of the best instruments in Paris) are also worthy of note.

St. Eustache is much frequented, especially on festivals, on account of the excellence of the music. Rossini's 'Stabat Mater' is performed here on Good Friday, with the aid of the orchestra of the Conservatoire and the singers of the Opéra and Opéra Comique. A solemn musical mass, with the same artistes, is given on St. Cecilia's Day (22nd Nov.).

II. FROM THE HALLES CENTRALES TO THE PLACE DE LA RÉPUBLIQUE.

Conservatoire des Arts et Métiers.

The *Rue de Turbigo* (Pl. R, 21; III), a handsome new street about $\frac{3}{4}$ M. long, beginning at the *Pointe St. Eustache*, at the end of the Rue Montmartre, leads to the Place de la République (p. 70). It soon crosses the Rue Etienne-Marcel (p. 169), in which, near the point of intersection, rises the *Tour de Jean sans Peur*, a fine specimen of the defensive architecture of the 15th cent., disengaged from the houses by which it was formerly enclosed. This tower, with its pinnacles and pointed arches, once belonged to the Hôtel de Bourgogne, where the *Confrères de la Passion* established their theatre in 1548. A handsome spiral staircase in the interior leads to the top. (Apply at 23 Rue Tiquetonne, at the back.)

Farther on, the Rue de Turbigo crosses the *Boulevard de Sébastopol*, which we follow to the left. At the end of a side-street, on the right, rises St. Nicolas-des-Champs (p. 175). Farther on, also on the right side of the boulevard, is the pleasant SQUARE DES ARTS ET MÉTIERS (Pl. R, 24; III). In its centre rises a lofty column surmounted by a Victory in bronze, by *Crauk*, with a pedestal bearing the names of the Crimean victories. On each side are small basins adorned with bronze figures of Agriculture and Industry, by *Gumery*, and Commerce and the Arts, by *Ottin*. On the S. side of the square is the *Théâtre de la Gaîté* (p. 30).

Rue Vanca n s e

alerie

Arts chimiques
(céramique)
Verrière (étage)
Constructions civiles (rez-de-ch.)



Jardin

Arts chimiques
Papier

Horlogerie, etc. (rez-de-ch.)
Géodésie & astronom. (rez-de-ch.)
Mach. & appareils divers

Mécanique (1^{er} étage)
Poids et mesures (rez-de-ch.)
Mach. à vapeur (1^{er} étage)

Chemins
de fer (1^{er} et.)
Salle Echo
(rez-de-ch.)

Physique : télégraphie
Mach. à vap. Mach. à vap. Mach. à vap.

Arts chim.
Papier
Papeterie
Gravure
Lithogr.
Typogr.
Grav. etc.
Photo-
graphie
Photogr.

Cour
de l'Administration

Tissage. Filature
(1^{er} étage)

Nicolas
Leblanc

Denis
Papin


Entrée

Cour d'honneur

Entrée principale

Portefeuille industriel

Rue S^t Martin



The ***Conservatoire des Arts et Métiers** (Pl. R, 24; *III*), the great industrial museum of Paris, is open daily from 10 to 4 (Sun., Tues., and Thurs. free; on other days special permission necessary). The machinery is set in motion on Sundays only. All the articles bear inscriptions. The collections preserved here are probably the most extensive of their kind in Europe; the last catalogue (1882; price 1 fr. 75 c.) contains 9925 numbers and is by no means exhaustive. This handsome edifice was formerly the Benedictine Abbey of *St. Martin des Champs*, but was secularised in 1789, and is now thoroughly restored and disengaged from other buildings. A new gallery has recently been erected next the Rue St. Martin, to accommodate some of the collections while the main building is undergoing some necessary repairs. The portal, erected in 1848-50, bears an inscription recording that the abbey was founded in 1060, that the foundation of the Conservatoire was decreed by the Convention in 1794, and that it was transferred to this edifice in 1798. The principal entrance is by the modern door at the back of the square and up the great staircase in the court. Beside the staircase, to the right, is a bronze *Statue of Papin* (1647-1714), discoverer of the elasticity of steam, by Millet; to the left, one of *Nic. Leblanc* (1742-1806), the inventor of the process of extracting soda from sea-salt, by Hiolle.

Ground Floor. The *Vestibule* and the '*Salle-Echo*', which adjoins it, contain ploughs, a rolling-machine for metal sheathing, a model of the screw-steamer '*Danube*', and a fine collection of Siberian jade and graphite, illustrating the numerous industrial applications of the latter mineral. The acoustic properties of the *Salle-Echo* resemble those of the *Whispering Gallery* at St. Paul's in London: words spoken quite softly in one corner of the saloon are distinctly audible in the angle diagonally opposite.

NORTH SIDE (to the left). — *Salle 1.* French and foreign weights and measures, most of them standards. The staircase to the left leads to the N. Wing on the first floor (see below). — *Salles 2-4.* Watchmaking apparatus; chronometers; anemometers; escapements and pendulums; automata; geodetic and astronomical instruments; artistic locks, etc. — *Salles 5, 6.* Geometrical and astronomical instruments; relief-plans; quadrants; globes moved by clockwork, etc. — *Room 4* is adjoined by the —

NORTH WING, with a new gallery which contains objects connected with architecture and mensuration (*Constructions Civiles* and *Géométrie Descriptive*). We leave the gallery and the room to the left unvisited for the present and turn to the right into *Salle 1.* Marbles, iron, locksmith's work, woods used in veneering and inlaying, etc. — *Salle 2.* Models for instruction in geometry; drawing instruments. — *Salle 3.* Prepared stones; timber work and frames; interesting models. — *Salle 4.* Models illustrative of bridge-building, and other hydraulic apparatus. — *Salle 5.* Building-tools, building material; models of house-building; workshops and tools. — We now enter the Gallery, which contains large models of mining and boring machines, cranes and other appliances for lifting heavy weights, and specimens of different kinds of building stones. — *Salle 6.* Ventilation, lighting, and heating apparatus.

SOUTH SIDE (to the right). *Salle 1.* Objects connected with mining and the manufacture of iron (*Exploitation des Mines, Métallurgie*); models of machines, furnaces, and workshops; specimens of ore. — *Salle 2.* Rolling and forging of iron and steel; rolling-mill for armour-plating. — *Salle 3.* Copper, lead, and zinc metallurgy; blast furnaces, ventilating and boring machines; models of machinery for extracting oil from minerals. —

Salles 4, 5 Agriculture; models of implements, granaries, and silos; specimens of grain, fruit, etc.

S. WING, to the left. Valuable collection of ploughs and other implements; heads of cattle.

The old Church, the choir of which dates from the 12th, the nave from the 13th cent., formerly contained the machinery that was set in motion on Sundays. It is to contain a Gallery of Hygiene, but is at present closed, and the machinery has been removed to one of the new galleries in the garden. — From the church a staircase ascends to the —

First Floor, which we traverse from S. to N. The first part of the GALERIE PRINCIPALE contains models of wind-mills, a ship, hydraulic and steam machinery. Near the middle the series is interrupted by the collection of turning-lathes and other tools worked by hand (*Tours et Outils à Main*), part of which is contained in an adjoining room to the left. Among the interesting objects in this collection are several machines by *Vaucanson* (d. 1782). — The centre of the Galerie Principale and part of the E. corridor (next the garden) are devoted to the Railway Collection (*Chemins de Fer*). Farther on, the first N. wing (see below) opens to the left. The end of the gallery and an adjoining room contain chemical apparatus (*Arts Chimiques*) and various culinary and domestic appliances and models. — The room at the end of the gallery contains objects relating to gas-making and lighting (*Industrie du Gaz, Appareils d'Eclairage*).

I. N. WING (to the left of the Galerie Principale). Spinning and weaving machines (*Filature et Tissage*). Sec. 1: Tools and machines for the preparation of textile fabrics. — Sec. 2: Spinning and weaving looms; to the right a large loom on *Vaucanson's* system; to the left a model of the *Jacquard* loom. Specimens of woven fabrics. — Sec. 3: Silk fabrics; dyed goods; tapestry from the Gobelins and Beauvais; a large Sèvres vase.

II. N. WING (to the left, at the end of the Galerie Principale). Continuation of the *Arts Chimiques*, and four rooms devoted to the *Arts Graphiques*. — Salle 1. Apparatus for carbonising and preserving wood; artificial combustibles. — Salles 2 & 3. Paper-making; the raw material used in the manufacture, and various kinds of finished paper. — Salles 4 & 5. Typography, engraving, and lithography; printing-presses, writing and copying machines, products of the graphic arts. — Salles 6 & 7. Photographs.

III. N. WING (opposite the last, on the side next the garden). Continuation of the *Arts Chimiques*; dyeing processes (*Teinturerie*); also glass (*Verrerie*) and porcelain (*Art Céramique*). — Salle 1. Chemical apparatus and products, such as powder, lime, gypsum, and cement; machinery for finishing, dyeing, and printing textile fabrics. — Salle 2. Modelling workshops (*Ateliers*); furnaces and machinery for making porcelain; porcelain statue of Bernard Palissy (p. 143); objects in hard and soft porcelain, some with very interesting ornamentation; enamels; faience. — Salle 3. Glass and crystal; artificial gems; a lump of *avanturine*. — Salle 4. Foreign glass and pottery.

Parallel with the Galerie Principale, on the side next the garden, runs a CORRIDOR, commanding a view of the new Ecole Centrale des Arts et Manufactures. Sec. 1: Models and devices illustrating *Kinematics*, or the theory of mechanical motion, especially the various kinds of transformation and transmission of motion; indicators; dynamometers; winches, capstans, cranes; calculating machines. In the middle are objects belonging to the railway collection mentioned above. — Sec. 2: *Physical Cabinet*. Electrical, acoustic, and optical instruments; telegraphic models, telephones, musical instruments, mirrors, camera lucida, etc.

S. WING. Physical Apparatus. Sec. 1: *Physique Mécanique*. Instruments for the study of the laws of gravity, impact, and momentum. — Sec. 2: *Physique Générale*. Pneumatic and hydrostatic machines; electric and electro-magnetic machines; instruments exemplifying the action of heat and radiation. — Sec. 3: *Salle de Lavoisier; Météorologie*. The apparatus with which Lavoisier recomposed water; thermometers, hygrometers, barometers, anemometers, etc.

The *Refectory of the ancient abbey, a beautiful Gothic hall, 47 yds. in length, and 7½ yds. in width, erected about the middle of the 13th

cent. by *Pierre de Montereau* (p. 218), has been judiciously fitted up as a *Library* (over 30,000 vols.). The vaulted ceiling with its handsome moulding is borne by seven slender columns, and the whole saloon is tastefully painted and gilded. The library is open to students only, from 10 to 3 and from 7.30 to 10 o'clock daily, except on Mondays, when it may be inspected by the public; a glimpse of it may, however, be obtained on other days. Entrance in the court, to the right.

Courses of public lectures, embracing the various provinces of industrial activity, for the benefit of artisans and others, are delivered here (see notices at the entrance). — The building to the N. (left) of the main entrance contains the '*Portefeuille Industriel*', where drawings of the newest machinery are exhibited for copying or study. The plans and specifications of patents are deposited and trade-marks are registered here (adm. daily 10-3, except Mon.).

The Rue St. Martin, which passes in front of the Conservatoire des Arts et Métiers, leads to the N. to the neighbouring boulevard and gate of the same name (p. 71). A few paces in the opposite direction (S.) is situated the church of **St. Nicolas-des-Champs**, a Gothic church, which was enlarged in the 15th cent., with a choir reconstructed in the Renaissance style. The handsome portal is flanked with a square tower on the right. The high-altar is adorned with an Assumption by *Simon Vouet*. The woodwork of the organ is also worthy of mention.

The Rue Réaumur, to the left of the church, leads us back of the Rue de Turbigo, and thence to the Square du Temple (p. 74). In the Rue de Turbigo, to the left, is the large *Ecole Centrale des Arts et Manufactures*, designed for the training of managers of industrial establishments, engineers, superintendents of public works, and teachers of industrial subjects. The pupils are admitted by competitive examination, and the course lasts three years. — Farther on, the Rue de Turbigo passes the *Ecole Municipale Turgot*, and the back of the church of *Ste. Elisabeth*, and soon reaches the Place de la République (p. 70).

III. FROM THE PLACE DE LA RÉPUBLIQUE TO PÈRE-LACHAISE.

The Cemetery of Père-Lachaise being nearly 1½ M. distant from the Place de la République, the visitor is recommended to drive thither (tramway F, 'en correspondance' with omnibus P). A slightly shorter route is via the Avenue de la République, recently prolonged as far as the cemetery. — Luncheon, see p. 168; the restaurants near the cemetery are inferior.

Leaving the Place, we follow the BOULEVARD VOLTAIRE (Pl. R, 26, 29; III), a handsome modern street, 2 M. long, leading straight to the Place de la Nation (p. 210), and traversed by the tramway to Vincennes. In about 7 min. from the Place we cross the Boulevard Richard-Lenoir, beneath which passes the Canal St. Martin (p. 186). Here stands the *Monument Bobillot*, erected in 1888 to the memory of French soldiers killed in Tonkin, with a bronze statue, by Aug. Paris, of Sergeant Bobillot, who fell at Tuyen-Quan. — A little farther on, to the left, rises the handsome Romanesque church of *St. Ambroise* (Pl. R, 29), erected by Ballu in 1869. The façade is flanked with two fine towers, 223 ft. high. Mural paintings in the interior by *Lenepveu* and stained glass by

Maréchal. — We next reach the *Place Ledru-Rollin* (Pl. R, 29), with the *Mairie du XI^e Arrondissement* and a *Statue of Ledru-Rollin* (d. 1874), the 'organiser of universal suffrage', by Steiner. To the left is the *Avenue Parmentier*, which passes near the *Square Parmentier*, embellished with a bronze group ('Non omnes morimur'), by Périeux.

Crossing the Place to its E. angle, we next follow the *Rue de la Roquette*, near the middle of which rise two massive, castellated edifices. That on the right is the **Prison de la Roquette**, in which condemned convicts await their execution or deportation. On the left is the *Prison des Jeunes Détenus*. Between these two prisons is the public place of execution.

On 24th May, 1871, during the Communist 'reign of terror', the Prison de la Roquette was the scene of the murder of the venerable Mgr. Darboy, Archbishop of Paris, the President Bonjean, the Abbé Allard, and three other priests, who had been seized by the Commune as 'hostages'. On 26th and 27th May thirty-seven persons imprisoned here by the Commune under various pretences were also shot, and on the night of the 26th twenty-eight gendarmes were conveyed from the Roquette to Père-Lachaise, where they shared the same fate. On the afternoon of the 27th all the convicts confined in the Roquette were liberated. Arms were placed in their hands, and they at once proceeded to massacre the persons imprisoned by the Commune, including seventy gendarmes. The approach of the troops, however, fortunately saved many who would otherwise have fallen victims to the same fiendish spirit of revenge.

Dépôts of tombstones and shops for the sale of wreaths and flowers now indicate that we are approaching the cemetery, which lies at the end of the Rue de la Roquette.

***Père-Lachaise** (Pl. R, 32), or *Cimetière de l'Est*, the largest and most interesting of the Parisian burial-grounds, lies on a hill at the N. E. end of the town, and is named after *Lachaise*, the Jesuit confessor of Louis XIV., whose country-seat occupied the site of the present chapel. In 1804 the ground was laid out as a cemetery, the precincts of which have since been greatly extended, and it now covers an area of about 110 acres. It is the burial-place of the inhabitants of the N.E. part of Paris, but persons of distinction from other parts of the city also are generally interred here. — On 30th March, 1814, the cemetery was the scene of an engagement between Russian and French troops, in which the former were victorious. On the 25-27th May, 1871, a series of violent struggles took place between the Communists, who had taken up and barricaded a position here, and the Versailles troops advancing from the Place de la République and the Bastille. With the help of a heavy bombardment from the batteries of Montmartre the latter succeeded in dislodging the insurgents.

Paris possesses 22 burial-grounds, of which the most important are those of Père-Lachaise, Montmartre (p. 191), and Montparnasse (p. 260). These, however, would hardly suffice for the 80-100 graves required daily, were it not that the poor who are buried gratuitously, forming nearly two-thirds of the community, are committed to the *Fosses Communes*, or large pits, each containing 40-50 coffins. Burials in 'common' graves now take place in the cemeteries outside the precincts of the city only, such

Avenue transversale

BOULEVARD DE MÉNILMONTANT

Rue de la V Roquette

le principal



1:4250

CIMETIÈRE
DU
PÈRE LACHAISE.

1:4250

0 20 40 60 80 100 120
Mètres

Place de la Nation (du Trône)

Wagner & Debes, Leipzig

as those of St. Ouen (p. 201) and Ivry. A *Concession Trentenaire*, providing that the grave shall remain undisturbed for 30 years, costs 300 fr.; a *Concession Temporaire*, for 5 years, costs 50 fr. A *Concession à perpétuité*, or private burial-place, may be secured for 700 fr., or half that sum for a child under seven. These spaces are very limited, being about 22½ sq. ft. only. The charge for a larger space is augmented in an increasing ratio, the price of each square mètre (about 11½ sq. ft.) beyond six being 2000 fr.

All burials within the Department of the Seine are undertaken by the *Compagnie des Pompes Funèbres*, Rue d'Aubervilliers 104, whose charges are regulated by tariff, varying from 12 fr. 75 c. to 7144 fr., exclusive of the fee of the officiating clergyman. Two chaplains are attached to each cemetery for the gratuitous performance of the burial-service for the poor.

In summer the cemetery is open from 7 a.m. till 7 p.m.; in spring, autumn, and winter till sunset. Half-an-hour before the closing of the gates a bell is rung, and the custodians call out, '*On ferme les portes*', allowing ample time for visitors to reach the gates. Visitors are not permitted to carry anything out of the cemetery without a '*laissez-passer*'.

It may be observed here that it is the invariable custom for persons to take off their hats on meeting a funeral procession, whether in the cemetery or in the public streets.

Conducteurs will be found at the small building to the right on entering, but their services (3 fr.) are rendered unnecessary by the accompanying plan, unless the visitor is much pressed for time.

Even a superficial survey of the most interesting monuments in the cemetery will occupy 3-4 hours. On All Saints' Day (*Jour de la Toussaint*) and All Souls' Day (*Jour des Morts*; November 1st and 2nd) it is visited by about 100,000 people. The number of monuments in this vast necropolis amounts to about 20,000, many of which are deeply interesting as memorials of illustrious persons, while others are noteworthy on account of their artistic excellence. Well-shaded walks and avenues intersect each other in every direction, and many of them afford an admirable view of the city.

We follow the route indicated on the plan by means of arrows. Hurried visitors may omit the parts described in small type.

In the *Avenue Principale*, to the left: *Pineyro* (d. 1874), the marble monument of a child, with a figure of Hope.

We follow the second lateral avenue to the right, called the *AVENUE DU PUITS*. — To the left: *Worms de Romilly*; a handsome granite chapel. In the side-walk to the left: *St. Victor* (d. 1881), the author, and *Berthelier* (d. 1882). Farther on in the *Avenue du Puits*, to the left: *P. L. Dulong* (d. 1838), chemist and physician; obelisk with medallion by David d'Angers. — Farther on: *Abélard* (d. 1141) and *Héloïse* (d. 1163), sarcophagus with recumbent statues, beneath a Gothic canopy, reconstructed from the fragments of an old monument by Lenoir (p. 247), and lately restored.

Abélard, according to the well-known story, was a learned theologian, who, having married his pupil Héloïse, was afterwards separated from her by jealous relations and cruelly mutilated. The monument is partly constructed of fragments from the convent of Paraclet, near Nogent-sur-Seine, which Abélard had founded, and where the tomb was originally

situated. The tomb is often decorated with fresh flowers and wreaths, the offerings of those who regard this as the shrine of disappointed love.

To the W. of this point lies the Jewish burial-place.

Visitors whose time is limited should now ascend the AVENUE CASIMIR-PÉRIER to the Grand-Rond (see below).

In the lateral path, to the left: *Serré* (d. 1857), captain of cavalry. — We now ascend to the left by the second side-path. On the right: **Baron Desbassayns*; a weeping figure by Ricci. On the left: **Fr. Lebrun* (d. 1824), Duke of Piacenza, Third Consul after the 18th Brumaire, and translator of Homer and Tasso, as indicated by the genii.

On the right: *Victims of June, 1832*. — On the left: *Marshal Lauriston* (d. 1828); also a chapel of the *Laroche-foucaulds*. — We turn to the right here and return in the opposite direction, by a path flanked with handsome new monuments, to the Chemin Serré, where we observe the tasteful *Chapelle Boutet*. We then again ascend to the left by another path flanked with imposing modern chapels. To the right, *L. Cogniet* (d. 1880), the artist. At the top, on the left: *Nélaton* (d. 1873), the eminent surgeon; chapel of the *Lesseps* family.

Turning to the left, we soon reach the walk adjoining the Victims of June, and opposite that monument we turn to the right and then to the left. Among the trees to the left: *Bail*, a handsome 'pleureuse' in marble. Farther on, to the right, near the edge of the other walk: *Count La Bédoyère*, colonel of the first regiment which went over to Napoleon on his return from Elba, afterwards condemned to death, and shot (1815). The ill-fated man had arranged to sail for America, but incautiously returned to Paris to take leave of his wife and child, and was there arrested. The sculptures refer to this affecting incident. — Beyond this monument, on the right side of the same path: *Victor Perrin, Duc de Bellune* (d. 1841), marshal of the empire, and French ambassador in Vienna under Louis XVIII. — We now reach the —

GRAND ROND. — In the centre: **Casimir Périer* (d. 1832), deputy, a famous orator, and minister of Louis Philippe; a statue in bronze by Cortot, on a lofty pedestal. — On the N. side: **Raspail* (d. 1878), the famous democrat; a covered monument adorned with crowns; admirable bas-relief by Etex, in memory of the death of Raspail's wife during his imprisonment for the conspiracy of May, 1848, to dissolve the National Assembly. — Farther on, to the right: **Crusol d'Uzès*, general; handsome allegorical bas-reliefs. — Nearer the Grand-Rond, to the left of Raspail: *Gall* (d. 1825), the phrenologist; *Monge* (d. 1820), the mathematician.

We now follow the broad Avenue de la Chapelle as far as the Chemin Méhul, the first side-path to the left. On the right, opposite a broad walk to which we shall return: *Talma* (d. 1826), the famous tragedian. Our walk turns to the left. On the right: *Ravrio* (d. 1814), manufacturer of bronze. Then, on the left: **Cherubini* (d. 1842), the composer; bas-relief by Dumont. Right: **Denon* (d. 1825), director of museums; statue by Cartellier; *Gohier* (d. 1830), president of the Directory; medallion by David. Left: **Chopin* (d. 1849), pianist and composer; statue by Clésinger. Behind: **Wilhem* (d. 1842), composer; medallion by David. A few paces farther, at the foot of a small flight of steps, *Gareau*, with a beautiful figure of a weeping woman.

We turn to the left of the clump of trees. Right, a little way back: **Borsa* (d. 1820); monument with a high relief; farther on,

Héroid (d. 1833), composer; *Mme. Blanchard* (d. 1819), an aéronaut who perished while making an ascent.

Again turning to the left, we enter a plot specially dedicated to artists, round which we have already passed. This is one of the oldest parts of the cemetery, where the monuments are disposed with little regard to regularity. To the left of the walk opposite Talma: the two *Brongniarts*, the mineralogist (d. 1847), and the architect (d. 1813); *Héroid* (d. 1882), prefect of the Seine; on the right, *Lesueur* (d. 1837), composer; **Tamberlick* (d. 1889), the tenor, with an angel strewing flowers, by Godebski. At the end of the allée, *Delille* (d. 1813), the poet, in a tasteless style. Behind: **Bellini* (d. 1813), the composer, whose remains have been removed to Catania, his native place; *Grétry* (d. 1813) and *Boieldieu* (d. 1834), composers.

We cross the walk we have hitherto followed, pass a column in memory of *Mme. Lavoisier*, skirt the monument of Casimir Périer on the right, and follow the AVENUE DES ACACIAS, to the right of Raspail's tomb. — On the left: *Champollion* (d. 1836), the celebrated Egyptologist. Then: *Kellermann* (d. 1820), Duc de Valmy, marshal of France. Higher up is the *Démidoff Chapel* (p. 181). Then: *Serres* (d. 1868), professor of medicine. **A. Duchesnois* (d. 1835), the tragic actress; bas-relief by Lemaire. — Right: *Maret*, Duc de Bassano (d. 1839), diplomatist, and minister under the first empire; a temple with Doric columns, without inscription. — Left: *Sieyès* (d. 1836), the statesman, member of the Convention and Directory, and consul after the 18th Brumaire. Then, right: **Panhard Dufour*, a handsome chapel. Left: **Gouvion Saint-Cyr* (d. 1830), marshal of the empire; statue by David. *Macdonald* (d. 1840), Duc de Tarente, marshal of the empire. Right: chapel of the *De Biré* family, containing a **Bas-relief* of Christ as the vanquisher of death, by Duseigneur. To the left, above, Baron Gobert (see below), an equestrian statue. At the foot of the flight of steps on the right, **Edmond About* (1885), author, with bronze statue by Crauk; to the right *Crespin aîné*, organizer of the 'vente à crédit', bust and bronze statue by E. Leroux. To the right of the Avenue des Acacias, **Ch. de Lavalette* (d. 1830), general, and director of the post-office, who was condemned to death in 1815, but escaped from prison by exchanging clothes with his wife. Left: *Dupuytren* (d. 1835), the celebrated surgeon. Right, before we reach the lateral avenue: *Monod* (d. 1856), president of the consistency of the Protestant church. On the left of the side-walk: *Count Belliard* (d. 1832), general, and French ambassador at Brussels. Behind: large chapel of the *Marquise de Dalmatie* (d. 1866). Right, a little way back: **Schickler*, a chapel with caryatides, facing the other direction. Below, **d'Hauregard*, Renaissance chapel, with statues. From this point we enjoy a fine view in the direction of Vincennes, the tower of which is distinguishable.

Returning to the Avenue des Acacias, we observe on the right the monument of *Eugène Scribe* (d. 1861), the well-known dramatist.

Farther on we ascend a flight of steps to the Chemin des Anglais, on the right. Left: large chapel of the *De Rougemont* family. Farther on, right: *Destors*, a handsome Renaissance chapel. Adjacent: *Count Monserrat* (d. 1820), general. Left, beyond a footpath: *Picard* (d. 1829), dramatist. Right: *Audiffret*. Left: *Admiral Sir Sidney Smith* (d. 1840), who defeated Napoleon at St. Jean d'Acre in 1799. Farther on, right: **Triqueti* (d. 1874), sculptor; bas-relief of the Raising of Lazarus, by himself. A little farther up: *A. Blanqui* (d. 1881), the revolutionary; statue, in bronze, by Dalou.

We now retrace our steps, turn to the left, and follow the AVENUE TRANSVERSALE No. 1. At the corner: *A. de Bruges* (d. 1820), general. On the same side: *D. de Pradt* (d. 1837), bishop of Malines, statesman, and publicist. **Forestier*, with a statue by Toussaint. Beyond a footpath: *Count Truguet* (d. 1839), admiral and statesman. Right: *Enfantin* (d. 1864), the St. Simonian; colossal bust by Millet. Left, in descending: *Count Pachod* (d. 1830), general.

At the corner, right: *Delanneau* (d. 1830). Then: **Marshal Suchet* (d. 1826), Duc d'Albuféra. Farther on, left: *Ruty* (d. 1823), general. Right, beyond a side-walk: *Marshal Lefebvre* (d. 1820), Duc de Dantzick. **Marshal Masséna* (d. 1817), Duc de Rivoli and Prince d'Essling; monument by Bosio and Jacques. Then, left: *Windsor* (d. 1830), introducer of gas-lighting; *Larrey* (d. 1848), surgeon. Farther on: **Baron Gobert*, a general killed in Spain in 1808, and his son (d. 1833); a group and bas-relief by David. Opposite: *Beaumarchais* (d. 1799), dramatist. At a bifurcation: *Marshal Ney* (d. 1815), Prince d'Elchingen and Duc de la Moskowa (see p. 260); no monument marks the grave of the 'brave des braves'. We follow the same path to the right. Left: *Bassompierre* (d. 1877), engineer. **Prince and Princess Bibesco*, Wallachia; a Byzantine chapel. Farther on: **Foy* (d. 1825), a general and celebrated orator; statue and bas-reliefs by David.

Many of the monuments we are now about to mention may be passed over, but those of Lord Seymour and Béranger deserve a visit.

After Foy, in the same walk: *Stan. de Girardin* (d. 1827), politician. Then *Girodet-Trioson* (d. 1824), the painter. At the end of the walk, to the left, beyond a lateral path: family of *Victor Hugo* (for the poet's own tomb, see p. 238).

In the walk leading hence to the right, on the left side: *C. Jordan* (d. 1821), member of the Council of Five Hundred. Farther on, left: *Turpin* (d. 1840), naturalist. Then the mausoleum of *Boode*, merchant of Amsterdam. *Cambacérès* (d. 1824), jurist, and second consul after the 18th Brumaire. Behind, right: *Bourke* (d. 1821), Danish ambassador; bas-relief by David d'Angers (d. 1856), whose own plain monument is in the third row, not far from Boode. — At the end of the walk, left: *Admiral Decrès* (d. 1821), duke and minister of the first empire.

We have now regained a part of the cemetery which we have already visited, and enter the clump of trees to the right, soon reaching the large and handsome chapel of **Lord Seymour*; then that of *Marshal Mortier* (d. 1835), Duc de Trévisé, and minister. Then *Manuel* (d. 1827), popular deputy, and *Béranger* (d. 1857), the poet, buried, according to his wish, in the same grave as Manuel. To the left, three columns of the brothers *Lameth* (d. 1829, 1832, 1854).

We next follow the Chemin du Dragon, opposite Foy's monument. Right: *Barton*, one of the largest family burial-places in the cemetery,

with a representation of the arrangement of the interior at the back. Left: **Boerne* (d. 1837), German poet; medallion and bas-relief by David. Right: **Admiral Bruat* (d. 1855). Left: the two *Garnier-Pagès* (d. 1841, 1878), distinguished politicians; monument by David. **Geoffroy Saint-Hilaire* (d. 1844), naturalist; medallion by David. **Démidoff*, countess (d. 1818), and prince (d. 1870), members of a wealthy Russian family; a superb mausoleum in a semi-oriental style. Farther on, same side: *Perry*, a chapel with a good bas-relief. At a corner: *Gaudin* (d. 1841), Duc de Gaète, minister. Left, in the same walk: **Duret* (d. 1865), sculptor; bas-relief and medallion. Then *Mazet* (d. 1871), lieutenant. Nearly opposite this walk: *Désaugiers* (d. 1827), poet. Right: *Pradier* (d. 1852), sculptor.

We now ascend the Chemin Molière et Lafontaine to the right. Right: *Gay-Lussac* (d. 1850), chemist. Left: *Lafontaine* (d. 1695), fabulist, and *Molière* (d. 1673), dramatist, transferred hither in 1804. Farther on: *Le Roi* and *Mailland*; surmounted with a fine statue of Cleopatra. To the right: **Elis. Coulson* (d. 1888); **C. Say* (d. 1871), a large Gothic chapel.

To the right of the walk which begins nearly opposite Gay-Lussac: *Laplace* (d. 1827), mathematician. A little way back: *Count Aboville* (d. 1843), general. Among the trees, in front: *Gros* (d. 1835), painter; and, farther off, the large obelisk of *Countess Gémont*. To the left of the path: *Count de Valence* (d. 1822). Behind: *Daubigny* (d. 1878), painter, with a bust. Farther on, to the left: *Marquis de Pérignon* (d. 1818), marshal of France. To the right: *Nelle* (d. 1851).

TRANSVERSE AVENUE (which we have now regained). Left: *Gourgaud* (d. 1852), general. Farther on, right: **Aguado* (d. 1842), financier. Left: *Rogniat* (d. 1840) general. Then the **Marquis d'Argenteuil* (d. 1838), founder of several charitable institutions.

We retrace our steps and descend to the right. Left, somewhat hidden: *Ingres* (d. 1867), historical painter; bust by Bonassieux. Right side of the avenue: **M. Schoelcher* (d. 1852); high-relief in bronze by Fromanger. — We take the walk to the right, and then ascend the avenue parallel with the last. Nearly opposite the walk: **Vve. Schoelcher* (d. 1839); recumbent figure in bronze. We now regain the avenue.

TRANSVERSE AVENUE (continuation). At the corner beyond the *Marquis d'Argenteuil*: *Persil* (d. 1841), deputy. At the other corner: the handsome *De Tencé* chapel.

In the first walk to the right: *Kardec* (d. 1869), 'fondateur de la philosophie spiritiste'; a curious monument in the form of a dolmen. **Marquis de Casariera*, a large chapel containing a statue. To the left: *Mme Rouvier* (d. 1888), better known as *Claude Vignon*, bronze bust by herself.

In the transverse avenue, left: *Daoust*, *Micard*, and *Repond*, three handsome monuments. — At the end of the avenue: **F. de Beaujour* (d. 1836), formerly consul, a conspicuous pyramid 105 ft. in height, visible from the Arc de l'Etoile, and commonly called the

'pain de sucre', erected by himself at a cost of 100,000 fr. — Nearer the path: **Dias Santos*; a lofty pyramid with sculptures by Fessard. — **View of Paris from the back of the Beaujour monument.* — To the right, *General de Wimpffen* (d. 1884), bronze bust by Richard; farther down, **A. Florens* (d. 1885), fine bas-relief by Boussard.

The upper part of the cemetery, formerly used for temporary graves and 'fosses communes', contains few monuments as yet. Near the W. end of the Avenue Transversale 2, however, stands the magnificent **Chapelle Yakovleff*, a marble structure in the Byzantine style, with paintings on a gold ground, by Fedoroff.

The adjoining door leads to a public Garden, laid out in 1890 between the cemetery and the new part of the Avenue de la République, which ends a little farther on in the Place des Pyrénées (p. 184).

Within the cemetery, beyond the second transverse avenue, is the Crematorium, opened in 1887 but not much used as yet. The price of cremation is 50 fr.

We again descend to the left. On the left: *Beaucé* (d. 1875), painter. Right: *Em. Souvestre* (d. 1854); *Balzac* (d. 1850); left: *Nodier* (d. 1844); **C. Delavigne* (d. 1843): four well-known authors. At the corner to the right: **Mme. de Faverolles*; **Delphine Cambacérès*; *Lachambeaudie* (d. 1872), fabulist; *Soulié* (d. 1847), novelist. — Lower down: **Dorian* (d. 1873), manufacturer, and minister during the siege of Paris; statue in bronze. Behind: **Mme. Moris* (d. 1875); group in bronze. Higher up: **Duc de Morny* (d. 1865), politician and minister, a natural brother of Napoleon III.; a chapel designed by Viollet-le-Duc. To the left of the Chemin du Bastion: **Michelet* (d. 1875), the historian; high relief by Mercié. Then *Delpech* (d. 1865), engineer; *Buloz* (d. 1877), editor of the 'Revue des Deux Mondes'. Beyond the next corner: *Savalle* (d. 1864), engineer; *Andrianoff*, Russian 'danseuse'. Left: *Delacroix* (d. 1843), painter; a very plain memorial, as desired by the deceased.

In the lateral path passing to the right of the Savalle tomb, left: *Crozatier* (d. 1855), sculptor. Right: handsome Gothic chapel of the *Guilhem* family. — Farther on we descend to the right. On the right side: *Fabre* (d. 1839), dramatist. — On the adjoining walk, left: **Roelofson* (d. 1871); marble tombstone with bas-relief.

THE CEMETERY CHAPEL contains nothing noteworthy. To the right is a large chapel with the sarcophagus of **Ad. Thiers* (d. 1877), the celebrated statesman. To the left: *Baron Taylor* (d. 1879), traveller and author; marble statue by G. J. Thomas.

To the right, at the beginning of the part of the avenue leading to the monument of Casimir Périer (p. 178): *Géricault* (d. 1824), the painter; statue and bas-relief, in bronze, by Etex.

The W. part of the AVENUE DE LA CHAPELLE is flanked with many handsome new monuments. Right: *Desèze* (d. 1828), one of the defenders of Louis XVI. **Cartellier* (d. 1831), sculptor; bust by Rude, bas-reliefs by Seurre. Farther on, right: *Seminario*, a handsome Gothic chapel. — At the corner of the avenue ascending to the right: *Cotes*; a chapel adorned with frescoes and bas-reliefs. Left:

**Boutillier*; a large and rich Romanesque chapel. Farther on: *Bizet* (d. 1875), composer of the opera 'Carmen'; a bust in bronze. Then to the right: *Ragot*; a Renaissance chapel. Left: *Guégnier*; a chapel with a fine pediment. Adjacent: *Acard*; a large Renaissance chapel. Right: **Gréger*; a Byzantine chapel embellished with paintings. Left: *Errazzu*, with four symbolical statues by M. Meusnier. Left: *Schmit*, a curious-looking chapel; *Horeau*, monument of a young girl, regarded as one of the curiosities of the cemetery; *Marie Royer* (d. 1873), of the Comédie Française. At the corner: **Cail* (d. 1858), engineer; a chapel with a dome.

At the end of the avenue, left: **Soldiers who fell in 1870-71*; a pyramid of granite with four bronze statues of soldiers by Schroeder and Lefèvre, erected by Government. Adjacent: *National Guards killed at Buzanval* (19th Jan., 1871). **Jean Reynaud* (d. 1863), philosopher and publicist; figure of Immortality by Chapu and bronze medallion by David.

In the avenue ascending past the Cail chapel, right: *Barillet* (d. 1873), gardener to the city of Paris. *Cleray* (d. 1882), bronze bust by Taluet; *Avilès*, with a figure of a mourner; *Appel* (d. 1882), handsome Renaissance chapel. *Crocé-Spinelli* and *Sivel* (d. 1875), victims of a balloon accident; recumbent figures in bronze, by Dumilâtre. *Grisar* (d. 1869), composer; *Lebertre*, a fine Renaissance chapel. Right, near Dorian (p. 182): *Desclée* (d. 1874), actress.

We now descend by the avenue to the right of Dorian. Left: *E. Adam* (d. 1877); bust in bronze by A. Millet. *Convents* (d. 1877), architect. *Molz* family, a handsome granite chapel with a bronze coping. *Ricord* (d. 1876), medical specialist; a fine Renaissance chapel. **Countess d'Agoult* (d. 1873), who wrote under the pseudonym of Daniel Stern; a sumptuous white marble tombstone with an allegorical relief. Opposite: *Ségalas* (d. 1876), member of the Academy of Medicine. — Lower down runs the Avenue de la Chapelle, which we have already seen. We now descend the flight of steps by the Boutillier monument.

A path to the left is flanked with the handsome tombstones of persons unknown to fame. Left: *J. Belloir*; a handsome granite sarcophagus with gilded ornamentation. Higher up, right: *Perelli* (d. 1871), commandant of carabineers; bust in bronze by Marchi. Among the trees, farther back: *Martinet* (d. 1867), printer; medallion by Etex. Then *David* (d. 1825), the painter; medallion in bronze. Lower, at the corner: *Neigre* (d. 1847), general of artillery. In the lateral walk is the tasteful Gothic chapel in marble of the *Bourbonnaud* family.

At one of the corners formed by the two walks descending towards the 'parterre': *Ed. Blanc* (d. 1877), lessee of the gaming-tables at Monaco; a large chapel surmounted by a sarcophagus. Lower down, to the right: *Charles* and *Louis Blanc* (d. 1882). Then *Ménier* (d. 1881), industrialist and economist. To the left of the parterre, in descending: *Pozzo di Borgo* (d. 1842), a Corsican, afterwards a Russian diplomatist and a bitter antagonist of Napoleon I.; a colossal bust in bronze. Adjacent: *Marchal de Calvi*

(d. 1873), physician; a bust in bronze. At the cross-way: the handsome *Hautoy* chapel.

We again ascend to the left of the parterre and turn to the left. At the angle of a footpath, left: the handsome Renaissance chapel of the *Bouhey* family.

At the corner of the AVENUE CIRCULAIRE, left: **Walewski* (d. 1868), statesman; a large and handsome mausoleum. A little higher, on the right side of the avenue: **Anjubault* (d. 1868), mechanician; a 'pleureuse' by Maillet. — We now descend the Avenue Circulaire. Left: *Mottet*, and opposite to it *E. Périer*, two fine Gothic chapels. Right: *Luzarraga*; opposite, *Cabirol*; two handsome Renaissance chapels. Then, left: *Count Pepoli* (d. 1867); a handsome sarcophagus. Right: *Prince Pignatelli* (d. 1868); with a bust. We next observe several chapels.

The upper part of the AVENUE PRINCIPALE, which we now reach, is one of the most interesting portions of the cemetery. Left: **Eugène Berge* (d. 1882; aged 15 years), a monument in granite and white marble, with beautifully sculptured floral and other ornamentation; *Visconti*, father (d. 1818), philologist, and son (d. 1854), architect; *Beulé* (d. 1874), archæologist; **Dantan* (d. 1842), sculptor; a family-vault; *Ach. Fould* (d. 1869), minister of finance; *Rossini* (d. 1868), composer (whose remains, however, were removed to Florence in 1887); *Alf. de Musset* (d. 1857), poet (beautiful lines inscribed on the monument, written by the deceased); *Ph. Béchard* (d. 1864), ambassador; **Clément-Thomas* and *Lecomte* (d. 1871), the first victims of the Commune, with sculptures by Cugnot; *Lebas* (d. 1873), the engineer who erected the obelisk in the Place de la Concorde; **Lenoir* and *Vavin*, with a 'pleureuse'; *Paul Baudry* (d. 1886), painter, with bust and statue by A. Mercié. In the centre of the Avenue, *Monument de Souvenir*, to the memory of the dead whose graves are not denoted by monuments. — Descending on the other side: **Th. Couture* (d. 1879), painter, with a bust and genii in bronze by Barrias; *Ledru-Rollin* (d. 1875), radical deputy, with a bronze bust; *Cousin* (d. 1867), author and philosopher; *Auber* (d. 1871), the composer, with a bust by Dantan; *Ern. Baroche* (d. 1870), 'chef de bataillon', killed at Le Bourget, with a bust; *P. J. Baroche* (d. 1870), advocate and politician; *Lefébure-Wély* (d. 1869), organist and composer; *Perdonnet* (d. 1867), engineer, with a statue and medallion by Dubray; *Fr. Arago* (d. 1853), the astronomer, with a bust by David; *Mouton*, with interesting bas-reliefs.

The Avenue de la République joins the outer boulevards at the N.W. angle of Père-Lachaise, near which is the new *Lycée Voltaire*. The Avenue was prolonged in 1890, skirting the cemetery (garden), to the *Place des Pyrénées*, in which is the *Mairie of the XX^e Arrondissement* (Ménilmontant; Pl. R. 32), with paintings by Glaize and Bin. From the *Hôpital Tenon* (635 beds) the Mairie is separated by a square, embellished with a bronze group, by L. Michel, representing the Lame and the Blind.

A little to the N. of Père-Lachaise, on the right side of the

Boulevard de Ménilmontant, rises the church of *Notre-Dame-de-la-Croix* (Pl. R, 30), a fine Romanesque edifice, built in 1865-70 by Héret, with a spire rising above the portal. As it stands on a height, it is visible from a considerable distance.

The Rue Ménilmontant and Rue St. Fargeau (omnibus-line O) lead to the E. from the church to (¼ hr.) the Reservoirs de la Dhuis (Pl. R, 36), which supply one-fifth of Paris with spring-water, brought hither from a distance of 80 M.

We may return to the centre of the city by the *Chemin de Fer de Ceinture*, which has a station at Ménilmontant, near the church. The route by Bercy, Bel-Air, and Auteuil, or by the left bank, is longer but more interesting than that by Courcelles-Ceinture (see Appx., p. 25). The line goes on to the Gare St. Lazare (p. 204).

Various public conveyances ply from Père-Lachaise to the town; an omnibus runs from Charonne to the Place d'Italie (P), another from Ménilmontant to the Gare Montparnasse (O), and a tramway plies from La Villette (TE), all with 'correspondance'; see Appx.

5. From the Boulevards to La Villette and to Montmartre.

Visitors who are interested in the market at La Villette will see it to most advantage on *Monday* or *Thursday* morning (omnibus lines AC; tramway to Pantin and Aubervilliers; Chemin de Fer de Ceinture), and may afterwards visit the Buttes-Chaumont and other adjacent points. — Luncheon may be obtained near the Gare du Nord or Gare de l'Est (see p. 14), or in the restaurant at the market.

I. FROM THE BOULEVARDS TO LA VILLETTE.

St. Laurent. Gare de l'Est. Gare du Nord. Buttes-Chaumont. Market and Abattoirs at La Villette.

We leave the Grands Boulevards beyond the Porte St. Denis (p. 72), and follow the *Boulevard de Strasbourg* (p. 72), to the left, to the Gare de l'Est. The *Eldorado*, on the right, and *La Scala*, on the left, are both so-called 'cafés-concerts'. Before reaching the station we cross the *Boulevard de Magenta*, about ½ M. from the Place de la République (p. 70).

The church of **St. Laurent** (Pl. B, 24), immediately to the right, was founded in 593, but has been repeatedly rebuilt and restored. It was finally remodelled in 1865-66, when two bays were added to the nave, and a handsome Gothic façade with a spire was constructed towards the boulevard. The choir was decorated by *Blondel* (d. 1853), and the high-altar by *Lepautre*. In the S. transept is a Martyrdom of St. Lawrence, by *Greuze*; on the opposite side, St. Lawrence among the poor, by *Trezel*. The chapel of Notre-Dame-des-Malades in the apse contains numerous votive offerings.

The **Gare de l'Est**, or *de Strasbourg* (Pl. B, 24), a handsome building designed by *Duquesnay* (d. 1849), is situated opposite the end of the Boulevard de Strasbourg. The façade is surmounted by a sitting figure of the city of Strasbourg. The pavilions projecting on each side are connected by a colonnade, on the balustrade of which is a clock-dial with statues of the Seine and the Rhine. Trains, hotels, etc., see pp. 24, 2.

The Rue de Strasbourg, leading to the W. past the front of the station, joins the Boulevard de Magenta, which brings us in 5 min. to the wide and handsome *Rue de Lafayette* or *de la Fayette*. This new street, nearly 2 M. long, beginning at the Boulevard Haussmann, behind the Opéra, runs in a straight line to the N.E. quarters of the city, where it is continued by the Rue d'Allemagne (see below), about $1\frac{1}{4}$ M. long.

The **Gare du Nord** (Pl. B, 24), a railway-station constructed in 1863-64 by *Hittorff*, is situated a short distance to the right. The principal part of the extensive façade, which is 170 yds in length, is surmounted by a pediment crowned with a statue of Paris in the centre and those of eight important foreign cities connected with Paris by the Ligne du Nord. Behind this façade is the great hall, 220 yds. long, 77 yds. in width. Though by no means the handsomest, this station is the most practically arranged in Paris. All the platforms are on the street-level; and the ticket-offices and waiting-rooms are most conveniently situated. — Lines starting hence, see p. 24; hotels in the vicinity, see p. 2.

The church of *St. Vincent-de-Paul* (p. 188) is near the station; its façade is turned towards the Rue de la Fayette.

We regain the Rue de la Fayette by following the street that leads to the E. in front of the station, and continue in a straight direction, crossing the railway from the Gare de l'Est.

The Rue de la Fayette ends at the Boulevard de la Villette, near the Canal St. Martin. On the left we observe the *Douane*, occupying the site of an old gateway erected at the end of last century by Ledoux. To the right is the **Bassin de la Villette** (Pl. B, 26, 27), formed by the *Canal de l'Oureq*, which connects the Oureq, an affluent of the Marne, with the Seine. This canal, $5\frac{1}{4}$ M. long, cuts off a long curve formed by the river, while the *Canal de St. Denis*, $2\frac{1}{2}$ M. long, a ramification towards the N.E., shortens the water-route between the Upper and Lower Seine by 10 M. The *Canal St. Martin* (p. 67), 4 M. long, continues the Canal de l'Oureq to the S.

The basin is surrounded by extensive warehouses, which serve to convey an idea of the commerce carried on by these waterways of Paris. About 1200 barges enter the basin monthly, with an average burden of 250 tons each (equal to about 25 railway-trucks), but the port is being enlarged so as to admit vessels of 700-1000 tons.

The basin is crossed by a lofty *Footbridge*, the single arch of which has a span of 310 ft. At the other end, in the Rue de Crimée, is a hydraulic *Drawbridge*, worked by the water of the canal.

We now follow the *Rue d'Allemagne* as far as the broad Avenue Laumière, which leads to the right to the Buttes-Chaumont. On the left, at the end of this avenue, is the large *Mairie du XXI^e Arrondissement*, in the style of Louis XIII., by Davidoud and Bourdais. The Salle des Mariages is embellished with paintings by Gervex and Blanchon.

The park of the ***Buttes-Chaumont** (Pl. B, 30, 29) lies on the

N.E. side of Paris, at the W. end of the hill of Belleville. It extends in the form of an irregular crescent over an area of about 55 acres, but does not cover the whole of the 'buttes' (hills), part of which is still a barren waste. On the summit of these hills once rose the gibbet of *Montfaucon*, where numerous criminals and others were hanged during the middle ages. The gallows were removed in 1761, and the place afterwards became notorious as a haunt of malefactors. About the year 1865 the authorities, owing to sanitary considerations, began to remove the heaps of rubbish accumulated here, and it was resolved to convert this ill-favoured locality into a park for the benefit of the artisans of this quarter of the city. The peculiar nature of the ground afforded an opportunity of laying it out in a novel and picturesque manner, and the task was skilfully executed by *M. Alphand*, the engineer, and *M. Barillet* (d. 1874), *jardinier-en-chef* of Paris, at an outlay of 3,412,620 fr.

The quarries formerly worked here have been transformed into a rocky wilderness surrounded by a small lake, while the adjacent rugged surface is now covered with gardens and walks shaded by trees. A cascade falling from a considerable height into an artificial stalactite grotto (formerly the entrance to the quarries) is intended to enhance the attractions of the scene. The highest rock is surmounted by a miniature Corinthian temple, which, as well as the other hills, commands an admirable view in the direction of St. Denis. The city itself, with its ocean of houses, is best surveyed from a hill on the S. side of the park. A wire bridge, 70 yds. in length, crosses from one of the rocks to another, while others are connected by means of a stone arch, so as to facilitate access to the different points of interest. Here and there are bronze sculptures: in the direction of the main entrance, *The Rescue*, by *F. Rodard*; beside the small cascade beyond the restaurant, *The Ford*, by *C. Lefèvre*; *Eagle-hunter*, by *Desca*, on this side of the large bridge; *Corsair*, by *Ogé*, near the great waterfall; *Wolf-hunt*, by *Hiolin*, in the upper part of the park. — The *Chemin de Fer de Ceinture* (p. 24) is carried through the E. end of the park by means of a cutting and two tunnels, and in the vicinity is the *Belleville-la-Villette* station (see Appx.).

In 1871, the *Buttes-Chaumont* was one of the last positions occupied by the insurgents, who held their ground here till May 27th, when they were driven out by an incessant cannonade from *Montmartre*.

In the Belleville quarter, to the S.E. of the *Buttes-Chaumont*, is the handsome church of *St. Jean-Baptiste* (Pl. B, 33), built in the Gothic style of the 13th cent. by *Lassus* (d. 1857), and consecrated in 1858. The chief portal is flanked by two towers, 189 ft. in height, which are conspicuous from every part of the city. Mural paintings in the transept by *Leloir* and *Maillet*.

The *Rue d'Allemagne* (p. 186) leads to the fortifications of the city, where it terminates at the *Porte de Pantin* (see below). To the left, within the 'enceinte', about $\frac{3}{4}$ M. from the *Buttes-Chaumont*, is situated the *Marché-aux-Bestiaux de la Villette* (Pl. B, 34), which

presents a busy scene, especially on Monday and Thursday mornings. It consists of three large pavilions, like those of the Halles Centrales, constructed by Baltard and Janvier, and covers an area of ten acres. The central hall is capable of containing 4600 oxen, that on the right about 7000 calves and pigs, and that on the left 22,000 sheep. Most of the cattle arrive by a branch of the Ceinture railway, on the E. side. Behind the market are stables and offices, at the back of which runs the Canal de l'Ourcq. Beyond the canal are the *Abattoirs*, or slaughter-houses, which are also open to the public. The chief entrance to them is in the Rue de Flandre, on the N.W. side, beside which are two sculptured groups of animals, by A. Lefevre and Lefevre-Deslonchamps. The busiest time here is also in the morning, but the scene is not one which will attract many visitors, though the premises are kept scrupulously clean. The market and abattoirs together have cost the city about 60 million francs.

On the left bank of the Seine are two other large slaughter-houses, the *Abattoir de Villejuif* (Pl. G, 23), near the Place d'Italie, and the *Abattoir de Grenelle* (Pl. R, 13), near the Place de Breteuil.

The animals killed annually in the Paris slaughter-houses number about 2,950,000. The oxen come chiefly from Normandy, Anjou, and Poitou; the sheep from Germany, Hungary, Russia, and Italy; and the pigs from Maine (U. S.), Poitou, and Brittany.

The neighbouring quarters of *Aubervilliers* (21,900 inhab.), *Pantin* (19,200 inhab.), and *Pré St. Gervais* (7400 inhab.) are uninteresting. The new *Mairie* at Pantin (Pl. B, 31, 34) is built in the Renaissance style.

II. FROM LA VILLETTE TO MONTMARTRE.

St. Vincent-de-Paul. Butte Montmartre. Cemetery of Montmartre.

Those who have already inspected the Bassin de la Villette and the Buttes-Chaumont may take a cab to the Gare du Nord, which is about 2 M. from the Abattoirs, or they may use the tramway coming from Aubervilliers, leaving it at the Rue du Faubourg-St. Denis, near the station.

From the *Gare du Nord* (p. 186) we descend the Rue de Lafayette for a short distance to the church of St. Vincent-de-Paul, which may be reached from the boulevards by ascending the same street or the Rue d'Hauteville.

**St. Vincent-de-Paul* (Pl. B, 24), erected in 1824-44, by *Le père* and *Hittorff* (d. 1867), is a more successful example of the basilica style than *Notre-Dame-de-Lorette* (length 264 ft., width 120 ft.). The church is approached by two handsome drives, and by a broad flight of 46 steps. Above this spacious amphitheatre rises a projecting portico of twelve fluted Ionic columns, bearing a pediment with a relief by *Lemaire*, representing St. Vincent-de-Paul with a cross in his hand, between Faith and Charity. The two somewhat feeble towers flanking the façade, 138 ft. in height, are connected by a balustrade with statues of the Evangelists. The door under the portico is embellished with reliefs by *Farochon* (d. 1871), representing Christ and the Apostles.

INTERIOR. The church consists of a nave flanked with double aisles, the latter being partly occupied by chapels, and partly by galleries. The roof is borne by 84 Ionic stuccoed columns. The open roof is tastefully decorated. The windows of the aisles are filled with stained glass by *Maréchal* and *Grignon*.

The nave is adorned with a celebrated **Frieze by *Hippolyte Flandrin*, the best pupil of Ingres (p. xxxvi), representing a procession of saints, apostles, prophets, martyrs, and popes. The conception of this admirable composition, which is Flandrin's masterpiece, and remarkable for the classic beauty of its forms, is based on the mosaics of the church of S. Apollinare Nuovo at Ravenna. In the dome of the choir is another fresco, by *Picot* (d. 1868), representing St. Vincent-de-Paul kneeling before Christ on his throne, and presenting children to him. The high-altar is adorned with a handsome Crucifixion in bronze, by *Rude* (d. 1855). The chapel of the Virgin at the back of the choir contains a fine group of the Virgin and Child by *Carrier-Belleuse*, and paintings by *Bouguereau*, representing the Annunciation, the Visitation, the Adoration of the Magi, the Adoration of the Shepherds, the Flight into Egypt, and Jesus found by his Mother.

The Rue St. Vincent-de-Paul, behind the church, intersects the Boulevard de Magenta, and ends at the *Hôpital Lariboisière* (Pl. B, 23), erected in 1846-53, and called after the countess of that name, who bequeathed 2,900,000 fr. to the poor of Paris. Visitors are admitted on Sundays and Thursdays, from 1 to 3 p. m. The chapel contains the tomb of Mme. de Lariboisière, by *Marochetti*.

A little to the N. of the hospital, beyond the Boul. de la Chapelle, is the handsome church of *St. Bernard* (Pl. B, 23), with its fine spire, erected in 1858-61, by *Magne*, in the Gothic style of the 14th century. The paintings, pulpit, 'chemin de croix', stained glass by *Gsell-Laurent*, and several good altar-pieces in the transept may be inspected.

The Boul. de Magenta ends at the *Boulevards Extérieurs*, between the Boul. de la Chapelle and the Boul. de Rochechouart. To the N. it is continued to St. Ouen (p. 201) by the *Boulevard Barbès* and the *Boulevard Ornano*.

A little to the W., in the Boul. de Rochechouart, is the *Collège Rollin* (Pl. B, 20), a large edifice, finished in 1876, on the site of the former Abattoirs de Montmartre. It is adjoined by the *Square d'Anvers*, which is embellished with a column bearing a bronze statue of Armed Peace, by Coutan, and with bronze statues of *Sedaine* (1719-1797) and *Diderot* (1713-1784) by Lecoq. Facing the college is the *Bal de l'Elysée-Montmartre* (p. 34).

The **Butte Montmartre**, near the top of which we have now arrived, is a hill famous in the annals of Paris, rising to a height of 330 ft. above the Seine, and containing ancient quarries of gypsum (from which, when calcined, is obtained 'plaster of Paris'). According to tradition, St. Denis, the first bishop of Paris, and his companions suffered martyrdom here in 270, and the name of the hill is supposed to have once been *Mons Martyrum*. Others derive the name from *Mons Martis*, from a temple of Mars which is said to have stood here. In 1147 Louis VI. founded a Benedictine abbey here, to which the church of *St. Pierre de Montmartre* (Pl. B, 20), on the top of the hill, once belonged. To the right, and at the back of the church, is a '*Jardin des Oliviers*', containing oratories with

curious sculptures. This point can be reached only by a long détour or by flights of steps. The most direct of the latter, leading to the left from the *Place St. Pierre*, has 266 steps.

The heights of Montmartre witnessed the final struggle between the French troops and the Prussian and Russian allies on 30th March, 1814, and also played an important part in the sieges of 1870-71. On 18th March, 1871, the insurgent soldiers, having assassinated the generals Clément-Thomas and Lecomte, took possession of the cannon on the Montmartre, which had been entrusted to a body of the National Guard. Thus began the Communist rebellion of 18th March to 28th May, 1871, a period of horrors almost without parallel in the chequered annals of Paris. The insurgents were dislodged by the victorious troops on 24th May, and the batteries of Montmartre were then directed against the Communists who occupied the Buttes-Chaumont (p. 187) and Père-Lachaise (p. 176).

The *Eglise du Sacré-Cœur*, adjoining St. Pierre, begun in 1874 from designs by *Abadie*, will when completed be an imposing edifice in the Romanesque-Byzantine style. As yet the progress has been slow, as the extensive substructions required for the support of the building have already absorbed a sum of 3,500,000 fr., while of the 25,000,000 fr. at which the total cost is estimated 2,500,000 have yet to be raised by subscription. The crypt has been finished for some time, and the walls of the superstructure have risen as far as the spring of the arches in the nave. Visitors are admitted (50 c. : entrance at the back; tickets at No. 31).

The slopes of the Butte next the city have been laid out as a *Public Garden*, huge supporting-walls having been built to retain the necessary soil. To the left of the church is a very large *Reservoir* (2,420,000 gal.), used for watering the garden, etc. In clear weather a fine *View of Paris is obtained from the top of the lofty flight of steps in front of the reservoir (custodian with telescope; gratuity).

The principal features from left to right, seen from the corner of the street, are as follows: in the foreground, St. Vincent-de-Paul and the Gare du Nord; farther off, the Buttes-Chaumont, the two towers of Belleville, the tower of Ménilmontant, and Père-Lachaise with its 'sugar-loaf'; to the right, the campanili of St. Ambroise, the Colonne de Juillet, and the dome of St. Paul's; in front, the Chapelle des Arts et Métiers; more remote, still to the right, the dome of La Salpêtrière; St. Gervais, the Hôtel de Ville, Notre Dame, Tour St. Jacques, St. Etienne-du-Mont, and the Panthéon; next, St. Eustache and the Halles Centrales, with the domes of the Sorbonne and the Val-de-Grace behind; the Observatory, the twin towers of St. Sulpice, the Louvre; in the distance, the tower of Montrouge; then comparatively near, to the right, the imposing Opera-house, above which rise the spires of Ste. Clotilde; to the left the Vendôme Column; again to the right the dome of the church of the Assumption, the gilded cupola of the Invalides, the Eiffel Tower, and the domed halls of the Exhibition of 1889, with the Machinery Hall to the left; nearer, still to the right, the campanile of La Trinité; the Madeleine, the Palais de l'Industrie; then the dome of St. Augustin and the towers of the Trocadéro. On the horizon rise the hills of Châtillon, Clamart, and Meudon, on which in clear weather the Hospice de Fleury may be made out. The Arc de Triomphe de l'Etoile is hidden, but the fort of Mont Valérien may be seen between the houses from the other end of the terrace.

Behind the reservoir lies the old church of *St. Pierre de Montmartre*, a relic of a Benedictine monastery founded in 1147, by

Louis VI. Beside it is a Gethsemane, with curious sculptures, a Calvary, etc.

On the other side, to the E. of the new church, at the corner of the Rue de la Barre and the Rue Lamarck, is a *Diorama of Jerusalem*, by Ol. Pichat (adm. 1 fr., on Sun. and holidays 50 c.).


Descending once more to the Boulevards Extérieurs, we follow them to the W. for about $\frac{3}{4}$ M., to the cemetery of Montmartre.

At the end of the Boul. de Rochechouart, where it is joined by the Rue des Martyrs, is the little *Cirque Fernando* (p. 31).

From this point we may, if necessary, return direct to the centre of the town by the Rue des Martyrs and Notre-Dame-de-Lorette (p. 194).

The Boul. de Rochechouart is continued westwards by the Boul. de Clichy, leading past the *Place Pigalle* and the *Place Blanche*. A short avenue leads to the right (N.) to the —

Cemetery of Montmartre, or du Nord (Pl. B, 16, 17), the oldest



burial-ground of modern Paris, which, though inferior to Père-Lachaise, is also worthy of a visit. Hours of adm., see p. 177.

The approach was lowered in 1888, when the *Viaduc Caulaincourt*, about 200 yds. long, was carried over the cemetery, uniting the Rue Caulaincourt, to the N. of the Butte de Montmartre, with the Boul. de Clichy. The viaduct is now the main carriage-road to the Butte.

In the short avenue to the right of the entrance are four tombs of Polish refugees, the first of which bears the inscription, '*Exoriare aliquis nostris ex ossibus ultor!*' ('may an avenger one day spring from our ashes'). — In the transverse avenue are several noteworthy monuments, among them those of the architect *Laurecisque* (d. 1860) and of the family *Benazet* (left). We descend a flight of steps near this point and reach the —

CARREFOUR DE LA CROIX. Beneath the cross are interred the victims of the 'coup d'état' of 1851. On the side next the principal avenue is the vault of the *Cavaignac family, to which belonged the author *Godefroy* (d. 1845), and the general *Eugène* (d. 1857), president of the republic in 1848. The recumbent figure of the latter, in bronze, is by Rude. To the right, under the viaduct, *Castagnary* (d. 1888), politician.

We now follow the AVENUE DUBUISSON, beyond the cross, turn to the left, and then, after a few more paces, to the right, and thus reach the JEWISH CEMETERY (closed on Saturdays). At the end of the walk, on the left, **Halévy*, the celebrated composer (d. 1862), with a statue by Duret. Behind it, the Mausoleum of the *Millaud* family.

We now return to the principal cemetery and follow the AVENUE MONTEBELLO, one of the most interesting in the cemetery. To the left, *Miecislus Kamienski*, a Polish volunteer who fell at Magenta in 1859, with recumbent bronze figure by Franceschi. To the right, *Marshal Lannes* (d. 1809), Duc de Montebello. Left, **Rohart*, with angel in bronze. Farther on is a large block of marble marking the grave of *Paul Delaroche* (d. 1856), the painter. Behind, *Chas. Maury* (d. 1866), the composer. — Right, **Princess Solतिकoff* (d. 1845), a chapel covered with gilding and painting. — Left, *Horace Vernet* (d. 1863), the painter; a marble sarcophagus.

We now enter the AVENUE DU TUNNEL, leading to the now disused 'concessions temporaires' and 'fosses communes', which are covered with streets and houses. To the right, *Léon Foucault* (d. 1868), the natural philosopher.

Farther on we turn to the left into the AVENUE CORDIER. Left, **Murger* (d. 1861), author of the 'Vie de Bohème', with a statue of Youth by Millet. Left, **Thouret-Rouvenat*, with the recumbent figure of a girl in marble, by Cavalier. Right, *Gozlan* (d. 1866), the author. Adjacent, on the left, is the tomb of **Théophile Gautier* (d. 1873), the poet, a sarcophagus with a statue of Calliope, by Godebski, bearing, among others, the following inscription: —

*'L'oiseau s'en va, la feuille tombe,
L'amour s'éteint, car c'est l'hiver;
Petit oiseau, viens sur ma tombe
Chanter quand l'arbre sera vert.'*

Farther on, to the right, *Gust. Guillaumet* (d. 1887), the painter, with allegorical figure and bronze-medallion by Barrias.

We now ascend by the grave of *Gozlan* and proceed towards the right to the AVENUE MONTMORENCY. Right: *Ch. Zeuner* (d. 1841), pianist and composer. Farther on, *Duchesse d'Abrantès* (d. 1838), wife of Marshal Junot, and their son; medallion by David d'Angers. Adjacent, *Ary Scheffer* (d. 1858), the painter; with a weeping angel above the door. — Right: *Nourrit* (d. 1839), a singer.

We here turn to the left and follow the AVENUE DE LA CLOCHE. On the left: *Victor Massé* (d. 1884), composer; with bronze ornamentation on the handsome tomb; *De Braux d'Anglure* (d. 1849);

a bust and bas-relief in bronze. To the right, in a side-path: *A. L. Thiboust* (d. 1867), the dramatist; monument with a relief in marble. In the avenue, on the left: *Armand Marrast* (d. 1852), member of the provisional government, mayor of Paris, and president of the National Assembly in 1848. — To the right, opposite the last, in the second row of graves, repose *Heinrich Heine* (d. 1856), the poet, and his wife *Mathilde* (d. 1883); simple tombstone with a marble tablet. — Farther on, *Famille Daru*, including Count Daru (d. 1829), the constant companion of Napoleon I., and his representative at the negotiations of Pressburg, Tilsit, and Vienna, Minister of War in 1813. Then, *Viollet-le-Duc* (d. 1879), architect.

Opposite is the Chemin Duc, crossing the CHEMIN TROYON, which traverses the most interesting part of the cemetery, containing numerous handsome modern monuments. Right: *Troyon* (d. 1865), the painter; *Aglaë Didier* (d. 1863), author. Among the trees, to the left: *Nefftzer* (d. 1876), chief editor of 'La Presse' and founder of 'Le Temps', a fine statue in bronze, by Bartholdi. Left: *Clapisson* (d. 1866), composer; *H. Storks* (d. 1866), recorder of Cambridge, marble monument, with medallion. Right: **Baudin*, 'mort en défendant le droit et la loi, le 3 déc. 1851: ses concitoyens, 1872'; a handsome recumbent figure in bronze, by Millet (the remains were removed to the Pantheon in 1889). A little to the right, *Martin Bernard* (d. 1883), 'representative of the people'. To the left of the Chemin Troyon: **Méry* (d. 1866), author; statue of Poetry, in bronze, by Lud. Durand. Right: *Rouvière* (d. 1865), tragedian; medallion and bas-relief by Préault, representing the deceased as Hamlet. Left: **Chauvey* (d. 1871), editor of the 'Siècle', shot by the Communists; an expressive medallion, with a quotation from the journal. Right: **Ward* family, with a large Christ in bronze. Left: *Mène* (d. 1879), sculptor. Right: **Rostan* (d. 1866), professor of medicine; marble figure in high-relief; *Larmoyer*, with a bas-relief in stone. Left: **Marc-Lejeune*; a chapel, surmounted by a sarcophagus with four symbolical statues.

We have now again reached the Avenue de Montmorency (see p. 192). Left: *Duchesse de Montmorency-Luxembourg* (d. 1829) and *Marquise de Mortemart* (d. 1876); a large obelisk. Right: *Polignac* (d. 1863), officer; a large and rich chapel.

A little farther on is a flight of steps descending to the AVENUE SAMSON. Right: **Samson* (d. 1871), actor; bronze bust by Crauk. Farther on, beyond the Avenue du Tunnel, to the right: *Dupotet de Sennevoy*, 'Chef de l'École magnétique moderne', with a fine marble bust by Bracony. Adjacent, to the left: *Ricard* (d. 1873), painter, with a marble bust by Ferru.

At the end of the AVENUE DES ANGLAIS, the first diverging to the left from the Avenue Samson, reposes *Jacques Offenbach* (d. 1881), the composer, under a rich monument of porphyry, with a lyre and palm of bronze.

From the Avenue Samson we return to the Carrefour de la Croix and the entrance. — *Place Clichy*, etc., see p. 201.

III. FROM MONTMARTRE TO THE BOULEVARDS.

Notre-Dame-de-Lorette.

Returning by the Boul. de Clichy to (2-3 min.) the Place Blanche (p. 191), we now follow the Rue Fontaine and the Rue Notre-Dame-de-Lorette to the church of that name, about 1 M. from the cemetery. Or we may proceed to the Place Clichy (p. 201), whence an omnibus (line *H*) runs past the church.

The Rue Notre-Dame-de-Lorette crosses the little *Place St. Georges* (Pl. B, 21), on the right side of which is the house of the celebrated statesman A. Thiers (d. 1877), demolished by the Communists in 1871, and restored by government.

The church of ***Notre-Dame-de-Lorette** (Pl. B, 21), situated at the N. end of the Rue Laffitte, which leads to the Boulevard des Italiens, was erected in 1823-36 in the simple style of an early-Christian basilica, and is 74 yds. in length, and 35 yds. in width. The tympanum of the Corinthian portico is adorned with a group of the Child Jesus adored by angels, by *Nanteuil* (d. 1865); the statues of the Virtues are by *Foyatier*, *Laitié*, and *Lemaire*.

The INTERIOR, with its gaudy decorations, somewhat resembles a ball or concert room. The aisles are separated from the nave by thirty-two columns of yellow stucco, and the ceiling is divided into huge coffers lavishly gilded and painted. The most interesting of the frescoes which cover the walls are those in the nave and choir. In the nave: to the right, Nativity of the Virgin, by *Monvoisin*; Her Consecration, by *Vinchon*; Her Marriage, by *Langlois*; Annunciation, by *Dubois*; to the left, as we return, Visitation, by *Dubois*; Adoration of the Shepherds, by *Hesse*; Adoration of the Magi, by *Granger*; Assumption, by *Dejuinne*. In the choir: on the left, the Presentation in the Temple, by *Heim* (d. 1865); on the right, Jesus teaching in the Temple, by *Drolling*; in the centre, the Coronation of the Virgin, by *Picot* (d. 1868).

This quarter of the city is inhabited by 'artistes' of every kind, and also by the women who are sometimes called 'Lorettes' from the neighbouring church. — To the Butte de Montmartre by the Rue des Martyrs, behind the church, see p. 191.

The handsome *Rue de Châteaudun*, which passes in front of the church, extends from the Rue de la Fayette (p. 186) to the Place de la Trinité (p. 200), traversing the N. of the *Quartier du Chaussée d'Antin*, one of the handsomest central districts of the city, with the Opera-house, several of the principal banks, and some of the large hotels. It owes its name to the Rue de la Chaussée-d'Antin, between the church of La Trinité and the Boul. des Capucines.

Beyond the Rue de Châteaudun is the *Rue de la Victoire* (Pl. B, 21), where we observe the *Synagogue* of the same name, a new building by Aldrophe, with a modern Romanesque façade. Another smaller synagogue in the same style, in the Rue Buffault, running off the Rue de la Fayette, is used by the Portuguese Jews.

Farther on, to the left of the last-named street, is the pretty *Square Montholon* (Pl. B, 21), embellished with a bronze group by Roland, representing a mountebank with a monkey.

We finally regain the boulevards either by the Rue du Faubourg-Montmartre or by the Rue Drouot (Pl. B, 21). No. 26 in the latter is the *Hôtel de Figaro*, or 'Figaro' office, built in the style of the Spanish Renaissance. No. 9 is the *Hôtel des Ventes Mobilières*, see p. 75.

The Rue Drouot reaches the Grands Boulevards, at a point between the Boul. Montmartre and the Boul. des Italiens (pp. 73, 74).

6. From the Palais-Royal to Batignolles.

The following walk should be taken on a *Tuesday* or a *Friday*, as the Bibliothèque Nationale is open on these days. Spare time, before the library is open, may be spent in exploring the neighbourhood; or, if the visitor have already done so, he should go first to La Trinité. In the latter case, he will then proceed directly from the library to the Batignolles quarter, taking, if desired, the omnibus (*H*) which passes the Palais-Royal. — Restaurants at the Palais-Royal or on the boulevards, see pp. 12-15.

I. FROM THE PALAIS-ROYAL TO LA TRINITÉ.

Bibliothèque Nationale.

The *Rue de Richelieu* (Pl. R, 21; II), a street 1000 yds. in length, which passes on the E. side of the Palais-Royal, leads direct from the Place du Théâtre-Français and the lower end of the Avenue de l'Opéra (p. 76) to the 'Grands Boulevards'.

We first observe on the left, at the corner of the Rue Molière, the *Fontaine Molière*, erected in 1844 to the memory of the famous dramatist, who died in 1673 in the house opposite (No. 34). The monument is in the Renaissance style, 51 ft. high and 21 ft. wide, and was designed by *Visconti*. The statue of Molière is by *Seurre*, while the muses of serious and light comedy are by *Pradier*.

Farther on, the Rue de Richelieu crosses the Rue des Petits-Champs, leading to the right to the Place des Victoires (p. 169). Then to the right is the Bibliothèque Nationale, opposite the principal entrance to which (farther on) is the **Fontaine Richelieu*, or *Louvois*, in bronze, by *Visconti*, with statues by *Klagmann* representing the Seine, the Loire, the Garonne, and the Saône. It stands in the small *Square Richelieu*, on the site of the old Grand-Opéra, on leaving which the Duc de Berry was assassinated in 1820, and which was taken down in consequence. A chapel was to have been erected on the spot, but the plan was abandoned after the July Revolution.

The *Bibliothèque Nationale* (Pl. R, 21; II), formerly called the *Bibliothèque du Roi*, and afterwards the *Bibliothèque Impériale*, occupies the entire block of buildings formed by the Rues de Richelieu, des Petits-Champs, Vivienne, and Colbert. The library stands on the site of the palace of Cardinal Mazarin, the powerful minister of Louis XIII. and Louis XIV., but almost every trace of the old building has been removed in the process of extension and alteration. The handsome façades in the Rue Vivienne and the Rue des Petits-Champs are modern.

The Bibliothèque Nationale is open daily, 10-4 o'clock, except on holidays and during the fortnight preceding Easter Monday; but these exceptions do not apply to the public reading-room. The hall for study belonging to the department of printed books is open till 6 o'clock, from May 1st till Sept. 15th. The rooms reserved for purposes of study are not shown except to visitors provided with a ticket from the 'administration' (p. 197). There are, however, rooms for the exhibition of geographical charts, printed books, MSS., and engravings, and a cabinet of medals, which are open to the public on Tuesdays and Fridays (the first four collections 10-4 o'clock; the last 10.30 to 3.30). All these objects are catalogued, except the medals.

Charles V., surnamed the Wise (d. 1380), was the first French king who possessed any considerable number of books. This collection, however, was lost during the wars with England, and the actual founder of the present library was *Francis I.*, who assiduously purchased or caused copies to be made of manuscripts from every quarter, particularly from Italy, and in 1536 decreed that a copy of every work printed in France should be furnished to the royal library at Fontainebleau. Twenty years later *Henri II.* added the provision that each copy so furnished should be printed on vellum and handsomely bound. For this an act of parliament afterwards substituted two copies printed on ordinary paper. This rule, however, is far from being strictly adhered to. On the expulsion of the Jesuits, *Henri IV.* transferred the library to their college at Clermont, and used the confiscated wealth of the order in encasing the books in rich and handsome bindings. On the return of the Jesuits in 1604 the library had to undergo another removal; and it changed quarters again during the reign of *Louis XIII.*, and in that of *Louis XIV.* (1684), when it numbered 40,000 printed books and about 1100 MSS. Finally, in 1724, on the suggestion of the librarian *Abbé Bignon*, it was accommodated in the Hôtel Mazarin.

The Bibliothèque Nationale, probably the most extensive in the world, is divided into four departments: (1) Books and Maps; (2) MSS.; (3) Engravings; (4) Medals and Antiques.

The 1st Department (*Imprimés*, *Cartes et Collections Géographiques*) comprises about 3,000,000 vols., the bookcases containing which, if placed in a continuous line, would extend to a distance of 37 miles. Most of the books are copies of the best editions, and they are all carefully bound. There is no complete catalogue as yet, although one is in progress; but the volumes still uncatalogued are found by means of bundles of written slips on which their names are given.


The entrance to the *Salle Publique de Lecture* is by No. 3 Rue Colbert, while that of the *Salle de Travail* (p. 197) is in the Rue de Richelieu, opposite the Fontaine Richelieu. Sticks and umbrellas must be left at the entrance, but no charge is made for their custody. Visitors are not permitted to quit the building with books, papers, or portfolios in their hands without a 'laissez-passer' from one of the librarians.

On entering the *Salle de Lecture* or the *Salle de Travail* the visitor receives a slip of paper ('bulletin'), on which he writes his name and address. The employés write upon it the names of the books lent, and stamp it when the books are returned, and the bulletin is then given up to the official at the exit. On entering the room, the visitor next applies to the 'conservateurs' or librarians at the office in the middle for another 'bulletin'. On this he writes the name and description of the work he desires to consult, together with his name and address, and returns it to the office, after which he waits till the book is brought to him. In the *Salle de Travail* no applications are received after 3 o'clock in winter, and 5 o'clock in summer. Ink is provided for the use of visitors, and all the rooms, particularly the

Salle de Travail, are abundantly supplied with dictionaries, encyclopædias, and other books of reference. A table in the Salle de Travail is set apart for reviews and other periodicals. Close by, to the right and left, are catalogues of the latest additions. For farther details, see the notices affixed to the doors of the different saloons.

The **SALLE DE TRAVAIL** (entrance, see p. 196), constructed by *H. Labrousse*, and opened in 1868, is a lofty and spacious hall, upwards of 1400 sq. yds. in area, borne by sixteen light cast-iron columns 33 ft. in height, and lighted from nine cupolas made of fayence. At the end of the hall is a semicircular space where the officials are employed, and behind them is the 'Magasin', which is also lighted from above and is traversed by a number of longitudinal and transverse passages. The hall contains seats at the tables for 334 persons, and is warmed by means of hot-air pipes in winter.

R u e V i v i e n n e



BIBLIOTHÈQUE NATIONALE.

In the vestibule, at the entrance to this hall, a Sèvres vase has been temporarily placed to commemorate the share of the French savants in the observation of the Transit of Venus in 1884. — To the left is the 'vestiaire', to the right a buffet (moderate).

At the end of the vestibule is a staircase, at the foot of which are Roman inscriptions from Troesmis, an ancient city of Lower Mœsia (now Bulgaria). To the left are the offices of the *Administration*, the entrance to which is in the centre of the façade in the Cour de l'honneur; and to the right is the —

DÉPARTEMENT DES ESTAMPES, which contains more than 2,500,000 plates bound up into volumes (14,500) or arranged in portfolios (4000). A number of the most interesting are exposed to view at the same hours as the printed books and manuscripts (comp. p. 196).

The I. Room is devoted to French engravings. Right: works by *Callot*, *Nanteuil*, *Gér. Audran*, *Pierre Drevet*, *P. Imb. Drevet*, *Claude Drevet*, *Bervic*, *Henriquel Dupont*, etc.

The II. ROOM, or GALLERY, contains engravings bound up and in portfolios. On the wall of the entrance and by the windows a few are exhibited to view, but it is difficult to get near enough to examine them properly. By the entrance, the English School. 1st-3rd windows, Italian Schools beginning with Finiguerra. 4th and 5th, German School. 5th and 6th, Dutch School. 7th, Flemish School. 8th, Spanish School.

The DEPARTMENT of MSS. now occupies the first floor of the wing fronting the Rue de Richelieu. The entrance is to the right at the head of the staircase already mentioned. This department contains about 100,000 volumes.

Facing the staircase is the small *Galerie des Chartes*, where are also temporarily placed manuscript marine charts of the 15th and 16th centuries. At the end is a hall with three globes, a model of the Statue of Voltaire by Houdon, with his heart enclosed in the base, a cast of Thiers' head, etc. — Here, too, is the *Lending Office*, which is adjoined by the 'Grande Réserve', one of the 'Magasins', or store-rooms, of the library.

The *Salles d'Exposition des Imprimés et des Manuscrits* are reached by the same staircase, to the left (admission, see p. 196). They contain the chief treasures of the library, some of them beautifully illuminated and magnificently bound. These two rooms are on the first floor, facing the Rue Vivienne. The second, the *Galerie Mazarine*, is a remarkably fine saloon. At the top of the staircase are views and votive tables brought home by Bonaparte's Egyptian expedition. All the objects are labelled.

ROOM I. In the centre, the French Parnassus, a group in bronze representing the chief French authors and artists of the 17th cent., executed by Louis Garnier for Titon du Tillet. On the walls opposite the window, a large tapestry, designed by Ehrmann, representing Literature, Science, and Art in Antiquity. On the other walls, copies of epitaphs. In the glass-cases 1, 2, 3, 5, superb bindings, with the arms of the kings of France from Francis I. downwards. In the 4th case, by the window: 369. *Christianismi Restitutio*, by Michael Servetus, a copy saved from burning; 371, 372. Hippocrates and Theophrastus, with Rabelais' autograph; 373. Philo Judeus, with Montaigne's signature; 374. Sophocles, annotated by Racine; 376, 377. Manuscript music by Rousseau and Gluck.

ROOM II. This large saloon, called the *Galerie Mazarine*, has a fine ceiling-painting by *Romanelli* (d. 1662): Romulus and Remus suckled by the Wolf, Mars and Venus, Rape of Helen, Burning of Troy, Ganymede carried off, Jupiter hurling thunderbolts at the Titans, Awakening of Venus, Narcissus, Jupiter and Mercury, Mt. Parnassus, Judgment of Paris, Venus in a chariot, Apollo and Daphne.

The cupboards and glass-cases contain (1st half of the saloon) printed works and bindings. Cupboards VII, VIII, to the right of the entrance: books printed in Italy and Spain. — IX. Impressions from wooden types; others by Fust and Schöffer. — VI. In the centre of the saloon: books of the largest size, on vellum and paper; superb bindings of the 16th cent., and one above, in embossed silver, of the 17th century. — XXI-VI. (beside the windows, returning towards the entrance): books printed in different towns of France; illustrated books; books printed abroad. — XXVII-IX. (in the centre): books printed at Paris, with magnificent miniatures; above, bindings,

Second half of the gallery: MSS. and bindings. X. (to the right): MSS. relating to the foundation of the library in the 14th and 15th cent.; portrait of John II., le Bon (d. 1364), a painting on wood of the 14th century. — XI. French palæography from the time of Charlemagne down to the end of the middle ages. — XII. Palæography of Italy, Spain, England, and Germany for the period just mentioned; MSS. with miniatures of the 14th and 15th centuries. — XIII. Latin palæography, from ancient times down to the Carlovingian era. — XIV. Atlas and charts of the 15-16th centuries.

— XV. Oriental and American MSS. and impressions from wood. — XVI. Various MSS. — XVII. Greek MSS. — XVIII. Autographs. — XIX. Paintings from MSS. — XX. MSS. of kings and queens of France. — In the centre: latest additions, MSS. with and without paintings. — XXX, XXXI. Sumptuous bindings of the middle ages, adorned with ivory, jewels, bronze, chains, etc. — XXXII. Autographs, particularly of the 17th century.

At the end, to the right, is the *Section des Cartes et Collections géographiques*.

The *CABINET DES MÉDAILLES ET ANTIQUES (admission, see p. 196) has an entrance of its own in the Rue Richelieu, the door beyond the police-engine station when approached from the Boulevards, and the first when approached from the Palais-Royal (visitors ring). It contains an extensive collection of *Medals* (400,000) and *Antiques*, comprising gems, intaglios and cameos, small works of art, glasses, vases, arms, and other curiosities. The present arrangements are temporary, and few of the medals are exhibited.

VESTIBULE. On the wall at the back: *Zodiacal Monument from Dendera*. This monument occasioned much discussion in the learned world, until it was discovered that the temple of Dendera was not completed before the early days of the Roman empire, which pointed to the fact that the Greek signs of the Zodiac had been transported to Egypt. On the left the chamber of the kings from Karnak, constructed by Thotmes III. (18th Dynasty), with important inscriptions, but badly placed.

On the STAIRCASE and in the ANTE-ROOM, stelæ, and Greek and Latin. Coptic and Phœnician inscriptions. — On the left is the —

Grande Galerie. The glass-cases in the centre contain the most interesting objects. In front of CASE I. are several cylinders with cuneiform inscriptions, and cut gems from Assyria, Chaldæa, and Persia; also antique intaglios. — CASE II.: Intaglios and cameos of ancient, mediæval, Renaissance, and modern times. Among others, from left to right: 1st Division, in the middle, 2093. *Antoninus Pius*. 3rd Division, 2391. *Jupiter* enthroned, between Minerva and Mercury, in cornelian; 2396. *Abundance and Peace*, crowned by genii, in sardonyx; 2404. *Jugurtha* delivered to Sulla. 5th Division, *318. *Analogies of the Old and New Testament*, a cameo of the 16th cent.; 303. *Adoration of the Magi*, a Flemish work of the 15th century. 7th Division, 673, 674. *Bracelets of Diana of Poitiers*, each composed of seven cameos, also Renaissance work. 8th Division, *325. *Francis I.*; 337. *Louis XIII.*; *350. *Louis XIV.*; *334. *Henri IV.* and *Marie de Médicis*. — CASE III. (continuation of the cameos). 1st Division, *9. *Juno*, notable for fineness of workmanship and beauty of material; *4. *Jupiter*, one of the most valuable cameos in the collection, with a magnificent mounting executed under Charles V. (1367); 79. *Young Centaur playing the flute*, 86. *Venus Aphrodite*; 36. *Dispute between Minerva and Neptune*. 2nd Division, 158. *Alexander the Great*, agate mounted in enamelled gold. 4th Division, 159. *Julius Cæsar*, *Augustus*, *Tiberius*, and *Germanicus*, in Renaissance mounting; 209. *Apotheosis of Germanicus*; 201. *Julia*, daughter of Augustus; *240. *Trajan*; 197. *Augustus*.

CASE IV., in the centre of the hall, contains the greatest treasures of the collection: Goblet of sardonyx, known as the *Cup of the Ptolemies*, with Bacchic reliefs, from the treasury of St. Denis; Twelve antique gold medals, some mounted as ornaments; 2779. *Cup of Chosroes I.*, king of Persia (d. 575), composed of medallions of rock-crystal and glass of two colours, with Chosroes enthroned in the centre, also from the treasury of St. Denis, where it was known as the 'Cup of Solomon'; *Julia*, daughter of Titus, in aqua marina, with mediæval mounting; *Trésor de Gourdon*, a tray and flagon of massive gold (6th cent.), found at the village of Gourdon, an interesting memorial of early Christian times. Roman gold necklace; **Apotheosis of Augustus*, the largest cameo in the world, consisting of a sardonyx nearly 1 ft. in height; among the twenty-six figures are Augustus, Æneas, Julius Cæsar, Drusus, Tiberius, Livia, Agrippina, Germanicus,

and Caligula. This cameo was formerly in the treasury of the Sainte Chapelle, and was supposed to represent a triumphal procession of Joseph in Egypt. **Medal of Eucratides*, Greek king of Bactriana, found in 1867, weighing 6 oz. or twenty times the weight of a Greek stater, while the heaviest medals previously found weighed four staters only. Antique vessel in sardonyx, with mediæval mounting. **Patère de Rennes*, a cup of massive gold, found near Rennes in 1774, with reliefs representing the drinking contest of Bacchus and Hercules (triumph of wine over strength), and bordered with sixteen medallions of Roman emperors of the family of the Antonines from Hadrian to Geta, son of Septimius Severus. *Augustus*, antique cameo in a mediæval mounting; Bust of Constantine (?) in agate; *Trésor de Tarse*, four gold medals; *Augustus*, another cameo in a mediæval setting. The remaining divisions of the case contain antique gold trinkets, cameos, gold seals, etc. — CASES V, VI. Roman and Greek medals (all ticketed). — CASE VII. Interesting French and foreign coins. — CASE VIII. The *Silver Treasure of Villeret*, consisting of 67 silver statuettes and vases of different periods and varying value, part dating from the 2nd cent. B.C., found in Normandy in 1830.

The cabinets ranged along the wall opposite the windows contain the *Small Bronzes*, including antique utensils and arms; theu, 702. The '*Caillou Michaux*', an ovoid stone with cuneiform inscriptions, the most valuable Babylonian monument of the kind; specimens of ancient *Glass*; also a choice collection of *Painted Vases*, like those in the Louvre; lastly, more bronzes. — The cabinet on the following wall contains small antique *Terracottas*. In the cabinet on the other side of the door, interesting *Objects in Ivory*, four consular diptychs (presented by consuls to senators), and a mediæval triptych. Lastly, a silver disc, nearly 2½ ft. in diameter, known as the '*Bouclier de Scipion*', with reliefs representing the abduction of Briseis, or her restoration to Achilles by Agamemnon. It was found in the Rhone, near Avignon, in 1656, and probably dates from the fourth cent. of our era. — The glass-cases by the windows contain the most recent acquisitions of the collection (medals); articles found in 1653 in a tomb conjectured to be that of Childebert I.; gems; rings; enamels.

The *SALLE DU DUC DE LUYNES*, to the right of the ante-chamber, contains a choice collection of antique intaglios, cameos, medals, bronzes, and terracottas, bequeathed by the duke, who was a zealous antiquarian (d. 1867). In the centre, a beautiful female torso in Pariau marble. — The *ADJOINING ROOM* contains a fine collection of medals; also handsome furniture, and other mediæval and Renaissance works. In the *LAST ROOM* are the *Collections de Janzé and Oppermann*, consisting of ancient statuettes in bronze and terracotta, and a few vases; also the so-called *Throne of Dagobert*, claiming to date from the 7th century.

We now return to the Rue des Petits-Champs (p. 195; comp. p. 169), in order to reach, on the right, the Avenue de l'Opéra (p. 76), which we follow beyond the boulevards. We next proceed through the Rue Halévy, passing the Opéra on the right, to the open space formed by the junction of the Boulevard Haussmann (p. 75), the Rue de la Fayette (p. 186), and the Rue de la Chaussée-d'Antin (p. 194).

**La Trinité* (Pl. B, 18), at the end of this last street, a church in the latest Renaissance style, built by *Ballu* in 1861-67, has a porch with three large arches, approached by two carriage-drives. Above the façade rises an elegant story with a gallery and a rose of open-work, surmounted by a handsome clock-tower 206 ft. in height, which terminates in two domes, one above the other. The pillars of the somewhat over-decorated façade are adorned with statues of Fathers of the Church, and the balustrade of the second story with

groups representing the four cardinal virtues. The tower is flanked with two lanterns.

The INTERIOR consists of a large nave and two low aisles, separated by handsome columns alternating with pillars, which are embellished with statues of the Apostles. To the four bays of the nave, with their double arcades, correspond chapels on each side. The gallery forming the aisles projects into the choir, below which is a crypt. Over the high-altar rises a tasteful canopy. The apse is occupied by a large chapel richly decorated; paintings by *Em. Lévy* and *d'Elie Delaunay*, and stained glass by *Oudinot*. The nave and the other chapels are also adorned with paintings; those in the nave are by *Jobbé-Duval*; those in the chapels on the right by *Brisset*, *Lecomte-Dunoy*, *F. G. Barrias*, and *Laugée*; those on the left by *Eug. Thérion*, *Rom. Cazes*, *Mich. Dumas*, and *F. Français*. Near the entrance are elegant 'bénitiers', surmounted with marble statues of Innocence and Purity by *Gumery*. La Trinité has a good choir and organ.

In front of the church is the small SQUARE DE LA TRINITÉ, adorned with three fountains and statues of Faith, Hope, and Charity, executed by *Lequesne* from designs by *Duret*.

The broad street to the E. of the square in front of La Trinité is the Rue de Châteaudun, in which Notre-Dame-de-Lorette (p. 194) is situated. The Rue St. Lazare, in the opposite direction, leads to the Gare St. Lazare (p. 204) and the Boul. Malesherbes (p. 203). It passes to the S. of the *Quartier de l'Europe*, so called because most of the streets are named after the great towns of Europe.

The Rue de Londres, to the N.W. of the Place, leads almost straight to the Parc Monceaux (see p. 202), via the *Place de l'Europe* (Pl. B, 18), formed by the junction of six streets above the line of the Chemin de Fer de l'Ouest, behind the Gare St. Lazare. A statue of *Marc Séguin* (1786-1875), maker of the first railway in France (from St. Etienne to Lyons), is to be erected in this curiously shaped place.

II. FROM LA TRINITÉ TO THE PARC MONCEAUX.

Les Batignolles.

We ascend the Rue de Clichy to the left of the church, passing the Casino de Paris (p. 33), and soon reach the *Place de Clichy* or *Place Moncey* (Pl. B, 17), in which rises the *Monument of Moncey*, erected in 1869, a colossal group in bronze, by *Doublemard*, 19 ft. in height, on a pedestal 26 ft. high, adorned with bas-reliefs. It represents Marshal Moncey (d. 1842) defending Paris, with a dying soldier beside him.

Near this Place, to the right, is the *Square Vintimille*, where a bronze *Statue of Berlioz* (1803-1869), by AIF. Lenoir, was erected in 1886.

Opposite the monument of Moncey the *Avenue de Clichy* ascends to the N., and farther on bends to the left, while the *Avenue de St. Ouen* turns a little to the right. The former is the tramway-route to Asnières (p. 285) and Gennevilliers (p. 61), and the latter to St. Ouen and St. Denis (p. 318). *Clichy* (26,800 inhab.) and *St. Ouen* (21,400 inhab.) are uninteresting. The château of St. Ouen, where Louis XVIII. signed his famous declaration of 14th May, 1814, no longer exists, and the park is now private property. A new race-course has recently been opened here.

From the Place de Clichy the *Boulevard des Batignolles* leads us to the W., soon crossing the 'Ouest, Rive Droite' railway. We pass on the left the *Collège Chaptal* (Pl. B, 14, 15), a building constructed by *Train* in 1866-72, of stone and bricks of different

colours, and tastefully decorated. We next enter the *Boulevard de Courcelles* and cross the Boul. Malesherbes (p. 203), just beyond which we reach the —

Parc Monceaux, or *Parc de Monceau* (Pl. B, 15), enclosed by a very handsome railing. There are four entrances (see Plan), the chief of which is in the Boul. de Courcelles, where a small rotunda, from the former Barrière de Chartres, has been placed. The park owes its name to a property bought in 1778 by Philippe d'Orléans, surnamed *Egalité*, father of Louis Philippe, who laid it out in so novel and attractive a style that it soon became one of the most fashionable resorts of the 'beau monde'. Balls, plays, and fêtes of the most brilliant description were celebrated here. The Revolution converted the park into national property. Napoleon I. presented it to his chancellor Cambacérès, who however soon restored it to his imperial master, on account of the great expense in which it involved him. At the Restoration it again became the property of the house of Orleans, and was employed in 1848 for the 'national ateliers'. At length it was purchased by the city of Paris, and upwards of 25 acres of it were sold by the municipality for building purposes, while the remaining 22½ acres were converted into a public park, tastefully laid out in the English style, and accessible to carriages as well as pedestrians.

This park has no pretension to vie with the Bois de Boulogne, or even the Buttes-Chaumont, but it affords a pleasant and refreshing oasis in the midst of a well-peopled quarter of the city, and contains a very fine collection of brilliant exotics. It also retains a few relics of its old attractions, such as the *Naumachie*, an oval piece of water, flanked with a semicircular Corinthian colonnade, and embellished with a statue of Hylas, in bronze, by *Morice*. Among the sculptures with which the park has been recently embellished are the Charmer, a bronze figure by *B. de la Vingtrie*; 'Paradise Lost', in marble, by *Gautherin*; the Game of marbles, by *Lenoir*; the Sower, by *Chapu*; the Hay-maker, by *Gumery*; and the Reaper, by *Caudes*.

From the gate into the Avenue Hoche, at the end of which the Arc de l'Etoile is visible, we observe the gilded domes of the 'Eglise Russe' (Pl. B, 12), in the Rue Daru. This church was built in 1859-61 in the Byzanto-Muscovite style, from a design by *Kouzmine*, and is in the form of a Greek cross. The handsome porch is covered with a gilded dome and surmounted with five pyramids, that in the centre being 156 ft. in height, and all of them terminating in gilded domes with Russian crosses. The church is open on Sun. and Thurs., 3-5 o'clock. The interior consists of a vestibule, a nave, and a sanctuary, the last-named being screened off, according to the usage of the Greek church, with an 'ikonostas', which derives its name from the figures which adorn it. These last, representing Christ, the Virgin, and several Russian saints, were painted by the brothers *Sorokine* and by *Bronnikoff*. The rest of the church is adorned with paintings by the same artists from Scriptural subjects and with prophets by *Vassilief*.

The **Batignolles** quarter, to the N. of the Parc Monceaux, one of the communes annexed to Paris in 1860, is one of the finest parts

of the town. It has undergone immense alterations of late, and contains many handsome and tasteful private residences, presenting a pleasing contrast to the monotonous architecture of the ordinary streets of Paris. The traveller will find it worth while to inspect the *Rue Prony*, opposite the principal entrance to the park, and several of the side-streets, such as the *Rues Fortuny* and *Montchanin*, and lastly the *Avenue de Villiers* and part of the Boul. Malesherbes. In the *Place Malesherbes* (Pl. B, 14) there are also several very handsome mansions, particularly the lofty *Hôtel Gailard*, in the style of the 15th or 16th century, and recalling the Château de Blois. A bronze *Statue of Alex. Dumas* (d. 1870), designed by Gustave Doré, was erected here in 1883. The fine group in front represents Reading, and behind is the Musketeer D'Arctagnan (from Dumas' 'Trois Mousquetaires').

No. 145 in the Boulevard Malesherbes is the *Ecole Monge* (Pl. B, 11-14), an establishment founded in 1869, to prepare pupils for the government schools. Farther to the N. is the *Place Wagram* (Pl. 11), embellished with a bronze statue, by F. de St. Vidal, of *A. de Neuville* (1835-1885), the military painter. The Place is situated above the Chemin de Fer de Ceinture, not far from the stations of Courcelles and Batignolles (comp. Appx.), and it is the terminus of a line of omnibuses (*F*).

III. FROM THE PARC MONCEAUX TO THE OPERA.

St. Augustin. Chapelle Expiatoire. Gare St. Lazare.

The *Boulevard Malesherbes* (Pl. B, 11, 14, 15), which passes near the E. side of the Parc Monceaux, was completed in 1861. It extends as far as the fortifications, and is nearly $1\frac{3}{4}$ M. in length. It is flanked with handsome mansions, and contains few shops. Towards the middle of the lower part rises the church of —

St. Augustin (Pl. B, 15), built by *Baltard* in 1860-68, in a modernised Romanesque style. The building is in the form of an irregular triangle, towards the base of which rises a dome 80 ft. in diameter and 165 ft. in height, crowned with an elegant lantern, and flanked with four dome-covered turrets. The portal consists of three arches surmounted by a kind of gallery containing statues of Christ and the Apostles, above which are a rose-window and a triangular pediment. The pillars are also embellished with statues of prophets and doctors of the church.

INTERIOR. The church has no aisles, properly so called. The nave preserves its width the whole way back, while the increasing width of the triangle is filled with chapels increasing in depth as they approach the choir. Above are galleries, which are continued up to the dome. The nave is covered with an arched ceiling, borne by arcades of open iron-work, and the columns terminate in figures of angels. The high-altar, standing beneath a sumptuous canopy, is placed above a crypt, which also runs under the nave. The very short transepts terminate in chapels adorned with paintings by *Bouguereau*, that on the right being dedicated to St. Augustine, and that on the left to John the Baptist. In the dome, medallions of the Evangelists, painted by *Signol*. The Lady Chapel is adorned with a large Adoration of the Shepherds and Presentation in the Temple, by *Brissot*. Stained glass by *Maréchal* and *Lavergne*.

A little below St. Augustin the Boul. Malesherbes is crossed by

the *Boulevard Haussmann* (p. 75), in which, to the right, at the point where the *Avenue de Messina* diverges to the N.W. towards the *Parc de Monceaux*, a bronze statue of Shakspeare, by Paul Fournier, was erected in 1888. We, however, follow the *Boul. Haussmann* to the left as far as a square, in the middle of which stands the —

Chapelle Expiatoire (Pl. B, 18; II; fee to attendant), erected in 1820-26 to the memory of Louis XVI. and Marie Antoinette, on the site of the old cemetery of the Madeleine, where they were interred from 1793 to 1815, when their remains were removed to the royal vault at St. Denis. In front of the chapel, which faces the W., is a court flanked with galleries in imitation of ancient tombs, and intended as a monument to other victims of the Revolution. The E. entrance is also in the form of a tomb. The chapel is in the form of a Greek cross, with a portico, and is covered with a dome.

The INTERIOR contains two groups in marble. That on the right, by *Bosio*, represents Louis XVI. and an angel who addresses him with the words, '*Fils de St. Louis, montez au ciel!*' Below is inscribed the king's will. The group on the left, by *Cortot*, represents the Queen supported by Religion, a figure which bears the features of Madame Elizabeth, the king's sister, who was guillotined on 12th May, 1794. Inscribed on the monument is the last letter addressed by the queen to her sister-in-law (comp. p. 206). Staircases on each side of the altar descend to a crypt, which occupies the ground where Louis XVI. was originally interred.

By following the *Boulevard Hausmann* for 5 or 6 min. farther we reach the back of the *Opéra*.

The **Gare St. Lazare** (Pl. B, 18), which is reached from the *Boulevard Haussmann* and the *Chapelle Expiatoire* by the short *Rue Pasquier*, is a large and handsome building, remodelled in 1886-89 on plans by Lisch. It consists of two main parts, connected by a long waiting-room, and of the *Hôtel Terminus* (p. 3) in front, facing the street, and concealing the rest. The part or pavilion in the *Rue d'Amsterdam* is for the main line traffic, the other part, in the *Rue de Rome* for the *Chemin de Fer de Ceinture* and for the *Lignes de Banlieue*.

We now return through the *Rue du Havre* and the *Rue Auber* to the *Place de l'Opéra*, the most direct route between the station and the boulevards. To the left in the *Rue Havre* are the *Lycée Condorcet*, and, at the corner of the *Boulevard Haussmann*, the imposing *Magasins du Printemps*, rebuilt since a fire in 1882.

7. From the Louvre to Vincennes.

The Bois de Vincennes is worthy of a visit, but the excursion will take nearly a whole day. From the centre of the city the best route to it is by the Louvre and Vincennes tramway (C), besides which the tramway lines F and K are also available (see Appendix). The first-mentioned line, however, is generally in great request on Sun. and holidays, and passengers have to wait a long time before obtaining a seat. — The Charenton steamboats (not the others) call at Charenton (near the Bois; fares 20 c. on week-days and 25 c. on Sun. or holidays) and offer the most economical, and in summer the pleasantest route (see Appx.). The walk from

the landing-stage through the wood to Vincennes takes about an hour. — Railway to Vincennes (in connection with which an omnibus runs from the Bourse) inconvenient, as the station of departure is far from the centre of the town. Comp. p. 210. — The traveller who purposes visiting the Archives, the Imprimerie Nationale, and the Musée Carnavalet on his way to Vincennes must of course choose a day (Thurs.) on which they are open, and should be provided with the necessary orders (see below). On Sun. orders are not required for the Musée Carnavalet or the Archives. The former should be visited first, as it is opened earlier. — Luncheon may be taken at the Place de la Bastille (see pp. 13, 15).

I. FROM THE LOUVRE TO THE MUSÉE CARNAVALET AND THE BASTILLE.

We first proceed to the *Halles Centrales* (p. 170), by the Rue de Rivoli and the Rue du Pont-Neuf (to the left), and then follow the *Rue de Rambuteau* (to the right), leading across the Boul. de Sébastopol (p. 60) to the *Rue des Francs-Bourgeois*. Here, to the left as we enter the street, are situated the —

Archives Nationales (Pl. R, 23; *III*), established in the old *Hôtel de Soubise*. This building occupies the site of the mansion of the Connétable de Clisson, erected in 1371, of which there still exists in the Rue des Archives, to the left of the façade, a handsome gateway flanked with two turrets (restored in 1846). Down to 1696 the mansion belonged to the powerful Guise family, after which it came into the possession of the family of Soubise. The present Palais des Archives chiefly consists of buildings erected by François de Rohan, Prince de Soubise, at the beginning of the 18th cent., and others recently added or reconstructed. The entrance is in the Rue des Francs-Bourgeois. The court is surrounded by a handsome Corinthian colonnade by *Lamer*; the pediment, with its Corinthian and composite columns, is adorned with sculptures by *R. Lelorrain*.

By a decree of the constitutional assembly a committee was appointed in 1794 to examine and classify the official documents preserved in the public dépôts. This body finished its labours in 1801, and in 1808 the records were transferred to their present repositories.

The national archives are divided into four departments — the 'Secrétariat', the 'Section Historique', the 'Section Administrative', and the 'Section Législative et Judiciaire'. Visitors are admitted for purposes of research daily, 10-3 o'clock, except on holidays, on previous application at the *Bureau des Renseignements*. The 'Musée' consists of a collection of the chief treasures of the Archives.

The Musée des Archives, or *Musée Paléographique* (open to the public on Sun., 12-3; also on Thurs., during the same hours, by permission obtained from the director), occupies four rooms on the ground-floor and four on the first floor. The principal objects are labelled, and each room contains a catalogue.

GROUND FLOOR. — I. *Salle des Mérovingiens, des Carlovingiens, et des Capétiens*. Round the room are the most ancient documents, many of them with seals. In the centre-cases: registers in chronological order, some of them with miniatures; funeral scroll of Vital, Abbé de Savigny, with verses attributed to Héloïse (1122-23); the accounts of the Hôtel de St. Louis (1256-57), on tablets of green wax; registers with miniatures and drawings, including the register of the Parlement of Paris (on the middle of

the other side); papers relating to the trial of Joan of Arc (1431), with a caricature of the Maid drawn during the proceedings.

II. *Salle des Valois*. On the left, in the first row of glass-cases, is the Declaration of the Clergy of France in 1682; the Revocation of the Edict of Nantes by Louis XIV. (1685). The fourth row contains the famous Edict itself, signed by Henri IV. (1598). In the second and third rows are letters from Richelieu, Turenne, Louis XIII., Colbert, Louis XII., Marie de Médicis, Anne of Austria, Charles de Lorraine, duke of Guise, etc.

III. *Salle des Sceaux*. Reproductions of the finest seals in the Archives. Also an allegorical painting of little artistic value, but historically celebrated. It dates from the reign of Henri IV., and represents the vessel of the Church on its voyage towards the harbour of Salvation, surrounded with boats bringing believers to it, and with others containing assailants. It was discovered in a church of the Jesuits, and afforded an argument against them when the order was suppressed in 1762.

IV. *Salle des Traités*. Centre-case to the right: letter of Richard Cœur-de-Lion; commercial treaty, made between the King of Tunis and Philip III. of France (1270), after the death of St. Louis; treaty of Brétigny (1360); treaty between Henry VIII. of England and Francis I. of France (1532); to the left, treaty between Henri II. of France and the Swiss Cantons (1549); treaty of Münster (1648), with the golden seal of Ferdinand II.; treaty between France and Turkey (1812). Facing these, other treaties with Switzerland; Papal documents; bull of Leo X. abolishing the Pragmatic Sanction of 1438; agreement between Leo X. and Francis I. At the windows: Letter of Solymán I. to King Ferdinand (1549); from Solymán II. to Francis I.; from Tamerlane to Charles V. (1402); from the Sultan Amurath III. to the Emperor Rudolph II. (1578). Chinese documents.

V. *Salle des Documents Étrangers*. In the flat glass-cases, Charters arranged in order of countries, from left to right: Germany, Austria, Belgium, Denmark, Spain, Great Britain, Holland, Italy, Norway, Portugal, Russia, and Sweden. On the walls, Foreign seals.

FIRST FLOOR. — I. *Salle des Bourbons*, richly decorated, formerly a bed-chamber, and still retaining the gilded railing that enclosed the bed. Within the railing is a glass-case containing, among other curiosities, the 'procès-verbanx' of the examination of Marie Antoinette at the Conciergerie relative to the affair of the necklace; records of the examination of several other members of the royal family; journal of Louis XVI. (from 1st Jan., 1766, to 31st July, 1792); speech delivered by the King before the Convention after his defence by De Sèze (26th Dec., 1792); 'procès-verbal' of the interment of Louis XVI. (21st Jan., 1793). Above the case are the will of Louis XVI., executed at the Temple on 29th Dec., 1792, and the last letter of Marie Antoinette, written in the Conciergerie on 16th Oct., 1793. (The genuineness of these two documents is, however, doubtful; the letter does not bear the queen's signature.) In the centre of the room, near the railing, to the right: letters of Louis XV., Voltaire, Duke of Orleans, and Prince Condé; to the left the testament of Maria Leszcinska (21st June, 1767); an autograph of Beaumarchais; letters of Lafayette and Mme. Adelaide; edicts of Louis XVI.

II. *Salle Ovale*. Glass-case in the centre (right side): record of the Tiers-Etat of Paris (1789), Declaration of the rights of men and citizens (1789), and the Constitution of 1791; resolution by Mirabeau. On the other side: proclamation by Louis XVI. concerning the holding of the États-Généraux; draft of an address to the king by Mirabeau; the resolution ordering the destruction of the Bastille. — This saloon, once the drawing-room of Mme. de Rohan, has a ceiling-painting by *Natoire* (d. 1777), representing the adventures of Psyche.

III. *Salle de la République*. By the first window, treaty of Bâle between the French Republic and Frederick William II. (1795); several 'assignats', or notes issued by the Revolutionary government on the security of confiscated church-lands. By the second window is the famous Oath taken at the Jeu de Paume (p. 289), with the signatures. In the centre and round the room are documents executed by members of the Convention or by the Constitutional Government. In the second row, in the

glass-case at the back: judgment of the Girondists, letters of Robespierre, Bonaparte, Carnot, etc. In the third row, near the window, are several letters of Charlotte Corday and an order by Fouquier-Tinville for the execution of Marie Antoinette.

IV. *Salle du Consulat et de l'Empire*. Documents of less interest. At the first window, Constitution of 1802 (1'an 8). Behind, to the left, a table from the cabinet of Louis XVI., on which Robespierre, when wounded, was brought before the 'Comité du Salut Public' at the Tuileries.

Adjoining the Palais des Archives is the *Ecole des Chartes*, founded in 1820, a school for the training of palæographers.

Opposite the Archives is the *Mont-de-Piété*, or great pawnbroking establishment of Paris, which enjoys a monopoly of lending money on pledges for the benefit of the 'Assistance Publique'.

The loans are not made for less than a fortnight, but articles may be redeemed within that time on payment of the fees. The sums advanced vary from two-thirds to four-fifths of the value of the articles, the maximum lent being 10,000 fr. at this establishment, and 500 fr. at the branch-offices. The interest and fees, which before 1885 were as high as 9½ per cent, are now reduced to 7 per cent, with a minimum of 1 fr. The pledges are sold after fourteen months from the time when the borrower has failed to redeem them or to renew his ticket or 'reconnaissance'; but within three years more the excess of the price realised over the sum lent may still be claimed. The Mont-de-Piété lends upwards of 56,000,000 fr. annually on an average of 2¼ million articles. The sale of unredeemed pledges produces about 4,000,000 fr. annually.

Adjacent to the Mont-de-Piété is the church of *Notre-Dame-des-Blancs-Manteaux*, facing the street of that name. In the Rue des Francs-Bourgeois, farther on, at the corner of the Rue Vieille-du-Temple, rises a Gothic tower with arcades and a grating, a relic of the *Hôtel Barbette*, where Louis of Orleans was assassinated in 1407 by order of Jean sans Peur, Duke of Burgundy. — To the left, a little farther up the Rue Vieille-du-Temple, is the —

Imprimerie Nationale (Pl. R, 23; III), or government printing-office, established in the old *Hôtel de Strasbourg*, which once belonged to the celebrated Cardinal de Rohan (d. 1803). The court is adorned with a copy in bronze of the Statue of Gutenberg by *David d'Angers* (d. 1856) at Strasbourg. The printing-office employs about 1200 workpeople of both sexes. The types are cast, the paper made, and the binding executed within the same building. Oriental characters are particularly well represented, and on the occasion of a visit to the establishment by Pius VII. the Lord's Prayer was printed in his presence in 150 different languages. The chief business of the office consists in printing official documents of all kinds, books published at the expense of government, geological maps, and certain playing-cards (*viz.* the 'picture-cards' and the ace of clubs, the manufacture of which is a monopoly of the state). Visitors are admitted on Thurs. at 2 p.m. with tickets obtained from the director, but strangers who present themselves at that time are usually admitted even without tickets. The inspection takes 1-1½ hr.

Lower down the Rue Vieille-du-Temple, to the S. of the Rue des Francs-Bourgeois, is the *Hôtel de Hollande* (No. 47), a hand-

some edifice of the 17th cent., once occupied by the Dutch ambassador to the court of Louis XIV. The gateway is adorned with fine sculptures, and the court contains a large bas-relief of Romulus and Remus, by Regnaudin.

Beyond the Rue Vieille-du-Temple the Rue des Francs-Bourgeois passes on the right the old *Hôtel Lamoignon*, dating from the 16th century. Farther off, to the left, in the Rue Sévigné, is situated the —

Musée Carnavalet (Pl. R, 26; V; open to the public on Sun. and Thurs., 11-4), or *Musée Historique de la Ville*, containing a collection of Parisian antiquities and the new *Municipal Library*, which was established here in 1871. The name is a corruption of *Kernevalec*, a lady of that name having once been the proprietor of the mansion, and it was afterwards the residence of Mme. de Sévigné for twenty years (1677-98). The building, which dates from the 16th and 17th centuries, was begun from designs by *Lescot* and *Bullant*, and completed by *Du Cerceau* and *F. Mansart*. It was purchased by government in 1869, and thoroughly restored. The sculptures on the façade and those of the Seasons in the court, facing the entrance, are attributed to *Jean Goujon* (p. 106). The eight other statues, particularly those of four gods of mythology, are of no value. In the centre is a fine bronze statue, by Ant. Coyzevoz, of *Louis XIV.*, brought from the old Hôtel de Ville.

The Museum occupies fourteen rooms on the ground-floor, part of the sunk-floor, a gallery in the garden at the back, and seven rooms or galleries on the first floor. Descriptive labels everywhere; visitors receive gratuitous notices of the order of the rooms to be visited, which is adhered to in the following account.

GROUND FLOOR. *Right Wing* (entrance beneath the archway): Antiquities, in 9 small rooms. The first rooms contain photographs of Gallo-Roman monuments; stones from the Arena in the Rue Monge and other Roman buildings; and fossils and monuments of the stone age. — The following rooms contain Roman mill-stones, a reconstruction of a Roman mill, and sarcophagi, some of which are made of the remains of ancient monuments.

SUNK FLOOR (open in summer only; reached from the last room but one in the right wing): Sarcophagi. In one of the cellars are plaster casts of the skeletons found in the Arena.

GROUND FLOOR (continued). The *Main Building*, to the left as we come from the preceding rooms, passing the exit-staircase on the right, contains four rooms with additional antiquities; fragments of Gallo-Roman buildings; 16th cent. chimney-piece; earthenware, glass, bronzes, coins, etc., found in Gallo-Roman and in Merovingian and mediæval tombs; tomb-inscriptions, etc. — Continuation of the Ground Floor, see p. 209.

FIRST FLOOR (reached by the staircase at the end of the 4th of the above rooms, or by the staircase to the left in the first court), contains miscellaneous collections, some of great interest. On the *Staircase* (to the library, p. 209) are facsimiles of ancient plans of Paris; busts of Mme. de Sévigné and Jean Goujon, etc. — *On the S. Side of the Garden* are two rooms and two galleries, with views of Paris, engravings, and paintings; character-scenes; portraits of magistrates, etc.; *Departure of the Conscripits of 1807*, by Boilly; the old Boulevard du Temple. — *At the End of the Garden* are four rooms, the first two of which also contain plans of Paris, relief-plan of the neighbourhood of St. Germain-en-Laye and Marly, etc. In the next two are ceilings and panelling from an ancient

mansion of the time of Louis XIV. The first contains a bronze statuette of the Duke of Bordeaux as a child; a votive tablet of 1609; ancient processional banner, etc.; the second, a valuable collection of porcelain, dating from the revolutionary period. The ceiling of this last room is by Lebrun (Olympus, the Muses, etc.). — The adjoining *Staircase* descends to the garden (see below); upon it are flags, slabs from chimney-pieces, a cabinet with dies for coins, the manifesto of the Duke of Brunswick in 1792, etc. — *On the N. Side* of the garden are two galleries and a room containing *Relics of the Revolutionary Period*: paintings, portraits, decorations, coins, decimal clocks, porcelain, etc. In the first gallery, to the left, the Oath in the Jeu de Paume, completed reduction of the painting sketched by David (p. 142); jointed figure representing Voltaire; the ceiling and a curious clock in the central room, and some fans in the second gallery should be noticed. — *Large Room*, leading back to the main building: *Authentic Relics of the Revolutionary Period*. In the centre, Model of the Bastille, made from a stone of that building. Hung from the ceiling is the banner of the Emigrés, with the arms of France and the Allies, and the Hydra of the Revolution. On the entrance-wall, Cabinet with a representation of the Fall of the Bastille; declaration of the rights of men; weapons; playing-cards; bindings; Constitution of 1793 bound in human skin; busts, portraits, medallions, miniatures, etc. Exit-wall: engravings; curtains; head-dresses; cockades, belts, gloves, boots. Fireplace-wall: weapons; instruments of punishment; lettres de cachet; embroideries; caskets and snuff-boxes. Other wall: Cabinet decorated with patriotic scenes; decimal clock; placards; order of Louis XVI. commanding the Swiss guards to cease firing, on Aug. 10th, 1792; sword of honour of La Tour d'Auvergne; sabre of Général Augereau, etc. — *Last Room: Relics of the Revolutions in 1830 and 1848*: paintings, water-colours, decorations; glass cups; snuff-box with miniature painting of the Entry of Louis XVIII.; portrait of Louis Blanc; statuette of Ledru Rollin, etc. — *Exit-Staircase* (continuation of the above collection): iron fastenings and bolts of the dungeons of the Conciergerie; plans for the completion of the Louvre, etc.

GROUND FLOOR (continuation). The *Garden* is surrounded with constructions not belonging to the Hôtel Carnavalet. In the middle, to the left, the *Arc de Nazareth*, a gateway from the old street of that name in the Cité, with sculptures by Jean Goujon, and a tasteful modern railing. Opposite, to the right, a pavilion of the time of Louis XIV. Behind, façade of the old guild-house of the drapers, by Jacques Bruant (17th cent.). In the galleries, to the right and left, are fragments of buildings of the Middle Ages, the Renaissance, and the 17th and 18th centuries. — *End Galleries*: Relics of Paris. The first gallery, to the right, is devoted to the Palais Royal, and contains a relief model of the galleries of the Palais, executed in 1843; paintings; curious engravings; medallions, etc. In the second gallery are relics of the old Hôtel de Ville; statues of the Comtes de Chabrol and de Rambuteau; fragment of an altar of the 16th century. The third gallery contains a collection of caricatures of numerous celebrities of the time of Louis Philippe; plaster statuettes and busts, by *Dantan the Younger*.

The Bibliothèque de la Ville, founded in 1871, to replace the library destroyed in the Hôtel de Ville, already consists of about 80,000 vols. and 70,000 engravings and charts, all illustrative of the history of Paris and the Revolution. It occupies part of the first floor and is reached by the above-mentioned staircase, at the end of the court. It is open to readers on week-days, 10-4 in winter, and 11-5 after Easter (closed in Easter week and Aug. 15th-Oct. 1st).

A little beyond the Musée Carnavalet the Rue des Francs-Bourgeois ends at the *Place des Vosges* (Pl. R, 26; V), formerly called the *Place Royale*. The garden in the centre, planted with limes and plane-trees, and enclosed by a railing, is adorned with an *Equestrian Statue of Louis XIII.*, in marble, by Dupaty and Cortot, which was erected in 1829 to replace a statue erected by

Richelieu in 1639 and destroyed in 1792. The angles of the square are adorned with fountains.

The Place des Vosges occupies the site of the court of the old *Palais des Tournelles*, where the tournament at which Henri II. was accidentally killed took place in 1565 (p. 64). Catherine de Médicis caused the palace to be demolished, and Henri IV. erected the square which still occupies its site. The houses, uniformly built of brick and stone, with lofty roofs, are flanked with arcades on the ground-floor. The children who make this their playground, and the military band which plays in the square on Thursday afternoons in summer, impart a little life to this sequestered nook; but at other times it presents an almost monastic appearance. The inhabitants of the square and the neighbouring streets, called the *Quartier du Marais*, are chiefly retired officials and persons of small independent means, who lead a quiet and secluded life. It is difficult to believe that this was the fashionable quarter of Paris in the reign of Louis XIII., when the 'place' may be said to have formed the Palais-Royal of the period. The Place des Vosges was first so named after the Revolution, in honour of the department of that name, which had been the first to send patriotic contributions to Paris, and this name was revived in 1848 and again in 1870.

The Rue des Vosges, to the N. E. of the square, leads direct to the Boul. Beaumarchais (p. 70), near the *Bastille* (p. 65).

II. FROM THE BASTILLE TO VINCENNES.

The public vehicles from the Louvre to Vincennes have been already mentioned (p. 204). We may also use the Tramway Sud from the Bastille to Charenton, or the Vincennes railway (p. 24).

Tramway from the Louvre to Vincennes, see below.

The *Tramway from the Louvre to Charenton* (K) follows the Rues de Rivoli and St. Antoine (p. 65), passes the Bastille, and skirts the quays. Terminus in the lower part of Charenton, less than $\frac{1}{2}$ M. from the entrance to the Bois (p. 214). (Fare 50 or 25 c.)

The *Tramway from the Bastille to Charenton* follows the Rue de Lyon, to the right of the railway, and then the Avenue Daumesnil, passing the Place of the same name, which is adorned with a monumental fountain from the Place du Château d'Eau (Place de la République). Outside the town, the Avenue Daumesnil crosses a corner of the Bois de Vincennes near the Lac de Charenton (p. 214). (Fare 50 or 25 c.)

The *Chemin de Fer de Vincennes* corresponds with the Ligne de Ceinture at the *Station du Bel-Air*, and has another station at *St. Mandé* (p. 211). (Fare from Paris to Vincennes 50 or 30 c.) The station is in the Rue de Montreuil, whence we turn to the right to reach the Château. Farther on, this line skirts the wood, passing *Fontenay-sous-Bois*, *Nogent-sur-Marne* (p. 213), and *Joinville* (p. 213). — *Steamboats*, see p. 204.

THE TRAMWAY FROM THE LOUVRE TO VINCENNES (C; 40 or 20 c.) runs by the quays and the Boul. Henri IV. (p. 67) to the Bastille. It then follows the Rue du Faubourg St. Antoine to the **Place de la Nation** (Pl. R, 31), formerly the *Place du Trône*, which forms the E. extremity of Paris, while the Place de l'Etoile forms the N.W. end, upwards of 5 M. distant. The centre of the 'place' is adorned with a large basin and a bronze group by Dalou, representing the *Triumph of the Republic*. The surrounding buildings are uninteresting, with the exception perhaps of the *Ecole Arago*, a superior municipal school opened in 1880. About a dozen different streets radiate from this point, but the traffic is insignificant. In 1660, after the conclusion of the Peace of the Pyrenees, Louis XIV. received the homage of the Parisians on a throne erected here, and from that

event the 'place' derived its former name. The two lofty fluted Doric columns erected here on the site of the old barrière were begun in 1788, but not completed till 1847. Each is adorned with two basreliefs by *Desboeufs* and *Simart*. Those next the town represent Commerce and Industry, those on the other side Victory and Peace; and they are surmounted with bronze statues of St. Louis by *Etex* and Philippe le Bel by *Dumont*. Beyond the columns begins the *Cours de Vincennes*, a broad avenue leading direct to Vincennes (to the château $1\frac{3}{4}$ M.).

The *Foire au Pain d'Epices*, or 'gingerbread fair', held on the Place de la Nation and on the Cours during three weeks after Easter, always presents a very lively scene.

A tramway-line runs from the Place de la Nation to *Montreuil* (pop. 21,541), a place famous for its peaches, but otherwise uninteresting. This is also either the starting-point or a station of several other tramways (see Appx.).

The Vincennes tramway next traverses the Boul. de Picpus and the Avenue de St. Mandé, passing the station of that name on the Vincennes railway.

To the S. of the Avenue de St. Mandé, Rue de Picpus 25, is the small Cemetery of Picpus (Pl. G. 31; adm. 50 c.), which contains the tombs of members of some of the oldest families in France (*Montmorency*, *Noailles*, *Gramont*, *Crillon*, etc.). At the end is the 'Cimetière des Guillotinés', where 1300 victims of the Revolution, executed at the Barrière du Trône, are interred. In one corner is the tomb of *Lafayette* (d. 1834).

At *St. Mandé*, to the S., a village with 10,492 inhab., are two asylums for old men, and a cemetery containing a statue in bronze, by *David d'Angers*, of Armand Carrel (d. 1836), who was killed in a duel by Emile de Girardin. About 2 min. from the station is the pretty Lac de St. Mandé (p. 214).

Vincennes. — *Café de la Paix*, Cours Marigny, near the tramway-terminus, déj. $2\frac{1}{2}$, D. 3 fr.; *Continental*, Rue de Paris, 30, with a small garden, below the château, similar charges (also beds); *Français*, in front of the château; *Café-Restaurant de la Porte Jaune*, in the wood, p. 213. — *Tramway* (compressed air) from the Cours Marigny to ($\frac{1}{2}$ M.) Ville-Evrard, viâ Nogent-sur-Marne, see p. 213.

Vincennes, a town with 20,500 inhab., is a place of no importance except as one of the fortresses in the outskirts of Paris. The only object of interest in the town is the *Statue of General Dumesnil*, by Rochet, in the Cours Marigny, near the tramway-station. The gesture of the figure forms an allusion to the anecdote that when the general, who defended the château in 1814 and 1815, was called on to surrender, he replied that he would not do so till the Allies restored to him the leg he had lost at the battle of Wagram. At the end of the Cours is the modern Renaissance *Mairie*.

The **Château de Vincennes** was founded in the 12th cent. and afterwards gradually enlarged. It was used as a royal residence till 1740, when Louis XV. converted it into a manufactory of porcelain. In 1751 these works were removed to Sèvres, and the Château de Vincennes became first a military school and then (1757) a weapon-manufactory. In 1832-44, under Louis Philippe, the châ-

teau was strongly fortified and transformed into an extensive artillery dépôt, with an 'Ecole de Tir'. It is now seldom shown to foreigners.

The château was used as a *State Prison* from the days of Louis XI. (1461-83) onwards. Among many illustrious persons who have been confined within its walls, may be mentioned the King of Navarre (1574), the Grand Condé (1650), Cardinal de Retz (1652), Fouquet (1661), Count Mirabeau (1777), the Duc d'Enghien (1804), the ministers of Charles X. (1830), and the conspirators against the National Assembly (15th May, 1848).

A melancholy interest attaches to the fortress from its having been the scene of the execution of the unfortunate Duc d'Enghien, the last scion of the illustrious Condé family. On the suspicion that he was implicated in a conspiracy against the emperor, he was arrested by order of Napoleon on 14th March, 1804, on German territory, conveyed to Vincennes, and there condemned to death by a court-martial. The sentence was executed on 20th March, and the body of the duke interred in the fosse where he was shot. In 1816 Louis XVIII caused his remains to be removed to the chapel, where he erected a monument to his memory.

In May, 1871, the château was one of the last places occupied by the insurgents. They evacuated it on the approach of the Versailles troops, leaving one of their number concealed in a casemate, with instructions to set fire to the powder-magazine when the troops had entered. As, however, almost certain death awaited him in any case, the unfortunate man preferred suicide to the execution of his murderous commission.

The *Chapel*, with its tasteful Gothic front, begun in 1379 under Charles V., and completed in 1552 in the reign of Henri II., has recently been restored. The lofty vaulting and the stained glass by *Cousin* are worthy of notice. The monument of the Duc d'Enghien, now in the old sacristy, a poor work by *Deseine*, consists of four figures in marble: the duke supported by Religion, France bewailing his loss, and a figure emblematic of Vengeance.


The *Salle d'Armes*, or Armoury, fitted up in 1819, is said to contain weapons sufficient to equip 120,000 men. The artillery stores occupy the ground-floor, and the other arms the floor above.

The *Donjon*, or Keep, in which state-prisoners were formerly confined, is a massive square tower of five stories, 170 ft. in height, with four smaller towers at the corners. The walls are 10 ft. thick. The platform, to which 237 steps ascend, commands a fine view of the surrounding district.

To the E. of the château is the Fort de Vincennes, beyond which begins the —

Bois de Vincennes, a beautiful park, much less frequented than the Bois de Boulogne, but of scarcely inferior attraction, though unfortunately disfigured by the plain in the centre.

The park was once a forest, where Louis IX. (d. 1270) used to hunt and to administer justice; but it was entirely replanted by Louis XV. in 1731. Since that period considerable encroachments on its extent have been made by the railway and the fortifications, but it still covers an area of about 2250 acres, including the Champ de Manœuvres ($\frac{1}{2}$ M. wide) in the middle, and the artillery 'Polygone'. In 1857-58 it was successfully transformed into a public park by *Vicaire* and *Bassompierre*. It is more natural than the Bois de Boulogne, and contains fewer exotics.



Having reached the (8 min.) angle of the fort, we incline to the right and take the road in the centre, the Route de Joinville (see below), and, a little farther on, the Route de Nogent to the left (see below). About $1\frac{1}{4}$ M. from the château we reach the **Lac des Minimes**, formed in 1857 on ground which belonged to the order of that name from 1854 to 1784. The lake is 20 acres in area, and contains three islands. The smallest of these, the *Ile de la Porte-Jaune* at the N. end, is connected with the mainland by a bridge and contains a *Café-Restaurant*.

Opposite the Ile de la Porte-Jaune begins an avenue leading to *Fontenay-sous-Bois*, a village and railway-station about $\frac{1}{2}$ M. to the N.E., with a number of pleasant villas (6175 inhab.). — About $\frac{1}{2}$ M. to the E. of the lake, at the end of the Route de Nogent, lies *Nogent-sur-Marne*, a village with 7325 inhab., on a hill above the Marne, with a station on the same line as Joinville, another on the united lines of the Grande Ceinture and the Belfort railway, and reached also by a tramway from Vincennes (p. 211). The second of the above railway-lines crosses the Marne here by means of a curved viaduct, $\frac{1}{2}$ M. in length. Nogent has numerous country-houses on the side next the Bois, and to the N., towards Fontenay-sous-Bois (see above), is the *Fort de Nogent*. Champigny (p. 215) is $2\frac{1}{2}$ M. from Nogent by the Grande Ceinture. — The tramway is continued to (6 M. from Vincennes) *Ville-Evrard*, where there is a large lunatic asylum, and a branch goes to *Bry-sur-Marne*, a village on the left bank of the river.

Round the lake, at some distance from its banks, runs the *Route Circulaire*, and an avenue also skirts the bank (a circuit of 30-40 min.). Small boats may be hired on the W. side (50 c. per $\frac{1}{2}$ hr. for each person).

Proceeding towards the E. end of the lake, we pass the small *Cascades* by which it is fed, formed by the *Ruisseau de Nogent* and the *Ruisseau des Minimes*. Following a fine avenue to the left, a little farther on, we approach the latter brook and skirt it as far as the Route de Joinville and the *Plaine de Gravelle*, which divides the Bois into two distinct parts. The plain extends from this point to the château, nearly 2 M. distant, and is at places nearly 1 M. in width. On the left we observe the *Redoute de la Faisanderie*, with a military gymnastic school, and farther on, the *Redoute de Gravelle*. On the right is the *Race Course* (p. 34); beyond it lies the *Champ de Manœuvres*, used for infantry drill; and farther distant, on the left, is the *Polygone de l'Artillerie*. At a crossway in the Champ de Manœuvres rises a *Pyramid*, restored in 1871, where an oak under which St. Louis administered justice is said to have stood. From the outskirt of the Bois, near the Redoute de la Faisanderie, we obtain pleasant glimpses of the valley of the Marne and of the hills to the N. of Paris.

The road skirting the Bois on the side next to the plain leads from Vincennes to Joinville-le-Pont (3800 inhab.), a village situated on the right bank of the Marne, a little to the left of the Redoute, and a station on the Chemin de Fer de Vincennes (p. 210). Joinville is the chief boating-centre on this side of Paris, as Asnières (p. 285) is on the Seine. The subterranean *Canal de St. Maur*, which begins here, 660 yds. in length, constructed in 1825, enables barges to cut off a circuit of 8 M. described by the Marne. — Champigny, etc., see p. 215.

A little beyond the Redoute in the Bois de Vincennes we observe the *Ferme de la Faisanderie*, a model farm, connected with which are an Agricultural Institute and some experimental fields worked by the Ecole d'Alfort (see below). Beyond it the Avenue de la Ferme passes the stand of the race-course and ascends to the *Lac de Gravelle*. This small lake is fed by means of a steam-pump on the bank of the Marne, and is drained by streams flowing into the other lakes. A few paces from the lake is the **Rond-Point de Gravelle* (refreshments in summer at the *Pavillon Robert*), which commands an admirable survey of the valleys of the Marne and Seine (see Plans of the Bois and the Environs of Paris, pp. 212, 286).

The roads to the right beyond the Rond-Point are closed when artillery practice is going on at the Polygone. We follow the *Avenue de Gravelle*, to the left, towards the ($1\frac{1}{4}$ M.) Lac de Charenton. A little to the left are the *Hospice d'Aliénés* of Charenton-St. Maurice and the *Asile de Vincennes* for patients of the artizan class, the latter being much nearer to Charenton than to Vincennes.

The name of Charenton (*Café Bradamante*, at the bridge), a place with 12,500 inhab. (incl. *Conflans* and *Les Carrières*), is now chiefly known in connection with its Lunatic Asylum, which stands on the hill within the district of *St. Maurice*, a small town with 6508 inhab., which has sprung up since 1842. In 1606 a Protestant church was erected at Charenton with the sanction of Henri IV., but it was demolished in 1685 in consequence of the revocation of the famous Edict of Nantes. The Marne is crossed here by a bridge, a little above its influx into the Seine. (Steamboat and tramways, see p. 210.) — On the other side of the bridge is *Alfortville* (6525 inhab.), with the *Ecole Vétérinaire d'Alfort*.

That part of the Bois de Vincennes which lies to the N. of Charenton and adjoins the fortifications of Paris on the W. was laid out in 1857-58. Its chief ornament is the *Lac Daumesnil* or *de Charenton*, the largest lake (50 acres) in the Bois, containing two pretty islands, which are connected with each other and with the mainland by bridges. On one are an artificial grotto with a temple above it, and a café; on the other the *Pavillon des Forêts*, at the Trocadéro during the Exhibition of 1889, has been reërected, and will contain a *Musée Forestier*, consisting of the interesting collections previously exhibited in it, with a diorama, etc. Visitors to the islands may then cross to the Avenue Daumesnil by ferry (10 c.) instead of returning by the bridges. (Boats on the lake $\frac{1}{2}$ -2 fr. per hour, according to tariff.)

The Avenue Daumesnil, continuing the street in Paris of the same name leads to the right to the *Esplanade* in front of the château. Various paths diverge to the left of the avenue towards the *Lac de St. Mandé*, near the village of that name (p. 211), the smallest but prettiest of the lakes in the Bois, with beautifully wooded environs, affording charming walks. At St. Mandé there is a station of the Tramway Sud de la Bastille.

FROM VINCENNES (PARIS) TO BRIE-COMTE-ROBERT, 19 M., railway in $1\frac{1}{4}$ hr. (fares 2 fr. 75, 1 fr. 85 c.). Beyond Vincennes the line skirts the

Bois de Vincennes for some distance. — $1\frac{1}{4}$ M. *Fontenay-sous-Bois* (p. 213); $1\frac{3}{4}$ M. *Nogent-sur-Marne* (p. 213). Fine view of the Marne Valley to the left. — 3 M. *Joinville-le-Pont*, see p. 213. $4\frac{1}{2}$ M. *St. Maurice* (16,000 inhab.) is the nearest station to the curve of the Marne (p. 213). Créteil is on the left bank. — 5 M. *Parc de St. Maurice*.

6 M. *Champigny* (4100 inhab.), on the left bank of the Marne, is memorable as the scene of the battles of 30th Nov. and 2nd Dec., 1870, at which Generals Trochu and Ducrot vainly endeavoured to force a passage through the German lines. A monument on the hill behind Champigny marks the site of a crypt containing the remains of the French and German soldiers who fell on that occasion. Champigny is also a station on the Grande-Ceinture railway, rejoining the Ligne de l'Est at Nogent-sur-Marne (p. 213).

Fine views of the valley of the Marne, Vincennes, and Paris are obtained from the places on the hills beyond Champigny, such as *Chennevières* (2 M.; with a view superior to that from St. Germain-en-Laye, at least by morning light), *Sucy-en-Brie* ($2\frac{1}{2}$ M.), and *Boissy St. Léger* ($2\frac{1}{2}$ M.). These localities are reached from the stations of *La Varenne-Chennevières* ($\frac{3}{4}$ M.), beyond which we cross the Marne, *Sucy-Bonneuil* ($\frac{3}{4}$ M.), and *Boissy-St. Léger* ($\frac{1}{3}$ M.). From Sucy-Bonneuil a branch of the Grande-Ceinture leads to Valenton ($2\frac{1}{2}$ M.) and Villeneuve-St. Georges (2 M.). At Boissy-St. Léger, to the left of the railway, is the *Château du Piple*, with a Protestant Normal School for Girls. About $1\frac{1}{4}$ M. beyond the village is the fine *Château de Gros-Bois* (18th cent.), with a large park. Adjacent is an Inn. Less than 2 M. to the W. is the *Château de la Grange*, dating from the same period. We can descend from here to (3 M.) Brunoy (p. 327) or to Villeneuve-St. Georges (p. 327). — The following stations are of no interest.

19 M. ($22\frac{1}{2}$ M. from Paris) *Brie-Comte-Robert* (*Hôtel des Voyageurs*) is a very old and decayed little town. The Rue de la Gare, the Rue de Paris (to the left), and the Rue Gambetta (to the right) lead to the Place du Marché, whence we ascend to the left to the Church, a handsome building of the 12-16th cent., with fine but much damaged decorations. The interior is worth a visit. In the adjoining Rue des Halles is an interesting Gothic *Façade* of the 13th cent., belonging to an old hospital. Farther on are the ruins of a château of the 12th century.

THE CITÉ.

The *Cité* (Pl. R, 20, 23, 22; V), as already observed (p. xiv), is the most ancient part of Paris. Here lay, in the time of Cæsar, the Gallic town of *Lutetia Parisiorum*; and the Paris of the Romans and the Franks was confined to the same site, with the addition of a small settlement on the left bank of the Seine surrounded by forests and marshes. Under the Frankish monarchs the Church established her headquarters here. At a later period the town gradually extended on the right bank, where by the end of the 13th cent. there were 194 streets, while the two older quarters contained 116 only. The *Cité*, however, still retained its prestige as the seat of the old *Royal Palace* and of the cathedral of *Notre-Dame*. Almost every street at this time contained its church or chapel, regarded in some cases with peculiar veneration on account of the sanctity of an altar (as *St. Germain-le-Vieux* and *Ste. Geneviève d'Ardent*), or the possession of some wonder-working picture or image (as *St. Eloi*); while others, such as the *Sainte-Chapelle* in the royal palace (p. 218), were eminent for beauty of architecture and sumptuousness of decoration. On one side of *Notre-Dame* rose the *Episcopal Palace* and the *Hôtel-Dieu*, originally an asylum for pilgrims and the poor; on the other side was the house of the *Canons*, who play so prominent a part in the history of the university. In the *Cité* the predominant element in the population was the ecclesiastical, while the burgesses and the men of letters chiefly occupied the districts to the N. (right bank, *la Ville*) and S. (left bank, *l'Université*) respectively.

The *Cité* has long ceased to be the centre of Parisian life, but it possesses the two finest sacred edifices in Paris, the Cathedral of *Notre-Dame* and the *Sainte-Chapelle*. The *Hôtel-Dieu* still exists, but the site of the royal palace is occupied by the *Palais de Justice*.

8. Palais de Justice. Sainte-Chapelle. Notre Dame.

I. PALAIS DE JUSTICE AND SAINTE-CHAPELLE.

Tribunal de Commerce. Pont-Neuf. Préfecture de Police.

The *Cité* is approached from the right bank of the Seine by the *Pont au Change* (p. 62), and the *Boulevard du Palais*, or by the *Pont-Neuf* (p. 220).

The ***Palais de Justice** (Pl. R, 20; V) occupies the site of the ancient palace of the kings of France, which was presented by Charles VII. in 1431 to the Parlement, or supreme court of justice. In 1618 and again in 1776 the palace was so much injured by fire that nothing of it now remains except the *Tour de l'Horloge*, at the N.E. corner, near the Pont au Change, the *Tour de César* and the *Tour de Montgomery* on the N. side, the pinnacled *Tour d'Argent*, the *Sainte-Chapelle* or palace-chapel, the *Salle des Gardes*, and the *Kitchens of St. Louis*. The clock in the *Tour de l'Horloge*, adorned with two figures representing Justice and Piety, originally by Pilon, is the oldest public clock in France. It was constructed in 1370 by Henri de Vic, a German clockmaker, and was restored in 1685 and in 1852. The wanton destruction of a great part of the building on 22nd May, 1871, forms another of the numerous crimes of which the Commune was guilty. The damage has since been repaired.

The great size of this building and the fact that many of the arrangements are merely temporary render a visit somewhat perplexing to strangers. Besides the main entrances in the Boulevard de Paris and the Place Dauphine there are various side-entrances. Most of the courts are on the first floor. The *Court of First Instance*, with most of its offices, lies to the right of the *Salle des Pas-Perdus* (see below; civil courts) and to the left of the court of the Ste. Chapelle (p. 218; Police Correctionnelle). The *Cour de Cassation* is beyond the *Salle des Pas-Perdus* (see below), and the *Appeal Court* beyond the court of the Ste. Chapelle (p. 218).

The Palais is open daily, except Sundays and holidays, and visitors may, of course, enter the courts where they may have an opportunity of hearing some of the famous pleaders. The principal entrance of the Palais de Justice is by the *Cour du Mai* or *Cour d'Honneur*, adjoining the Boulevard du Palais, and separated from it by a handsome railing. The Doric pediment of the façade is adorned with statues of France and Plenty by Berruyer, and Justice and Prudence by Leconte, and covered with a quadrangular dome.

We ascend the handsome flight of 37 steps to the *Vestibule*, called the *Galerie Marchande*, which is also used by the members of the bar as a 'vestiaire'. The advocates in their black gowns are frequently seen pacing up and down the different galleries whilst the courts are sitting (from 11 to 4 o'clock). The staircase in the middle, adorned with a statue of Justice, leads to the rooms of the *Cour d'Appel*, which present no attraction.

Turning to the right, at the extreme end of the gallery, we enter the *Salle des Pas-Perdus*, serving as a vestibule to most of the *Civil Chambers* constituting the *Court of First Instance*. This hall (restored since 1871), one of the largest of the kind in existence, is 240 ft. long, 90 ft. in width, and 33 ft. in height. It consists of two vaulted galleries, separated by arcades with Doric pillars. Many historical reminiscences attach to this part of the building. Before the fire of 1618, this was the great hall of the palace, where the clergy of the '*basoche*' (a corruption of *basilica*, or royal palace) were privileged to perform moral plays and farces. On the right side is a monument

erected by Louis XVIII. in 1821 to the minister *Malesherbes*, who was beheaded in 1794, the defender of Louis XVI. before the revolutionary tribunal; the statue is by *J. Dumont*, the figures emblematic of France and Fidelity are by *Bosio*, and the basrelief by *Cortot*. Nearly opposite, a similar monument was erected in 1879 to *Berryer* (d. 1868), a celebrated advocate, with a statue by *Chapu*, between figures of Eloquence and Fidelity.

To the right of the neighbouring gallery are several halls of the *Cour de Cassation*. The first of these is the *Chambre Criminelle*, with a richly-carved ceiling. Adjoining it is the new *Galerie St. Louis*, adorned with a statue of St. Louis and frescoes by *Merson*. The second hall is the *Chambre des Requêtes*, also with a fine ceiling; the third, the *Salle d'Audience*, not yet completed, is to be adorned with a painting of Christ, by *Henner*, and others by *Baudry*.

At the end of the gallery is the *Vestibule de Harlay*, on the side next to the Place Dauphine, the façade of which is seen on the way to the Pont-Neuf. This hall is embellished with statues of four monarchs who were eminent as legislators: St. Louis and Philip Augustus on the N., and Charlemagne and Napoleon I. on the S. side. The staircase in the middle, with a figure of Justice by *Perraud*, leads to the left to the *Cour d'Assises*, and to the right to the *Chambre des Appels de la Police Correctionnelle*.

To the S. of the Cour d'Honneur is the *Cour de la Sainte-Chapelle*, where, on the left, is the entrance to the four *Chambres de Police Correctionnelle*, Nos. 8 and 9 on the first floor, Nos. 10 and 11 on the second. We may also reach this point from other parts of the Palais without descending into the Cour d'Honneur, by means of the corridor at the back of the first vestibule opposite the *Salle des Pas-Perdus*, and the following corridors. That to the right (temporary only) brings us to the new chambers of the *Cour d'Appel*, in the new wing to the W. of the court of the Ste. Chapelle, which also has a staircase to this court.

The **Sainte-Chapelle** is open to the public, 11-4 or 5 daily, except Mon. (fee). It is seen to advantage only in bright weather. This was the ancient palace-chapel, erected in 1245-48 during the reign of St. Louis by *Pierre de Montereau* for the reception of the sacred relics, now at Notre-Dame (p. 221), which St. Louis is said to have purchased from Jean de Brienne, King of Jerusalem, and his son-in-law Baldwin, Emperor of Constantinople, for 3 million francs. The chapel (115 ft. long, 36 ft. wide), which has been restored recently, is a perfect gem of Gothic architecture, but unfortunately is partly concealed by other portions of the Palais. In 1871 it narrowly escaped destruction, as it was almost entirely surrounded by a blazing pile of buildings. The only service now performed here is the 'Mass of the Holy Ghost', celebrated annually on the re-opening of the courts after the autumn vacation. The interior consists of two chapels, one above the other.

The **LOWER CHAPEL**, consisting of nave and aisles, was used by the domestics of the palace. It contains the tombs of numerous canons of the Ste. Chapelle. A spiral staircase ascends to the —

UPPER CHAPEL, in which the court attended divine service. The proportions of this chapel, which is 66 ft. in height, are remarkably light and elegant. Nearly the whole of the wall-surface is occupied by 15 large windows (49 ft. by 13 ft.), with magnificent stained glass framed in beautiful tracery. The stained glass, part of which dates from the time of St. Louis, has been recently restored. The subjects are from the Bible and the lives of saints. The glass in the rose-window, dating from the 15th cent., represents subjects from the Apocalypse.

The polychrome decoration of the walls harmonises well with the coloured windows. Against the pillars are placed statues of the twelve Apostles. Behind the handsome altar is the Gothic canopy, in wood, where the sacred relics were formerly preserved. One of the two small spiral staircases here, in gilded wood, was executed in the 13th cent.; the other is modern. We quit the chapel by the portal of the upper church, and turn to the right into the first vestibule of the Palais.

Quitting the Palais by the principal entrance, we observe to the left of the flight of steps one of the entrances to the **Conciergerie** (Pl. R, 20; V), a prison famous in the annals of France, which occupies the lower part of the Palais de Justice adjoining the Seine. (Open on Thursdays. Visitors enter from the quay. Permission must be obtained from the Préfet de Police, at the Préfecture, Rue de Lutèce, opposite the Palais, between 10.30 a.m. and 3 p.m.) Most of the political prisoners of the first Revolution were confined here before their execution. Profound interest attaches to the small chamber or cell in which Marie Antoinette was imprisoned, now converted into a chapel. Adjoining this chamber, and now connected with it by an archway, is the cell in which Robespierre was afterwards confined. Beyond these is the Hall of the Girondists, now a prison-chapel. — The so-called *Cuisines de St. Louis* are also situated in this part of the building. (Permission, see above.)

Opposite the Palais de Justice, on the E. side of the Boul. du Palais, rises the **Tribunal de Commerce** (Pl. R, 20; V), built by *Bailly* in the Renaissance style in 1860-66. Being placed across the line of the Boulevard de Sébastopol, it is visible from the Gare de l'Est. The interior, which is open to the public on week-days, deserves a visit. At the top of the staircase which ascends to the courts are some sculptures by Dubut. On the first landing are statues of Industrial Art by Pascal, Mechanical Art by Maindron, Commerce by Land by Cabet, and Maritime Commerce by Chapu; and above are Caryatides by Dubut. From this point we reach a long corridor, into which the court-rooms open. Enclosed within the building is a quadrangle surrounded by two colonnades, one above the other, above which are Caryatides by Carrier-Belleuse supporting the iron framework of the glass-covered roof. The *Salle d'Audience* on the first floor, to the left of the staircase, wainscoted with oak, is adorned with panels in imitation of porcelain paint-

ing, and with pictures by Fleury. Hearings daily, except Sun. and holidays, at 3 p.m.

The chief *Flower Market* in Paris is held on Wed. and Sat. behind the Tribunal. On Sun. there is a *Bird Market*.

Leaving the Tribunal de Commerce, we cross the boulevard to the Tour de l'Horloge, and skirt the Quai de l'Horloge, on the left side of which are entrances to the Conciergerie (p. 219), and the Cour de Cassation (p. 218).

The *W. Façade of the Palais de Justice*, towards the Place Dauphine, was constructed by Duc. The gravity of the style accords well with the purpose of the building. Eight fluted Doric columns and two corner-pillars support the rich entablature. The six allegorical figures below the windows represent Prudence and Truth, by Dumont; Punishment and Protection, by Jouffroy; Strength and Justice, by Jaley. A flight of steps ascends to the entrance of the Vestibule de Harlay (p. 218).

The **Pont-Neuf* (Pl. R, 20; V), farther on, at the W. end of the island, a bridge 360 yds. in length and 25 yds. in width, crossing both arms of the Seine, was constructed in 1578-1604, but was remodelled in 1852. The end next the left bank was restored in 1886. The masks supporting the cornice on the outside are copies of those originally executed by G. Pilon. On the island, halfway across the bridge, rises an *Equestrian Statue of Henri IV.*, by Lemot, erected in 1818 to replace one which had stood here from 1635 to 1792, when it was melted down and converted into cannon. By way of retaliation Louis XVIII. caused the statue of Napoleon on the Vendôme Column and that of Desaix in the Place des Victoires to be melted down in order to provide material for the new statue. The Latin inscription at the back is a copy of that on the original monument. At the sides are two reliefs in bronze, which represent Henri IV. distributing bread among the besieged Parisians, and causing peace to be proclaimed by the Archbishop of Paris at Notre-Dame.

In the 16th cent. the Pont-Neuf was the scene of the recitals of Tabarin, a famous satirist of the day, and it was long afterwards the favourite rendezvous of news-vendors, jugglers, showmen, loungers, and thieves. Any popular witticism in verse was long known as 'un Pont-Neuf'.

The bridge commands an admirable **View of the Louvre*. The large edifice on the left bank is the Monnaie (p. 245), and beyond it is the Institut (p. 244).

In returning to the Boul. du Palais by the Quai des Orfèvres, on the side of the Cité next to the left bank, we pass the S.W. portion of the Palais de Justice, originally intended for the 'préfecture de police'. The houses on this side are to be removed, so as to leave the Palais free.

The new *Préfecture de Police* (Pl. R, 19, 20; V; office-hours 9-4) occupies the old municipal barracks and two 'hôtels d'état major' in the Boul. du Palais, opposite the Palais de Justice, and

adjoining the Pont St. Michel (p. 225). From this point radiate all the threads which constitute the partly visible and partly invisible network of police authority which extends over the whole city, at a cost to the municipality of about 22 million fr. per annum. There are three main departments, those of the central administration, and of the commissariats of police and city police. The Prefect has his private offices, besides which there is the General Secretariat, with three subdivisions. The first of these is for the personnel, materials, archives, accounts, and treasury, the other two for the Parisian police and the market-police respectively. The municipal police force numbers about 10,250 men, including 1100 'gardiens de la paix', inspectors, etc. Besides these there are 6000 'gardes républicains' and 1750 'sapeurs-pompiers', or firemen.

II. NOTRE-DAME.

Hôtel-Dieu. Morgue. Ile St. Louis.

On the way from the Boul. du Palais to Notre-Dame we cross the Place du Parvis Notre-Dame, on the N. side of which is the Hôtel-Dieu (p. 224).

The *Cathedral of Notre-Dame (Pl. R, 22, V; admission, see below), founded in 1163 on the site of a church of the 4th cent., was consecrated in 1182, but the nave was not completed till the 13th century. The building has since been frequently altered, and has been judiciously restored since 1845; but the general effect is hardly commensurate with the renown of the edifice. This is owing partly to structural defects, partly to the lowness of its situation, and partly to the absence of spires. It is moreover now surrounded by lofty buildings which farther dwarf its dimensions; and, lastly, the surrounding soil has gradually been raised to the level of the pavement of the interior, whereas in 1748 the church was approached by a flight of thirteen steps.

During the Revolution the cathedral was sadly desecrated. A decree was passed in August, 1793, devoting the venerable pile to destruction, but this was afterwards rescinded, and the sculptures only were demolished. On 10th Nov. in the same year, the church was converted into a 'Temple of Reason', and the statue of the Virgin replaced by one of Liberty, while the patriotic hymns of the National Guard were heard instead of the usual sacred music. On a mound thrown up in the choir burned the 'torch of truth', over which rose a 'temple of philosophy', in the Greek style, adorned with busts of Voltaire, Rousseau, and others. The temple contained the enthroned figure of Reason (represented by Maillard, the ballet-dancer), who received in state the worship of her votaries. Damsels clothed in white, with torches in their hands, surrounded the temple, while the side-chapels were devoted to orgies of various kinds. After 12th May, 1794, the church was closed, but in 1802 it was at length re-opened by Napoleon as a place of divine worship.

In 1871 Notre-Dame was again desecrated by the Communists. The treasury was rifled, and the building used as a military dépôt. When the insurgents were at last compelled to retreat before the victorious troops, they set fire to the church, but fortunately little damage was done.

The *FACADE, the finest part of the cathedral, dating from the beginning of the 13th century, and the earliest of its kind, has

served as a model for the façades of many other churches in the N.E. of France. It is divided into three vertical sections by plain buttresses, and consists of three stories, exclusive of the towers. The three large recessed portals are adorned with sculptures, which, so far as they have survived the ravages of the Revolution, are fine specimens of early-Gothic workmanship. Those on the central portal represent the Last Judgment; the noble figure of Christ on the pillar in the middle is modern. The portal on the right (S.) is dedicated to St. Anne, and that on the left (N.), by which the church is generally entered, to the Virgin, both being adorned with sculptures relating to these saints. The relief representing the burial of the Virgin is noteworthy. This story is connected with the one above it by the *Galerie des Rois*, a series of niches containing modern statues of twenty-eight French kings replacing those destroyed during the Revolution. Above the gallery, in the centre, rises a statue of the Virgin, with two angels bearing torches, to the right and left of which are figures of Adam and Eve. — The centre of the second story is occupied by a large rose-window, 42 ft. in diameter, with the simple tracery of the early-Gothic style. At the sides are double pointed windows. — The third story is a gallery composed of pointed arches in pairs, about 26 ft. in height, borne by very slender columns, each double arch being crowned with an open trefoil. Above this gallery runs a balustrade, surmounted with figures of monsters and animals; and the façade then terminates in two uncompleted square towers, each pierced with a pair of pointed windows, about 54 ft. in height. The lateral portals and the exterior of the bold and elegant choir also deserve inspection. The S. door of the transept is embellished with fine iron-work, restored by Boulanger. The spire above the cross, 147 ft. in height, and constructed of wood covered with lead, was erected in 1859.

The INTERIOR is open to visitors the whole day, and the choir from 10 to 4; tickets admitting to the sacristy, treasury, and chapter-house (50 c.) are procurable on week-days from the vergier at the entrance to the choir in the right aisle. On Sundays and festivals the choir is closed after divine service.

The church, which consists of a nave and double aisles, crossed by a single transept, is 139 yds. long and 52 yds. broad. The double aisles are continued round the choir, affording the earliest example of this construction. The choir is circular in form, as in most early-Gothic churches. The chapels introduced into the spaces between the buttresses of the aisles and choir are in a late-Gothic style. The vaulting, 110 ft. high in the nave, is borne by 75 pillars, many of which, unlike those in other Gothic buildings, are round. Above the inner aisles runs a triforium borne by 108 small columns, and the clerestory is pierced with 37 large windows. The ancient stained glass of the roses over the principal and lateral portals is worthy of inspection. To the right of the S.

portal are two marble slabs in memory of 75 victims of the Commune (p. 176). The *Organ*, built in 1750, and restored and enlarged by Cavaillé-Coll in 1868, is a fine instrument, with 5246 pipes and 86 stops. The pulpit, designed by *Viollet-le-Duc*, and executed by *Mirgen*, is a master-piece of modern wood-carving.

The *Choir* and *Sanctuary* are separated from the ambulatory and from the nave by very handsome railings. The choir-stalls and the reliefs in wood, chiefly representing scenes from the history of Christ and the Virgin, should be noticed. Behind the new high-altar, completed in 1874, is a *Pietà* in marble by *N. Coustou* (p. 109). In the sanctuary, to the right and left, are statues of Louis XIII. and Louis XIV., also by *Coustou*.

The choir-chapels contain a number of monuments, chiefly of former archbishops of Paris. Beginning at the sacristy: *Archb. Affre* (d. 1849), by *Debay*; *Archb. Sibour* (d. 1857), by *Dubois*; *Comte d'Harcourt* (d. 1718), representing a dead man rising from the tomb, by *Pigalle*; *Archb. Darboy* (d. 1871), by *Bonnassieux*; his predecessor *Cardinal Morlot* (d. 1863); *Bishop Matiffas de Bucy* (d. 1304), behind the high-altar; *Cardinal de Belloy* (d. 1806), a group in marble by *Deseine*, representing the prelate at the age of ninety-nine giving alms; *Archbishop de Quelen* (d. 1839), by *G. Dechaume*; *Cardinal de Noailles* (d. 1729), by the same, in a chapel adorned with frescoes by *Maillot*; *Archb. Juigné* (d. 1811), by *Cartellier*; *Archb. de Beaumont* (d. 1781); monument of *Marshal Guébriant* (d. 1643), and his wife *Renée du Bec-Crépin*. — The wall outside the enclosure of the choir is adorned with twenty-three interesting reliefs in stone, representing scenes from the life of Christ, by *Jehan Ravy* and his nephew *Jehan de Bou-teillier*, completed in 1351, and once richly gilded.

At the beginning of the retro-choir, on the right (S.) side, is the entrance to the *New Sacristy* (*Sacristie du Chapitre*), erected in 1846-48 by *Viollet-le-Duc* in the same style as the cathedral. In this and in the adjoining Chapter House (adm. 10-4, 50 c.) is the —

TREASURY, most of the objects in which are modern and of little artistic value. The ancient objects include a large Greek cross, enamelled (12th or 13th cent.), silver busts of SS. Denis and Louis, and various chalices, reliquaries, and vestments of the 13-16th centuries. Among the objects of historical interest are the coronation robes of Napoleon I. and the blood-stained clothes and other mementoes of the archbishops *Affre* (p. 66), *Sibour* (p. 240), and *Darboy* (p. 176).

TOWERS. The *View from the towers of Notre-Dame (223 ft. in height), one of the finest in the city, embraces the course of the Seine with its numerous bridges and the principal public edifices in the environs. The entrance to the towers is outside the church, by the N. tower, to the left of the portals. The ascent may be made in summer from 9 to 5, on payment of 20 c. (including the bells 40 c.). The platform on the summit is reached by 378 steps. In the S. tower hangs the great *Bourdon de Notre-Dame*, one of the largest bells in existence, weighing 16 tons; the clapper alone weighs nearly half-a-ton. Another bell here was brought as a trophy from Sebastopol.

The PLACE DU PARVIS NOTRE-DAME (Pl. R, 22; V) in front of the Cathedral, on the S. side of which the Hôtel-Dieu was formerly situated, is embellished with an *Equestrian Statue of Charlemagne* in bronze, by *Rochet*, on a pedestal designed by *Viollet-le-Duc*. From the bridge to the S. a new section of the Rue Monge now penetrates to the Place Maubert (p. 241).

On the N. side of the Place du Parvis Notre-Dame rises the new **Hôtel-Dieu**, a large hospital with 559 beds, admirably fitted up, at a cost of 45 million fr., of which nearly one-half was paid for the site. This enormous sum might probably have been better expended elsewhere, as the lowness of the site and the proximity of the two arms of the river seem objectionable. The original Hôtel-Dieu was the oldest hospital at Paris and probably in Europe, having been founded in 660, under Clovis II.

At the back of the Cathedral is another 'place', occupying the site of the old archiepiscopal palace, in the centre of which rises the tasteful *Fontaine Notre-Dame*, designed by *Vigoureux*, and erected in 1845. The water is poured from the mouths of dragons subdued by angels into a double basin; and above them rises a Gothic canopy borne by columns, and containing a statue of the Virgin and Child.

At the S.E. end of the Ile de la Cité, not far from the fountain just described, stands the **Morgue** (open daily), a small building re-erected in 1864, where the bodies of unknown persons who have perished in the river or otherwise are exposed to view. They are placed on marble slabs, kept cool by a constant flow of water, and are exhibited in the clothes in which they were found. The process of refrigeration to which the bodies are exposed makes it possible to keep them here, if necessary, for three months. The bodies brought here number about 800 annually, one-seventh being those of women. The painful scene attracts many spectators, chiefly of the lower orders.

The Ile St. Louis (Pl. R, 22; V), an island above that of the Cité, with which it is connected by means of the Pont St. Louis, a few paces to the N. of the Morgue, is a dull and retired spot, though close to the busiest parts of Paris. It contains, however, several mediæval buildings of some interest. The most important of these is the handsome HÔTEL LAMBERT, Rue St. Louis 2, near the upper (S.E.) end of the island. It was built in the 17th cent. for Lambert de Thorigny, and decorated with paintings by *Lebrun* and *Lesueur*. The ceiling-painting of the 'Galerie de Lebrun' represents the marriage of Hercules and Hebe. Voltaire once visited Mme. de Châtet here. The mansion now belongs to Prince Czartoryski, who admits visitors. — The adjacent Boul. Henri IV. crosses to the right bank by one half of the *Pont-Sully*, and to the Halle-aux-Vins (p. 267) on the left bank by the other half.

LEFT BANK OF THE SEINE.

The semicircular part of Paris which lies on the left bank of the Seine forms fully one-third of the whole city, its distinctive feature consisting of numerous learned institutions, the chief of which is the *Sorbonne*, or university, in the *Quartier Latin*. The adjoining *Faubourg St. Germain* is the aristocratic quarter, where ministers, ambassadors, and many of the nobility reside; and at the W. end of this part of the town are several large military establishments. The chief objects of interest on the left bank are the *Palais du Luxembourg* with its gallery of modern works of art, the *Panthéon*, the *Musée de Cluny* and *École des Beaux-Arts*, the *Jardin des Plantes*, and the *Hôtel des Invalides*.

9. From the Cité to the Panthéon and the Parc Montsouris.

I. FROM THE CITÉ TO THE MUSÉE DE CLUNY.

Fontaine St. Michel. St. Séverin. Ecole de Médecine.

Approaching the left bank from the Cité by the Boul. du Palais de Justice (p. 216), we cross the narrower arm of the Seine by the *Pont St. Michel* (Pl. R, 19; V), a handsome bridge, rebuilt in 1857, which commands a fine view of Notre-Dame. At the S. end of the bridge we reach the **Boulevard St. Michel**, the principal artery of traffic on the left bank, forming a continuation of the Boul. de Strasbourg and Boul. de Sébastopol on the right bank, and the Boul. du Palais on the island of the Cité.

On the right, with its back to the corner of the boulevard, we observe the *Fontaine St. Michel*, a fountain 84 ft. high and 48 ft. in width, erected in 1860 in the *Place* called after it. The monument, which stands too low to be effective, consists of a niche in the form of a Roman triumphal arch, containing a group of St. Michael and the dragon in bronze, by *Duret*, placed on an artificial rock, from which the water falls into three basins flanked with griffins. At the sides of the niche are columns of red marble bearing bronze figures of Truth, Wisdom, Power, and Justice.

The first street to the left beyond the fountain penetrates an old-fashioned part of Paris, which is doomed to demolition, and leads to the church of **St. Séverin** (Pl. R, 19; V), one of the oldest

in Paris, dating from the 6th cent., if not earlier, but rebuilt in the 11th, in the 13th, and at the close of the 15th century. It consists of a nave and aisles flanked with chapels. The façade is now composed of a portal of the 13th cent., brought from a church in the Cité which was taken down in 1837, with a handsome tower of the 15th cent. rising above it.

THE INTERIOR is also worthy of inspection. Among the points of interest are the mouldings of the vaulting, the triforium, the stained glass of the 15th and 16th cent., and the modern mural paintings in the chapels. Right: 1st chapel, Scenes from the life of John the Baptist, by *Paul Flandrin*; 2nd and 3rd, Scenes from the lives of St. Anna and the Virgin, by *Heim* and *Signol*; 4th and 5th, Subjects relating to SS. Andrew and Peter, by *Schmetz* and *Biennoury*; 6th, Christ and the holy women, by *Murat*; 7th, St. John the Evangelist, by *Hip. Flandrin*, his first mural painting; 8th, Ste. Geneviève, by *A. Hesse*; 9th, the two SS. Séverin, one healing Clovis, the other ordaining St. Cloud as a monk, by *Cornu*. The 10th chapel and that in the apse, dedicated to Notre Dame de l'Espérance and des Sept Douleurs, contain sculptures and votive offerings. Chapels on the opposite side, as we return towards the entrance: Archh. de Belzunce and St. Jerome, by *Gérôme*; St. Louis, by *Lenoir*; St. Charles Borromée, by *Jobbé-Duval*; St. François de Sales, by *Mottez*; and St. Vincent de Paul, by *Richomme*.

A little farther on near the Rue Monge (p. 241) is the little old church of St. Julien-le-Pauvre (Pl. R, 19-22; V), the chapel of the former Hôtel Dieu. It is an unassuming edifice in the Gothic style of the 12th cent., without portal or tower, but the choir and side-apses are interesting. It is now occupied as a Greek church and is open only 8-10 a.m. The entrance is No. 11 in the same street.

Returning to the Boul. St. Michel, we next reach the *Square de Cluny*, the *Thermes*, and the *Hôtel de Cluny* (see below). We here cross the *Boulevard St. Germain*, another important artery of traffic, which leads from the Pont de la Concorde to the Pont Sully, a distance of 2½ M.

Following the Boul. St. Germain for a few paces to the right, we soon reach on the left the **Ecole de Médecine** (Pl. R, 19; V), a building of the 18th cent., with a modern façade towards the boulevard. The handsome court is flanked with an Ionic colonnade, and the building itself has a Corinthian portico, opposite which rises a bronze statue of *Bichat*, the anatomist (d. 1802), by David d'Angers, erected in 1857. The amphitheatre has seats for 1400 persons. The Library (90,000 vols.) is open to students and medical men daily, except on Sundays, holidays, and in vacation (Sept. and Oct.), 11-4 and 7.30-10 o'clock. The Ecole also possesses a *Museum of Comparative Anatomy*, or *Musée Orfila*, so named after its celebrated founder (d. 1853); it is open on the same conditions as the library. To the medical faculty also belongs the *Musée Dupuytren*, a valuable pathological-anatomical collection, established in the refectory of an old Franciscan monastery. A bronze statue of *Danton* (1759-1794), as 'organiser of the national defence', has been erected on the open space to the W. of the Ecole de Médecine.

The **Hôtel de Cluny** (Pl. R, 19; V), which is entered from the Rue du Sommerard (No. 14), occupies part of the site of a Roman palace supposed to have been founded by the Emperor Constantius

Chlorus, who resided in Gaul from 292 to 306. Julian was proclaimed emperor by his soldiers here in 360; and this was the residence of the early Frankish monarchs until they transferred their seat to the Cité (p. 246). The only relics of the palace still existing are the ruins of the *Thermes*, or baths once connected with it (p. 234).

In 1340 the ruins came into the possession of the wealthy Benedictine Abbey of Cluny (near Mâcon, in S. Burgundy), and at the end of the 15th and beginning of the 16th cent. the abbots caused a small mansion, the present *Hôtel de Cluny*, to be erected on the site of the ancient palace. This edifice still retains its mediæval exterior almost intact, and is a remarkably fine specimen of the late-Gothic style with several Renaissance features. The abbots, who seldom visited Paris, placed their mansion at the disposal of the kings of France.

The Revolution converted this estate into national property, and in 1833 the Hôtel de Cluny came into the possession of *M. Alex. du Sommerard*, a learned and indefatigable antiquarian. On his death in 1842 the edifice with its valuable collections was purchased by government, and united with the Thermes, which had hitherto belonged to the municipality of Paris. The collection has since been largely extended.

We enter the court of the 'hôtel' by a large gate or by a postern under a depressed arch, leading through a pinnacled wall, and framed with tasteful sculptures. The principal building and the wings have handsome mullioned windows, a picturesque open balustrade, and dormers with admirably-carved pediments. The tower in front is embellished with sculpturing, and the left wing with four large pointed arches. — The entrance to the garden is in the right wing, and a few paces to the left of it is that of the museum.

ADMISSION. The Musée de Cluny et des Thermes is open to the public every day except Mon. and certain holidays, from 11 to 5 in summer (April 1st-Oct. 1st), and from 11 to 4 in winter. Vestiaire 10 c. Catalogue in paper covers 4 fr., in boards 5 fr. Explanatory labels everywhere.


The ***Musée de Cluny** comprises a most valuable collection of mediæval objects of art and products of industry. As there are upwards of 11,000 objects, a single visit will hardly afford an idea of even the most important.

GROUND FLOOR. I. Room (Vestibule). Carved wood, paintings, sculptures in marble and alabaster. *Finely-carved screen from Augerolles (Dep. Puy-de-Dôme), 15th century. Weights and measures, etc.

II. Room. To the right and left of the entrance, Gothic benches with canopies, beside which are shelves with busts, tasteful statuettes, and small groups of saints in wood of the 15th and 16th centuries. In the glass-cases, an extensive collection of shoes from Europe, Africa, China, Japan, India, America, etc. On the walls are farther wood-carvings. At the 2nd window to the right, a marriage-chest of the 16th century. — The stone chimney-piece is

adorned with high reliefs dating from 1562. To the right and left are Flemish chests of the 16th century.

III. Room. Entrance-wall: *709. Large carved altarpiece in gilded and painted wood, of the end of the 15th cent.; *712. Flemish altarpiece (16th cent.); 816, 788. Holy Women and Mater Dolorosa (16th cent.). In the centre: 1422. German Gothic candelabrum, of the end of the 15th century. By the windows on both sides: medals. On the other wall: no number, *Altarpiece, larger than and as fine as that opposite; 715. Calvary, triptych in carved wood (16th cent.); *710. German triptych in carved wood, painted and gilt, of the end of the 15th cent., upon a French credence of the 15-16th centuries.



IV. Room. Furniture of the 16th and 17th centuries. The chimney-piece, with a basrelief representing Actæon changed into a stag, dates from the 16th century. Collection of tokens and counters.

V. Room. Collection Audeoud, presented to the museum in 1885. This consists of Italian and Spanish works of art of the 17th and 18th cent., amongst which we first notice an *Adoration of the Magi, composed of about 50 statuettes in rich costumes, with expressive faces and well arranged (Neapolitan, 17th cent.). In the corner to the right is a similar but smaller work, also noteworthy. Then a large glass case containing painted *Statuettes and groups of the Massacre of the Innocents and the Last Supper, etc. At the back, richly sculptured and gilt *Tabernacle, from the top of an altar, with a statue of St. Anthony of Padua holding the Infant Christ, a Spanish work of the 17th century. Fine carved, inlaid, and painted furniture. Richly framed mirrors, one with a Madonna and angels'

heads in the centre. Small carvings; portions of a Spanish bed; leathern hangings, etc.

Corridor. Italian paintings (14-16th cent.); fittings of a Spanish altar (15th cent.); fine painted altarpiece.

VI. Room, lighted from the roof, with doors to the garden (p. 234) and to the Thermes (p. 234), and, like the following room, surrounded with a gallery, which is accessible from the first floor only. *Sculptures*, especially religious statues, basreliefs, and ornaments. To the right: monuments of the Grand Masters of the order of St. John of Rhodes. By the walls, several *Altars from the abbey of St. Denis (14th cent.); *Altar-relief from the chapel of St. Germer near Beauvais, by Peter Wuessencourt (1259), injured in 1794; statues and alabaster-reliefs of the 14th cent., etc. On the furniture, interesting groups and statuettes, including a Coronation of the Virgin (15th cent.), five *Statuettes of mourners from the tomb of Philippe le Hardi, by *Cloux Sluter*, at Dijon (end of 14th cent.), and a marble Presentation in the Temple (14th cent.). At the side next the staircase is a large altar-screen in terracotta (15th cent.). In the middle, Angel of the Annunciation, an Italian work of the 14th cent.; several statues of the Virgin, St. John and an Apostle (14-15th cent.); Virgin at Calvary (16th cent.), etc.

VII. Room. On the walls are three admirable pieces of *Flemish tapestry, of the beginning of the 16th cent., belonging to a series of ten pieces, representing the history of David and Bathsheba. In the glass-cases, ecclesiastical vestments and ornaments, lace, antique stuffs, girdles, head-dresses, etc. Around are interesting sculptures: 283 (at the entrance), Prophet; 284. Grammar; no number, *Virgin; 282. Astronomy; 298. Saint; *460. Flora, a caryatid (all these of the 16th cent.); *448. Marble group of the Fates, attributed to *G. Pilon*, with a basrelief of his school on the pedestal; *251. Madonna and Child; 461. Salutation, 463. Queen of Sheba, 462. Judgment of Solomon, three basreliefs of the 16th century. — 479. Entombment, an Italian work of the 17th cent.; 457. Christ appearing to Mary Magdalen, Flemish basrelief of the 16th cent.; 456. Sleep, and 449. Ariadne deserted, both dating from the 16th cent.; 277. Virgin (end of 15th cent.); no number, Genius from a tomb, by *G. Pilon* or *Ponce Jacquo* (16th cent.); 279. Virgin (16th cent.).

VIII. Room. Continuation of the tapestry, ecclesiastical vestments, lace, etc.; *Hangings, mantles and collars of the Order of the Holy Ghost, founded by Henri III. in 1579. In the centre, *Lantern of a Venetian galley (16th cent.); two handsome monolithic columns (16th cent.) supporting two statues (15th cent.); before these, fragments from the Tuileries. On the right and left of the room: Statues of the 16th and 17th cent., basreliefs of the 16th cent., including one from the Château d'Anet (p. 237), and, to the left, portion of a chimney-piece by *C. de Vriendt*.

IX. Room. Sumptuous carriages of the 17th and 18th cent., sledges, rich trappings, Sedan chairs, etc. In particular, *Four carriages, the first (6951), of Italian workmanship, said to have belonged to Pope Paul V.; the second (6952), of French workmanship; the others also Italian.

First Floor. We return to the corridor between Rooms VI. and VII. and ascend a wooden staircase with the arms of Henri IV., formerly in the Palais de Justice.

In the Corridor are weapons and suits of armour.

1st Room, to the left. *French, Flemish, and Dutch Faïence, Earthenware*, etc., of the 16-18th centuries. 1st Glass-case, to the left: French faïence from Lille, Sinceny, etc.; reticulated vase from Münden. 2nd Case. Earthenware from Germany and Limbourg. 3rd Case: Palissy and Oiron faïence (16th cent.). 4th Case: Specimens from Sceaux, Paris, Niedervillers, Strassburg, Marseilles, Alcora (Spain), and Moustiers. 5th Case: *Rouen. 6th Case: Nevers. 7th Case: Dutch faïence (Delft). 8th Case: Various; 3962. German guild 'master-piece'. Tiles etc.

2nd Room, opposite. Magnificent collection of **Italian Faïence* of the 15-18th cent., contained in 8 glass-cases, and classed according to schools. From right to left, Case I. Faenza; II. Chaffagiolo and Deruta, etc.; III. Deruta; IV. Gubbio, Castel-Durante; V.-VII. Urbino; VIII. Venice, Castello, and Castelli. — Above Case VI. and before the next case are bas-reliefs in painted terracotta by *Luca della Robbia* and his school (15th cent.).

3rd Room (to the right of R. 2). **Tapestry* of the 15th cent., with scenes from Scripture history, legend, and the chivalric epic. Fine carved chimney-piece and ceiling from a house in Rouen (16th cent.). Works in *Glass* and **Enamel*.

Case 1, near the windows: *Ecclesiastical work in gold, reliquaries, book-covers, crosses, etc. (12-13th cent.). — Case 2: *Painted enamels (15th cent.); *4578. Calvary, by *Nardon Pénicaut* (1503). — Case 3: *Limoges enamels (16-17th cent.); *4617-4629. Large oval medallions representing scenes from the Passion, by *Léonard Limouzin*; 4630. Judas's kiss; *4579. Eleanor of Austria, wife of Francis I., and portraits (unnumbered) of the Duke and Duchess of Guise, also by *Léonard Limouzin*; 4698. Mary Magdalene, by *Jean Laudin*; 4591-96. Cups and coffer, by *Pierre Reymond*; 4597-4600. Cups, by *Jean Courteys*. — Case 4: *4589. Mourning-cabinet belonging to Catherine de Médicis, and upwards of thirty smaller enamels, by *Pénicaut, Courteys, Limouzin, Couly, Noytier, Suzanne Court*, etc. — Case 5: 4639-54. Sixteen scenes from the life of the Virgin and the Passion, by *P. Reymond*. Among the other enamels may be noticed Nos. 4706, 4708, 4606, 4610, 4611, 4612. — In the two cases in the second row: Venetian glass. Then a collection of wood-carvings from articles of furniture. At the back two other cases with glass; in the case to the right, Venetian glass: 4779-4782. Basin and plates (16th cent), with paintings of Psyche bringing to Juno the vase of Proserpine, Delilah and Sampson, Juno and Isis, Birth of Bacchus. In the case to the left: German and Dutch glass, etc. Between the cases, statue of Pandora on a pedestal on which are represented the siege and capture of Troy. On the wall, nine large plaques of enamel on copper, representing divinities and allegorical subjects, by *Pierre Courteys*, brought from the old Château de Madrid in the Bois de Boulogne (p. 159). These are the largest enamels known (5 ft. 6 in. × 3 ft. 4 in.).

4th Room. **Hispano-Moorish Faïence* with metallic glazing (14-17th cent.) and **Rhodian Faïence* of the same period, made by Persian workmen.

5th Room. In the centre, Altar-shutters of the Flemish school (1632), representing the donor with his patron saints and an emperor presenting the deed of gift; to the left of the chimney-piece (15th cent.), 1670. Mary Magdalene in Marseilles, by *King René* of Provence; in the corner, Visitation of the Virgin (Flemish school; 16th cent.), and other paintings, chiefly of the Italian school of the 15th century.

6th Room. Case 1: Musical instruments, psaltery, mandolins, pocket-violins used by dancing-masters, violin by Amati. Case 2 (in the middle): specimens of book-binding. Case 3: Collection of coffers. At the wall: **Venetian cabinet* of the 16th cent., representing the façade of a palace, adorned with plaques of ivory and mother-of-pearl, paintings, bronze-gilt statuettes, etc. Florentine cabinet, with costly mosaics, and three Italian writing-tables inlaid with tin (all 17th cent.). On the wall: *School of Janet*, Portrait of Charles V. Disciples on the way to Emmaus and the Doubting Thomas, painted in tempera on silk (school of Ferrara; 15th cent.), and other old paintings. Madonna and Child, mosaic by D. Ghirlandajo (15th cent.).

7th Room. Splendid Hispano-Flemish cabinet of the 17th cent., adorned with marquetry and painting; 1448. Richly ornamented Flemish cabinet, containing faïence, stone-ware, two ancient Chinese vases in cloisonné enamel, etc. The ceiling-painting was executed in the 17th century.

8th Room. State-bed of the time of Francis I. (16th cent.); to the right and left, 1431, 1432. French cabinets (16th cent.). — To the right of the chimney-piece: 1424. Cabinet from Clairvaux Abbey, time of Henri II. (16th cent.). — Opposite the windows: 1425, 1426. Cabinets (16th cent.). Central glass-case: MSS. with miniatures of the 13-16th cent., including portraits of Columbus (No. 1817) and Palissy. Above, statuettes and 743. Wooden figure of the Virgin (15th cent.). At the 1st window, knives, hunting-quivers (16th cent.) in chased and gilded iron, etc. At the 2nd window: tobacco-graters (17th cent.) in carved wood and ivory; sets of draughtsmen etc. (16th and 17th cent.); wooden combs (16th cent.), ivory snuff boxes (Nos. 1189 etc.) of the 17th cent.; fine wood-carving representing two women fighting; wooden box, nut-crackers, hilts of knives in wood (16-17th cent.).

9th Room. Works in ivory, etc. — Small glass-case in the centre, to the right: 1033, 1034. Fragments of boxes of the 6th cent.; book-covers, etc. of the 5th or 6th to the 12th century. 1035. Marriage of Emp. Otho II. and Theophano, daughter of the Greek emperor, in 973: Christ, in classic drapery, crowns the bridal pair, who are stiffly attired in Byzantine finery. 1041, 1042. Ivory

tablets with reliefs of mythological subjects on one side and Christian on the other, 10th and 11th centuries. On the other side, 1374. Carolingian chest and other chests of the 11-13th centuries. — In the large glass-case: 1052. Reliquary of St. Yved in ivory, 12th cent.; 1037. Madonna, 10th cent.; Madonnas, 14th and 17th cent.; no number, Adam and Eve, by *Francheville* (? 17th cent.); 1106. St. Catharine, 15th cent.; 5296-97. Two lions' heads of rock-crystal, 3rd or 4th cent., found in a tomb on the Rhine, together with an ivory statuette (1032) with the attributes of several deities (between the lions' heads); *1113. Virtue chastising Vice, attributed to *Giovanni da Bologna*; above it, 1153. Figure resembling the Manneken Pis at Brussels and by the same artist, *Duquesnoy* (1619). At the back: 1060. Reliquary with 51 bas-reliefs of Scriptural subjects (14th cent.); 1090. Coffin of the same style and period; 1087, 1061. Madonnas (14th cent.). — In the glass-case to the left: Wax medallions (1298. Margaret of Valois, Queen of Navarre; 1580); medals. — On the side next the entrance, 1459-63. Carved ebony furniture of the 17th cent.; to the left, 1057. Venetian coffin, 13th cent.; 1688-89. Scenes from the life of St. Ursula, by Israel van Meckenem (Cologne school, 15th cent.); 1056. Venetian coffin (13th cent.). — First window towards the garden: Distaffs and spindles with wood-carving (16th cent.); girdle of chastity. Between the windows: Furniture in carved ebony (17th cent.). By the back-wall, 1457. Large ebony cabinet and statuettes (17th cent.). In the adjoining glass-cases, statuettes, busts, medallions, ivory carvings of the 16-18th centuries. — First window towards the court: 1081. Altar-piece in the form of a triptych, adorned with bas-reliefs in ivory, 14th cent.; several other reliefs in ivory; 1177. Diptych of the 17th cent., with tablets no larger than a nutshell, containing 102 figures. 718. Spanish triptych in carved wood (16th cent.). Between the windows, on the right: 1079. Oratory of the Duchesses of Burgundy, ivory plaque of the 14th century. — Second window: in the centre, 1058. Pastoral staff, in boxwood, 13th cent.; 1062 and 1063-1066 (to the right), Scenes from the Passion and legends of martyrs (14th cent.); leaves of diptychs of the 14th and 15th cent.; to the left, 1055. Portion of a box with mirror of the 13th cent., with St. Louis and the Reine Blanche; 1082. Diptych of the 14th cent., carved and partly gilded, with eight scenes from the Passion; 1096. Diptych, and 1097. Triptych of the 15th cent.; 1074. Large diptych of the 14th cent.; 1104. Pax (15th cent.).

10th Room. Works in iron, locksmith's work, bronzes, etc. Locks of the 15-17th cent.; Reproduction of the Treasure of Hildesheim, ancient silver ware found in 1868; statuettes of saints; coffers and caskets; 5105-8. Panels in embossed and gilded copper, from a chapel (Ital., 15th cent.); lanterns; bells; girdles (6599); credence-tables; *Locks and *Keys (Case 8) of the 16th cent.; Goldsmith's

bench, German work of 1565; monstrances; astrological tables and instruments; Italian celestial globe (1502); clocks of the 16-17th cent., etc.

11th Room. *Objects in the precious metals, etc. Case to the right of the entrance next the garden: Large collection of spoons, forks, table requisites, etc., of the 16-17th cent.; purses of the same period; cases of various kinds. Next Case: *Ship in gilded and enamelled bronze, with movable figures of Charles V. (in gold) and his dignitaries, a piece of mechanism executed in the 16th century. Following Case: Watches of the 17-18th cent.; rings, some of great size (15th cent.); 5129. Mirror, 16th cent.; 5278. Portrait of Francis I. On the wall and opposite, Six Flemish tapestries, of the beginning of the 16th century.

In the central cabinet: *Nine gold crowns, found at Guerrazar near Toledo in 1858, the largest of which, inlaid with pearls, Oriental sapphires, and other jewels, is said by the inscription (probably added when the crown was converted into a votive offering) to have belonged to the Gothic king Reccesvinthus (649-72); 4980. Crown of Queen Sonnica (?). — In the glass-case on the left, next the garden: *5014. French reliquary of the 15th cent.; 5015-5017. Reliquaries of the same period, German work, the first by *Hans Greiff*, a famous Nuremberg goldsmith; 5006. Golden rose of Bâle, presented by Pope Clement V. to the Prince-Bishop of Bâle (14th cent.); 1067. Ivory crosier (14-15th cent.); 5022-5029. Reliquaries and monstrances (15th cent.). — In the glass-case on the right, next the garden: 5042. Large double cross in gilded copper, forming a reliquary, richly decorated with filigree-work and jewels, a valuable Limoges work of the 13th cent.; *5044. Processional cross, in silver, gilded, engraved, and enamelled, with statuettes at the ends representing God the Father, the Virgin, St. John, Mary Magdalene, etc., a very interesting Italian work of the 14th cent.; 5043. Archiepiscopal cross in silver-gilt filigree, lavishly enriched with jewels, pearls, and antique cut gems, and containing eight small reliquaries (Limoges, 13th cent.); 5019. Italian reliquary (15th cent.); chalices (15th cent.). — By the first window: *5299. Chess-board with men of rock-crystal, a German work of the 15th cent.; other objects in precious metal or gems, chiefly of the 15-17th cent.; 5293. (to the left), Child's head in blue chaledony, antique relief with 15th cent. setting. By the second window: Gallic torques and other objects, in massive gold, found at Rennes in 1856; 4989. Merovingian military ornament, in gold (end of a sword-belt); 4990. Merovingian scabbard, mounted in gold; 1040. Cover of a book of the Gospels, ivory with gold filigree, 10th cent.; 5041. Double cross, in silver-gilt, adorned with precious stones and reliefs (13th cent.); *5103. Prize for crossbow-shooting, in silver-gilt, embossed and chased (German, 15th cent.); 5098. Silver girdle, chased and gilded; 5076. Silver clasp, gilded and enamelled, German works of the

14th cent., etc. — End-wall: *4958. Golden antependium presented by Emp. Henry II. (d. 1024) to the cathedral of Bâle, 3 ft. high and 5½ ft. wide, with embossed reliefs, a most interesting specimen of the goldsmith's art, probably executed by Lombard artists under Byzantine influence. The tapestry and carpet also come from Bâle (16-17th cent.).

In the adjoining case, next the garden: Astrolabes, compasses, clocks of the 16-17th cent.; case of a German architect of the 16th cent. etc. — Next case: Covers of a Gospel; Last Supper in chased and gilded copper with enamels, Limoges work of the 12th and 13th cent.; censers and vessels used as hand-warmers (13th and 16th) cent.; Italian reliquaries of the 14-15th cent.; abbot's crosiers (12-14th cent.); monstrance and chalice (15th cent.).

We return to Room 8. On the right is the —

12th Room. State-bed (17th cent.) from the Château d'Effiat (Puy-de-Dôme); to the right and left: Venus and Cupid, a portrait of Diana of Poitiers, and Levee of a Court-lady, by *Primaticcio* and his school. On the chimney-piece: 937. Jesus Christ in an attitude of benediction, a statue by *Duquesnoy*. At the window: French and German moulds for pastry (16-18th cent.).

We next enter the rich Gothic **Chapel*, which is borne by a pillar in the centre. To the left, Large Flemish altar-piece, 15th century. Opposite, Gothic chairs and stalls. On the site of the altar, Large wooden reliquary (15th cent.). At the end: Christ, a wooden statue of life-size, 12th cent.; Statues of the Virgin and St. John, from an Italian 'Calvary', 13th century.

The *Thermes*, or ruins of the baths once belonging to the ancient palace of the emperors (p. 227), are on the side adjoining the Boul. St. Michel. The fact that the largest hall, which was the *Frigidarium*, or chamber for cold baths, is 65 ft. in length, 37½ ft. in breadth, and 59 ft. in height, will serve to convey some idea of the imposing dimensions of the ancient Roman palace. The architecture is simple, but the masonry is so substantial that the weight and moisture of a garden which lay above it for many years down to 1810 have left it uninjured. The vaulting is adorned with ships' prows, in allusion to the fact that Lutetia lay on a navigable river, whence the modern armorial bearings of Paris are said to be derived. A number of the Roman antiquities found at Paris are preserved here, but they will not interest ordinary visitors. The *Tepidarium*, or warm bath, was in the part adjoining the boulevard, now destitute of vaulting.

The *Garden*, or *Square Cluny*, the only entrance to which is through the court of the 'hôtel' (p. 227), contains interesting mediæval sculptures and architectural remains, including a large Romanesque portal from the Benedictine church at Argenteuil. Facing the Hôtel de Cluny is a cast of the fine Madonna de Notre-Dame at Paris.

II. FROM THE MUSÉE DE CLUNY TO THE PANTHÉON.

Sorbonne. Collège de France. Bibliothèque Ste. Geneviève. St. Etienne-du-Mont.

Ascending the Rue de la Sorbonne, opposite to the entrance to the Hôtel de Cluny, we see in front of us the new buildings of the Sorbonne.

The **Sorbonne** (Pl. R, 19; V), a building erected in 1629 by Cardinal Richelieu for the Theological Faculty of the University of Paris, is now also the seat of the *Facultés des Lettres et des Sciences*.

The Sorbonne was originally a kind of hostel founded by *Robert de Sorbon*, the confessor of St. Louis, in 1253, for the reception of poor students of theology and their teachers; but it soon acquired such a high reputation that it became the centre of the scholastic theology, and its name came to be applied to the theological faculty itself. This establishment has exercised considerable influence on Catholicism in France. While violently hostile to the Reformation, the Sorbonne was hardly less strongly opposed to the Jesuits; and for a long period it rejected the authority of the 'Unigenitus' bull directed against the Jansenists (1713). The faculty next came into collision with the philosophers of the 18th cent., of whose witticisms it was frequently the butt, until it was abolished by the Revolution. In 1808, when Napoleon I. founded the present university (under which term the French include the authorities who superintend the education of the whole country), the building was handed over to the three faculties mentioned above. The two other faculties belonging to the university (jurisprudence and medicine) occupy separate buildings (pp. 239, 226). The total number of students exceeds 10,500. The lectures are open to the public, ladies excepted, gratis. About the middle of August prizes founded in 1733 by *Legendre*, a canon of Notre-Dame, are annually distributed here among the pupils of the lyceums of Paris and Versailles. — The University Library (170,000 vols., catalogued) is open daily, except Sundays and holidays, 10-3 and 7-10 o'clock.

The **New Sorbonne*, erected in 1885-89 after *Nénot's* plans, presents a huge façade to the Rue des Ecoles, with colossal statues of Homer, by *Delaplanche*, and Archimedes, by *Falguière*, in front. Above are two pediments (Sciences, by *Mercié*; Letters, by *Chapu*) and eight statues: Chemistry (to the left), by *Injalbert*; Natural History, by *Carlier*; Physics, by *Lefeuve*; Mathematics, by *Suchetet*; History, by *Cordonnier*; Geography, by *Marqueste*; Philosophy, by *Longepied*; and Archæology, by *Paris*. — The new buildings so far comprise only the portion destined for the *Académie de Paris*; the older part, belonging to the *Faculté des Lettres*, is to be rebuilt (with the exception of the chapel, which will be preserved as it is); while on the other side the new accommodation for the *Faculté des Sciences* is now being built.

The interior decoration of the new buildings is still unfinished. The

rector's vestibule is to contain a statue of the University, by *Allard*. On the grand staircase, a statue of the Republic, by *Delhomme*, and paintings of Literature, by *Flameng*, and Science, by *Chartran*. The large amphitheatre, which holds 3000 persons, is to have six statues: Sorbon by *Crauk*, Richelieu by *Lanson*, Descartes by *Coutan*, Pascal by *Barrias*, Rollin by *Chaplain*, and Lavoisier by *Dalou*. The apse of this hall will be decorated with paintings by *Puvis de Chavannes*, the cupola by *Galland*. The paintings in the adjoining rooms are by *Wencker* and *Lerolle*; in the Salle des Actes, by *Jobbé-Duval* and *Duez*; in the Salle des Commissions, by *Lhermitte* and *Roll*; and in the rector's chambers, by *Raph. Collin*.

The CHURCH OF THE SORBONNE (open 8-11 and 1-4 o'clock; at other times apply to the concierge), the usual entrance of which is in the Place de la Sorbonne, was also built by Richelieu, 1635-59. It is surmounted by a conspicuous dome. The façade is embellished with four modern statues: Religion, Theology, Science, and Philosophy. In the interior, to the left of the entrance, is a large picture by *Hesse*: Robert de Sorbon presenting young students of theology to St. Louis. The spandrels of the dome were painted by *Phil. de Champaigne*. The left arm of the transept contains the History of Theology, a large picture by *Timbal*, and *Richelieu's Tomb (d. 1643), designed by Lebrun, and executed by *Girardon* in 1694.

In the Boul. St. Michel, opposite the church of the Sorbonne, is the *Lycée St. Louis*, formerly the Collège d'Harcourt, founded in 1280.

A little way beyond the new buildings of the Sorbonne is the Collège de France (Pl. R, 19; V), founded by Francis I. in 1530, entirely rebuilt at different times between 1611 and 1774, and restored and extended in 1831. The original name, 'Collège des trois langues', denoted its dedication to students from different provinces. The inscription 'Docet omnia' over the entrance indicates that its sphere embraces every branch of science. The lectures are intended for the benefit of adults, and are of a popular character. The public are admitted gratis, ladies included. The college, which contains 39 chairs, is not connected with the university, but is under the direct control of the minister of public instruction. A bronze statue of *Claude Bernard* (1813-78), the physiologist, by Guillaume, has been erected in front of the side of the Collège facing the Rue des Ecoles. Adjacent is a statue of *Dante* (d. 1321), by Aubé. In the court on the side next the Rue St. Jacques is a statue of *Budé* (d. 1540), one of the learned founders of the institution, by L. Bourgeois.

Farther on, the Rue des Ecoles passes the Square Monge (p. 241) and ends behind the Halle aux Vins (p. 267), near the Jardin des Plantes (p. 263).

We now ascend the old Rue St. Jacques, passing the *Lycée Louis-le-Grand* (recently largely rebuilt), formerly the Collège de Clermont belonging to the Jesuits, and reach the wide and handsome *Rue Soufflot*, which leads to the Jardin du Luxembourg (p. 258) and to the Panthéon, with its imposing dome.

The ***Panthéon** (Pl. R, 19, V; admission, see 237) stands on the highest ground in the quarters of the city on the left bank,

occupying the site of the tomb of Ste. Geneviève (d. 512), the patron saint of Paris. The chapel erected over her tomb was succeeded by a church, which having fallen to decay was removed about the middle of last century. The present edifice, designed by *Soufflot*, was completed in 1790, the foundation-stone having been laid by Louis XV. in 1764. The new church was also dedicated to Ste. Geneviève, but in 1791 the Convention resolved to convert it into a kind of memorial temple, which they named the 'Panthéon', inscribing on it the words, '*Aux grands hommes la patrie reconnaissante*'. It was restored to religious uses in 1806, but was again made a temple after the July Revolution in 1830. Once more consecrated in 1851, it was finally secularised in 1885 for the obsequies of Victor Hugo.

EXTERIOR. The edifice is of most imposing dimensions, and its form is that of a Greek cross (with equal arms), 370 ft. long and 276 ft. wide, surmounted by a dome 272 ft. in height and over 75 ft. in diameter. The dome rests on a lofty cylinder or drum enclosed by an open Corinthian colonnade, and is crowned with a lantern. A huge colonnade consisting of twenty-two fluted Corinthian columns, 81 ft. in height, resembling that of the Pantheon at Rome, forms the portico, to which eleven steps ascend. The tympanum, 117 ft. long and 23 ft. high, contains a fine *Group of sculptures by *David d'Angers* (d. 1856), illustrative of the inscription mentioned above. The principal figure, 16 ft. in height, represents France distributing wreaths to her sons, who form spirited groups on each side.

To the left, under the protection of Liberty, are a number of illustrious men, including *Malesherbes*, *Mirabeau*, *Monge*, and *Fénelon*; then *Manuel*; *Carnot*, the celebrated general of the Republic; *Berthollet*, the chemist, and *Laplace*, the astronomer. In the second row are the painter *David*, *Cuvier*, *Lafayette*, *Voltaire*, *Rousseau*, and the physician *Bichat*. To the right, beside the figure of History, are soldiers of the Republic and of the Empire, with *Bonaparte* among them; behind him an old grenadier leaning on his musket, emblematic of discipline, and the drummer-hoy of Arcola as the representative of youthful bravery. In the angles of the pediment are students of the University and the Ecole Polytechnique.

Under the portico are two groups in marble by *Maindron* (d. 1884): Ste. Geneviève imploring Attila, the leader of the Huns, to spare the city of Paris; and the Baptism of Clovis by St. Remigius.

ADMISSION. The Panthéon is open daily, except Mon., from 10 to 4. For the dome an order is necessary from the Administration des Beaux Arts, Rue de Valois 3 (Palais-Royal); and the vaults are shown from 1 to 4 only by the custodian.

INTERIOR. Three handsome bronze doors form the entrance to the simple but majestic interior. On each side of the aisles is a Corinthian colonnade, bearing a gallery running round the church. Over the centre of the edifice rises the dome, which according to *Soufflot*'s design was to have rested on columns, but these proved too weak for the weight of the superstructure. *J. Rondelet*, who succeeded *Soufflot* in 1781, substituted pillars, connected by massive arches, for the original columns, to the detriment, however, of the

general effect produced by the nave. The dome consists of three sections, one above the other, the second of which is adorned with paintings by *Gros*. The paintings on the spandrels, by *Carvalho*, after *Gérard*, represent Death, France, Justice, and Glory.

The interior of the Panthéon is decorated with paintings and other works of art of a national and historical character (some still unfinished). In the nave, on the right, Preaching of St. Denis, by *Galand*; Childhood of Ste. Geneviève, by *Puvis de Chavannes*. On the left, Martyrdom of St. Denis, by *Bonnat*; Ste. Geneviève interceding with Attila, by *Delaunay*, and some unfinished frescoes. Right arm of the transept (in which a statue of Mirabeau, by Injalbert, is to be placed): Coronation of Charlemagne, and Charlemagne as restorer of literature and science, by *H. Lévy*; to the left, Baptism of Clovis and his Vow at the battle of Tolbiac, by *Blanc*; farther back, Pilgrimage of Ste. Geneviève and Procession with her relics, by *Maillot*, and a piece of tapestry, 'Gratia Plena'. To the right of the choir, Death of Ste. Geneviève, by *J. P. Laurens*; and a statue of the saint, by Guillaume. The paintings on the left side, by *Meissonier*, will depict Ste. Geneviève saving Paris from famine. An Apotheosis of the Republic will occupy the apse, on the arch of which is Christ showing to the Angel of France the destiny of her people, a mosaic by *Hébert*. Left arm of the transept (in which a statue of Victor Hugo, by *Rodin*, is to be placed): St. Louis administering justice, founding the Sorbonne and the Quinze-Vingts, and a captive of the Saracens, by *Cabanel*; above, a procession of saints. To the right: Joan of Arc before Orleans, at Rheims, and in prison, by *Lenepveu*; behind, famous Frenchwomen, by *Humbert*, and a piece of tapestry, 'Pro Patria'. — Against the pillars are placed statues of St. Denis, St. Remy, St. Germain, St. Martin, St. Bernard, St. Jean de Matha, St. Eloi, St. Gregory of Tours, St. Vincent de Paul, and La Salle.

The DOME is reached by a staircase in the left (N.) transept. We ascend 139 steps to the roof, and then 192 more to the first section of the dome, where we obtain a view of the painting in the second section, executed by *Gros*, in 1824. This large composition, which finds many admirers, covers a surface of 352 sq. yds., and represents Ste. Geneviève receiving homage from Clovis (the first Christian monarch), Charlemagne, St. Louis, and Louis XVIII.; above are Louis XVI., Marie Antoinette, Louis XVII., and Madame Elisabeth, the victims of the Revolution. — We may now ascend by 94 steps more to the lantern, which commands a magnificent view of the city and environs, but less interesting than that from the Tour St. Jacques or Notre-Dame, as its position is not so central.

The entrance to the VAULTS (*Caveaux*), which are uninteresting, is at the end of the building, to the left. Visitors wait at the entrance for the custodian, who conducts parties through the vaults at intervals. They are supported by 20 pillars, and divided by partitions of masonry.

Mirabeau was the first person whose remains were deposited here (1791), and near him was placed *Marat*, the most furious of the Jacobins, who fell in 1793 by the hand of Charlotte Corday; but their bodies were afterwards removed by order of the Convention.

To the right, near the entrance, is the tomb of *Victor Hugo*, interred here in 1885. A monument is to be erected, with a statue of the poet by Dalou. — Opposite is a monument in poor taste, erected to *J.-J. Rousseau*, and on the other side, to the left, is a monument to *Voltaire*, with a statue by *Houdon*. Both tombs are, however, empty, the remains of the two philosophers having been secretly removed after the Restoration, and interred in some unknown spot, as a kind of paltry retaliation for the desecration

of the tombs of St. Denis. — Opposite Voltaire's tomb is that of *Soufflot* (d. 1781), the architect of the Panthéon, a plaster-model of which is shown beneath the left transept. Farther on, to the left, is a vault in which were placed in 1889 the remains of *Lazare Carnot* (1811-51), member of the Convention, General *Marceau* (1769-1796), *La Tour d'Auvergne* (1743-1800), 'the first grenadier of France', and *Baudin* (1811-51), representative of the people (p. 193). On the other side are the tombs of *Marshal Lannes* (1769-1809), *Lagrange* (1736-1813), the mathematician, *Bougainville* (1729-1811), the circumnavigator, and a number of senators of the first Empire. In these vaults a remarkably loud echo may be awakened. The egress from the vaults is on the W. side, near the principal portal (fee optional).

The Panthéon was the headquarters of the insurgents in June, 1848, and was also one of the chief strongholds of the Communists in 1871; and on both occasions the neighbouring barricades were only stormed by the troops after a severe struggle. On the latter occasion the insurgents had placed gunpowder in the vaults for the purpose of blowing up the building, but were dislodged before much damage had been done.

Opposite the portal of the Panthéon, to the left, are the *Mairie du 5^e Arrondissement*, erected in 1849, and the bronze *Statue of J.-J. Rousseau* (1712-1778), by P. Berthet, erected in 1889. On the right is the *Ecole de Droit*, or school of jurisprudence connected with the university, begun by Soufflot, the architect of the Panthéon, in 1771.

A little to the left, in the Rue d'Ulm (No. 45), is the *Ecole Normale Supérieure* (Pl. G, 19; F), founded in 1794 for the training of teachers for the 'lycées'. It has produced many famous writers and savants. The building dates from 1845. — Not far off is the Val-de-Grâce (p. 241).

The **Bibliothèque Ste. Geneviève**, a long building on the N. side of the Place du Panthéon, was built by *Labrousse* in 1843-50. On the walls are inscribed names of celebrated authors of all nations. The collection of books, which is judiciously arranged in the lower and upper apartments, was founded by Cardinal de la Rochefoucauld in 1624 in the Abbey of Ste. Geneviève, and greatly augmented by the library of Cardinal Le Tellier, archbishop of Rheims, in 1710. The library now contains 35,000 MSS., dating from the 11th to the 17th cent., some of them illuminated with beautiful miniatures; numerous 'incunabula', or specimens of the earliest printing (1457-1520); 5000-6000 engravings; and various curiosities, including a portrait of Queen Mary Stuart, presented by herself to the monastery. The printed books number 120,000 vols., including a nearly complete collection of Aldines, or books by the celebrated firm of Manutius at Venice (so called from Aldus, the elder member of the firm; 15th and 16th cent.), and Elzevirs, or books printed by the family of that name at Leyden and Amsterdam (16th and 17th cent.); and also most of the periodicals published in the 17th and 18th centuries.

The vestibule contains busts of famous French authors; and on the staircase is one of *Gering*, who in 1469 established at the Sorbonne the first printing-press used in Paris. Above the landing is a copy, by *Balze*, of Raphael's School of Athens in the Vatican.

At the sides are medallions (also by Balze) emblematic of Science, Art, Theology, and Jurisprudence, and busts of Laroche-foucauld and Labrousse. At the entrance to the hall is a fine piece of Gobelins tapestry, representing Study surprised by night, after Balze.

The *READING ROOM (*Salle de Lecture*) on the first floor, 330 ft. in length, 66 ft. in width, and 42 ft. in height, is very skilfully constructed. The vaulting is borne by seventeen iron girders, supported in the centre by sixteen slender columns; and 420 readers can be accommodated. The library is open to the public daily, except in the vacation (1st to 15th Sept.), from 11 to 4, and from 6 to 10 p.m.; in the evening it is frequented almost exclusively by students. On the tables to the right are about 300 periodicals (nearly all French) for the use of readers.

At the N. E. corner of the Place du Panthéon rises —

***St. Etienne-du-Mont** (Pl. R, 22; V), a late-Gothic church, the choir of which was begun in 1517. The incongruous Renaissance façade was added in 1620. To the left of the portal is a tower, flanked with a round turret, probably part of an earlier building.

The INTERIOR consists of a nave and two aisles. Slender round pillars, twelve on each side, united by a gallery halfway up, bear the lofty vaulting, from which spring the ribs terminating in pendent key-stones. The choir is separated from the nave by a **Jubé*, or rood-loft, of exquisite workmanship, by *Biard* (1600-05), round the pillars of which two graceful spiral staircases ascend. — The *Pulpit*, by *Lestocart*, from designs by *Lahire* (d. 1655), is borne by a Samson, and adorned with numerous statuette.

Most of the paintings are of the 18th cent.; but the S. chapels contain some modern works. The stained glass dates from 1568 and is ascribed to *Pinaigrier*.

The 3rd Chapel on the right contains inscriptions in memory of several eminent persons once buried here, whose remains have been removed. The 5th Chapel on the same side contains a 'Holy Sepulchre' with life-size figures in terracotta, dating from the end of the 16th century. Above, the Plague, by *Jouvenet*.

Farther on, to the right on the wall of the choir-ambulatory, are three large pictures, two of them being votive offerings to Ste. Geneviève presented by the city, by *Largillière* (1696) and *De Troy* (1726), and the third, the Stoning of St. Stephen, by *Abel de Pujol*.

The 2nd Chapel on the same side contains the *Tomb of Ste. Geneviève* (p. 237), with a sarcophagus, which is said to date from the period of her death, but is probably not earlier than 1221. The chapel was restored in 1862, and richly decorated with carved wood, painted and gilded. The first chapel on the left side of the choir contains the Martyrdom of ten thousand Christian soldiers under Maximian, a mural painting of the 16th century. On the fête of Ste. Geneviève (3rd Jan.) numerous worshippers flock to St. Etienne-du-Mont.

On 3rd Jan., 1857, Archbishop Sibour was assassinated in this church by Verger, an ex-priest.

A relic of the old Abbey of Ste. Geneviève still exists in the square tower, in the transitional style, to the right of St. Etienne, which now forms part of the *Lycée Henri IV.*, and is separated from the church by the Rue Clovis.

Nearly at the back of St. Etienne, to the N.E., is the **Ecole Polytechnique** (Pl. R, 22; V), for the education of military engineers, staff-officers, telegraphists, and officials of the government

tobacco-manufactory. It was founded by the celebrated Monge in 1794.

On the other side of the building passes the *Rue Monge*, which connects the Boul. St. Germain with the Avenue des Gobelins. At the angle formed by the Rue Monge and the Rue des Ecoles is the *Square Monge*, with bronze statues of *Voltaire*, after Houdon, and *F. Villon*, by Etcheto, and two stone statues from the old Hôtel de Ville, etc.

A little lower down, to the right of the Rue Monge, is the *Eglise St. Nicolas-du-Chardonnet*, dating from the end of the 17th century. Beyond this are the Boul. St. Germain and the *Place Maubert*, where a bronze statue, by Guilbert, was erected in 1889 to *Etienne Dolet*, burned in 1546, in the reign of Francis I., for 'impiety and atheism'. The reliefs represent Paris raising Freedom of Thought, and the Arrest and Execution of Dolet.

III. FROM THE PANTHÉON TO THE PARC MONTSOURIS.

Val-de-Grâce. Catacombs.

Those who do not intend to visit the deaf-and-dumb asylum, or the hospital of Val-de-Grâce, had better drive to the park, 2 M. distant; or they may take the Gare de l'Est and Montrouge tramway in the Boul. St. Michel as far as its terminus, whence they turn to the left in order to reach the park. The railway to Sceaux (see p. 336) also passes the Parc Montsouris.

If time be limited, the traveller should proceed at once from the Panthéon to the Luxembourg (p. 253).

The Rue St. Jacques (p. 236), which crosses the Rue Soufflot near the Panthéon, passes, higher up, in front of the insignificant church of *St. Jacques-du-Haut-Pas* (Pl. G, 19; V), of the 17th cent., which contains several valuable pictures.

Adjoining this church is the *Institution des Sourds-Muets* (admission by permission of the director), the court of which contains a statue of the *Abbé de l'Epée*, the founder, by Félix Martin, a deaf-mute, and an elm-tree, 100 ft. high, said to have been planted in 1605, and probably the oldest tree in Paris.

The Rue de l'Abbé de l'Epée leads between the church of St. Jacques and the Deaf and Dumb Institution to the Rue Gay-Lussac, No. 41 in which is the *Musée Pédagogique*, open Sun. and Thurs. 10-4.

To the left in the Rue St. Jacques, farther on, we observe the —

Val-de-Grâce (Pl. G, 19), formerly a Benedictine nunnery, founded by Anne of Austria, mother of Louis XIV., in accordance with a vow, but converted into a military hospital in 1790. The Church, designed by *Fr. Mansart*, and erected in 1645-66, is a handsome building. The court in front of it is embellished with a bronze statue of Larrey (d. 1848), the famous surgeon, by *David d'Angers*. Above the façade, with its Corinthian and composite columns, rises the handsome dome, a reduced copy of that of St. Peter's at Rome, 53 ft. in diameter, and 133 ft. in height, flanked with four towers which also terminate in domes.

THE INTERIOR (open in the middle of the day) is somewhat bare. The coffered vaulting is adorned with medallions. The high-altar, with its canopy borne by spiral columns, is a copy of that of St. Peter's at Rome. On the dome is painted a celebrated fresco by Pierre Mignard (d. 1695), representing the glory of the blessed, but badly preserved. The church contains the tomb of Queen Henrietta, wife of Charles I. of England, over whose remains a famous funeral oration was pronounced by Bossuet. It was also the burial-place of members of the royal family of France and princes of Orleans.

A little farther on, the Rue St. Jacques ends at the *Boulevard de Port-Royal*, not far from the Carrefour de l'Observatoire (to the right; p. 260). From the Carrefour the Rue Denfert-Rochereau leads to the S., passing the *Hospice des Enfants Assistés* (foundlings), to the *Place Denfert-Rochereau*, formerly *Place d'Enfer* (Pl. G, 17), adorned with a huge gilded lion, by Bartholdi. Here also converge the *Boulevard Raspail* (p. 260), to the right, leading to the cemetery of Montparnasse; to the left the *Boulevard Arago*, running E. to the Avenue des Gobelins (p. 270), and the Boulevard St. Jacques, which is continued by the Boulevard d'Italie to the Place d'Italie (p. 270). The 'place' still contains the buildings belonging to the city 'barrière' which was formerly here; their friezes are worthy of notice. In the court of that on the right is one of the chief entrances to the *Catacombs*.

The *Catacombs* were formerly subterranean quarries, worked as far back as the Roman period, and yielding a soft kind of limestone which hardens on exposure to the air. Visitors are admitted to the *Catacombs* at intervals (generally the 1st and 3rd Sat. of each month) by the special permission of the Directeur des Travaux, Hôtel de Ville. Each visitor must carry a torch, which may be bought at the entrance (50 c.), with a guard of cardboard to protect the clothes from the melting wax. Overcoats and thick shoes are desirable. The visit occupies about 1 hr., and the exit is made at No. 92, Rue Dareau, near the Avenue Montsouris (Pl. G, 17-20).

The *Catacombs* extend under a great part of the quarters on the left bank and have upwards of sixty entrances in different suburbs. Several streets in the S. quarters of Paris, situated above these quarries, having begun in 1784 to show symptoms of sinking, steps were taken by government to avert the danger by constructing piers and buttresses where the upper surface was insufficiently supported. About the same time the Council of State ordered the removal of the bodies from the Cemetery of the Innocents, and others, which were closed at that period, to these subterranean quarries. In 1786 the quarries were accordingly converted into a vast charnel-house, and called *Catacombs*. During the Revolution and the Reign of Terror, immense numbers of bodies and bones brought from various quarters were thrown in confused masses into these cavities; but in 1810 a regular system was organised for the more seemly disposition of these remains and the preservation of their resting-place. New pillars have since been erected to support the roof, excavations made to admit more air, and channels dug to carry off the water. The galleries and different compartments are completely lined with human bones and skulls, carefully arranged. Several small chapels have been built with the bones.

From the Place Denfert-Rochereau the AVENUE MONTSOURIS leads past the *Gare de Sceaux* (p. 24) direct to the Parc Montsouris (see below). A more interesting, though slightly longer, route follows the *Avenue d'Orléans* to the right, along which the tramway runs. This traverses the Montrouge quarter, properly called the

Petit-Montrouge. The *Grand-Montrouge* is a village outside the fortifications.

The second street to the right leads from the Avenue d'Orléans to the SQUARE DE MONTRouGE (Pl. G, 17), with the new *Mairie of the 14th Arrondissement*. The square is embellished with a marble bust of the Republic, by *Baffier*; and by bronze figures of a Torchbearer by *Steuer*, a Horse attacked by a tiger by *Fratin*, and an Auvergnat Peasant by *Mombur*.

Farther on, at the corner of the Avenue d'Orléans and the Avenue du Maine, is the church of *St. Pierre-de-Montrouge* (Pl. G, 17), a neo-Romanesque edifice, with a lofty tower terminating in a lantern. — The Rue d'Alésia leads hence to the left to the Avenue Montsouris, which may also be reached from the extremity of the Avenue d'Orléans.

The **Parc Montsouris** (Pl. G, 21) may be reached, as already stated, by the Montrouge tramway, or by the Ceinture railway (Gentilly station). This new park, completed in 1878, affords an attractive public promenade for the S. side of the town, but is smaller and less picturesque than the Buttes-Chaumont on the N.E. side. It is about 40 acres in area, and adjoins the fortifications. It is intersected by the Sceaux and Ceinture lines of railway. On the highest ground stands the *Bardo*, or palace of the Bey of Tunis, a picturesque Moorish edifice with four domes, which was shown at the Exhibition of 1867 and has been rebuilt here. It is now an observatory. A little lower down is an *Obelisk* erected to *Colonel Flatters* and his companions, slain by the Touaregs in 1881, while making surveys with a view to the construction of a railway through the Sahara. At the foot of the hill is a lake fed by a small cascade. Above the lake, in front of a pavilion, is a marble group by *Etex* ('*Les Naufragés*'); and to the E. of the Observatory is the Old Mother, a bronze group by *J. Escoüla*. The park commands an extensive view of Paris, particularly of the hill of Ste. Geneviève (Panthéon) and the valley of the Bièvre. Beyond the precincts of the city, to the S.E., are the *Hospice* and *Fort de Bicêtre*.

To the W., by the principal entrance to the park, lies the large *Réservoir de la Vanne*, 7½ acres in area, with sides built of solid stone, 10 ft. thick, and capable of holding eleven million cubic feet of water. Nearly one-third of the quantity is supplied daily by a conduit, 7 ft. in diameter and about 100 M. in length, which brings to Paris the water of the Vanne, a stream rising in Champagne, about 9 M. from Troyes. Visitors are admitted to inspect the reservoir; entrance in the Rue de la Tombe-Issoire.

The Rue Beaunier, opposite the entrance to the reservoir, leads to the Avenue d'Orléans, near the station of the tramway to the Gare de l'Est, and near a station of the Ceinture line.

We may now return to the centre of the town by the *Tramway de la Gare de l'Est*, mentioned at p. 241 (see also Appx., p. 29). Or we may take the *Chemin de Fer de Ceinture* from Montrouge or the Parc Montsouris to the Gare St. Lazare (comp. Appx., p. 25).

10. From the Louvre to the Luxembourg and the Cemetery of Montparnasse.

I. INSTITUT. HOTEL DES MONNAIES. ECOLE DES BEAUX-ARTS.

In this route the visitor should begin with the collections that are opened at the earliest hour. The Mint is not shown except on Tues. and Friday. — Luncheon may be taken near the Luxembourg (pp. 14, 15).

The *Pont des Arts* (Pl. R, 20; V), between the Old Louvre and the Institut, an iron bridge for foot-passengers only, constructed in 1802-4, derives its name from the 'Palais des Arts', as the Louvre was once called. It commands a fine view up and down the river.

The *Institut*, a somewhat clumsy edifice, covered with a dome, is situated on the left bank of the Seine, at the S. end of the Pont des Arts, and opposite the Louvre. The crescent-shaped façade is flanked with wings adorned with arcades. In front of the Corinthian portico rises a *Statue of the Republic* by Soitoux, erected in 1880. The institution was originally founded by Cardinal Mazarin for the education of youths from the newly-acquired provinces of Roussillon, Pignerol, Flanders, and Alsace, and was called the *Collège Mazarin*, but was popularly known as the *Collège des Quatre Nations*. The building was erected in the latter half of the 17th cent., on the site of the *Hôtel de Nesle*, to which, according to tradition, Margaret of Burgundy, wife of Louis X., used to cause young strangers to be brought to minister to her pleasures, and afterwards to be assassinated and thrown into the Seine. During the Revolution it was used as a prison, but in 1795 it was ceded by the Convention to the *Académies*, or societies of savants, who had hitherto met in the Louvre. Its name was then changed to the Palais de l'Institut, and it was not again employed as a school.

The Institut embraces five different academies: the *Académie Française*, the *Académie des Inscriptions et Belles-Lettres*, the *Académie des Sciences*, the *Académie des Beaux-Arts*, and the *Académie des Sciences Morales et Politiques*.

1. The *Académie Française* is mainly occupied with the superintendence of the French language and its orthography, and with the publication or revision of the *Dictionnaire de la Langue Française* or *de l'Académie*, and the *Dictionnaire Historique de la Langue Française*. It also distributes various prizes, such as the *Prix Montyon*, a sum of 22,463 fr. annually, bequeathed by a famous philanthropist of that name for the purpose of being awarded to the poor man who should be held to have done the most virtuous action during the year. The money, however, is now divided among a considerable number of deserving persons. Another prize of nearly the same value is awarded to the author of the literary work considered most useful to the cause of public morality. This department consists of 40 members. The annual meeting takes place in May; the weekly meetings are on Thursday, 2.30 to 4.30 p.m.

2. The *Académie des Inscriptions et Belles Lettres* is chiefly devoted to the study of the ancient languages and to archæological research, and publishes its *Mémoires* periodically. There are 40 ordinary members, 10 honorary members (*libres*), 8 foreign associates, 50 corresponding members, and two secretaries. Annual meeting in July; weekly meeting every Friday, 3.5 p.m. This and the other departments also possess the control of valuable money-prizes.

3. The *Académie des Sciences* cultivates the study of mathematics and natural science, and consists of 66 ordinary (*membres titulaires*) and 10 honorary members, 8 foreign associates, and 92 correspondents. Its publications consist of *Mémoires* and *Comptes-Rendus des Séances*. Annual meeting in December; weekly meetings on Mondays, 3-5 p.m.

4. The *Académie des Beaux-Arts*, for the promotion of painting, sculpture, architecture, and musical composition, consists of 40 ordinary and 10 honorary members, 10 foreign associates, and 40 correspondents. One of its tasks is the publication of a *Dictionnaire de la Langue des Beaux-Arts*. Annual meeting on the first Saturday in October; weekly meetings on Saturdays, 3-5 p.m.

5. The *Académie des Sciences Morales et Politiques*, for the study of philosophy, history, and political economy, consists of 40 ordinary and 6 honorary members, 9 foreign associates, and from 37 to 47 correspondents, and publishes its *Mémoires*. Annual meeting in April; weekly meeting every Saturday, 12-2 p.m.

The Institut thus numbers 226 members, vacancies being filled by the votes of the members in whose department they occur, subject to the approval of government. There are also about 300 honorary and corresponding members. Each ordinary member receives a salary of 1200 fr.

The title of 'Membre de l'Institut' is the object of the highest ambition of every literary and scientific Frenchman. All their meetings take place at the *Palais de l'Institut*, and are of course extremely interesting, as the most eminent French savants take part in the discussions. The grand meeting of the five departments combined is held on 25th October. Tickets of admission are issued at the secretary's office.

In a small square adjoining the quay to the W. of the Institut is a *Statue of Voltaire* (1694-1778), in bronze, by Caillé, erected here in 1885. A statue of *Condorcet*, by J. Perrin, is to be placed opposite.

The courts of the Institut are used as a public thoroughfare. The first on the right contains the entrance to the *Salle des Séances Solennelles*, formerly the chapel, situated under the dome. This saloon and the vestibule are embellished with statues of authors, scholars, and artists. On the other side of the court is the *Bibliothèque Mazarine*, which is open to the public daily, 9 to 4, 5, or 6 o'clock, except on Sundays and holidays (vacation from 15th Sept. to 1st Oct.). It contains 250,000 vols. and 6000 MSS., 80 models of Pelasgic monuments from Italy, Greece, and Asia Minor, and several ancient works of art.

The second court contains the rooms in which the ordinary meetings are held and the library of the Institut (no admission).

In the pavilion next the statue of Voltaire, is the small *Musée de Mme. de Caën* (not open to the public; adm. on request at No. 1 Rue de Seine). The Countess de Caën (d. 1870) bequeathed the greater part of her property to the Institute, for the support of art-students in Rome, on the condition that each beneficiary should contribute an original work to the musée, which now contains a considerable number of paintings, sculptures, and architectural designs.

The *Hôtel des Monnaies* (Pl. R, 20; IV), or *La Monnaie*, the Parisian Mint, is a large building to the left of the Institut and near the Pont-Neuf (p. 220), erected in 1771-75. The façade, 132 yds. in length, and adorned with Ionic columns, is surmounted by allegorical figures of Peace, Plenty, Commerce, Power, Wisdom, and Law.

The Monnaie contains a *Musée Monétaire*, or collection of coins, which is shown on Tuesdays and Fridays, 12-3 o'clock, to visitors provided with an order from the Director. This order, which must be applied for in writing, also admits to the workshops; it is available for 4-5 persons.

The Museum is reached by the staircase to the right of the entrance.

The vestibule contains specimens of the metals used in coining. — A cabinet to the right of the vestibule contains a glass-case with ancient coins, and presses with medals. The cabinet to the left contains specimens of postage-stamps.

The numerous glass-cases in the principal saloon contain an interesting collection of *French Coins*, arranged chronologically, from the earliest times down to the present day, those of Louis XIV. and Louis Philippe being most numerous; a collection of *Foreign Coins* of every country (including a Chinese coin of B.C. 1700), and another of *Medals* of various kinds. The series begin on the left. The coins are in the centre, and the medals near the windows.

Farther on is a passage containing *Essais d'Argent*, and a room with models of *Instruments* and *Furnaces* used in coining.

The following room contains *Dies*, and, in the cabinets, the *Medals* of the Consulate and the Empire. The wax models of the reliefs on the Vendôme Column preserved here, and the small model of the column itself, afford a better idea of the details than the originals. A bust of Napoleon I. by *Canova*, executed in 1806, and a cast of the emperor's face taken 20 hours after death are also shown.

The *Ateliers*, with their steam-engines, furnaces, and machinery, are well worth visiting. Those only are shown in which silver pieces and medals are struck. Each of the six furnaces in which the silver is melted is capable of containing from 15 to 22½ cwt. of metal, worth 160,000 to 240,000 francs. The machines invented by M. Thonnelier are highly ingenious, sixty pieces of money being struck by each of them per minute, while the whole of them in operation at once are capable of yielding two million francs per day. In the Monnaie are also performed all the operations of assaying and stamping the gold and silver wares of the jewellers. The 'Atelier du Monnayage' contains a marble figure of Fortune, by Mouchy.


Returning to the Institut, we soon reach the Rue Bonaparte, the second street to the left beyond that building. No. 14 in this street is the —

Ecole des Beaux-Arts (Pl. R, 17, 20; IV), or *Palais des Beaux-Arts*, founded in 1648, for the teaching of painting, sculpture, engraving, gem-cutting, and architecture (open to the public on Sun., 12-4; strangers admitted also on week-days, 10-4). The pupils who obtain the first prizes in the different departments are sent to Rome at the expense of government for four years. The works they send home, termed 'grands prix de Rome', are exhibited here annually in summer. The school has a staff of 50 professors, and is attended by upwards of 1100 pupils of different nationalities. It contains a valuable and extensive *Collection of Copies* of sculptures and paintings, forming an admirable supplement to the collections of the Louvre.

The building, erected in 1820-38 and 1860-62 by *Debret* and *Duban*, occupies the site of the old *Couvent des Petits-Augustins*. In 1860-62 a new wing facing the Quai Malaquais was added, and the old Hôtel Chimay, adjoining this wing, was acquired in 1885

for the workshops. At the entrance are colossal busts of Puget and Poussin.

The FIRST COURT contains many handsome fragments of French edifices, from the Gallo-Roman period down to the 16th century. These are the remains of the Musée des Monuments founded here at the time of the first Revolution by the painter *Alex. Lenoir* (d. 1839), and consisting chiefly of tombstones and reliefs rescued from the ruins of churches and châteaux. In 1816 Louis XVIII. dispersed the collection, and ordered most of the objects to be restored to the churches or their original proprietors. In the centre of the court is a Corinthian column in red marble, surmounted by a bronze statue of Plenty (16th cent.). By the wall to the left is a fresco painted on lava by the brothers *Balze*, after the work of Ra-



phael's school in the Villa Magliana (p. 121). To the right is the celebrated and beautiful portal of the Château d'Anet, which was erected for Diana of Poitiers by *Philibert Delorme* and *Jean Goujon* in 1548, by order of Henri II., and which now forms the entrance to the old abbey-chapel (see p. 249).

The SECOND COURT is separated from the first by part of the façade of the château of Gaillon (p. 364), which was erected in 1500 by *Pierre Fain* of Rouen for Cardinal d'Amboise, minister of Louis XII., and one of the chief promoters of the Renaissance in France. It is in a mixed Gothic and Renaissance style, affording a good idea of the character of the château, which was destroyed during the Revolution. Beyond it are other fragments of French architecture and sculpture, statues copied from antiques, and a fine stone basin, 13 ft. in diameter, adorned with heads of gods or heroes, animals,

and the four elements, a work of the close of the 12th cent., brought from the abbey of St. Denis.

The principal *FACADE, which flanks this court on the W., designed by *Duban*, and completed in 1838, is a good example of modern French architecture. It is adorned with two series of arcades, one above the other, and with Corinthian semi-columns and pilasters, and is crowned with an attic.

The VESTIBULE contains copies of ancient Pompeian and other paintings and casts of sculptures of the Parthenon and the temple of Minerva in Ægina, the originals of which are in London and Munich. — We next enter an INNER COURT, roofed with glass, containing numerous casts from famous antiques at Rome and elsewhere: to the right, the Greek gallery; to the left, the Roman gallery (inscriptions). At the ends are restored columns from the Parthenon, with the entablature, and from the temple of Jupiter Stator at Rome. In an adjoining room, to the right (No. 4 on the Plan), are casts of the sculptures of the temples of Zeus at Olympia and Nike Apteros at Athens, of the statue of Mausolus (now in London), etc.

Opposite the entrance to the inner court is the AMPHITHEATRE, adorned with the celebrated **Hémicycle of Paul Delaroche* (d. 1856), an encaustic painting which represents distinguished artists of all ages and nations, and contains in all 75 colossal figures (23 ft. in height).

On a lofty throne in the centre are the great Greek masters, *Phidias* the sculptor, *Ictinus*, the architect of the Parthenon, and *Apelles* the painter. Four female figures in front represent (left) Greek, Gothic, and (right) Roman, and Renaissance art. The Mnse of Gothic art, with long fair hair, is a portrait of the artist's wife, a daughter of Horace Vernet. To the right, beginning from the end, are the most famous painters and (under the columns) architects, and the chief masters of the French school. On the left are sculptors and landscape-painters and (towards the centre) colourists of every school. Delaroche spent 3½ years on this work, and received for it 80,000 fr. It was much injured by a fire in 1855, but has been skilfully restored by *Mercier* and *Fleury*.

Opposite the Hémicycle is a large painting by *Ingres*, representing Romulus victorious over Acron, king of the Sabines. — We now return to the vestibule and ascend to the right to the —

First Floor. On the wall of the staircase is a copy of a fine fresco by *Pinturicchio*, representing the Betrothal of Emp. Frederick III. and Eleanor of Portugal. On the S. and N. sides of the glass-roofed court are galleries adorned with sixty-two copies from Raphael's loggie in the Vatican, by the brothers *Balze*. — The SALLE DES MODÈLES, opposite the staircase, contains a valuable collection of casts from small antiques and Renaissance works, cork models of Roman and other buildings, part of the *Musée des Copies*, and a number of admirable *Drawings by ancient masters. Among the copies are represented the master-pieces of every important school, a good idea of which is thus afforded to persons unacquainted with the originals.

Two other rooms on the first floor (Pl. 3, 4), which are not open on Sundays, contain portraits of members and the professors of the

old Academy. A gallery between these two rooms affords a good survey of the Hémicycle of Delaroche.

Descending to the ground-floor, we cross the second court and enter the former CHAPEL by the portal (or, if it be closed, by a door to the left in the Vestibule des Ecoles, mentioned below). This apartment now contains the continuation of the *Musée des Copies*, consisting of reproductions of the finest sculptures and paintings of the Renaissance, chiefly of the Italian school.

In a kind of vestibule are exhibited copies of the frescoes by *Giotto* in the church of the Madonna dell' Arena at Padua, of a Calvary by *Fra Angelico*, of the battle of Heraclius against the Persians by *Piero della Francesca*, of the battle of Constantine by *Giulio Romano*, and of several bas-reliefs. — Among the casts we observe on the right that of the pulpit of the cathedral of Pisa by *Giov. Pisano* (1302-11); numerous busts, bas-reliefs, and medals; candelabrum of the cathedral of Milan (16th cent.); St. George and an allegorical figure by *Donatello* (1386-1466), from Or S. Michele at Florence; monument of Fil. Decio by *Stagio Stagi* (about 1530); John the Baptist by *Ben. da Majano* (1442-97). A small side-chapel contains the Moses, the Slaves, the monuments of Giuliano and Lorenzo de' Medici, the Pietà, Bacchus, Cupid, and other works of *Mich. Angelo*, and *Ghiberti's* doors of the baptistery at Florence. In the centre: Mourning Adonis and Virgin and Child. — Principal chapel: David as the conqueror of Goliath, by *Donatello*; same subject, by *Verrocchio*; alto-reliefs by *Luca della Robbia*; Relief of Jonah by *Lorenzetto*, and others; Last Judgment of *Mich. Angelo*, by Sigalon; in front of it casts of statues at St. Denis and in the Louvre, that of Ilaria de Caretto by *Jac. della Quercia* (1377-1438), stalls of the 16th cent.; figure of St. Michael from Dijon (15th cent.); the Graces by *Germain Pilon* (16th cent., Louvre); reliquary of St. Sebaldus by *P. Vischer*; statues of the cathedral of Chartres (13th cent.); Virgin from the portal of Notre-Dame at Paris; fountains from Hildesheim. In the middle are numerous bas-reliefs: Descent from the Cross by *Niccolò Pisano*; the Madonna and saints, by *Mino da Fiesole*; Perseus, by *Ben. Cellini*, etc. — Besides the copies of paintings already mentioned: (right) *P. della Francesca*, Discovery of the True Cross; *Mezzo da Forlì*, Platina at the feet of Sixtus IV.; *Fr. Penni*, Clemency and Justice; *Raphael*, Venus, Juno and Ceres, Poetry, Jupiter and Cupid. Left, in returning: *Raphael*, Sibyls; *Manegna*, St. James conducted to martyrdom; *Ghirlandajo*, Adoration of the Magi; *Sodoma*, Goths destroying the monastery of Monte Cassino; *Raphael*, Sistine Madonna.

We now cross the VESTIBULE DES ECOLES (Pl. 5), which contains a monument to Ingres, with his bust in bronze, and medallions of Flandrin and Simart by Guillaume. We next enter the —

COUR DU MÛRIER, with galleries containing sculptures executed at Rome by former pupils and casts of ancient bas-reliefs. At the end is the monument of *Henri Regnault*, the painter, and other pupils killed during the defence of Paris in 1870-71; between the columns bearing the names are a bust of Regnault and a statue of a Youth offering him an olive-branch, by *Chapu*. On the wall next to the Vestibule des Ecoles: Galatea of *Raphael*, copied on porcelain by Balze. Below, and in the corridors on the same side, are casts from the terracotta frieze of the Ospedale del Ceppo at Pistoja, by the *Della Robbia* (15th cent.).

Opposite this wall is another vestibule containing several copies, next to which is the SALLE DE MELPOMÈNE, occupied with the remainder of the Musée des Copies and used for the exhibition of

competitive works. On Sun. and on the occasion of such exhibitions this room may also be entered from the Quai Malaquais (Pl. 10). The rooms on the first floor on this side are also used for exhibitions.

Principal copies (from right to the left): *Velazquez*, Don Fernando and Philip IV.; *Filippo Lippi*, Madonna; *Mich. Angelo* (above), Sibyls; *P. Veronese* (below), Adoration of the Virgin; *Correggio*, Madonna and Child, with Mary Magdalene and St. Jerome; *Titian*, Patron saints of Venice, Death of St. Peter the Dominican; *Palma Vecchio*, St. Barbara; *Titian*, Heavenly and earthly love, Assumption; *Raphael*, Jurisprudence; *A. del Sarto*, Last Supper; *Perugino*, Marriage of the Virgin; *Verocchio*, Baptism of Christ; *Masaccio* or *Filippino Lippi*, Miracle of St. Peter; *Raphael*, Atila expelled from Rome; *Fil. Lippi*, Vision of St. Bernard; *Raphael*, Reduced copies of his cartoons, Christ at the Sepulchre; *Holbein*, His wife and children; *Rembrandt*, Lesson in anatomy; *Raphael*, Disputation regarding the sacrament, Marriage of the Virgin; *Botticelli*, Adoration of the Magi, Force; *Mantegna*, Virgin, angels, and saints; *Raphael*, School of Athens; *Sodoma*, Swoon of St. Catharine; *Masaccio*, St. Paul in the prison of St. Peter; *Raphael*, Leo X.; *Masaccio*, Liberation of St. Peter. — Small room at the end, to the right (closed at present), contains copies from *Carpaccio*, *Bonifacio*, *P. Veronese*, *Titian*, and *Correggio*. On the other side of the Salle de Melpomène are three rooms containing prize works since the end of the 17th cent. (apply to a custodian). — Vestibule next the Quai Malaquais: Copies of frescoes; Copies of *Michael Angelo*; casts from the antique.

II. FROM THE ECOLE DES BEAUX-ARTS TO THE LUXEMBOURG.

St. Germain-des-Prés. St. Sulpice.

The Rue Bonaparte leads in 3 min. from the Ecole des Beaux-Arts to St. Germain-des-Prés (Pl. R, 19; IV), one of the most ancient churches in Paris. It belonged to the powerful abbey of St. Germain, founded in the 6th cent., the abbots of which were sometimes cardinals and even kings, as in the case of Hugh Capet and Casimir of Poland. The abbey was originally dedicated to St. Vincent, but afterwards to St. Germain, a bishop of Paris, and was once surrounded by meadows, including the famous 'Pré-aux-Clercs'. The nave is said to belong to an edifice of 1001-1014, but the style is rather that of the end of the 11th century. The choir, consecrated in 1163, was afterwards altered, particularly in the windows, which show a tendency to Gothic. During the Revolution the church was used as a saltpetre-manufactory, and fell into a very dilapidated condition, but it was restored in 1824-36.

The INTERIOR was redecorated in 1852-61. To the right of the principal entrance is a marble statue of the Virgin, called 'Notre Dame la Blanche', dating from the 14th century.

NAVE. The admirable *Mural Paintings were executed by *Hippolyte Flandrin* (d. 1864) and other masters under his superintendence. There are twenty on each side, placed in pairs over the arches, representing parallel scenes from the Old and New Testament. On the left side of the entrance: the Burning Bush and the Annunciation; the Promise of a Redeemer and the Nativity; the Prophecy of Balaam and the Adoration of the Magi; the *Passage of the Red Sea and the Baptism of Christ; Melchisedek's offering of bread and wine to Abraham and the Institution of the Eucharist. — On the other side, returning towards the entrance: the Sale of Joseph and the Betrayal of Christ; the Offering of Isaac and the Death of Christ; Jonah issuing from the whale's belly and the Resurrection; the Scattering of the nations and the Dispersal of the apostles. — Above are figures from the Old Testament, on a golden ground.

The CHOIR is embellished with two large paintings on a golden ground, also by *Flandrin*: on the left the Entry of Christ into Jerusalem; on the right the Bearing of the Cross. Then, above the arcades, the Prophets and Apostles, and the angel, lion, bull, and eagle, the symbols of the Evangelists.

In the N. TRANSEPT are paintings by *Cornu* (d. 1871), more recently executed, representing on the right Christ among the children, the Mission of the apostles, the Transfiguration, and the Descent into hell; and on the left the Finding of the Cross.

The S. TRANSEPT contains, on the right, the tomb of *Olivier* and *Louis de Castellan* (d. 1644, 1699), by *Girardon*. To the left, above the altar, is a marble statue of St. Margaret, by *J. Bourlet* (1705).

CHOIR CHAPELS. The second chapel on the right contains the monument of *James, Duke of Douglas* (d. 1645). — The following chapel contains slabs of black marble to the memory of the philosopher *Descartes* (d. 1650) and the learned *Mabillon* (d. 1707) and *Montfaucon* (d. 1641). — Behind the high-altar is the modern Chapel of Notre-Dame, with painted reliefs of the Adoration of the Magi and the Presentation in the Temple. — In the chapel of SS. Peter and Paul is the monument of the poet *Boileau* (d. 1711), whose remains were brought here from the Sainte-Chapelle. — The following chapel contains a second monument of the *Douglas* family.

The N. AISLE contains a statue of St. Francis Xavier, by G. Cous-tou, and the monument of *Casimir V.* (d. 1672), king of Poland, who was at first a Jesuit, then a cardinal, and in 1648 succeeded his brother on the Polish throne, but abdicated in 1668 and resumed his cowl as abbot of St. Germain-des-Prés. By the wall, opposite the pulpit, is the monument of *Hippolyte Flandrin* (d. 1864), painter of the frescoes mentioned above.

Behind the church of St. Germain is the *Palais Abbatial*, dating from the latter half of the 16th cent., a relic of the ancient Abbey. It is in private possession. The *Abbey Prison*, notorious for the massacres of Sept. 1792, was situated farther back, on a site now traversed by the Boulevard St. Germain.

The grounds surrounding the church are embellished with a bronze *Statue of Bernard Palissy* (p. 143), by Barrias.

The S. side of the church adjoins the Boul. St. Germain (p. 226), in which is a *Statue of Diderot* (1713-84), in bronze, by Gautherin. To the S.W. runs the handsome *Rue de Rennes*, leading to the Gare Montparnasse (p. 262). We continue to follow the Rue Bonaparte, to the left, and in a few minutes reach the *Place St. Sulpice*.

***St. Sulpice** (Pl. R, 19; IV), situated in the Place of that name, is the richest and one of the most important of the churches on the left bank of the Seine. The rebuilding of the church was begun in the reign of Louis XIV. and finished in 1749, chiefly after the plans of *Servandoni*.

The church is remarkable for its imposing dimensions (length 462 ft., width 183 ft., height 108 ft.). The façade, which is considered one of the best of the early part of the 18th cent., consists of a Doric and an Ionic colonnade, placed one above the other. It is flanked with two towers, the highest of which, rebuilt by Chalgrin, and 224 ft. high, is alone finished. The chief portal is approached by five flights of steps, divided by the bases of the columns.

The INTERIOR consists of nave, aisles, transept, and eighteen lateral chapels. The spherical vaulting is borne by Corinthian pillars. Adjoin-

ing the second pillar are bénitiers consisting of two enormous shells (*tridachna gigas*), presented to Francis I. by the Republic of Venice, resting on rock-work of marble designed by *Pigalle*. The church contains in different oil-paintings by *Van Loo*; the chapels interesting frescoes.

RIGHT AISLE. 1st Chapel: Jacob wrestling with the Angel; Heliόδorus expelled from the Temple; on the ceiling St. Michael; all by *Eugène Delacroix* (1861). — 2nd Chapel: Religion solacing a dying man; Efficacy of prayer for the dead; by *Heim*. — 3rd Chapel: St. Roch praying for the plague-stricken; Death of the saint in the prison of Montpellier; by *Abel de Pujol* (1821). — 4th Chapel: Scenes from the life of St. Maurice; by *Vinchon* (1822). — 5th Chapel: Marble monument of the curé Languet (d. 1870), by *Stodtz*.

LEFT AISLE. 1st Chapel: St. François Xavier resuscitating a dead man, and Miraculous cure of sick persons at the burial of the saint, by *Lafon* (1859). — 2nd Chapel: St. François de Sales preaching in Savoy, and Ste. Chantal receiving from the saint the constitution of a new order of nuns, by *Hesse* (1860). — 3rd Chapel: St. Paul's Conversion, and St. Paul in the Areopagus, by *Drolling* (1850). — 4th Chapel: St. Vincent de Paul recommending foundlings to the care of sisters of charity, and the saint at the death-bed of Louis XIII., by *Guillemot* (1825).

TRANSEPT. Left arm: Betrayal by Judas, and the Crucifixion. Right arm: Resurrection and Ascension, and Prophets. These are all by *Signol* (1874-76). On the pavement here a *Meridian Line* was drawn in 1743, with the signs of the zodiac. It is prolonged to an obelisk of white marble which indicates the direction of due north, while towards the S. it corresponds with a closed window, from a small aperture in which a ray of the sun falls at noon on the vertical line of the obelisk.

CHOIR CHAPELS, N. or left side. 1st: Martyrdom and Triumph of St. John the Evangelist, by *Glaize* (1859). — 2nd: S. Carlo Borromeo at a procession during the plague at Milan, and The saint administering the last sacraments to Pius IV., his uncle, by *Pichon* (1867). — 4th: St. Louis, king of France, carrying a dying man during the plague, and The king administering justice under the oak of Vincennes, by *Matout* (1870). — Above the side-entrance: Death of the Virgin, by *Bin* (1874).

CHOIR CHAPELS, S. or right side. 1st: St. Denis preaching to the heathen Romans, and Condemnation of the saint, by *Jobbé-Duval* (1859). — 2nd: St. Martin dividing his cloak with a beggar, and The saint resuscitating a dead man, by *Motter* (1863). — 3rd: Ste. Geneviève succouring Troyes (Champagne), and Miracles wrought by her relics during a procession, by *Timbal* (1864). — 4th: Nativity of the Virgin, and Her presentation in the Temple, by *Lenepveu* (1864). — Above the door of the Sacristy: Assumption, by *Bin* (1874).

The statue of the Virgin in the chapel behind the high-altar, by *Pajou* (d. 1809), is lighted from above. The fresco of the Assumption on the dome is by *Lemoine* (d. 1737). The statues of St. Paul and St. John by the sacristy are by *Pradier*; those of the twelve apostles by the pillars of the nave are by *Boucardon*. — The pulpit is supported solely by the steps which ascend to it. The fine organ, originally built by Cliquot and reconstructed by Cavaillé-Coll, has 6 keyboards, 118 stops, and about 7000 pipes. The organist, M. Widor, is one of the best in Paris, and the choir has a reputation for its 'plain song'.

The PLACE ST. SULPICE in front of the church is adorned with the handsome *Fontaine St. Sulpice*, designed by *Visconti*, and erected in 1847. The fountain consists of three concentric basins, one above the other, and is embellished with statues of the four most celebrated French preachers: Bossuet (d. 1704), Fénelon (d. 1715), Massillon (d. 1742), and Fléchier (d. 1710). The long building on the S. side of the Place is the *Séminaire de St. Sulpice*, for the education of priests. On the W. is the *Mairie of the 6th Arrondissement*; the ceiling-painting in the Salle des Fêtes is by Lévy.

The Rue Férou, to the left of this building, leads straight to the *Musée du Luxembourg* (p. 255). Or we may follow the Rue St. Sulpice, to the left of the church, and take the Rue de Tournon, the second cross-street to the right, which ascends to the Palais du Luxembourg.

III. PALACE, GALLERY, AND GARDEN OF THE LUXEMBOURG.

1. Palais du Luxembourg.

The *Palais du Luxembourg* (Pl. R, 19; IV) was erected in 1615-20 for *Marie de Médicis* by *Jacques Debrosse*, one of the ablest French architects of the beginning of the 17th century. It occupies the site of the old Hôtel de Luxembourg, a mansion from which it derives its name. It bears some resemblance to the palaces of Florence, and particularly to the court of the Pitti Palace, *Marie's* ancestral home, but is at the same time an unmistakably French creation. The principal façade, which notwithstanding many restorations still reveals the original design, looks towards the Rue Vaugirard on the N. side, opposite the Rue Tournon. It is nearly 100 yds. in width, and consists of three pavilions connected by galleries. Each of the three stories is adorned with pillars. Important alterations, the chief of which was the addition of the columns in the court, were made by *Chalgrin* in 1804, by order of Napoleon I. The façade towards the garden, formerly similar to the principal front, was restored under Louis Philippe in 1836-44 by *A. de Gisors*, who adhered as far as possible to the style of the original building.

The palace continued to be a royal residence down to the Revolution. Its last occupant, the Count of Provence, afterwards Louis XVIII., left it in June, 1791. The Convention converted it into a state-prison. In 1795 the building was named the *Palais du Directoire*, and afterwards, in 1799, the *Palais du Consulat*. The Consulate, however, sat here for a short period only, as Bonaparte removed his residence to the Tuileries in February, 1800.

During the first Empire the palace was occupied by the senate, and styled *Palais du Sénat-Conservateur*. After the Restoration, and under Louis Philippe, the *Chamber of Peers* met here. From 1852 to 1870 it was named *Palais du Sénat*, that body having again sat here during the second Empire. It was next occupied by the offices of the Préfet de la Seine, after the destruction of the Hôtel de Ville; but in 1879, on the return of the Chambers to Paris, the senate resumed its old quarters here. The president of the senate resides in the wing called the *Petit-Luxembourg*, to the right of the principal façade. This wing too, was probably built for *Marie de Médicis*. Adjoining it was a convent of Filles du Calvaire, the Renaissance chapel of which (1625) is seen from the Rue de Vaugirard.

Part of the palace is occupied by the *Musée du Luxembourg*, which is open to the public daily, except Mondays (see p. 255);

the rest of the building is shown daily, except Sundays and during the sittings of the senate, from 9 a.m. till dusk. We cross the court to the foot of the staircase in the corner to the left, where one of the custodians is to be found (gratuity). We are first escorted to the first floor. The rooms on the left are used by different committees of the senate. We obtain a glimpse only into the *Library*, the dome of which is adorned with fine paintings by Eugène Delacroix, representing the infernal regions according to Dante. — The **Salle des Séances* (to which visitors are admitted during the sittings of the senate by tickets obtainable through a senator or on written application to the 'secrétaire de la questure') is one of the most interesting apartments. During the sittings the entrance is by the platform in the middle, at the end of the court, and if the sitting is not of special importance, visitors may sometimes obtain admission here without a ticket. This chamber, which is lighted from above, consists of a small semicircular part, occupied by the president, and a larger part, of the same form, containing the seats of the senators. The 'tribune' is in front of the president's desk. The colonnade at the back is adorned with statues of Turgot, d'Aguesseau, l'Hôpital, Colbert, Molé, Malesherbes, and Portalis. On each side of the president's seat is a painting by Blondel: the peers offering the crown to Philip le Long, and the estates of Tours conferring on Louis XII. the title of 'father of the people'. At the beginning of the larger semicircle is a statue of Charlemagne, by Etex, and one of St. Louis by Dumont. Facing the seat of the president are two public galleries. — We are next conducted to the *Gallery of Busts*, and to the *Buvette*, formerly the room of Napoleon I., which contains the paintings which adorned it at that period (the chancellor del'Hôpital returning the seals to Charles IX.; Achilles de Harlay rejecting the proposals of the Duc de Guise; Charlemagne; St. Louis; Louis XIV.). Adjoining the gallery and the buvette is the **Salle des Pas-perdus*, formerly the Salle du Trône. The handsome modern decorations in the Louis XIV. style were executed in 1856-80. On the vaulting, in the centre, the Apotheosis of Napoleon I. by Alaux; at the sides, Peace and War, by Brune; at the ends, the Apotheosis of the kings of France, by Lehmann. Handsome chimney-piece of 1880. — The *Grande Galerie*, formerly occupied by the Musée du Luxembourg (p. 255), on the first floor of the E. wing, has a ceiling adorned with an Aurora by Callet (18th cent.) and the Months by Jordaens. — Descending to the ground-floor, we visit, in the W. part of the palace, the small **Chambre de Marie de Médicis*, adorned with paintings by pupils of Rubens. The medallions on the walls are attributed to Van Thulden and Van Huden. The Apotheosis of the queen and other ceiling-paintings are by Hoeck. — The *Chapel*, on the same side, dating from the reign of Louis Philippe, is also richly decorated. Opposite the windows are paintings by Gigoux. Behind the altar are the

twenty-four Elders of the Apocalypse, by Abel de Pujol. Under the organ is a group of angels, by Jaley.

2. Musée du Luxembourg.

The Luxembourg Gallery is open daily, except Mondays, 10-4, and in summer 9-5 o'clock; on Sundays and holidays 10-4 only.

The **Musée du Luxembourg*, a collection of *Works of Living Artists*, consisting of paintings, sculptures, drawings, engravings, and lithographs, has since 1886 occupied a new building to the W. of the Petit-Luxembourg, on the left side of the Rue Vaugirard. At the foot of the staircase, to the right, Orpheus charming Cerberus to sleep, to the left, Phaeton, bronzes by *Peinte* and *Houssin*. On the pediment, Fame distributing crowns to the plastic arts, by *Crauk*. The works of the most distinguished masters are generally transferred to the Louvre, or sent to provincial galleries, about ten years after their death; so that a comprehensive survey of modern French art cannot be obtained in one place.

The arrangement of the works is so often changed that to prevent confusion we shall enumerate the most important of them in the alphabetical order of the names of the artists, that being also the order in which they are arranged in the catalogue (45 c.). Each work bears the name of the artist.

SCULPTURES.

331. *Aizelin*, Psyche. 332. *Allar*, Death of Alceste. 332^{bis}. *Aubé*, Bailly (bronze).

333, 334. *Barrias* (*L. E.*), Young girl of Megara; Mozart (bronze). 335, 336. *Becquet*, Ishmael; St. Sebastian. 339. *Bonnassieux*, Meditation.

341, 342. *Carlès*, Youth; Abel. *343. *Carrier-Belleuse*, Hebe asleep. No number, *Carlier*, Gilliatt seized by the octopus. *344, 345, 345^{bis}. *Cavelier*, Truth; Mother of the Gracchi; Neophyte. 346, 347. *Chapu*, Mercury inventing the caduceus; Joan of Arc at Domrémy. 348. *Chatrousse*, Girl reading. 349. *Christophe*, Fatality, a group in bronze. 352. *Cordonnier*, Joan of Arc. 353. *Coutan*, Cupid. 355. *Crauk*, Youth and Love. 356. *Croisy*, The nest.

357. *Dampt*, St. John. 360, 361, 362. *Delaplanche*, Eve after the Fall; Love's Messenger; Dawn. *364, 365, *366. *Dubois*, Infant St. John, in bronze; Narcissus; Florentine singer of the 15th cent., bronze gilt.

368. *Etez*, St. Benedict rolling himself on thorns.

*369, *370. *Falguière*, Tarcisius the Martyr; The victor in a cock-fight, in bronze. 471. *Franceschi*, Fortune. 375, 376. *Frémiet*, Wounded dog, in bronze; Pan with a bear.

No number, *J.-L. Gérôme*, Tanagra, painted marble; 378, 379. *Guillaume*, Anacreon; the Gracchi, bronze.

381, 382. *Hiolle*, Narcissus; Arion seated on the dolphin.

383, 384. *Idrac*, Mercury inventing the caduceus; Salammô (from Flaubert).

387. *Lanson*, Age of iron. 389. *Lenoir*, Bust of St. John. 390. *Longepied*, Immortality.

391. *Marcello*, Bianca Capello, bust. 392, 393, and no number, *Marqueste*, Cupid; Galatea; Perseus and the Gorgon. 394, 395. *Mercié*, David, in bronze; Souvenir. *396, *397. *Millet (Aimé)*, Ariadne; Cassandra placing herself under the protection of Athena.

399. *Oliva*, Rembrandt, bronze bust.

401. *Pêtre*, Maréchal, former maire of Metz, bust. 402. *Peynot*, 'Pro Patria'. No number, *D. Puech*, Syren.

404. *Rodin*, St. John, bronze.

406, 407. *Saint-Marceaux*, Youth of Dante; Genius guarding the secret of the tomb. 408. *Salmson (Jean Jules)*, Skein-winder, in bronze. 409. *Schoenewerk*, In the morning.

411. *Thomas*, Virgil. 412. *Turcan*, The blind and the lame.

On the terrace next the garden are a number of bronzes: 415. *Guillaume*, Reaper; 416. *Barthélemy*, Goat-herd; 417. *Injalbert*, Hippomenes; 418. *Maniglier*, Engraver; 419. *Charpentier*, Improvisatore; 421. *Laoust*, Indian singer; 422. *Leroux*, Violet-seller; 423. *Moulin*, Discovery at Pompeii; 424. *Tournois*, Bacchus inventing comedy.

PAINTINGS.

7. *Bail*, Still-life. 10. *Bashkirtseff (Marie)*, The meeting. 12. *Baudry*, Fortune and the child. *20. *Bonheur (Rosa)*, Husbandry in Nivernais, with masterly animals and charming details. *Bonnat*, *21. Léon Cogniet, the painter; *22. Job. 26, *27, *28. *Bouguereau*, Triumph of martyrdom (St. Cecilia); The Virgin as consoler; Birth of Venus. *33, *34, 35. *Breton (J. A.)*, Blessing the crops; Recall of the gleaners; Gleaner. 39. *Butin*, Burial of a sailor in Normandy.

40, *41. *Cabanel*, Tamar; Birth of Venus. *Carolus-Duran*, 44. Lady with a glove; no number, Lilia. 45. *Carrier-Belleuse (L. Rob.)*, Asphalt-workers. 46. *Cazin*, Ishmael. 48. *Chaplin*, Souvenirs. 51. *Chenavard*, Divine tragedy. 52. *Collin*, May ('Floréal'). 53. *Comte*, Henri III. and the Duo de Guise, on their way to Communion on the eve of the latter's assassination. 54. *Constant*, The last rebels. 55, *56. *Cormon*, Cain; Victors at Salamis. 57. *Cot*, Mireille. *58. *Courbet*, Landscape.

62. *Dagnan-Bouveret*, The sacred wafer. 65. *Dantan*, Studio. 67. *Dawant*, Children's masterpiece. 68. *Defaux*, Harbour of Pont-Aven (Finistère). 70, *71, 72. *Delaunay*, Communion of the Apostles; Plague at Rome; Diana. 75. *Demont-Breton*, Beach. 77. and no number, *Desgoffe*, Still-life. 80. *Detaille*, The Dream. 81. *Didier*, Husbandry on the ruins of Ostia. 84. *Duez*, St. Cuthbert, a triptych. 87, 88, *Dupré*, Morning; Evening.

92. *Edelfelt*, Divine service on the sea-shore.

93. *Falguière* (the sculptor), Fan and Dagger. 95. *Feyen*, Gleaners of the sea. *96. *Feyen-Perrin*, Oyster-fishers. No number, *Fouace*, 'Ma Pêche'. 102, 104. *Français*, End of winter; Daphnis and Chloe. 105. *Friant*, All Saints' Day.

*111. *Georges Bertrand*, Fatherland. 112. *Gérôme*, Cock-fight. 113. *Gervex*, Satyr and Bacchante. 114. *Giacomotti*, Rape of Amy-mone. 281. *Gilbert*, Renovating tapestry (crayon). 119. *Glaize*, Ancient Roman ceremony. 121-123. *Guillaumet*, Evening-prayer in the desert; Laghouat; Segua, in Algeria. 124. *Guillemet*, View of Bercy in winter.

127-128. *Hanoteau*, Landscapes. 129-131. *Harpignies*, Landscapes. 132-134. *Hébert*, Malaria; The kiss of Judas; The Cervarolles (Roman Campagna). 137-139. *Henner*, The chaste Susanna; The Good Samaritan; Naiad. 140. *Herpin*, View of Paris from the Pont des Saints-Pères, evening. 142. *Humbert*, Madonna with the Infant Christ and John the Baptist.

142. *Isabey*, Embarkation of De Ruyter and De Witt.

*145. *Jacomin*, View of the Forest of St. Germain.

151. *La Boulaye*, Sermon in the Bresse. 158, *159. *Laurens* (J. P.), Excommunication of King Robert of France; Deliverance of the prisoners of Carcassonne. 162. *La Vilette* (Mme.), Coast-scene, near Lorient. *165. *Lefebvre* (Jules), Truth, a beautiful figure, but a portrait rather than a type. 170. *Leleux* (Arm.), Protestant wedding. 171. *Lenepveu*, The Martyrs in the Catacombs. 172. *Lerolle*, In the country. 175. *Lévy* (E.), The Meta Sudans in Rome. 188. *Lévy* (H.), Body of Sarpedon brought to Jupiter. 179. *Lhermitte*, Reapers' pay-day.

180. *Maignan*, Dante meeting Matilda. *183. *Meissonier*, Napoleon III. at Solferino, a good example of this master, who excels in individualising his figures within a very limited space. 184. *Melida*, Churching-service in Spain. 185. *Mélingue*, Etienne Marcel, the 'prévôt des marchands', saving the life of the Dauphin (Charles V.) by changing caps with him (1358). 186. *Mercié*, Venus. 191. *Montenard*, The transport 'Corrèze' leaving Toulon. *193. *Moreau*, Greek maiden with the head and lyre of the murdered Orpheus. 194. *Morot*, Rezonville. 195. *Mosler* (H., an American artist), 'Le Retour'.

200. *Neuville* (A. de), 'Le Parlementaire'.

*206. *Perret*, Priest bearing the Viaticum to a dying man, a scene in Burgundy. 208. *Protais*, Battalion in square (1815).

211. *Raffaelli*, At the melter's. 217-220. *Ribot*, St. Sebastian; The Samaritan; Jesus and the Doctors. 221-223. *Robert-Fleury* (J. N.), Conference at Poissy, in presence of Catherine de Médicis and Charles IX. (1561); Galileo before the Inquisition; Columbus after his return from America. *225. *Robert-Fleury* (Tony), Last Days of Corinth, a thoughtful composition, full of dramatic sen-

timent. 226, 227. *Roll*, Forward; Scene in Normandy. 229-231. *Rousseau* (*Ph.*), Rat retired from the world; Sleeping storks; Goat eating flowers.

*233, 234. *Salmson* (*H.*), An arrest in Picardy; Swedish landscape. 235. *Sautai*, Eve of an execution (Rome).

244. *Tassaert*, Distressed family. 246. *Thirion*, Finding of Moses. 247. *Tissot*, Faust and Margaret. 248. *Trayer*, Vendor of cakes at the fair of Quimperlé.

250. *Vernier*, Landscape. 252, 253. *Vollon*, Curiosities; Fish. 254, 255. *Vuillefroy*, Return of the flock; In the meadows.

255bis. *Weerts*, Death of Jos. Bara.

260, 261. *Ziem*, Views of Venice. 264. *Zuber*, Hollandsch Diep.

3. Jardin du Luxembourg.

The ***Garden of the Luxembourg** (open daily from early morning till 10 or 11 p.m.), laid out by *Jacques Debrosse*, the architect of the Palais, is the only remaining Renaissance garden in Paris, resembling, with its marble fountains, balustrades, and steps, the famous Boboli garden at Florence. A military band plays here, to the left under the trees, in summer on Tues., Frid., and Sun., from 4 to 5, or from 5 to 6 (comp. p. 33).

The ***Fontaine de Médicis**, by *Debrosse*, in the Doric style, with imitations of stalactites, rises to the left, not far from the gate. Three niches between the columns contain sculptures by *Ottin*; the group in the middle represents Polyphemus surprising Acis and Galatea. At the back of this fountain is a 'Fontaine de Lédæ'. — To the left of the long basin of the fountain are a marble group of Adam and his family, by *Garraud* (1851), and a figure of Bacchus, by *Crauk*.

In the centre of the garden, in front of the palace, is a large flower-bed, embellished with a fountain, consisting of a basin with a group of children. Adjoining the fountain rise two columns in speckled Italian marble, bearing a David, the conqueror of Goliath, and a Nymph, Italian works of the 16th century. In the vicinity are an Archidamas about to throw the disc, by *Lemaire*, and copies of the Borghese Gladiator and the Diana of Versailles ('Diana à la biche').

The terraces around the parterre are embellished with twenty modern statues in marble (brought from the Parc of Sceaux, p. 337), of celebrated Frenchwomen, the stiffness of which does not harmonise well with the garden. The best are Clémence Isaure, by *Préault*, and Mlle. de Montpensier, by *Demesmay*, at the end, to the left (bearing inscriptions). A little farther on, Velleda, by *Maindron*, from the 'Martyrs' of Châteaubriand, and Eloa, from Alf. de Vigny, by *Pollet*. Among the other statues in this part of the garden are the Mask-seller, by *Astruc*, in bronze, and a Dancing Faun, in bronze, by *Lequesne*, by the railing near the Panthéon.

The dome-covered building visible at the end of the avenue leading from the basin is the Observatory (see p. 260). To the right is the 'Jardin Anglais', occupying the site of the old 'pépinière', or nursery, and to the left is the new Orangery, beyond which rises the Ecole des Mines (see below).

The parterres of the W. side are also embellished with statuary. Thus, in the Jardin Anglais: (side next the railing) Lion subduing an ostrich, by *Caïn*; Wrestlers, by *Ottin*; (side next the palace) Orlando Furioso, by *Du Seigneur*; all in bronze; Eustache Le-sueur, by *Husson*; at the end of the same avenue, Charity, by *Petitot*; nearer the Rue de Vaugirard, Bathsheba, by *Moreau Vauthier*; Faun playing with a panther, by *Caillé*; etc.

Between the Musée and the Palais rises the new *Monument of Eugène Delacroix* (1798-1863), the painter, by Dalou. It consists of a fountain with a bronze bust, and bronze figures of Time bringing fame to the artist and the Genius of Art applauding him.

In the vicinity, No. 70 Rue de Vaugirard, is *St. Joseph-des-Carmes*, the former chapel of the monastery notorious for the massacres of Sept. 1792. The crypt (open on Frid.) still shows traces of these atrocities and contains the tombs of the victims. Adjoining is the *Institut Catholique*, a kind of free university, established in 1875.

IV. FROM THE LUXEMBOURG TO THE CEMETERY OF MONT-PARNASSE.

Continuing to ascend the Boul. St. Michel beyond the Luxembourg Garden, we pass on the right the **Ecole Supérieure des Mines**, which possesses a valuable **Musée de Minéralogie, de Géologie, et de Paléontologie* (open on Tues., Thurs., and Sat., 11-3). The entrance is from the platform in the centre. The staircase is adorned with paintings of places of geological celebrity, by *Hugard*.

The mineralogical and geological collections occupy sixteen rooms on the first floor. The glass-cases are numbered from the S. end (left on entering), and the principal objects are all labelled. The first section is devoted to geology, and round the rooms are exhibited natural products utilised in manufactures. The mineralogical collection is classified in the order of the composition of the specimens, beginning with silica and ending with the metals. — The two small rooms adjoining the entrance and a third beyond the staircase to the second floor make a small mineralogical museum of themselves, forming a 'résumé' of the large collection.

The palæontological collection, on the second floor, is arranged zoologically, and contains many interesting and valuable curiosities.

The garden of the Luxembourg has of late been considerably reduced in extent. The triangle which it formed to the S. and S.W. of the Ecole des Mines has been separated from it, and laid out in streets. The central *Allée de l'Observatoire*, however, has been reserved and converted into a promenade, embellished with columns bearing vases, and with marble groups of the Dawn by *Jouffroy*, Day by *Perraud*, Twilight by *Crauk*, and Night by *Gumery*. On the right is the *Petit Lycée Louis-le-Grand*, a 'dépendance' of the old lyceum behind the Sorbonne (p. 236). Farther on are the *Ecole de Pharmacie* and the new *Clinique d'Accouchement*.

At the S. end of the promenade rises the handsome **Fontaine de l'Observatoire* or *du Luxembourg* (Pl. G, 19), erected in 1874 from designs by *Frémiet*, adorned with eight sea-horses, a group of four allegorical figures bearing an armillary sphere, by *Carpeaux*, and water-spouting dolphins and tortoises. To the E. is the cupola of the Val-de-Grâce (p. 241).

The *Statue of Ney*, to the left of the CARREFOUR DE L'OBSERVATOIRE (Pl. G, 19), marks the spot where the marshal was shot on 7th Dec., 1815, in accordance with the sentence pronounced by the Chamber of Peers on the previous evening. The statue in bronze, by *Rude*, erected in 1853, with its forced attitude and open mouth, is not a successful work. At the back of this monument is the *Bal Bullier* (p. 34). — The *Avenue de l'Observatoire*, the continuation of the Allée of that name, leads to the observatory.

The *Observatoire* (Pl. G, 19, 20), an institution of great reputation, occupying a building which has repeatedly been enlarged, was founded in 1672. The meridian of Paris runs through the centre of the building, and the latitude of the S. façade is held to be that of Paris. The copper dome, to the left, containing a large parallax telescope, is 42 ft. in diameter, and is constructed so as to revolve round its vertical axis. The observatory is in telegraphic communication with the most important of the other observatories in Europe. None but scientific visitors are admitted to the interior, which is very completely fitted up. The *Musée Astronomique*, on the second floor, is shown on the first Saturday of each month, by permission of the director (obtained on written application). The vaults below the building, as deep (90 ft.) as the latter is high, are used for experiments on the heat of different bodies.

In front of the façade is a *Statue of Le Verrier* (1811-77), the astronomer, by Chapu. A bronze statue of *Arago* (1786-1853), by Oliva, is to be placed in the gardens to the S.

From the Carrefour we follow, to the right, the *Boulevard Montparnasse*, which leads to the station of that name, crossing the *Boulevard Raspail*, which when complete will run from the Boul. St. Germain (Pl. R, 17; IV) to the Place Denfert-Rochereau (p. 242), skirting the Cemetery of Montparnasse. In this street, to the left, at the corner of the Boulevard Edgar-Quinet, is a bronze statue, by Morice, of *Raspail* (1794-1878), the famous chemist and democrat.

The *Cemetery of Montparnasse*, or *Cimetière du Sud* (Pl. G, 16), has its principal entrance in the Boulevard Edgar Quinet. This is the third of the great Parisian burial-grounds. It was laid out in 1824, but is uninteresting compared with the cemetery of Père Lachaise, and even with that of Montmartre. — The Rue des Plantes (formed 1890) traverses the cemetery between two walls (pierced with two gates on each side), beginning near the principal entrance, and is continued to the Square de Montrouge (p. 243) and thence to the fortifications.

The cemetery is divided by walks into large oblong plots, so that the visitor will easily find his way.

Near the entrance, on the right: family of *Henri Martin* (d. 1833), the historian; a small pyramid enriched with palms and terminating in a star. Behind it, a space enclosed by a railing is the burial-place of the sisters of charity, among whom lies *Sœur Rosalie Rendu*, who was decorated by the Legion of Honour in recognition of her devoted labours in the Crimea. *General Petit* (d. 1863), sarcophagus with column and bronze bust, by Boitel. — At the beginning of the Avenue du Nord, to the right, *Pierre Larousse* (d. 1875), author of the 'Dictionnaire Universel du 19ième siècle', a handsome monument with a bronze bust.

In the main walk, at the corner to the left, *Léontine Spiegel*, with a statue in white marble; farther on, *Héloïse Loustal* (d. 1855), also with a statue. At the corner, before we reach the second walk beyond the last monument: *Henri Grégoire* (d. 1831), deputy to the States General, one of the first of the clergy who swore fidelity to the new constitution in 1790, afterwards Bishop of Blois, member of the Council of Five Hundred in 1795. In 1815 he was deprived of his bishopric by Louis XVIII., and excluded from the Institut (p. 244), of which he was a member, and on his death the Archbishop of Paris refused his remains Christian burial, as he had declined to retract his oath.

At the Rond-Point, on the right: *Desenne* (d. 1827), designer, a bronze bust; *Orylla* (d. 1853), the physician, with a medallion. — Farther back, *Boyer* (d. 1833), surgeon, with bust.

Farther up, to the right of the principal avenue: *Chaudet* (d. 1810), sculptor, a handsome chapel; *Mme. de Gary* (d. 1876), statue by H. de Vauréal. On the other side, among the trees, near the circular avenue: *Rude* (d. 1855), sculptor, with a bust and basrelief; *Gérard* (d. 1837), painter, pyramid with a medallion and basreliefs. In the same plot is a handsome pseudo-Gothic chapel, without an inscription.

Transverse avenue on the same side, on the left: *Ottavi* (d. 1841), deputy, with a bust. Opposite the Avenue de l'Est: *H. de Mylius* (d. 1866), general; a large monument with a bust in bronze. Farther up, to the right: *Le Verrier* (d. 1877), the astronomer. Opposite is the tasteful *Chapelle Bingham*. The Allée Raffet, to the right, also contains some interesting monuments.

The newer part of the cemetery, on the other side of the Rue des Plantes (p. 260; entrance by the gates at the end of the Avenue du Nord), formerly used for Concessions temporaires (p. 177), contains few monuments. Near the entrance, to the right of the avenue, *J. Moulin*, French consul in Saloniki (murdered in 1876). Towards the centre rises a large monument to *Soldiers* who have died in defence of France. Opposite is one to *Firemen* who have perished in the execution of their duties. Behind the former, in the Avenue Thierry, to the right: *Valentin* (d. 1879), prefect of Strassburg, with bronze bust. Adjacent are the pleasing monuments of two ladies (Elisa, Hélène). In receding the same avenue, to the right: *Col. Herbing* (d. 1886); bust and relief by Etex.

We return to the older part of the cemetery, and follow the Avenue du Nord. On the right: *Th. Olivier* (d. 1853), founder of the Ecole Centrale des Arts et Manufactures, with a medallion. Towards the end, on the left: *Jacques Lisfranc* (d. 1847), surgeon and professor, with a bust and reliefs. Opposite, beyond a public 'Caveau Dépositaire', *Dumont* (d. 1834), the sculptor; pyramid, with bust by Thomas. Adjacent: *Perraud* (d. 1876), the sculptor, with a bust; *Comte de Gaspari* (d. 1879), consul in Venezuela, with a bronze bust.

Then, in the Avenue de l'Est, on the right: *Hipp. Lebas* (d. 1867), architect; *Boulay de la Meurthe* (d. 1840), member of the Council of Five Hundred, president of the legislative section of the Conseil d'Etat, and minister under Napoleon I., with a bust by David; *Boulay* (d. 1858), son of the last, deputy, vice-president of the republic in 1849, president of the Conseil d'Etat, and senator.

On the left side rises a rock with a medallion, marking the grave of *Aug. Dornès*, 'représentant du peuple', who was killed by the insur-

gents in June, 1848. — At the end of the Avenue de l'Est, to the right: **Collard-Bigé* (d. 1871), a tasteful Renaissance temple with a statue by Franceschi. Adjacent: *Duban* (d. 1872), architect, with a medallion; opposite, *Caruelle d'Aligny* (d. 1871), painter; bust by Etex.

The Avenue du Boulevard, skirts the W. side of the *Cimetière Israélite* (closed on Sat.), which contains several handsome chapels. — Opposite the entrance of this cemetery: *Fr. Huet* (d. 1869), author, with a medallion.

In the Avenue de l'Ouest, near the middle, on the right: *Dumont d'Urville*, a distinguished admiral, who, after having circumnavigated the world several times, perished with his wife and only son by an accident on the Versailles railway in 1842; a grotesque, painted monument, with scenes from his voyages. — In the upper part of the avenue, on the left: *Mme. Grados* and her daughter (d. 1867), with an angel holding the inscription, 'Ne cherchez pas ici'.

On quitting the cemetery we may return to the centre of the town by the Carrefour de l'Observatoire (p. 260) and the Boul. St. Michel, or we may follow the Boul. Montparnasse farther to the W. and return by the Rue de Rennes (p. 251). On the right, in the last-named boulevard, stands the church of *Notre-Dame-des-Champs*, built in 1867-75 in a spurious Romanesque style. To the left is the *Gare Montparnasse* (Pl. G, 16), which somewhat resembles the Gare de l'Est (p. 185).

11. From the Louvre to the Jardin des Plantes and the Gobelins.

I. FROM THE LOUVRE TO THE JARDIN DES PLANTES.

Saturday is the only day on which it is possible to visit both the Jardin des Plantes, with its galleries, and the Gobelins. As the latter are closed at 3 p.m., the best plan is to interrupt the visit to the Jardin des Plantes and return to it later. On Wed. the Natural History Galleries are closed, while on the other days of the week there is no admission to the Gobelins. — Luncheon should be taken before starting, or at the *Café-Restaurant* in the Place Valhubert, at the entrance to the Jardin des Plantes.

The pleasantest way of reaching the Jardin des Plantes is by steamboat (see p. 22). The piers nearest the Louvre are at the Pont des Arts (p. 244) and the Pont Royal (p. 270), on the right bank, and near the *Pont des Saints-Pères* or *Pont du Carrousel*, on the left bank, which connects the Place du Carrousel (p. 149) with the Rue des Sts. Pères. This handsome bridge, constructed in 1832-34 by *Polonceau*, spans the river with three iron arches, and is embellished with colossal statues in stone: Plenty and Industry on the right bank, and the Seine and the City of Paris on the left.

From the steamboat we observe on the left the Louvre and the tower of St. Germain-l'Auxerrois (p. 59), and on the right the Institut (p. 244). Beyond the Pont des Arts the Mounaie lies on the right. We next observe the statue of Henri IV. on the right, and pass under the Pont-Neuf. On the right rises the Palais de Justice; on the left is the Place du Châtelet, with its fountain and theatres. Beyond the Pont au Change the Tribunal de Commerce is on the right, and beyond the Pont Notre-Dame we observe the extensive Hôtel-Dieu on the same side. We next pass under

the Pont d'Arcole. On the left rises the Hôtel de Ville, and on the right, on the other side of the island, Notre-Dame (p. 224). On the left we next observe St. Gervais (p. 64), and in the distance the dome of St. Paul and the Colonne de Juillet (p. 67). We next have the Ile St. Louis (p. 224), on the left and the Cité on the right, passing under the Pont St. Louis. To the right, the Morgue (p. 224). Farther on, the Pont de la Tournelle and the Pont Sully (p. 68). On the right are the Halle-aux-Vins and the Jardin des Plantes. We disembark below the *Pont d'Austerlitz*, which was enlarged in 1884-5 to a width of 100 ft. and is now one of the most important bridges in Paris.

The *Jardin des Plantes*, in the wider sense, is open daily from an early hour till dusk, but the Ménagerie, the Collections, the Hothouses, and the Library are shown at certain hours only. The *Ménagerie* is open daily from 11 to 5 (6 on Sun.) from 1st March to 31st Oct., and from 11 to 4 during the rest of the year. The *Galleries des Animaux Vivants* are open to the public on Tues., 1-4, when the animals are not outside, and also on other days by tickets obtained from the 'Administration' (p. 284). — The *Galleries of Natural History* are open to the public on Sun. and Thurs. 11-3, and on Tues., Frid., and Sat. by ticket. — The *Gallery of Palaeontology* and the *Hothouses (Serres)* are shown by ticket only, the former on Tues., the latter on Tues., Frid., and Sat., 1-4. The *Library* is open daily from 10 to 3, except on Sun. and holidays, and during the vacations (Sept. and a fortnight at Easter). — From the above it will be noted that everything may be seen on Tues.; the tickets, which are readily granted to strangers, are available for 5 persons.

In the **Jardin des Plantes* or *Muséum d'Histoire Naturelle* (Pl. G, R, 22, 25; V), which lies at the E. end of the quarters of the city on the left bank, are concentrated most of the Parisian institutions connected with natural science. Besides the zoological and botanical garden, it comprises natural history collections, laboratories, and a library. Lectures on natural history, to which the public are admitted gratuitously, are also given here in the *Amphithéâtre*, a hall capable of containing 1200 persons. Among the scientific men of European celebrity who have taught here may be mentioned the botanists De Jussieu (Bernard d. 1776, Laurent d. 1836, Adrien d. 1853), the mineralogists Daubenton (d. 1799) and Haüy (d. 1822), and the zoologists Buffon (d. 1788), Lacépède (d. 1826), Lamarck (d. 1829), Cuvier (d. 1832), and Geoffroy St. Hilaire (d. 1844).

The *Jardin des Plantes*, projected in 1626, was founded by *Guy de La-brosse*, one of the most eminent botanists of his time, about 1635, when he laid out the *Jardin Royal des Plantes Médicinales*. After several years of mismanagement by the court physicians, the celebrated *Buffon* was appointed director of the gardens in 1732. He entirely remodelled them, founded collections in every department of natural history, and gave the whole establishment the name of *Jardin du Roi*. Buffon was succeeded by *Bernardin de Saint-Pierre*, who transferred hither the royal menagerie of Versailles in 1793, and opened the library in 1794. The garden was then called *Muséum d'Histoire Naturelle*, by which name it is still officially known. Under Napoleon I. the collections were considerably enlarged. In our own times the garden was long under the charge of *M. Chevreul*, the celebrated chemist and centenarian (1786-1889). The present director is *M. E. Fremy*. In 1805 *Humboldt* presented to the garden a collection of 4500 tropical

plants, brought by him from America, 3000 of which belonged to species hitherto unknown. During the siege of Paris by the Prussians in 1870-71, the garden was seriously injured by the bombardment. Ambulances were established here at that time, and afterwards under the Commune, and when the citizens were driven to extremities by famine, the authorities directed a number of the animals to be sold to the butchers.

The Jardin des Plantes (see annexed Plan) covers an irregular quadrilateral area of 75 acres. On the N.E. side, next the Seine, it is bounded by the *Quai St. Bernard* and the *Place Valhubert*, where the principal entrance is situated; on the S.E. by the *Rue de Buffon*; on the N.W. by the *Rue Cuvier*; and on the S.W. by the *Rue Geoffroy St. Hilaire*, which is prolonged towards the N. by the *Rue Linné*. The gardens are divided into three parts. (1) The *Partie Basse*, which includes the *Jardin Botanique*, extends from the principal entrance in the Place Valhubert to the Galerie de Zoologie at the other end. (2) The *Vallée Suisse*, to the right (N.) of the first, contains the zoological department, or ménagerie. (3) The *Haute Partie*, or pleasure-garden, occupying the N.W. corner of the gardens, consists of an eminence, 80 ft. high, called the *Labyrinthe*.

We shall first describe the 'Vallée Suisse', the second and most frequented of these three parts. The annexed plan will enable visitors to find their way without difficulty. The names of the animals, as well as those of the plants, and their place of origin are marked in each case.

Ménagerie. Entering the gardens from the Place Valhubert, we turn to the right and proceed to visit the 21 cages of the *Animaux Féroces*. [Admission to the houses when the animals are inside, see p. 263.] The surrounding enclosures are occupied by the *Animaux Paisibles*, including numerous antelopes, deer, and other animals of the kind.


A little to the W. of the *Animaux Féroces* is the *Palais des Singes*, or monkey-house, the inmates of which are an unfailing source of amusement. A little farther to the W. are numerous other graminivorous or 'peaceable' animals, and on the left we observe the *Rotonde des Grands Animaux*, containing elephants, a hippopotamus, camels, etc. The elephant, as usual, is the favourite here, but the most generous of his admirers never succeed in satiating his prodigious appetite. — A few paces to the S. of the Rotonde is the *Fosse - aux - Ours*, or bears' den, adjoining the botanical garden. 'Martin', as Bruin is called here, also enjoys an excellent appetite, and understands and obeys the commands, 'à l'arbre!' 'fais le beau!' — To the N. and N.W. of the rotunda, are the cages of the *Birds of Prey*, the *Grande Volière*, or aviary, the *Faisanderie*, and the pavilion of the *Reptiles*, which is specially interesting. Adjacent is the *Crocodile Pond*. Proceeding hence to the S. we reach the Anatomical Gallery (p. 265) on the right, and the basin of the *Otary* or *Sea Lion* (fed at 3 p.m.) on the left. Behind this is the *Orangery*. Farther on are the *Amphithéâtre*, or lecture-hall (to the right of which is Cuvier's house), and the office of the 'Administration', where the tickets mentioned at p. 263 are obtained.

JARDIN DES PLANTES

1: 5000

Mètres

- 1 Petit Labyrinthe
- 2 Labyrinthe
- 3 Botrederie
- 4 Caire du Liban
- 5 Tombeau de Dubouton
- EE Fossés de la Ménagerie



Carte et imprimée par

Wagner et Compagnie, Imp.

The *Labyrinthe*, as the artificial mound at the N.W. corner of the garden is called, is planted with carefully-kept hedges, and intersected by numerous paths. It has been formed almost entirely of rubbish collected from the neighbouring Quartier St. Victor, and is surmounted by a pavilion called the *Gloriette*, the view from which is partly obstructed by the trees. The sun-dial at the top bears the inscription — 'Horas non numero nisi serenas'.

On the N.E. side of the hill is a magnificent *Cedar of Lebanon* (Pl. 4), 10 ft. in circumference, planted here in 1735 by the elder Jussieu, who brought it home from Syria. A little higher up is a monument to the memory of *Daubenton* (d. 1799; Pl. 5), an eminent naturalist and director of the Jardin des Plantes.

A gate beyond the labyrinth leads into the Rue Linné, at the corner of which and the Rue Cuvier rises the *Fontaine Cuvier*, erected in 1840 from designs by Vigoureux. It consists of a niche with a statue of Nature sitting on a lion, and holding a tablet with the inscription '*rerum cognoscere causas*'.

On the other side of the labyrinth are the hothouses for tropical plants (*Serres Tempérées* and *Serres Chaudes*), which are so full that it is impossible to open them unrestrictedly to the public (see p. 263).

***Galleries** (hours of admission, see p. 263). The natural history galleries of the Jardin des Plantes are among the most extensive in existence, though their arrangement has hitherto been unsatisfactory.

GALLERIES OF COMPARATIVE ANATOMY, ANTHROPOLOGY, AND PALEONTOLOGY, to the right as we come from the Ménagerie, a little before the amphitheatre. — The *Gallery of Comparative Anatomy*, a very extensive collection founded by Cuvier, occupies fourteen rooms, three on the ground-floor, and eleven smaller on the first floor.

GROUND FLOOR. Outside the entrance is placed the body of a whale, with the whalebone complete. The 1st and 2nd Rooms on the right contain skeletons of large fish and amphibious animals. The 3rd Room, on the opposite side, by which visitors quit the building, is set apart for the skeletons of large quadrupeds. — The eleven rooms on the FIRST FLOOR contain skeletons and anatomical preparations of all kinds, in spirit, or modelled in wax.

The *Gallery of Anthropology* occupies the thirteen remaining rooms of the first floor. Every variety of the human species is represented here by means of casts, portraits in water-colours, photographs, busts, mummies, and even by fossils.

The 1st Room contains the skeleton of Bébé (d. 1764, at the age of 15), the dwarf of King Stanislaus of Poland, 27 inches only in height. — The 2nd Room contains the phrenological collection of Dr. Gall, including busts, crania, and casts of the heads of celebrated men (Voltaire, Casimir Périer, François Arago, Rousseau) and of notorious criminals. — In the 3rd Room is the skeleton of *Soliman el-Halebi*, the assassin of General Kléber, who was condemned to have his right hand burned and to be impaled. — In the 8th Room a Hottentot Venus. — The last room is connected by a passage with the second room of the previous collection, through which we retrace our steps to the 11th room. We then descend by a staircase to the left, which leads to the exit on the ground-floor.

The court surrounded by the buildings of the collections just named contains the *Gallery of Palaeontology* (adm., see p. 263), which chiefly consists of the fossilised skeletons of such extinct animals as the megatherium, dinornis, glyptodon, mastodon, Irish elk, etc. The Palæotherium Magnum, by the exit-wall, is unique.

The *GALLERIES OF ZOOLOGY were arranged in 1889 in a handsome new building on the W. side of the Botanical Garden. The façade is embellished with a figure of Science in high-relief and medallions of famous naturalists. We enter from the right side. On the ground-floor, in front, is a gallery, behind which is a central hall, 180 ft. long and 85 ft. wide, surrounded by wings, 25 ft. wide. A staircase ascends from each end of the gallery to the upper floor above the latter and above the side-wings.

GROUND-FLOOR: *Mammals, Reptiles, and Fishes*. — 1st Gallery, to the left of the entrance. The first case in the centre, that to the right, and part of that to the left, are occupied with a rich collection of *Quadrupeds*, from the smallest monkeys to gorillas, chimpanzees, and orang-outangs. In the other cases: *Carnivora*; lions, tigers, leopards, and other feline animals, etc.

Central Hall: *Large Mammalia*. — Giraffes, elephants, hippopotami, rhinoceroses, camels, buffaloes, etc. Skeletons of large whales. — Sides. In the half next the garden and the small rooms at the ends: *Mammalia* of various kinds, the most interesting being in the central glass-cases. In the opposite half: *Fish*; dried specimens in the central cases, specimens in spirits in the cases along the wall. — At the foot of the staircase (at the end of the gallery) to the first floor is a bronze statue of the Age of Stone, by Fréminet.

FIRST FLOOR: *Birds, Reptiles, Batrachians, Molluscs, and Zoophytes*. — The Gallery next the garden contains the finest "Specimens of the very rich collection of *Birds*. In the centre are first the smallest species and those distinguished by fine plumage, such as humming-birds, birds of paradise, etc.; then birds of prey. At the sides, climbing birds (parrots, etc.), birds of prey, and nocturnal birds. — Round the hall: next the front gallery, web-footed, wading, and gallinaceous birds. — Cross-gallery next the hothouses, *Mammalia* and a collection of European birds, presented to the museum; collection of *Birds' Nests*. — Other long gallery, *Reptiles*, tortoises, crocodiles, serpents, etc.; frogs. Round the hall: *Molluscs (shells)* and *Zoophytes*.

SECOND FLOOR, not yet arranged: *Insects, Crustacea, etc., Molluscs* preserved in alcohol.

THIRD FLOOR (only on the side next the garden): interesting collection of *Nests of Insects*, such as wasps, hornets, spiders, ants, and illustrations of damage from insects to plants, wood, books, and even metals; silkworm-cocoons; bee-hives. Fine specimens of *Crustacea*: crabs, cray-fish, lobsters, sea-spiders, squillidae, etc.

The GALLERY OF GEOLOGY AND MINERALOGY, with the gallery of botany and the library, occupies the long building beside the galleries just named. — The *Vestibule* contains the collection of the celebrated mineralogist Haüy (1743-1822), who spent forty years in its formation. This room and the ends of the adjoining gallery are adorned with mural paintings of Arctic scenery and various natural phenomena.

The *Gallery*, to the left, is 300 ft. long, and is divided longitudinally into three sections, the sides being higher than the centre. — The *Geological Collection* comprises (1) Varieties of earth, in the

central glass-cases, (2) Rock specimens and (3) Fossils, in the cases in the side corridors, and (4) Geographical collection, in the drawers. — The *Mineralogical Collection* is distributed round the gallery, and is arranged to facilitate the study of the composition of minerals, and the uses to which they may be applied. At the beginning, to the right, and farther on, is the collection of precious stones. — In the centre are statues of *Cuvier*, by David d'Angers, and *Hallé*, by Brion. — The collection of *Meteorolites*, also placed here, is one of the largest in the world. One of the specimens weighs nearly 13 cwt.

The GALLERY OF BOTANY adjoins the preceding and is entered from it. Only a portion of it is open to the public. In the *Vestibule*, with a statue of *Adrien de Jussieu*, by Legendre-Héral, are interesting specimens of *Exotic Plants*, date and other palms, bamboos, sugar-canes, ferns, etc. The collection contains, among other objects, specimens of fruit preserved or imitated in wax, wax models of exotic fruits by Robillard d'Angelle, and of fungi, executed by Pinson, and a collection of fossil-plants, in the glass-cases at the sides. — The herbaria on the upper floor are open to students only. In 1885 the collection was enriched by the herbarium of Lamarck, repurchased from the University of Rostock.

The LIBRARY, in the part of the building next the Ménagerie, contains about 80,000 vols. and a valuable collection of MSS., original drawings, and paintings of flowers and fruit on vellum.

The **Botanic Garden** is divided into quadrangular beds by a number of handsome avenues. Many of the trees and flowers now common in Europe have been introduced and naturalised by the directors of the Jardin des Plantes. Adjoining the Ménagerie is the *Ecole de Botanique*, open daily except Sun. and holidays, 6-11 a. m. and 1-6 p. m. The edible herbs are denoted by green labels, medicinal plants by red, poisonous plants by black, those used in dyeing by blue, and ornamental plants by yellow. At the end next to the quay are the *Aquatic Plants*; and the distribution of the other plants in shown on the accompanying plan. Within the garden is the *Ecole des Arbrisseaux d'Ornement*, which contains the first acacia ('*Robinia pseudacacia*') introduced into Europe. It was brought to France by Robin in 1600, and planted here in 1636. Lastly, a little farther to the E., are the nurseries of apples, pears, nuts, and stone-fruit.

To the S.E. of the Jardin des Plantes is the *Gare d'Orléans* (p. 23); to the N.W. the *Halle aux Vins* (open from 6 a.m. to 6 p.m.); and near the S.W. angle are the large *Hôpital de la Pitié* (709 beds) and the *Prison of Ste. Pélagie*.

II. FROM THE JARDIN DES PLANTES TO THE GOBELINS.

The Gobelins are nearly 1 M. to the S.W. of the Place Valhubert (tramway, see Appx.). We follow the Boul. de l'Hôpital, so called from the *Hôpital de la Salpêtrière* on the left. This vast establishment, originally an arsenal, built by Louis XIII., has been converted

into an asylum for aged and insane women. (Visitors admitted on Sun. and Thurs., 12. 30 to 4 p.m.) In front of the building is a *Statue of Dr. Pinel* (d. 1826), an eminent benefactor of the insane, by Durand. The large amphitheatre of the institution also contains a painting by *Robert-Fleury*, in which Dr. Pinel is represented as delivering the insane from torture.

The Boulevard St. Marcel diverges here to the right, passes the *Horse Market*, and crosses the Avenue des Gobelins. We follow the latter to the left and soon reach the manufactory on the right (No. 42). Tanneries abound in this neighbourhood.

The **Gobelins**, or '*Manufactures de tapisseries des Gobelins et de tapis de la Savonnerie*' (Pl. G, 23), occupy a building which was almost entirely destroyed by the Communists on 25th May, 1871. Some of the most valuable pieces of tapestry in the collection had been removed to a place of safety before the war, but seventy pieces were destroyed. The establishment, though now greatly reduced in extent, is still worthy of a visit. The manufactory is open to the public on Wed. and Sat., 1-3 o'clock. A permission from the manager is, strictly speaking, necessary, but strangers are seldom denied admission. Catalogue unnecessary, as all the works are labelled.

The *Bièvre*, a brook on the left bank of the Seine, traverses the S.E. angle of the city, and falls into the Seine above the Pont d'Austerlitz. In 1450 *Jean Gobelin* erected a dyeing establishment on its banks, and with this his successors combined a manufactory of tapestry. The Gobelins tapestry had acquired so high a reputation by the middle of the 17th cent., that *Colbert*, the minister of Louis XIV., and a great patron of industrial enterprise, bought the establishment in 1662, and caused it to be carried on at the expense of government. In course of time it was found that the manufactory did not pay; but it was believed to exercise a stimulating influence on the national industries of a similar kind, and the government prided itself on being able to produce fabrics of a kind unrivalled in the rest of the world. From a very early period, therefore, these choice manufactures have been excluded from the public market, and have been reserved for the use of the heads of the state and for the decoration of public buildings, or presented as gifts to foreign courts, ambassadors, and other persons of high rank. The same remarks apply to the *Savonnerie*, a carpet-factory founded in 1604 by Marie de Médicis, and so named from having been originally established in a soap-manufactory, but united with the Gobelins in 1826.

The loom resembles that in ordinary use. The small part of the design on which the workman is actually engaged is drawn in chalk on the stretched threads. The picture to be copied is at his side, and in front of him is a basket with wools of every possible colour, each distinct hue being represented by 24 different shades. The reverse side of the tapestry is turned towards the workman.

The work requires the utmost patience and the most practised eye. An area of 6 sq. inches is the average daily task of each workman. Many years are therefore sometimes requisite for the execution of the larger designs, which when complete are worth 2000*l.* and upwards. The visitor who has seen nothing but faded old Gobelins tapestry or other inferior kinds will be struck with the beauty and brightness of the colours and the delicacy of the shading, while the eye is never offended by the varnish which is apt to mar the enjoyment of painted pictures. Silk is sometimes mixed with the wool in representing flowers, fruit, and metallic lustre, but the whole of the rest of the work is in wools, the colours of which are more durable. There is of course little or no room for the display of originality, as the works are all copies of well-known pictures; but the art has attained to a marvellous degree of perfection, and its results may be fitly compared to able literary translations.

We first visit the EXHIBITION ROOMS, some of which occupy a temporary building to the left of the entrance.

1st Room. To the right: Abraham's sacrifice, after *Sim. Vouet*; Artemis and the Triumph of Apollo (*Lerambert*); Players at 'tiquet', part of a curtain by Gombaut and Macé (17th cent.); Dancing nymphs (*Raphael*); Autumn (*Lebrun*); Louis XIV. (*H. Rigaud*); J. B. Colbert (*P. Lefebvre*); Air, Juno (*Cl. Audran*); Ch. Lebrun (*Rigaud*); Winter, Saturn (*Cl. Audran*); Repast of Syphax, after *Giulio Romano*; Marriage of Alexander and Campaspe (*Raphael*); Triumph of Pallas (*N. Coypel*); Louis XIV. visiting the Gobelins Manufactory (*Lebrun* and *Van der Meulen*); Crossing the Ponte Mollé (*Raphael*); Ascent of Elijah (*Sim. Vouet*).

2nd Room. To the right: The Flemings demanding peace from Clovis (from Brussels; 17th cent.); to the left: Blood-hound (*Oudry*). At the end: Two bulls, Animals fighting (*F. Desportes*).

The 3rd Room, to the left of the last, contains tapestry of the 16-18th cent. from different manufactories. To the right: Calydonian Boar; fragments of Egyptian tapestry, woven by Copts, the most ancient specimens known; the Idol (15th cent.); Louis XI. raising the siege of Dôle (1477), from Bruges; more Egyptian tapestry; Miracle of the 'Landit' fair (15th cent.); Annunciation, Dead Christ, Adoration of the Magi (Flemish); above the Christ, Fine piece of ancient Persian tapestry; in the middle of the room, a similar piece; on the other wall, four pieces of Flemish tapestry, after Raphael; Death of Joab (*A. du Cerceau*).

4th Room (adjoining R. 2). Flora, of the Fontainebleau school (?) of the 16th cent.; the Concert, French tapestry of the beginning of the 16th cent.; Cybele, also of the Fontainebleau school (?).

We next visit the WORKSHOPS. The principal work at present in hand in the first of these is a large piece of tapestry for the Bibliothèque Nationale, designed by *Ehrmann* and representing the literature, science, and art of the Middle Ages. Farther on are some panels (*Galland*) for the Palais de l'Élysée. At the end of the room is a representation of June, after a tapestry of the 16th century. — 2nd Workshop: on the staircase, Juno, a portière by *Audran*; on the looms, Ceremony, after *Jos. Blanc* (for the Odéon); Printing and Manuscript, after *Ehrmann* (for the Bibliothèque Nationale); Pharmacy and Medicine, after *Galland*; Spring, by *Baudry*; Air, by *Audran*; Tapestry, by *Merson*.

We now traverse a corridor hung with antique tapestry, and descend a staircase to another part of the building, containing an exhibition room (to the left) and the workshop of the Savonnerie (to the right). — The SALLE D'EXPOSITION mainly contains recently finished pieces, exhibited here before removal to their ultimate destination. Among others are Love, after *Raphael*; St. Jerome, by *Correggio*; Venus bidding farewell to Ceres and Juno,

after *Raphael*; Nymph and Satyr, by *J. Lefèvre*; Holy Sepulchre. *Champagne*; Spring and Summer, by *Baudry*; Wolf and lamb, by *Oudry*; Touch, by *Baudry*; Martial and pastoral Music, by *Chardin*; Don Quixote, by *Ch. Coypel*; Venus and Vulcan, and Aminthus and Sylvia, by *Boucher*; Ceres, by *Audran*; Esther, by *De Troy*; Bacchus, by *Audran*. Japanese and Chinese tapestries, etc. In the WORKSHOP carpets are being made for the Bibliothèque Nationale.

We leave the Gobelins by a court to the left, with the old CHAPEL, containing tapestry after paintings by *Raphael*: Battle of Constantine; Fair of Bolsena; St. Stephen's martyrdom; Elymas the Sorcerer; Heliodorus expelled from the Temple; St. Paul at Athens. Copies of mosaics; Christian tombs in mosaic from Tunis (5-6th cent.).

The Avenue des Gobelins leads to the S. to the *Place d'Italie* (Pl. G, 23), where five other boulevards or avenues converge. In the centre is a fountain. On the N. side is the *Mairie of the 13th Arrondissement*, built in 1867-77, with a handsome tower.

Ivry (21,076 inhab.), *Bicêtre*, *Vitry* (6122 inhab.), and *Villejuif* (3163 inhab.), all of which are reached by the tramways passing the Place d'Italie, possess little interest for the stranger.

The Boulevard Arago, forming a prolongation of the Boulevard St. Marcel (p. 268), passes the *Hôpital de Lourcine* and the extensive *Prison de la Santé*, a little beyond which it terminates in the Place Denfert-Rochereau (p. 242). The Boulevard de Port Royal, leaving the Avenue des Gobelins to the N. of the Boulevard Arago, leads past the Val-de-Grâce (p. 241) to the Carrefour de l'Observatoire (p. 260).

At the N. end of the Avenue des Gobelins begins the *Rue Mouffetard*, a street occupied by the poorest classes. At this point rises the church of *St. Médard* (Pl. G, 22), of the 15-16th cent., the burial-ground of which, in the 18th cent., contained the 'wonder-working' tomb of the Jansenist deacon Abbé Paris. Pilgrimages to the tomb were at length prohibited by Louis XV. in 1732, which gave rise to the witticism: —

*'De par le Roi, défense à Dieu,
De faire miracle en ce lieu.'*

The Rue Monge at the back of the church leads to the Boulevard St. Germain (tramway), passing the *Place Monge*, where a bronze statue of *Louis Blanc* (1811-82), the historian, by Delhomme, was erected in 1887. In the vicinity are the scanty remains of the *Arènes de Lutèce*, at the corner of the Rue de Navarre, to the right.

12. From the Tuileries to the Invalides and the Champ-de-Mars.

The best days for a visit to the Invalides is Tues. or Thurs., when the tomb of Napoleon and the Artillery Museum are both open (comp. p. 270). — Luncheon may be taken in the Boul. St. Germain or the Square Ste. Clotilde p. 16).

I. FROM THE TUILERIES TO THE INVALIDES.

Chambre des Députés. Ste. Clotilde.

We cross to the left bank by the *Pont-Royal*, which was constructed in 1685 from plans by Gabriel and Mansart.

This part of the town suffered severely from the Communist atrocities of 1871. In the *Rue du Bac* and the *Rue de Lille*, which runs parallel with the river, 34 buildings were totally destroyed between 22nd and 28th May. Among these were the *Quartier* (or *Caserne*) *Bonaparte*, the *Palais du Quai d'Orsay*, and the *Palais de la Légion d'Honneur* (see p. 272), all in the Rue de Lille, with façades towards the Seine. The *Palais de la Chambre des Députés* (p. 272) was frequently struck by projectiles during the sieges of 1870-71, but otherwise escaped injury. The adjoining *Ministère des Affaires Etrangères* was partly destroyed by the Communists, but has since been restored.

On the S. side of the bridge begins the old RUE DU BAC (Pl. R, 17, 16; IV), which traverses the **Faubourg St. Germain**, the aristocratic quarter, where the principal streets are the Rue de Lille, Rue de Verneuil, Rue de l'Université, Rue St. Dominique, Rue de Grenelle, and Rue de Varenne, all running parallel to the Seine. Most of the houses in these streets are private mansions, and the quarter presents a dull and deserted appearance, especially in summer and on Sundays and holidays. Among the public edifices here are the *Ministères des Travaux Publics* (Pl. R, 17; IV), *de l'Instruction Publique* (Pl. R, 17; IV), *des Postes et Télégraphes* (Pl. R, 14; IV), *de la Guerre* (Pl. R, 17; IV), and *des Affaires Etrangères* (p. 273); the *Embassies of Russia* (Pl. R, 17; IV), *of Austria* (Pl. R, 17; IV), and *of Germany* (Pl. R, 17; II); the *Ecole d'Etat-Major* (Pl. R, 14; IV), the *Palais Archiépiscopeal* (Pl. R, 14; IV), and several others mentioned below.

At the end of a small street on the left of the Rue du Bac, near the Boul. St. Germain, rises the church of **St. Thomas d'Aquin** (Pl. R, 17; IV), erected in 1682-1740. The portal was not completed till 1787. On the façade are two good modern bas-reliefs: St. Thomas Aquinas by *Vilain*, and St. Dominic, by *Gruyère*. The interior contains frescoes by *Blondel*; a ceiling-painting by *Lemoine*, representing the Ascension; Descent from the Cross, by *Guillemot*; St. Thomas Aquinas, calming a storm, by *Ary Scheffer*; Christ on the Mt. of Olives, by *Bertin*.

The Rue du Bac then crosses the Boul. St. Germain and the *Rue de Grenelle*, in which, to the left, rises the *Fontaine de Grenelle* (Pl. R, 17; IV), erected in 1739 from designs by *Bouchardon* (d. 1762), and one of the finest fountains in Paris. It consists of a crescent 31 yds. in diameter and 38 ft. in height. In the centre is a small Ionic portico, adorned with an allegorical group in white marble representing the City of Paris with the Seine and the Marne. In niches at the sides, framed with Doric pilasters, are statues of the Seasons with appropriate reliefs, also by *Bouchardon*.

Near the S. end of the Rue du Bac, on the right, is the *Séminaire des Missions Etrangères* (Pl. R, 16; IV), for the training of Roman Catholic missionaries. A melancholy sight is afforded here by the *Chambre des Martyrs* (shown on application), which contains numerous instruments, especially from China, used in torturing and killing Christian martyrs, blood-stained clothes of missionaries, and other relics.

Farther on, at the corner of the Rue du Bac and the Rue de Sèvres, are the extensive magazines of the *Bon-Marché* (p. 38), which also look into the Rue de Babylone and the *Square des Ménages* (so called after an old fopish of that name), with a marble group of Sleep by *M. Moreau*.

No. 63 Rue de Sèvres is the headquarters of the Jesuits. In the court rises the *Eglise du Jésus*, a modern Gothic edifice in the style of the 13th cent., erected by *Père Tournesac* in 1866-68. The chapels are adorned with frescoes representing Jesuits who have been canonised. One of them contains a monument in memory of Jesuits killed by the Communists in 1871. The church was closed by order of government in 1880.

We now return to the *Quai d'Orsay*. The most important of the edifices here which were destroyed in 1871 was the *Palais du Quai d'Orsay*, close to the Pont-Royal, and still a ruin. It was built in 1810-35, and was latterly used by the Conseil d'Etat and the Cour des Comptes. Lower down the river, near the Pont de Solferino, rises the *Palais de la Légion d'Honneur* (Pl. R, 17; II), erected in 1786 by Prince Salm-Kyrburg, and interesting as the scene of Mme. de Staël's réunions during the Directory. It has recently been restored by subscriptions from members of the order. The entrance is in the Rue de Lille.

The adjoining *Pont de Solferino* was constructed in 1858-59. The large and low square tower in the Boul. St. Germain, at the end of the Rue de Solferino, belongs to the *Ministère de la Guerre*. Lower down the river is the Pont de la Concorde (p. 83), opposite which on the left rises the —

Chambre des Députés (Pl. R, 14; II), otherwise known as the *Palais du Corps Législatif* or *Palais Bourbon*, which was begun in 1722 by Girardini for the dowager Duchess of Bourbon. The Prince de Condé afterwards expended no less than 20 million francs on the building, which in 1790 was declared national property. After having been used for various purposes, it was set apart for the sittings of the Council of Five Hundred, and afterwards for those of the Corps Législatif or Chamber of Deputies, which has 574 members.

The façade towards the Seine, built by Poyet in 1804-7, is in the style of a Greek temple, with a handsome Corinthian colonnade of twelve columns and a lofty flight of steps. On the latter are placed statues of Themis, Minerva, D'Aguesseau, Colbert, L'Hôpital, and Sully. On each side of the portico are reliefs by Rude and Pradier, and in the tympanum a group by Cortot, which represents France with the constitution, between Liberty and Order, summoning Commerce, Agriculture, and Peace to her aid. The original façade fronts the Rue de l'Université, which expands here into a *place*, embellished with a marble statue of 'Law' by Feuchères (1855).

When the Chamber is sitting visitors are admitted only to the Salle des Séances, for which they require a ticket from a deputy or from the 'secrétaire de la questure'. At other times the building is open to the public. The chief entrance is in the small building to the right of the grand staircase which ascends from the quay. Visitors are escorted by an attendant (fee). The **SALLE DES PAS-PERDUS** has a ceiling-painting by Horace Vernet, and several copies of antiques. The **SALLE DES SÉANCES**, or *Assembly Hall*, is semicircular in form, and is borne by twenty marble columns, behind which are the public galleries. The hall is embellished with a reproduction in tapestry of Raphael's School of Athens, and by marble statues of Liberty and Public Order. The presidential chair and the platform below it are said to be the same as those once used by the Five Hundred.

Here, on 24th Febr., 1848, the Duchess of Orléans appeared before the National Assembly with her two sons, the Count of Paris and the Duke of Chartres, in order to endeavour to secure the throne for them. On 15th May of the same year the National Assembly was expelled from this hall by the Socialists, and order was restored by the National Guard. On 4th Sept., 1870, an excited mob forced its way into the hall, shouting 'Vive la République', whereupon the assembly dispersed, and the republican members repaired to the Hôtel de Ville to form a new government.

The *SALLE DES CONFÉRENCES* contains a ceiling-painting by *Heim*, representing the history of legislation in France, and several pictures: President Molé arrested during the Fronde, by *Vincent*; Opening of the States General by Philippe le Bel, by *Vinchon*; *Devotedness of the burghers of Calais, by *Ary Scheffer*. The *Library*, with ceiling-paintings by *Eug. Delacroix*, contains MSS. of Rousseau. In the *SALLE DES DISTRIBUTIONS* are scenes in grisaille by *Ab. de Pujol*. The *SALLE CASIMIR PÉRIER* is embellished with statues of Mirabeau and Bailly by *Jaley*, Perrier by *Duret*, and General Foy by *Deprez*, and a basrelief by *Triqueti*. The *SALLE DU TRÔNE* contains paintings of Justice, War, Industry, Agriculture, and the Seas and Rivers of France by *Eug. Delacroix*.

The residence of the president of the Chamber is to the right of the building, and is entered from the Rue de l'Université. Adjacent to it, and facing the quay, is the *Ministère des Affaires Étrangères*, a handsome edifice built in 1845 and restored since 1871. The façade is embellished with Doric and Ionic columns, with balustrades on each story, and at the top with medallions of the armorial bearings of the principal powers. Immediately beyond this building is the *Esplanade des Invalides* (p. 274). We now retrace our steps, pass the *Chambre des Députés*, and follow a street to the right, skirting the E. side of the building. We soon reach the *Place du Palais Bourbon*, adorned with the statue of Law above mentioned, and obtain a view of the S. façade of the *Chambre*. A little farther to the S. we follow the *Rue St. Dominique* to the left and soon reach —

**Ste. Clotilde* (Pl. R, 14; IV), one of the finest modern churches in Paris, erected in 1846-59 by *Gau* and *Ballu* in the Gothic style of the 14th cent. at a cost of 8 million francs. It is 110 yds. in length, 35 yds. in width, and 85 ft. in height. The façade consists of three portals, richly sculptured, and flanked with two towers, which terminate in slender spires, rising to a height of 216 ft.

The *INTERIOR* is simple and dignified, being decorated with marble reliefs only. The magnificent stained-glass windows, which were damaged by an explosion in 1871, are by *Maréchal*, *Galimard*, *Jourdy*, *Thibaut*, *Duval*, *Lusson*, and *Hesse*. The two small chapels of the aisles are adorned with paintings by *Delaborde*. Under the windows of the aisles and in the transept are basreliefs by *Duret* and *Pradier*, forming a 'Chemin de la Croix'. — The chapel of *Ste. Valère*, the martyr of Limousin, to whom a church was once dedicated on this site, is in the right (W.) transept. It contains scenes from her history by *Lenepveu*. The enclosure of the choir is adorned with basreliefs by *Guillaume*, two on the right representing *Ste. Valère*, and two on the left *Ste. Clotilde*. — The choir-chapels are embellished with mural paintings: 1st on the right (*St. Remi*), by *Pils*

and *Laemlein*; 2nd (St. Joseph), by *Bezard*; 3rd (Virgin), by *Lenepveu*; 4th (Ste. Croix), by *Brisset*; 5th (St. Louis), by *Bouguereau*. — In the left transept are two large compositions by *Laugée*: St. Clotilde succouring the poor, and the Baptism of Clovis. — The carved choir-stalls and the high-altar, which is enriched and inlaid in the mediæval style, also deserve inspection. — The organ is by Cavaillé-Coll.

The square in front of the church is adorned with a handsome group in marble, by *Delaplanche*, representing Maternal Education.

The Rue de Grenelle passes near the back of the church, and leads thence to the W. in a few minutes to the Invalides.

II. HÔTEL DES INVALIDES.

Musée d'Artillerie. Eglise des Invalides. Tomb of Napoleon I.

The HÔTEL DES INVALIDES is shown daily, 12-4; the ARTILLERY MUSEUM is open to the public on Tues., Thurs., and Sun., 12-3 (in summer till 4), and the EMPEROR'S TOMB on Mon., Tues., Thurs., and Frid., 12-3. No fees.

The *Hôtel des Invalides* (Pl. R, 14; IV), with its conspicuous gilded dome, a vast establishment occupying an area of about 30 acres, was founded in 1670 by Louis XIV., 'pour assurer une existence heureuse aux militaires qui, vieillards mutilés ou infirmes, se trouveraient sans ressources après avoir blanchi sous les drapeaux ou versé leur sang pour la patrie'. The building was begun in 1671 by *Libéral Bruant*, and completed in 1675 by *Mansart*.

Soldiers disabled by wounds, and those who have served for 30 years, are entitled to be received into the Invalides. The building was intended to accommodate 5000 inmates, but there are now about 400 only, and the number is decreasing, as most of the 'invalides' prefer to live independently on their pensions. A 'Revue' and 'Défilé' of the Invalides take place on Sun. at noon.

The handsome *Esplanade des Invalides*, about 550 yds. in length, and 270 yds. in width, embellished with several rows of trees, lying between the Seine and the Hotel, was occupied by the colonial section, etc., of the Exhibition of 1889. The railway station now in the Champ-de-Mars is to be transferred hither, and the Rue Constantine is to be prolonged by a new bridge. A railing separates the Place from the outer court of the Invalides, which is enclosed on three sides by a dry moat. A 'Batterie Triomphale' placed here is used in firing salutes on grand occasions. It consists of eight guns and a mortar on each side, besides which there are eleven unmounted pieces, including eight Algerian cannons with Arabic inscriptions, a Cochín-Chinese, and a Chinese cannon.

On the right, as we face the Seine, are two Austrian cannons, one cast at Vienna in 1681, the other in 1580, with the inscription in German, 'When my song resounds in the air, many a wall will fall before me'; four Prussian guns, cast at Berlin in 1708, captured there by the Austrians during the Seven Years' War, and brought by Napoleon from Vienna after the Battle of Austerlitz along with 2353 other cannon; a Dutch piece, captured at the siege of Antwerp in 1832; a rifled cannon from Sebastopol; a mortar from Algiers. — *On the left*: a long swivel-gun from Wurtemberg, a master-piece of its kind, decorated with a serpent and allegorical figures; a Venetian piece, of 1708; the remaining piece correspond to those on the right side.

The rest of the outer court is laid out as a garden, and is adorned with a *Statue of Prince Eugène*, in bronze, by Dumont.

The *Façade* of this vast edifice is about 220 yds. in length. The three stories are surmounted with trophies in stone. Above the principal entrance is an equestrian figure of Louis XIV. in basrelief, by *Coustou the Younger*. Flanking the entrance are statues of Mars and Minerva, in bronze, also by *Coustou*. In front of the wings are placed four groups in bronze, by *Desjardins*, emblematical of four conquered nations. They formerly belonged to the statue of Louis XIV. in the Place des Victoires (p. 169), but were brought here in 1800.

The building is open to visitors daily (see p. 274; fees prohibited).

The *Cour d'Honneur*, the first court, is enclosed with arcades, parts of which are adorned with paintings by *Masson*, representing scenes from the epochs of Charlemagne, St. Louis, Louis XIV., and Napoleon I. On the S. side is the church (p. 278); on the W. the Musée d'Artillerie (see below); on the E. are the refectories and kitchens, beyond which, on the first floor, are the Library and Salle du Conseil, dormitories, and other apartments.

The *Refectories* and the museum on the ground-floor are adorned with allegorical pictures, chiefly relating to the campaign of Louis XIV. in the Netherlands (1672). Among those in the officers' dining-room are the capture of Wesel, Emmerich, and Utrecht (1672), towns which were unable to defend themselves and surrendered almost without a blow. Most of these paintings are by Martin, a pupil of the prolific Van der Meulen.

The *Library*, on the first floor, on the N. side, containing about 30,000 vols. and several MSS. of Sully and Colbert, is not open to the public.

The *SALLE DES MARÉCHAUX* and *SALLE DU CONSEIL* adjoin the library. The vestibule contains souvenirs of Napoleon I., flags of different nations, and armorial bearings of towns.

Salle des Maréchaux. Portraits of French marshals. Model of the Vendôme Column; small statue of Louis XIV. by *Raggi*; large missal executed by two 'invalides'.

Salle du Conseil: Portraits of former governors of the Invalides. To the right on entering, we observe under glass the ball which killed Turenne at Salsbach in 1675, and a statuette of the marshal. Above the door are portraits of the architects *Bruant* and *Mansart*.


The **Musée d'Artillerie* (admission, see p. 274) occupies a considerable part of the W. wing of the building. This interesting collection consists of 4000 specimens of weapons of all kinds. The objects of interest are furnished with explanatory labels. The catalogue, though bearing the date 1887, is antiquated.

The *Vestibule* contains a number of large cannon, among which, on the side next the passage, are two Arabian pieces and a cannon from Cochin China in wood hooped with iron; then two Spanish pieces from Mexico, to the right, as we turn towards the corridor; also casts of monuments to Roman soldiers found in the Rhine.

The *1st Galerie des Armures*, to the right on the same side, contains a collection of armour and weapons of the 16-17th centuries. The suits of armour include those of the Connétable de Montmo-

rency, the Ducs de Guise and de Mayenne, the Baron des Adrets, Sully, and Turenne; and eleven suits of German workmanship (early 16th cent.), known as 'Maximiliennes'. At the end of the saloon is a model of the Château of Pierrefonds. In front, juvenile armour. The glass-cases in the centre contain richly-decorated weapons and artistically-executed portions of armour, and jousting-armour. Above and against the walls are French flags and standards, originals to the right, copies to the left. The second on the left is the red Oriflamme of St. Denis; the ninth is the white standard of Joan of Arc, enriched with fleurs-de-llys.

The 2nd *Galerie des Armures* contains a splendid collection of armour worn by horsemen and foot-soldiers, chiefly of the 15th and 16th centuries. In the centre, among other suits of armour, are



the jousting-armour of Maximilian I., a German equestrian suit, and suits of a prince of Burgundy and a prince of Bavaria of the 16th cent.; and a Saracen suit of the same date. Here also are the suits of armour of the kings of France from Francis I. to Louis XIV. The glass-cases contain many other objects of interest. *1st Case: helmet, armlets, mace, and head-piece of Henri II.; gorget of Louis XIII.; cross-bow of Catherine de Médicis; spurs, stirrups, and gauntlets of Louis XIV.; sword of Francis I.; swords of Henri IV.; muskets of Louis XIII.; swords and musket of Louis XIV. (behind); carabine of Napoleon I.; sword of Louis XVI. and scabbard enriched with jewels; etc. — *2nd Case: helmets, morions, bucklers, maces of the 16th cent., of Italian workmanship; German helmet of the same period. — 3rd Case. Three admirable suits of the same period, that on the left being known as 'l'armure aux lions' (1550), while that on the right is enriched with reliefs

designed by Giulio Romano (16th cent.). — 4th Case: helmet, shield, and swords, 16th cent., of beautiful workmanship. — 5th Case: helmets and morions of the 16th cent., hunting-horn of the 11th cent., handcuffs of the 16th cent.; German arquebusses of the 16th cent.; behind, sabre of Stephen Bathory, king of Poland, etc. — *6th Case: buckler, helmets, swords, etc., 16-17th centuries. — Above, on the walls, foreign flags, with labels.

A small room on the right contains numerous helmets and bucklers, coats of mail, boots, etc.

A door at the end of the Salle des Armures leads into a passage, beyond which are the four rooms of the **Ethnographical Gallery*, an interesting collection of 78 wax and wooden figures of savages in their war-costume.

Returning to the vestibule, we follow the passage to the left, whence a staircase ascends to the new rooms on the first floor, where there are also two long galleries parallel with the court. That on the left, divided by partitions into four rooms, contains a very interesting collection of **Costumes de Guerre*. The 1st is devoted to those of the Gauls, the 2nd to Greek and Roman costumes, and the 3rd and 4th to those of the French from the time of Charlemagne down to the end of the 18th century. — The gallery on the right is occupied with a valuable collection of small *Modèles d'Artillerie* from the earliest period down to the present day.

The passage on the ground-floor leads to the —

Salles des Armes Blanches et Armes à Feu. The 1st and 2nd Rooms contain Arabian, Persian, Albanian, Montenegrin, Greek, Chinese, Japanese, and Indian weapons, some of them most elaborately executed. Opposite the entrance is the war-costume of an emperor of China, captured in the summer-palace during the expedition of 1860. — 3rd Room, on the right, weapons with wooden shafts, a collection of cutting weapons from the 12th, and of fire-arms from the 15th cent., down to the present day. The most interesting objects are in glass-cases. To the left: fire-arms of the earliest types; saddles of the 15-16th cent.; others, richly adorned, belonging to Charles X., Napoleon I., Emp. Maximilian II., Louis XVI., etc. In the glass-cases at the windows are weapons of celebrities of the First Empire. Against the wall of the entrance is a cabinet with specimens of French orders, military rewards, and marshals' batons. — 4th Room, on the opposite side: modern fire-arms and old thrusting weapons. At the end, modern helmets. To the left as we return, ancient weapons, originals and models. Collection of crossbows and pistols. — To the left is a 5th Room, containing modern weapons and a collection of drums.

The remainder of the collection is placed under the gates and in the courts on each side of the passage. On the right is the *Cour de la Victoire*, containing naval cannon, Chinese gun-carriage, a Russian gun and carriage from Sebastopol, and several cannon re-

covered in 1872 from Spanish galleons which foundered in the Bay of Vigo in 1701; armour plates pierced by cannon-shots. On the other side is the *Cour d'Angoulême*, where among other pieces is placed the Griffin, a culverin captured at Ehrenbreitstein on the Rhine in 1797, cast in 1528, and weighing nearly 13 tons. Statue of *J. B. Gribeauval* (1715-1789), first inspector-general of ordnance, in bronze by Bartholdi. By the wall here is a chain 190 yds. long, and $3\frac{1}{2}$ tons in weight, used by the Turks at the siege of Vienna in 1683 for the purpose of barricading an arm of the Danube. It was brought in 1805 from Vienna, where a similar chain is preserved in the imperial museum of armour. Under the carriage-entrance, by which the visitor may now leave the Hôtel, is a chain with fifty iron collars for prisoners, captured in the Morocco camp after the battle of Isly in 1844.

The *Gallery of Relief-Plans* of ancient fortresses is open to the public only from May 15 to June 30.

The **Eglise des Invalides** consists of two distinct parts, the *Eglise de St. Louis*, and the *Dôme*.

The EGLISE DE ST. LOUIS is entered from the S. side of the *Cour d'Honneur*. The nave is adorned with banners captured in Algeria under Louis Philippe, and in the Crimea, Italy, China, and Mexico.

On 30th March, 1814, the evening before the entry of the Allies into Paris, about 1500 flags, the victorious trophies of Napoleon I., were burned in the court of the Invalides to prevent their falling into the hands of the enemy. The sword brought by Napoleon from the tomb of Frederick the Great at Potsdam in 1806 was destroyed on the same occasion. A number of other flags captured during the wars of the Republic and the first Empire were accidentally burned during the funeral obsequies of Marshal Sébastiani in 1851.

The columns of the church bear a number of monuments and tablets in memory of former governors of the Hôtel des Invalides, including Marshals *Mouton*, Comte de Lobau (d. 1838); *Oudinot*, Duc de Reggio (d. 1847); and *Jourdan*, Comte d'Ornano (d. 1833). Three bronze tablets record the names of the marshals and officers interred in the vaults of the church. Behind the high-altar is a large window filled with modern stained glass, below which is a door leading into the *Dôme*, but generally closed.

The DÔME DES INVALIDES has an entrance of its own on the S. side, in the *Place Vauban*, at the back of the Hôtel, which may be reached by the corridor to the left of the church, opposite the museum (admission, see p. 274). Sticks and umbrellas must be left at the entrance (no charge).

This second church was built by *J. H. Mansart* in 1706. It is entered by a portal with two series of columns, Doric and Corinthian, placed one above the other, and adorned with statues. The church is a square pile, 198 ft. in breadth, surmounted by a circular tower with twelve windows and a lofty dome, above which rise a lantern and cross, 344 ft. in height. The dome, 86 ft. in diameter, gilded

during the first Empire, and again, by the electro-plating system, in 1861, is constructed of woodwork covered with lead, and is embellished with reliefs representing military trophies.

The **Tomb of Napoleon I.*, constructed by *Visconti*, and situated beneath the dome, is an open circular crypt, 20 ft. in depth and 36 ft. in diameter; the walls are of polished slabs of granite, adorned with ten marble reliefs by *Simart* (d. 1858): Restoration of public order, the Concordat, the Reformed Administration, the State-council, the Code, the University, the Chamber of finance, the Development of commerce and industry, Public works, and the Legion of Honour. The 12 colossal Victories between these reliefs were among the last works of *Pradier* (d. 1851). The 6 trophies consist of 60 flags which had long lain concealed in the Luxembourg. On the pavement are recorded the names of battles (*Rivoli, Pyramids, Marengo, Austerlitz, Jena, Friedland, Wagram, and Moscow*).

On the mosaic pavement, which represents a wreath of laurels, rises the sarcophagus, 13 ft. long, 6½ ft. wide, and 14½ ft. high, consisting of a single huge block of reddish-brown granite weighing upwards of 67 tons, brought from Finland at a cost of 140,000 fr.

The entrance to the crypt (closed) is at the back of the high-altar. It is flanked by two sarcophagi, bearing the names of *Duroc* and *Bertrand*, the emperor's faithful friends. The former fell at the battle of Bautzen in 1813; the latter (d. 1844) was the emperor's constant companion throughout his wars and his captivity, and followed his remains when brought by Prince Joinville from St. Helena in 1840 to their present resting place. Above the entrance are these words from the emperor's will: 'Je désire que mes cendres reposent sur les bords de la Seine, au milieu de ce peuple français que j'ai tant aimé.' On each side is a colossal Caryatide in bronze, by *Duret*, one bearing a globe, the other a sceptre and crown.

Above the crypt, at a height of 160 ft., rises the lofty dome in two sections. The first of these is divided into twelve compartments, painted with figures of the Apostles by *Jouvenet* (d. 1717). The upper section is adorned with a large composition by *Delafosse* (d. 1716): St. Louis offering to Christ the sword with which he had vanquished the foes of Christianity. The Evangelists in the spandrels are by the same artist. The faint, bluish light admitted from above, and the sombre appearance of the crypt and its surroundings greatly enhance the solemn grandeur of the scene.

Two lofty chapels on each side of the crypt contain the monuments of *Vauban* (d. 1707) and *Turenne* (d. 1675), with recumbent figures. The former, by *Etex*, was erected in 1807; the latter, by *Tuby* and *Marsy*, was brought from St. Denis.

The chapel to the left of the entrance contains the tomb of *Jérôme Bonaparte* (d. 1860), once King of Westphalia, with a bronze statue by *Guillaume*, a small sarcophagus with the remains of his eldest son, and another containing the heart of his wife. The chapel to the right of the entrance contains the sarcophagus of *Joseph Bonaparte* (d. 1844), once King of Spain.

The tower which rises opposite the Place Vauban is that of the *Artesian Well of Grenelle*, which is 1800 ft. deep. Nearer, to the left, are the towers of the church of *St. François Xavier*, erected in 1861-75 by Lusson and Uchard in a pseudo-Renaissance style. It is adorned with mural paintings by Lameire, E. Delaunay, Cazes, and Bougnereau, a Virgin by Bonassieux, and stained glass by Maréchal. The arrangement of the interior is somewhat peculiar.

Farther on in the same direction, at the end of the Boulevard des Invalides, on the right, is the *Blind Asylum*, or *Institution des Jeunes Aveugles* (Pl. R, 13; admission by permission of the director, except during the vacation in Aug. and Sept.). This handsome edifice was erected in 1839-45. The relief in the tympanum, by *Jouffroy*, represents *Valentin Haüy* (d. 1822), founder of the institution, instructing his pupils under the protection of Religion. In the court is placed another statue of the founder. — In the neighbourhood, Rue Bertrand No. 14, is the *Musée Haüy* (open on Tues., 11 to 4 or 5), containing articles manufactured by or for the use of the blind.

On the quay to the E. of the Esplanade des Invalides (p. 274) rises the extensive *Manufacture des Tabacs* (Pl. R, 14), Quai d'Orsay 63. It is shown on Thursdays from 2-4 o'clock. This extensive establishment, known as '*du Gros-Cailloù*', is worthy of a visit, but the pungent smell of the tobacco saturates the clothes and is not easily got rid of. About 2200 workpeople, including 1900 women and girls, are employed here, and nearly 12½ million lbs. of tobacco are annually manufactured. — The *Ingénieurs aux Tabacs*, or higher officials, are educated at the Polytechnic School, and study 2 years at the '*Ecole d'application pour les Tabacs*'. There are several other government manfactories of tobacco in France, all dependent on that of Paris, yielding an annnal revenue of 300,000,000 fr.

Farther on towards the Champ-de-Mars, at No. 103, Quai d'Orsay, is the temporary *Garde Meuble de l'Etat* (Pl. R, 11; J). It contains an interesting collection of furniture, tapestry, bronzes, and other objects of artistic and historical value. This museum is open to the public on Sun., Thurs., and holidays, 10-4 o'clock; visitors write their names in a book on entering. Two large rooms to the right contain furniture, bronzes, tapestry, vases, etc. in the styles of Louis XIV., Louis XV., and Louis XVI.; and a smaller room to the left contains porcelain and small objects of art. The catalogue (1 fr.) contains 400 numbers.

III. THE CHAMP-DE-MARS.

Eiffel Tower. Fontaine du Progrès. Dôme Central. Exhibition Palaces.
Ecole Militaire.

The Champ-de-Mars may be reached direct by *Steamboat* (see p. 22), by the *Tramways* from the Louvre to St. Cloud (*TA*), Sèvres (*TB*), or Versailles (*TAB*), or from the Bastille to the Porte Rapp and the Trocadéro (*TL*); and by *Omnibus* from the Porte St. Martin to Grenelle (*Y*), or from the Place de la République to the Ecole Militaire (*AD*) or to the Trocadéro. — Cafés and restaurants are to be found in the Champ-de-Mars in summer.

The **Champ-de-Mars* (Pl. R, 8, 10, 11; I), a little to the W. of the Invalides, was, until the exhibition of 1889, a large sandy space, 1100 yds. in length and 550 yds. in breadth, used for military manœuvres. Down to 1861 it was enclosed by embankments, 15-20 ft. in height, which were planted with trees, and in the formation of which no fewer than 60,000 Parisians of both sexes and all classes participated in the year 1790. These banks were then furnished with rows of seats, which enabled hundreds of thousands of the people to witness the *Fête de la Fédération*, which took place on 14th July of the same year. In front of the École

Militaire was erected the *Autel de la Patrie*, where the king, the national assembly, and the representatives of the army and the provinces, swore fidelity to the new constitution. Talleyrand, Bishop of Autun, with 400 of the clergy, robed in white, officiated in the religious part of the ceremony. The rejoicings on this occasion were universal, as it was believed that the Revolution was now happily terminated. A similar festival, the famous *Champ de Mai*, was celebrated here with the utmost pomp by Napoleon on 1st June, 1815. Here too, in August, 1830, Louis Philippe presented colours to the National Guard, and in 1852 Napoleon III. distributed to the army the eagles which were to replace the Gallic cock. The Champ-de-Mars was the site of the '*Expositions Universelles*' of 1867, 1878, and 1889.

The Palais des Machines and the Ecole Militaire lie nearest to the Hôtel des Invalides, but in order to obtain a general idea of the structures which have remained since the successful exhibition of 1889, it is advisable to begin our visit from the quays on the Seine or at least from the middle of the square.

The ***Eiffel Tower** (*Tour Eiffel* or *Tour de 300 mètres*), close to the Seine and opposite the Trocadéro, naturally the most conspicuous object in view, was built by *M. Gust. Eiffel* (b. 1832 at Dijon) in rather less than two years (July 1887-May 1889). This enormous structure is the loftiest monument in the world, attaining a height of 984 ft., or not far short of twice the height (555 ft.) of the Washington Column at Washington (tower of Ulm cathedral 528 ft., Cologne 511 ft., Rouen 492 ft., Great Pyramid 449 ft., St. Paul's in London 404 ft.). At the same time it is an interesting specimen of bold and accurate skill in design and of the marvellous scientific precision of modern engineering. Owing to an optical delusion the tower, especially when seen close, appears to be lower than it really is.

The foundations were laid by means of iron caissons, sunk to a depth of 46 ft. on the side next the Seine, and 29½ ft. on the other side, compressed air being used to expel the water. Concrete was then poured in to form a bed for four massive foundation-piers of masonry, 85 ft. thick, arranged in a quadrangle 112 yds. square.

Upon this base, which covers about 2½ acres of ground, rises the extraordinary yet graceful structure of interlaced iron-work. The four uprights have an initial inclination of 54°, and beneath the first platform are united with each other by round spans, forming a kind of huge triumphal archway, higher than the Nelson Column in Trafalgar Square. Above the first platform the four uprights are still distinct, but they gradually approach each other as they ascend, and finally coalesce into a single shaft at a height of about 590 ft. The iron girders and beams used are hollow, while the upright standards are each 2 ft. in breadth. The successive platforms may be reached either by means of the staircases or by

hydraulic lifts (fare, see below). A calculation has been made that the rivet-holes in the tower, if placed in line, would form a small tunnel upwards of 40 M. in length; while 2,500,000 bolts and rivets were used in the construction. By means of hydraulic rams sunk in the foundations of masonry any one or all of the four uprights can be raised or lowered if necessary.

The *First Platform*, which is 190 ft. above the ground, and has an area of about 5860 sq. yds., is ornamented with paintings and accommodates a large restaurant (band almost daily at 8 p.m.). — The *Second Platform*, 32 yds. square, at the height of 380 ft., is occupied by a glass-covered hall, and the reservoir of the hydraulic lifts. At 680 ft. is a kind of landing-place or floor. Even as it approaches the top the tower is 33 ft. square. — The *Third Platform*, at the foot of the double lantern which terminates the tower, 904 ft. from the ground, is surrounded by a balcony 13 ft. across. It supports a glass pavilion, 54 ft. square, capable of holding 800 people. The view from this height commands a radius of nearly 90 M. The *Lantern*, which rises 79 ft. higher, is not open to the public; it contains an observatory and physiological and other laboratories. A staircase ascends within it to a circular balcony, 16½ ft. in diameter, above which again is the electric light (alternately red, white, and blue) which is seen at night for a distance of 45 miles. The ball at the base of the flag-staff which forms the apex of this unique erection is upwards of 300 mètres (984 ft.) from the ground. — There are in all 1792 steps from base to summit: to the first platform 350 (7-8 min.), thence to the second 380 (10 min.), and thence to the top 1062.

The *Ascent* of the tower is recommended only in clear weather. The tower is open daily from 9 a.m. till dusk, from March to November. Visitors ascend to the second platform by staircases or lifts (*ascenseurs*); beyond that by the lift alone. The staircases to the first platform are in the two legs of the tower nearest the Seine; those to the second platform in the others; but one can also ascend from the one platform to the other. The *Charge* is the same for the staircases or lifts: to the first two platforms 1, to the 3rd 2 fr.; on Sun. and holidays ½ and 1 fr.; children half-price on week-days only. On Sun. and holidays all visitors are not guaranteed an ascent to the top.

The **View* from the top is very extensive, but varies greatly, with the state of the atmosphere. In certain directions it extends for 55 M. in a direct line, i. e. beyond the limits to the N. and S. of the map at p. 334. To the S.W., for example, we may see as far as Chartres, to the N.E. as far as Villers-Cotterets. The view from the first two platforms is bounded by the hills surrounding Paris.

Beyond the tower extends a tasteful garden, in which are the **Fontaine du Progrès*, by *Coutan* and the so-called 'Fontaines Lumineuses'. The principal basin of the former is adorned with a colossal ship, symbolizing Progress, in which is France, with the Republic at the helm, and at the sides Science, Commerce, Art, Agriculture, etc. Below, a statue of the Seine. The jets of water which rise in all directions from the cornucopias, urns, dolphins, reeds, etc., and the cascade, 120 ft. broad, which falls from the

upper basin, are beautifully illuminated on Sun. evenings in summer by electric light cast upon them from subterranean galleries through coloured glass, and produce a most charming effect.

The ***Central Dome**, which was the principal entrance to the exhibition of 1889, the **Palais des Beaux Arts**, to the left, and the **Palais des Arts Libéraux** to the right, though constructed mainly of iron, have been relieved and embellished by means of terracotta mouldings, and by a skilful use of masonry, ornaments of lead, zinc, and brass, glass, coloured tiles, and painting. They are far superior to the iron sheds of the previous Paris Exhibition, and in fact they are themselves interesting specimens of the advance of construction in iron. The exterior diameter of the Central Dome is 130 ft., and its height is 212 ft. On the summit is a copper statue (24 ft. high), by *Delaplanche*, of France distributing palms and crowns. The painted frieze round the interior of the dome, by *Lavastre* and *Carpezat*, represents a procession of the different peoples of the world. The dome and the immense portal, flanked by colossal statues of Commerce and Industry, were executed by the architect *Bouvard*, with the aid of 39 assistants. A gallery, 100 ft. broad, connects the dome with the Palais des Machines (see below). The *Hall of the Fine Arts* and the *Hall of the Liberal Arts*, by *Formigé*, are nearly as effective though not so gorgeous as the central dome. Each is surmounted by a cupola, 183 ft. high, with a polychrome roof. The former is to be devoted to the *Musée des Arts Décoratifs* (p. 154); the latter to a *Musée Industriel et Commercial*.

The ***Palais des Machines** or *Hall of Machinery*, at the end of the Champ-de-Mars, designed by *Dutert* and *Contamin*, is, like the Eiffel Tower, a marvel of construction in iron. Its dimensions far exceed those of any other building of the kind. It is 450 yds. long, 165 yds. broad, and 160 ft. high, and its glass-roof has a span of 374 ft. The ribs of the roof spring from the ground, where their lower ends rest upon cast-iron sockets, embedded in masses of masonry resembling the piers of a bridge. The side-galleries have two stories and are connected with each other by transverse galleries at the ends, so as to afford an extensive promenade, to which we ascend by staircases on each of the four sides of the hall. The main entrance is on the side next the Avenue de la Bourdonnais; it is adorned with sculptured groups, 30 ft. high, representing Steam (by *Chapu*) and Electricity (by *Barrias*). The immense windows at each end are filled with stained glass; on one side, the Battle of Bouvines (1214), by *Champigneulle*, on the other the Oath in the Jeu de Paume (p. 289). The hall is now used as a military *Riding-School* in the early morning, and from 10.15 a.m. to 4 or 6 p.m. it is thrown open to riders and private carriages. Foot passengers, with tickets obtained from the Conservation du Champ-de-Mars, at the Porte Rapp (Pl. R, 11; I), are admitted to the galleries. The public are admitted free, to the first gallery only, on Sun. after 12 noon.

The **Ecole Militaire** (Pl. R, 10; I), an imposing edifice situated a little to the S.W. of the Invalides and covering an area of 26 acres, was founded in 1751 by Louis XV., 'pour y élever 500 gentilshommes dans toutes les sciences nécessaires et convenables à un officier'. In 1792 it was converted into a barrack, but it is now the seat of the *Ecole Supérieure de Guerre*. The principal part, on the N.W. side, presents a palatial appearance and is $\frac{1}{4}$ M. in length. The Corinthian portico in the centre is surmounted by a quadrangular dome. The wings were added in 1855. The chapel resembles that of the palace of Versailles. The public are not admitted to the Ecole without special permission.

In the *Place de Fontenoy*, behind the school, is a pyramidal *Monument* to those who fell in the war of 1870-71, erected in 1889.

At the corner of the Avenue de Suffren and the Avenue de la Motte-Picquet, beyond the school, is an interesting reproduction of the Bastille, and part of the Rue St. Antoine as in 1789. The entrance is formed by a reproduction of the old *Porte de la Conférence* (p. 168); at the other end, next the Bastille, is the old *Porte St. Antoine*; and towards the middle is the *Church of the Visitation* (p. 65). Shops, houses, costumes, etc. are reproduced with great regard to historical accuracy; and the attractions are numerous and frequently changed. Adm. 1 fr. The structure, erected in 1888, is not intended to be permanent.

PARIS et ses ENVIRONS


Echelle 1:200,000

Mantes

Fontaine

Neuilly

MONTMORENCY



ENVIRONS OF PARIS.

13. From Paris to Versailles.

Versailles is situated to the S.W. of Paris, with which it is connected by two railways, and by a high-road with a tramway-line running between them. By the railway on the *Rive Droite*, or right bank of the Seine, the distance is $14\frac{1}{2}$ M., by that on the *Rive Gauche*, or left bank, $11\frac{1}{4}$ M., and by the road about 10 M.

Those who can only pay one visit to Versailles should start early and visit the gardens before the opening of the palace. A second visit, in summer, may be combined with a pleasant afternoon-excursion to Rambouillet (p. 307).

a. **Rive Droite** (Gare St. Lazare, Pl. B, 18; booking-office and platform of departure in the upper arcade).

Trains start from Paris every hour from 6.30 a.m. till 12.35 p.m., and from Versailles every hour from 6 a.m. till 11 p.m. There are also several additional trains, particularly on Sundays and holidays (see *Indicateur*). The journey occupies 35-50 minutes. Fares 1 fr. 65, 1 fr. 35 c.; return-tickets, on which there is no reduction, are available for the *Rive Gauche* (p. 286). — Best views to the left.

The train passes under the bridge of the Place de l'Europe and through a short tunnel. To the left is the Chemin de Fer de Ceinture. The fortifications are then traversed. — 3 M. *Clichy-Vallelois*, two towns with 26,741 and 35,649 inhab. respectively. The train crosses the Seine.

$3\frac{3}{4}$ M. *Asnières*, a village on the left bank of the Seine, with 15,200 inhab., is a favourite resort for boating and other amusements in summer. The lines to Argenteuil, St. Germain (p. 315), and Rouen diverge here to the right, and the Versailles line describes a wide curve to the left. *Asnières* may also be reached by tramway from the Boul. Haussmann.

5 M. *Courbevoie*, a town with 16,000 inhabitants is also connected with Paris by two tramways (from the Madeleine and the Arc de l'Etoile). The long building to the left of the station is a barrack erected by Louis XV. for his Swiss Guards. Beyond the station the line crosses the W. end of the Avenue de Neuilly, the direct continuation of the Champs Elysées. The Arc de Triomphe appears, $2\frac{1}{2}$ M. distant. A rondel near the railway is embellished with a bronze group by Barrias, representing the Defence of Paris (comp. p. 156).

$6\frac{1}{4}$ M. *Puteaux*, with 15,736 inhab., chemical and dye-works, etc., is the junction of the line from Les Moulineaux to Paris (Champs-de-Mars) via Sèvres and St. Cloud. — The line traverses high ground, affording a view of Paris, the Bois de Boulogne, and the Seine.

$7\frac{1}{2}$ M. *Suresnes* (Cafés-Restaurants at the bridge), a village with 7683 inhab., at the base of Mont Valérien (p. 286), was

the scene of the conferences which resulted in the adoption of Roman Catholicism by Henri IV. A 'Rosière' is crowned here on the Sun. nearest Ang. 21st. The produce of the neighbouring vineyards is mediocre. A bridge crosses from Suresnes to the Bois de Boulogne, near Longchamp (p. 159).

Mont Valérien is crowned by the most important of the defensive forts around Paris. 650 ft. above the Seine. The summit was formerly occupied by *Le Calvaire*, a monastery erected in the reign of Louis XIII., and a favourite resort of pilgrims. In 1870-71 Mont Valérien played a prominent part in both the sieges of Paris. Admission to the fort, which commands a fine panorama, is granted by order only.

9½ M. *St. Cloud-Montretout* (p. 311). The train passes through several tunnels. To the right diverges a branch to Noisy-le-Roi (p. 307). Tunnel.

10½ M. *Sèvres-Ville d'Avray*; the station is 1 M. from the porcelain manufactory (p. 312), but near the village of Ville d'Avray (Restaurant de la Chaumière), charmingly situated to the right. The *Villa des Jardies*, once occupied by Balzac and the scene of Gambetta's death, is near the railway. A monument, by Bartholdi, with figures of Alsace and Lorraine, is to be erected here, and is to be the depository of the heart of Gambetta. The Church contains models of statues by Pradier, Rude, and Duret, a St. Jerome painted by Corot, an Ecce Homo by Aug. Hesse, etc. In the middle of the village stands a *Château*, dating from the end of the 18th century. Near the end of the Rue de Versailles, to the left, are the picturesque ponds that figure so often in the paintings of Corot, to whom a monument has been erected here.

13 M. *Viroflay*. To the left, farther on, is seen the viaduct which crosses the high-road and unites the lines of the right and left banks. — 14½ M. *Versailles*.

b. Rive Gauche (Gare Montparnasse, Pl. G, 16; booking-office to the left, ground-floor; platform of departure to the left, upstairs).

Trains from Paris at least once an hour from 6.35 a.m. till 12.40 a.m.; from Versailles every hour from 6.5 a.m. till 11.35 p.m. The journey occupies 40 minutes. Fares the same as by the Rive Droite; return-tickets available for either line. The finest views are to the right. — Passengers for Sèvres should alight at Bellevue.


This line crosses and corresponds with the Chemin de Fer de Ceinture at the *Ouest-Ceinture* station (see Appx.). — 2½ M. *Vanves-Malakoff*, between Vanves, with a 'lycée' (to the right), and Malakoff (p. 335). On the left and right of the line rise the forts of Vanves and Issy, both of which were almost entirely destroyed during the sieges of 1870-71, but have been restored.

3¼ M. *Clamart*, ½ M. from the village of that name (5112 inhab.), which is also connected with Paris by a tramway-line (terminus in the Place St. Germain-des-Prés). [The latter passes Issy (12,080 inhab.), with the Hospice des Ménages, some religious houses, and a small ruined château, and the village of *Vanves* (6000 inhab.).] The *Hospice Ferrari*, a large establishment for old

ASNIÈRES RUEIL-BOUCIVAL

1:75,000

0 1 2 3 Kilomètres



Gravé et imprimé par M. Guez & Debes, Leipzig.

St. Germain

St. Germain

men, is due to the munificence of the Duchess of Galliera (d. 1888). The *Bois de Clamart*, to the E. of the Bois de Meudon, is a favourite Sunday resort of the Parisian 'bourgeoisie'.

The line skirts the hills above the Seine. Fine view to the right of Paris and the river near Meudon. The train crosses the river by a viaduct 120 ft. high.

4 $\frac{1}{2}$ M. *Meudon*, see p. 313. To the left is the large orphanage of *Fleury*, erected and endowed by the Duchess of Galliera. — 5 $\frac{1}{2}$ M. *Bellevue*, beautifully situated on the hills of Meudon, see p. 312. — 6 $\frac{1}{4}$ M. *Sèvres* (p. 312). Fine view of the Seine and the park of St. Cloud (p. 310) to the right. — 8 M. *Chaville*. — 8 $\frac{3}{4}$ M. *Viroflay*. — 11 $\frac{1}{4}$ M. *Versailles*.

c. **Tramway.** The cars start from the Quai du Louvre, and follow the high-road from Paris to Versailles by Sèvres.

Cars from Paris run every hour from 7.30 a.m. till 10 p.m.; from Versailles every hour from 6 or 7 a.m. till 10 p.m.; fare 1 fr., outside 85 c.; to Sèvres in 70 min., to Versailles in 1 $\frac{3}{4}$ hour.

For some distance the road skirts the Seine, passing the Trocadéro (p. 163) and the suburbs of *Passy* and *Auteuil* (p. 162), with the **Pont-Viaduc du Point-du-Jour*, a large and handsome viaduct with two roadways and the line of the Chemin de Fer de Ceinture (comp. p. 162 and Appendix). It then intersects the fortifications (the road to St. Cloud diverges to the right), traverses *Billancourt*, crosses the Seine, and reaches *Sèvres*. The drive from Sèvres to Versailles occupies 40 min. more; the road passes under the railway-viaduct mentioned at p. 286 (42 ft. high.), and soon reaches the *Avenue de Paris*. Terminus in the *Place d'Armes*.

Versailles.

Arrival. The *Station of the Rive Droite Line* is nearly 1 M. distant from the palace: omnibus 30 c.; cabs 1 $\frac{1}{4}$ (one-horse) or 1 $\frac{1}{2}$ fr. (two-horse), per hr. 2 $\frac{1}{2}$ fr. — The *Station of the Rive Gauche Line* is about $\frac{1}{2}$ M. from the palace. — The *Gare des Chantiers*, of the *Chemin de Fer de Grande Ceinture*, is 1 M. from the palace and is called at only by a few trains (comp. the *Indicateur*). — The *Tramways* extend to the palace, and may be used for passing from one station to the other.

Hotels. **HÔTEL DES RÉSERVOIRS*, Rue des Réservoirs 9, D. 5 or 6 fr.; *HÔTEL VATEL*, Rue des Réservoirs 26-28, good cuisine; *HÔTEL SUISSE*, near the latter, Rue Petigny and Rue Neuve, déj. 2 $\frac{1}{2}$, D. 3 $\frac{1}{2}$, pens. 8-10 fr.; *HÔTEL DE FRANCE*, Rue Colbert 5, to the right of the Place d'Armes on the way to the palace; *HÔTEL DE LA CHASSE*, Rue de la Chancellerie 6, to the S. of the Place d'Armes, with a restaurant.

Cafés-Restaurants (generally expensive). *Rest. de Neptune*, Rue des Réservoirs 14; *Café-Rest. Lacharte*, No. 19 same street, near the railing, 3-4 fr.; *Hôtel Suisse*, see above; *Café de la Comédie*, in the park, also entered from the Rue des Réservoirs 13, déj. 3, D. 4 fr.; *Café Anglais*, Rue du Plessis 49, near the station of the Rive Droite, déj. 3, D. 5 fr.; *Café Américain*, Rue du Plessis 47, déj. 3, D. 5 fr.; *Hôtel du Sabot d'Or*, Rue du Plessis 23, déj. 2 $\frac{1}{2}$, D. 3 $\frac{1}{2}$ fr.; *Brasserie Müller*, at the corner of the Avenue St. Cloud and the Rue de la Pompe; *Café de la Place d'Armes*, corner of the Rue Hoche.

English Church, Rue du Peintre Lebrun, corner of Rue de la Pompe; services at 11 a.m. and 4 p.m.

Versailles, the capital of the Seine-et-Oise department, with

49,852 inhab., is indebted for its origin to Louis XIV. During the first years of his reign that monarch, like his predecessors, had resided at St. Germain in summer, but is said to have conceived a dislike to it as it commanded a view of the tower of St. Denis (p. 318), the royal burying-place.

The site of Versailles was hardly favourable for a town, and still less so for a park, as the water for its ornamental ponds had to be conveyed to it from a great distance at a vast expense. The town was called by Voltaire '*l'abîme des dépenses*', its palace and park having cost the treasury of Louis XIV. the enormous sum of 1000 million fr., while its annual maintenance also involved heavy expenditure. The accounts handed down to us regarding the erection of this sumptuous palace and the laying out of its grounds almost border on the fabulous. Thus no fewer than 36,000 men and 6000 horses are said to have been employed at one time in forming the terraces of the garden, levelling the park, and constructing a road to it from Paris and an aqueduct from Maintenon, a distance of 31 M. from Versailles. This aqueduct was intended to bring the water of the Eure to Versailles, but was discontinued owing to the great mortality among the soldiers employed; and the breaking out of the war in 1688 prevented the resumption of the works. The waterworks of Marly (p. 314) were afterwards constructed, and a farther supply of water obtained from the ponds on the plateau between Versailles and Rambouillet.

After the year 1682 Versailles became the permanent headquarters of the court, and is therefore intimately associated with the history of that period. It witnessed the zenith and the decadence of the prosperity of Louis XIV.; and under his successor the magnificent palace of the 'grand monarque' became the scene of the disreputable Pompadour and Du Barry domination. It was at the meeting of the Estates held here in 1789 that the 'Tiers Etat' took the memorable step, — the first on the way to the Revolution, — of forming itself into a separate body, the *Assemblée Nationale*. A few months later the unfortunate Louis XVI. saw the palace of Versailles sacked by a Parisian mob, which included many thousands of women ('*les dames de la halle*'), and since that period it has remained uninhabited. During the Revolution it narrowly escaped being sold. Napoleon neglected it owing to the great expense which its repair would have entailed, and the Bourbons on their restoration merely prevented it from falling to decay and erected the pavilion on the S. side. Louis Philippe at length restored the building, and converted part of it into an historical picture-gallery.

From 19th Sept., 1870, to 6th March, 1871, the palace was the headquarters of the King of Prussia, and a great part of the edifice was then used as a military hospital, the pictures having been carefully covered to protect them from injury. An impressive scene took place here on 18th Jan., 1871, when the Prussian monarch, with the unanimous consent of the German states, was saluted as Emperor of Germany. To describe minutely all the events which occurred at Versailles during the above period would be to write a history of the Franco-Prussian war. The house No. 1, Boulevard du Roi, was the scene of the negotiations between Prince Bismarck and Jules Favre on 23rd-24th Jan. and 26th-28th Jan., which decided the terms for the capitulation of Paris and the preliminaries of peace. After the departure of the German troops (12th Mar., 1871), Versailles became the seat of the French government, and it was from here that Marshal Macmahon directed the struggle against the outbreak of the Commune. It was not till 1879 that the government and the chambers transferred their headquarters to Paris.

On the way from the station of the Rive Droite to the palace, we pass on the right a *Statue of General Hoche*, 'né à Versailles le 24 Juin 1768, soldat à 16 ans, général en chef à 25, mort à 29, pacificateur de la Vendée', by Lemaire. Near it is the *Church of*





Notre-Dame, erected by Mansart in 1684, containing the monument of the *Comte de Vergennes* (d. 1787), minister of Louis XVI.

To the S.W. of the palace is the *Salle du Jeu de Paume*, or tennis-court, in which the members of the Third Estate met in June, 1789 (see above), after they had found the assembly-room closed against them, and where, on the motion of the deputy Mounier, they took a solemn oath, 'de ne jamais se séparer, de se rassembler partout où les circonstances l'exigeront, jusqu'à ce que la constitution du royaume soit établie et affermie sur des fondements solides'.

In 1883 a *Musée de la Révolution* was established in this famous hall (open daily, except Mon., 12-4). Opposite the entrance is a marble statue of Bailly, the president of the sitting above mentioned, by St. Marceaux. On the walls are busts of 20 members of the Third Estate and the names of the 700 persons who signed the minutes of the meeting. On the end-wall is a copy in grisaille of David's 'Oath of the Jeu de Paume' (p. 142). The glass-cases contain portraits, engravings, and other relics of the same period.

A little to the S. of the *Jeu de Paume* is the *EGLISE ST. LOUIS*, or cathedral of Versailles, a heavy and ungraceful building of the 18th century. On the exterior, to the left, is a *Statue of Abbé de l'Épée*, in bronze by Michaut. Inside are a St. John and a St. Peter by Boucher, several other pictures, a monument to the Duc de Berry, by Pradier, and stained-glass windows made at Sèvres, from designs by Devéria.

The high-road from Paris, or *Avenue de Paris*, unites with the two other chief streets of Versailles in the spacious *Place d'Armes*. On approaching the palace the traveller is assailed by vendors of 'complete' guides to the collection, which, however, are rendered quite unnecessary by the following explanations and the inscriptions on the pictures themselves.

The ***Palace** of Versailles presents a less imposing appearance when approached from the *Place d'Armes* than when seen from the garden, the façade towards which is no less than $\frac{1}{4}$ M. in length. The building dates from several different periods, and its style lacks uniformity. The central part is the original château of Louis XIII., built of brick and stone, and the wings were added by *J. H. Mansart* (d. 1708) under Louis XIV. On the right rises the chapel with its pointed roof; adjoining it is a pavilion erected by Louis XV.; and to the left of the court is a corresponding pavilion added by Louis XVIII. Other buildings of considerable size situated on each side are concealed by those of the first court, which Louis XIV. intended for his ministers. Those to the right of the chapel include the *Theatre*, constructed in the reign of Louis XV., which was used from 1871 to the end of 1875 for the meetings of the *Assemblée Nationale*, and from 1875 to 1879 for those of the Senate. The injudicious fête given by the court to the Gardes du Corps, after which Louis XVI. was compelled to quit Versailles, also took place in the Theatre. The left wing was used as the *Chambre des Députés*.

The public are admitted to five different courts—the first great court, or Cour d'Honneur; the Cour Royale, between the pavilions;

the Cour de Marbre, in front of the central building; the Cour de la Chapelle, between the pavilion on the right and the chapel; and lastly the Cour des Princes, on the other side of the pavilion on the left. The gardens are entered through the last two courts.

The COUR D'HONNEUR is separated from the Place d'Armes by a railing. The groups which adorn the pillars at the entrance are emblematical of the victories of Louis XIV. over Austria (the eagle) and Spain (the lion). Around the court are placed two rows of *Statues*, some of which stood on the Pont de la Concorde until 1837.

On the *right*: Cardinal Richelieu (d. 1642), regent of France under Louis XIII.; Bayard (d. 1524), the 'chevalier sans peur et sans reproche'; Colbert (d. 1683), the able finance minister of Louis XIV.; Marshal Jourdan (d. 1833); Marshal Masséna (d. 1817); Admiral Tourville (d. 1701); Admiral Dugay-Trouin (d. 1736); Marshal Turenne (d. 1675). On the *left*: Suger (d. 1152), Abbot of St. Denis and regent under Louis VII.; Bertrand du Guesclin (d. 1380), Connétable of France; Sully (d. 1641), the celebrated minister of Henri IV.; Marshal Lannes (d. 1809); Marshal Mortier (d. 1835); Admiral Suffren (d. 1788); Admiral Duquesne (d. 1687); the Great Condé (d. 1686), general of Louis XIV, by *David d'Angers*.

In the centre of the court stands a colossal *Equestrian Statue of Louis XIV.* in bronze, the horse by *Cartellier* (d. 1831), the figure by *Petitot* (d. 1862). The pavilions bear the inscription, '*A toutes les gloires de la France.*'

The ***Musée Historique**, founded by Louis Philippe, and occupying an almost interminable suite of apartments in the palace, is an unrivalled collection of its kind. In 1832 these rooms were entirely refitted, and adorned with historical pictures brought from the Louvre and other palaces, the deficiencies being supplied by works of the most eminent living artists. The foundation of the museum is said to have cost 15 million fr., the greater part of which was paid out of the royal coffers. The subsequent governments have left the original arrangements of the museum undisturbed, and have greatly enriched and extended it. The historical object of the foundation of the gallery having always been predominant, numerous works have necessarily been received without much regard to their artistic merit. The critical eye will therefore detect very inferior productions intermingled with the efforts of undoubted genius. The number of rooms is so great, that a single visit suffices only for an inspection of the more important works. The order of the following description should be adhered to, so that no objects of special interest may be overlooked and no time wasted on those of secondary consideration. The descriptions of the latter are printed below in smaller type.

The principal *Entrance* to the Musée (open daily, except Mon., 10-5 in summer, 11-4 in winter), is from the vestibule of the chapel, to the right (comp. the Plan, p. 292), and there is another entrance on the opposite side, by the Cour des Princes. Wet umbrellas must be left in the custody of an attendant (10 c.).

Ground Floor of the N. Wing. The ***PALACE CHAPEL**, erected in 1699-1710, produces a better impression when seen from the first

floor, as its proportions were calculated from the galleries of the court. It is richly adorned with sculptures and paintings. Over the entrance-door is the royal gallery, above which is a Descent of the Holy Ghost, by *Jouvenet* (1709). The Resurrection over the high-altar is by *Charles de Lafosse*. The large *Paintings in the vaulting of the roof, with God the Father in the centre, are by *Coyvel*. The decorations of the altar and of the side-galleries, and the ornamental details of the architecture also deserve attention.

From the vestibule of the chapel we enter the I. GALLERY OF THE HISTORY OF FRANCE, consisting of eleven rooms with historical pictures from the time of Charlemagne to that of Louis XVI.


I. Room. *Ary Scheffer* (1827), Charlemagne submitting his capitularies (laws and ordinances) to the Frankish estates in 779. *Paul Delaroche*, Charlemagne crossing the Alps in 773. *Rouget*, St. Louis (d. 1270) mediating between the King of England and his barons. — II. Room. *Brenet*, Death of Bertrand du Guesclin before Châteauneuf-de-Randon in Langue doc, 1380. *Vinchon*, Charles VII. anointed at Rheims, 1429. *Berthélemy*, The French army entering Paris, 1436. — III. Room. *Jollivet*, Battle of Agnadello, in Venetia, 1509. *Larivière*, Bayard wounded at the capture of Brescia, 1512. — IV. Room. *Ary Scheffer* (1824), Gaston de Foix's death at the Battle of Ravenna, 1512. *Schnetz*, Battle of Ceresole, 1544. — V. Room. Large pictures of little interest. — VI. Room. Sieges and battles of the reign of Louis XIII. and the early part of the reign of Louis XIV. — Rooms VII. & VIII. Campaigns of Louis XIV. — Rooms IX. & X. Scenes from the Seven Years' War. *Hersent* (1817), Louis XVI. and his family distributing alms (1788).

A handsome modern staircase here ascends to the second and third floors. To the right is the Galerie des Tombeaux, and in front of us the Theatre (p. 289).

The GALERIE DES TOMBEAUX, parallel to the Historical Gallery, contains casts of funereal monuments, and formerly served as vestibule for the Senate. — To the left (open the door if closed) is the entrance to the five —

*SALLES DES CROISADES, remarkable for their sumptuous decoration, and the magnificent modern pictures they contain: —

*1st Saloon. *Larivière*, Battle of Ascalon, 1157. *Hesse*, Taking of Beyrout, 1197. *Gallait* (1847), Coronation of Count Baldwin of Flanders as Greek Emperor, 1204. — *2nd Saloon. *Rouget*, Louis IX. receiving the emissaries of the 'Old Man of the Mountain', 1251. *Papety*, Defence of Ptolemais by Guill. de Clermont, 1291. *Jacquand*, Taking of Jerusalem by Jacques de Molay, Grand Master of the Templars, 1299. — *3rd Saloon (large hall). The armorial bearings on the pillars are those of Frederick Barbarossa, Richard Cœur-de-Lion, and other celebrated Crusaders. A mortar from the island of Rhodes, and the gates of the hospital of the knights of St. John, from Rhodes, presented by Sultan Mahmoud to Prince Joinville in 1836, are also preserved here. *Blondel*, Surrender of Ptolemais to Philip Augustus and Richard Cœur-de-Lion, 1191. After *Delacroix* (original, see p. 136), Capture of Constantinople, 1204. *Odier*, Raising of the siege of Rhodes, 1480. *Larivière*, Raising of the siege of Malta, 1565. *Schnetz*, Procession



FIRST FLOOR.

N. Wing.

Galerie de Sculpture (p. 294).

I-VII. *Galerie de Constantine* (p. 294).

1-10. *Seconde Galerie de l'Histoire de France* (p. 295).

Main Edifice.

I, II. *Salons d'Hercule et de l'Abondance* (N. wing, p. 296).

III, IV. *Salles des Gouaches* (p. 296).

V. *Salle des Etats-Généraux* (p. 296).

VI-X. *Salons de Vénus, Diane, Mars, Mercure, Apollon* (p. 296).

1-5. *Appartements de Louis XIV.* (p. 297).

Petits Appartements de Louis XV. (p. 297).

B. *Salon de la Guerre* (p. 296).

Galerie des Glaces (p. 296).

C. *Salon de la Paix* (p. 297).

I-VIII. (S. side) *Grands Appartements de la Reine* (p. 298).

V. *Salle du Sacre de Napoléon* (p. 298).

f, g, h, i, j, k. *Petits Appartements de la Reine* (p. 297).

A. *Escalier de Marbre* (p. 300), adjoining which is the *Escalier de la Reine* (p. 300).

D. *Aquarelles de 1796 à 1814* (p. 299).

S. Wing.

E. *Escalier des Princes* (pp. 299, 301).

Galerie des Batailles (p. 299).

Salle de 1830 (p. 300).

SECOND FLOOR.

Main Edifice.

A. *Escalier de la Reine* (p. 300).

a-k. *Salles et Cabinets des Portraits* (p. 298).

N. and S. Wings.

Galleries et Salles des Portraits (pp. 295, 300).

of Crusaders round Jerusalem, 1099. *Horace Vernet*, Battle of Las Navas de Tolosa (Spain), 1212. — 4th Saloon. *Schnetz*, Battle of Ascalon, 1099. *Signol* (1840), St. Bernard preaching the 2nd Crusade at Vézelay in Burgundy (1146). — 5th Saloon. *Signol*, Crusaders crossing the Bosphorus under Godfrey de Bouillon, 1097. Opposite: *Signol*, Taking of Jerusalem, 1099. *Hesse*, Adoption of Godfrey de Bouillon by Alexander Comnenus, 1097. *Gallait*, Taking of Antioch, 1098.

We now return to the Galerie des Tombeaux and ascend by a small staircase, adjoining the chapel, to the —

First Floor of the North Wing. After viewing the interior of the chapel from the royal gallery, we enter a GALLERY OF SCULPTURES, containing several fine marble statues by *Nanteuil*, *Foyatier*, *Jaley*, *Etex*, etc. To the right, the monument of Henri Chabot (d. 1655), by *Franc. Anguier*. Farther on are several works by *Pradier*, the best of which is the *Monument of the Duke of Orléans (p. 156), with reliefs relating to the sieges of Antwerp and Constantine. At the end, a *Statue of Joan of Arc by *Princess Marie of Orleans* (d. 1839), daughter of Louis Philippe.

To the right is the *GALERIE DE CONSTANTINE (Pl. I-VII), consisting of seven rooms which contain some of the finest pictures in the collection, particularly the battle-scenes by *Horace Vernet*.

Room I.: Principal wall: *Ch. L. Muller*, Opening of the Chambers on 29th March, 1852. *Dubufe*, Congress of Paris, 1856. *Gérôme*, Napoleon III. receiving ambassadors from Siam, 1861.

Room II.: **Yvon*, Retreat from Russia, 1812. *Protais*, Storming of the 'Mamelon Vert' at Sebastopol, 1855.

Room III.: **Horace Vernet* (1845), Taking of the Smalah of Abd-el-Kader (16th May, 1843), a magnificent picture 71 ft. in length and 16 ft. in height, containing numerous portraits, to which the sketch below it is a key.

The 'Smalah' of Abd-el-Kader, consisting of his camp, his itinerant residence, his court, harem, and treasury, and upwards of 20,000 persons, including the chiefs of the principal tribes with their families, was taken by surprise on this occasion by the Duc d'Aumale at the head of two cavalry-regiments. Booty of enormous value and 5000 prisoners were the prize acquired with so little difficulty. Abd-el-Kader himself was absent at the time.

**H. Vernet* (1846), Battle of Isly, 1844. *Beaucé*, Taking of Fort St. Xavier, near Puebla, 1863. *Vernet*, Capture of Rome in 1849. *Beaucé*, Entry into Mexico, 1863. *Beaucé*, Storming and capture of Laghouat (Algeria), 4th Dec., 1852. *Tissier*, Napoleon III. liberating Abd-el-Kader.

Room IV.: Seven large and seven small pictures by *Horace Vernet*: Battle of the Habrah, 3rd Dec., 1835. Siege of Constantine, 10th Oct., 1837. Preparations for the assault of Constantine, 13th Oct., 1837; in the central group the English Lieutenant Temple and other foreign officers. Taking of Constantine, 13th Oct., 1837. Attack on the Mexican fort St. Jean d'Ulloa by Ad-

miral Baudin, 27th Nov., 1838. Storming of the pass of Tenia Mouzaia, 12th May, 1840. Siege of the citadel of Antwerp, 1832.

Room V.: **Yvon*, Entrance to the Malakoff tower; Storming of the Malakoff (8th Sept., 1855); Curtain of the Malakoff; Battle of Solferino (1859). *Pils*, Battle of the Alma (1854). *Rigo*, Battle of Magenta (1859). *Barrias*, Debarkation on the coast of the Crimea.

Room VI.: **Bouchot*, Bonaparte dissolving the Council of Five Hundred, 9th Nov., 1799. *Vinchon*, Louis XVIII. tendering the 'Charte' of the constitution, and opening the Chambers. *Couder*, 'Fête de la Fédération' in the Champ-de-Mars, 14th July, 1790. **Couder*, Oath taken on 20th June, 1789, in the Jeu de Paume (p. 289). *Couder*, Institution of the Conseil d'Etat, 1799.

Room VII.: To the left: **C. L. Muller*, Roll-call of the last victims of the Reign of Terror (1794), containing many portraits; the seated figure in the middle is André Chénier, the poet. *Vinchon*, Departure of the National Guard for the army, 1792.

We now return to the Sculpture Gallery (p. 294), which we traverse to the Theatre (p. 289), at the N. end.

The staircase to the left ascends to the *ATTIQUE DU NORD*, a suite of eleven rooms on the Second Floor, containing an immense collection of portraits of sovereigns and other celebrated persons from the 14th to the 19th century. Most of these are uninteresting and of little artistic value, but there are a few good works by *Rigaud*, *Mignard*, *Lebrun*, *Van Loo*, *Coypel*, and others. The rooms also contain a few casts and medals. We descend by the same staircase. Visitors who are pressed for time may omit this part of the collection.

THE II. GALLERY OF THE HISTORY OF FRANCE (Pl. 1-10), parallel with the gallery of sculptures, consists of ten rooms with historical scenes from the years 1797-1835.

1st Room (1830-1835): *Court*, Louis Philippe signing the well-known proclamation of 31st July, 1830, ending with the words: '*La Charte sera désormais une vérité*'. The portraits deserve inspection. — 2nd Room (1824-1830): *Gérard* (1829), Coronation of Charles X. at Rheims (1825). *H. Vernet*, Charles X. reviewing the National Guard in the Champ-de-Mars (1824). — 3rd Room (1814-1823): *Paul Delaroche* (1827), Storming of the Trocadéro near Cadiz, under the Duke of Angoulême, 1823. *Gros*, Louis XVIII. quitting the Tuileries on the night of 19th March, 1815, on being apprised of Napoleon's approach. — 4th Room (1811-1814): *Henri Scheffer* (brother of Ary), after *H. Vernet* (1835), Battle of Montmirail, 1814. *Féron*, after *Horace Vernet* (1835), Battle of Hanau, 1813. *Beaume* (1837), Battle of Lützen, 1813. — 5th Room (1809-1812): *Langlois* (1837), Battles of Borodino (1812), Smolensk (1812), and Castella (1812). — 6th Room (1809-1810): *Meynier* (1812), Napoleon in the island of Lobau after the battle of Easing. *Bellangé* (1837), Battle of Wagram, 1809, a bird's-eye view. *Gautherot*, Napoleon wounded on the battle-field of Ratisbon, 1809 (engravings from this picture are common). — 7th Room (1807-1809): *Hersent* (1810), Taking of Landshut, 1809. *Thévenin* (1811), Taking of Ratisbon, 1809. — 8th Room (1806, 1807): *Camus* (1808), Napoleon at the tomb of Frederick the Great at Potsdam, 1806. *Vafflard* (1810), Destruction of the monument at Rossbach, where the French had been defeated by Frederick the Great in 1757. Over the door: *Röhm* (1808), Military hospital in the château of Marienburg, occupied by Russians and French after the battle of Friedland, 1807. — 9th Room (1800-1805): *Taunay*, The French entering Munich, 1805. — 10th Room (1797-1800): *Hennequin*, Battle of the Pyramids, 1798. *Colson*, Napoleon entering Alexandria, 1798. *Langlois*, Battle of Benouth, 1799.

At the top of the staircase ascending from the vestibule of the chapel, we turn to the right into the —

Main Edifice. The rooms on the N. side of the first floor of the central part of the palace formed part of the *Grands Appartements du Roi*, which also included several rooms to the S. of the Cour de Marbre, parallel with the Galerie des Glaces (see below). The walls are hung with battle-pieces by *Van der Meulen* and his pupils, illustrating the campaigns of Louis XIV.

I. Room, with the Apotheosis of Hercules on the ceiling, by *Lemoine*. — II. Room, with ceiling-painting by *Houasse*, emblematical of royal abundance or magnificence. — III & IV. Rooms (to the left of the last, see Plan) contain drawings in crayon ('Gouaches') by *Van Blarenberghe*, chiefly from the campaigns in the Netherlands in 1745-46. — V. Room, containing large pictures by *Bézuard* and *Alaux* referring to the States General, and a frieze by *Boulanger*, representing the Procession of the States General to the Church of Notre-Dame at Versailles on 4th May, 1789. Model of the statue of Bailly taking the oath in the Jeu de Paume (p. 289). On the wall, tapestry with the Apotheosis of Homer, designed by Ingres. — The rooms on the other side of Room III. are the *Petits Appartements du Roi*, of which at present only the three last are accessible from this side (p. 297). — VI. Room, with a ceiling-painting by *Houasse* and a statue of Louis XIV. by *J. Warin*. — VII. Room, with ceiling-painting by *Blanchard*, representing Diana as goddess of hunting and navigation. On the arches paintings by *Audran*, *Lafosse*, and *Sarrazin*. Busts of Louis XIV. by *Bernini*, and other busts of the royal family. — VIII. Room, with a fine ceiling adorned with paintings by *Audran* (Mars in a chariot drawn by wolves), *Houasse* (Horrors of war), and *Jouvenet* (Benefits of war). — IX. Room, with ceiling by *J. B. de Champagne*; Mercury in a chariot drawn by two cocks. — X. Room, with ceiling by *Lafosse*: Apollo in a four-horse chariot, escorted by the Seasons.

We now enter the **SALON DE LA GUERRE* (Pl. B), so called from its allegorical ceiling-paintings by *Lebrun*: in the cupola, France, hurling thunderbolts and carrying a shield with a portrait of Louis XIV; in the spandrels, Bellona, Spain, Germany, and Holland covering in terror. The walls are lined with parti-coloured marbles and embellished with bronze reliefs. Over the fire-place is a huge plaster relief, by *Coyzevox*, representing Louis XIV. on horseback. — We next enter the —

***GRANDE GALERIE*, also called the *GALERIE DES GLACES* or *DE LOUIS XIV.*, a superbly-decorated hall, 240 ft. long, 35 ft. wide, and 42 ft. high, commanding a beautiful view of the garden and its ornamental sheets of water from the seventeen large arched windows, opposite which are as many mirrors in gilded niches. The paintings on the ceiling, distinguished by great harmony of colouring and wonderfully effective, were executed by *Charles Lebrun*

in 1679-83. They represent, in 21 large scenes and 6 imitations of reliefs, the achievements of Louis XIV. from the Pyrenean Peace in 1659 to the Peace of Nymwegen in 1678. In the centre is a large picture occupying the entire width of the vaulting: 'Le roi gouverne par lui-même'. — King William of Prussia was proclaimed German Emperor in this hall in 1871.

The first door to the left leads from the Galerie des Glaces to the **SALLE DU CONSEIL** (Pl. 5), containing a time-piece with very ingenious mechanism, and adorned with the monogram of Louis XIV. The walls are richly embellished with wood-carving and gilding.

Those who have time to spare may now visit the **PETITS APPARTEMENTS DU ROI**, a series of very tastefully decorated rooms (unnumbered on the Plan). The clocks are almost the only relics of the original furniture. 1. Bedchamber of Louis XV., in which he died on May 10th, 1774. This room contains a model of the statue of Louis XV. erected in the Place de la Concorde (p. 81) and a large picture of his coronation by Sigol. — 2. Salon des Pendules, with a meridian-line marked on the floor. In the middle are several interesting old eight-day clocks. — 3. To the left, Cabinet des Chasses, with a frieze of sporting scenes; below, portraits of Colbert, Louvois, and Louis XIV. — 4. Dining-room, containing an elaborately-decorated desk of the period of Charles X. — We now return through the Salle des Pendules to the Study of Louis XV. (5). — 6. To the left, Cabinet de la Vaiselle d'Or, formerly containing gold plate and jewellery. — 7. Cabinet des Médailles, richly decorated; on the mantel-piece, Dresden china. — 8. Library of Louis XV. and Louis XVI. — This room is adjoined by R. III. of the Grands Appartements (p. 296). Some of these rooms are at present closed for repairs (see p. 296).

Adjoining the Salle du Conseil is the **BEDCHAMBER OF LOUIS XIV.** (Pl. 4), with gorgeous mural decorations, and containing the richly adorned bed of the king. The furniture, in tortoise-shell and gilded bronze, was made by *Charles Andrée Boule* or *Buhl*, court-cabinet-maker under Louis XIV. (1642-1732), whose name has since been applied to this kind of work. The candelabra should also be noticed. The pictures did not form part of the original contents of the room. From the balcony of this apartment, on 1st Sept., 1715, the first chamberlain publicly announced the death of Louis XIV. by exclaiming '*Le roi est mort!*', at the same time breaking his wand of office; then taking another, he exclaimed, '*Vive le roi!*' — We now enter the —

SALLE DE L'ŒIL DE BŒUF (Pl. 3), so called from its oval window, where the courtiers used to await the '*lever*' of the king, and celebrated as the scene of numerous intrigues. The walls are embellished with a frieze of dancing genii.

To the left are the *Première Antichambre* and the *Salle des Gardes* (Pl. 2, 1), containing pictures of battles. We now return to the Salle de l'Œil de Bœuf.

A door to the left here (closed; apply to an attendant) leads to the *Petits Appartements de la Reine* (g, f, h, i, j, k, on the Plan). Most of the original furniture has disappeared.

We now return to the Galerie des Glaces, adjoining which, to the left, is the ***SALON DE LA PAIX** (Pl. C), with ceiling-paintings

by *Lebrun*, representing France surrounded by Abundance and other allegorical figures, while in the spandrels are figures of Holland, Germany, Spain, and France rejoicing in the blessings of peace. On the exit-wall: Portrait of Louis XIV. with the helm of the state, by *Le Moine*.

We now come to the —

GRANDS APPARTEMENTS DE LA REINE (Plan I-VIII), the decorations of which are more interesting than the pictures. Room I., the CHAMBRE DE LA REINE, has tasteful ceiling-paintings in grey and gold, by *Boucher*. To the left: Marriage of Louis XIV. and Maria Theresa of Austria, by *Lebrun*; *Marie Antoinette, by *Mme. Lebrun*; *Maria Leszcinska, by *Nattier*. — Room II. (SALON DE LA REINE). To the right: Louis XIV. visiting the Gobelins Manufactory, a reversed copy of a work by *Lebrun* and *Van der Meulen* (now at the Gobelins manufactory, p. 269), painted as a guide in the execution of tapestry. Ceiling-painting by *Michel Corneille*, representing Mercury as the patron of the arts and sciences. These two rooms were successively the bedroom and drawing-room of Maria Theresa, Maria Leszcinska, and Marie Antoinette. — Room III., the SALON DU GRAND COUVERT or ANTICHAMBRE DE LA REINE, has fine ceiling-decoration, after *Lebrun*, representing Darius at the feet of Alexander. Among the pictures are the following originals: Louis XIV. on horseback, by *Lebrun*; Turenne defeating the Spanish troops at the Canal of Bruges (1567), by *Lebrun* and *Vander Meulen*; Philip of France, Duke of Anjou, proclaimed King of Spain as Philip V. (1700), painted by *Gérard* in 1834. — In Room IV., the SALLE DES GARDES DE LA REINE, the walls of which are lined with marble, are several interesting busts: Louis XVI., Marie Antoinette, both probably by *Houdon*; Maria Leszcinska, by *G. Coustou*; Mme. Elisabeth. This room was invaded by the mob in 1789, when three guards sacrificed themselves to save the queen. The ceiling-painting by *Noël Coypel* represents Jupiter accompanied by Justice and Peace. — Room V., the SALLE DU SACRE DE NAPOLEON, was not one of the queen's apartments, but was used by the king's body-guard. The picture of the Coronation of Napoleon, by *David*, formerly exhibited here, is now in the Louvre. Among the paintings still here are: *C. Vernet*, Battle of Marengo; *David* (1810), Napoleon distributing Eagles to the Army in 1804; *Gros* (1806), Battle of Aboukir (1799). In the centre of the room: Last moments of Napoleon I., by *Vela*, a sitting figure in white marble. To the right we enter Room VI.: Campaigns of 1792, 1793: *Lami* (1836), Battles of Hondschooten and Watignies. — Room VII., to the left: *Bellangé* (1836), Battle of Fleurus.

A small door to the left leads to three *Cabinets*, containing pictures illustrating the campaigns of 1794-96. They may also be entered from the other side, from the landing of the Escalier de Marbre (Pl. A; p. 300).

Room VIII., continuation of VI (1792): Portraits of celebrated soldiers, represented according to the rank they held in 1792. Above

the door: Bonaparte, 'lieutenant-colonel'; Murat, 'sous-lieutenant', by *Paulin Guérin*; Berthier, 'maréchal de camp', by *Lépaulle*; opposite, Bernadotte, 'lieutenant', by *Amiel*; then Gérard and Marceau, 'volontaires'; Soult and Junot, 'sergents', and many others. Among the large paintings here are two by *H. Vernet*: the Cannonade of Valmy, and the Battle of Jemappes, at both of which Louis Philippe distinguished himself (1792); then, *Cogniet*, Departure of the National Guard to join the army. In the centre of the room is a column in Sèvres porcelain, embellished with paintings, and crowned with a statue of Victory, which was presented by the city of Paris to Napoleon I., on the occasion of his marriage with Marie Louise.

A few steps to the left ascend to the SALLES DES AQUARELLES DES CAMPAGNES DE 1796 À 1814 (Pl. D). The water-colours here, executed by French staff-officers, are interesting on account of the subjects alone.

South Wing. Quitting the 8th Room to the right, we cross the landing of the *Escalier des Princes* (Pl. E), and enter the —

****GALERIE DES BATAILLES.** This is a magnificent hall, 132 yds. in length, and 14 yds. in width, and is divided into two parts. It contains 33 admirable compositions by modern painters, and busts of 80 celebrated generals who have fallen in battle, their names being inscribed on tablets in the corners and window-recesses.

Left: **Ary Scheffer* (1837), Battle of Tolbiac, near Cologne (496); **Steuben* (1836), Battle of Tours (732); **Ary Scheffer* (1836), Submission of the Saxon Duke Wittekind to Charlemagne (785); *Schnetz*, Count Eudes defending Paris against the Normans (885-886); **Horace Vernet*, Philip Augustus victorious over the Barons at Bouvines (1214); *Eug. Delacroix* (1837), Battle of Taillebourg (1242); *Larivière*, Battle of Mons-en-Puelle (1304); *Henri Scheffer* (brother of Ary, 1836), Battle of Cassel in Flanders (1328); *Larivière*, Battle of Cocherel (1364); *H. Scheffer*, Joan of Arc relieving Orleans (1429); *Larivière*, Battle of Castillon (1453); *Féron*, Charles VIII. entering Naples (1495); *Fragonard*, Francis I. defeating the Swiss at Marignan (1515); *Picot*, The Duc de Guise taking Calais from the English (1558); *Gérard*, (1817), Henri IV. entering Paris (1594); *Heim*, Condé defeating the Spaniards at Rocroy (1643); *Franque*, Condé defeating the Spaniards at Lens (1645); *Larivière*, Siege of Dunkirk by Turenne (1658); *Alaux* (1837), Capture of Valenciennes (1677).

On the other side, in returning: *Alaux*, Battle of Villaviciosa, the Duc de Vendôme defeats the Imperial army under Starhemberg (1710); Marshal Villars defeating Prince Eugene at Denain (1712). **H. Vernet* (1828), Battle of Fontenoy, in which the English were defeated by Marshal Saxe (1745); *Couder*, Battle of Læffelt or Lawfeld, near Maastricht (1747); *Couder*, Siege of Yorktown in America, conducted by Generals Rochambeau and Washington (1781); *Mauzaisse*, Battle of Fleurus (1794). — **Philippoteaux*, Battle of Rivoli, Bonaparte defeats the Austrians (1797); *Bouchot*, Battle of Zürich (1799); *H. Schopin*, Battle of Hohenlinden (1800); **Gérard*,

Battle of Austerlitz (1805). *Vernet*, Napoleon addressing the Guards before the Battle of Jena (1806); Battle of Friedland (1807); **Battle of Wagram (1809).

The following *SALLE DE 1830* contains five large pictures referring to the 'July Monarchy': — *Larivière*, Arrival of the Duke of Orléans at the Place de l'Hôtel de Ville, where he is received by Lafayette, 31st July, 1830. *Gérard*, The declaration of the deputies read, and the Duke of Orléans proclaimed 'lieutenant-général du royaume'. *Ary Scheffer*, Louis Philippe at the Barrière du Trône, receiving his eldest son the Duc de Chartres, afterwards Duc d'Orléans, at the head of his regiment of hussars, 4th Aug. 1830. *Eug. Devéria*, Louis Philippe proclaimed king, and swearing fidelity to the charter, 9th Aug. 1830. *Court*, The King distributing colours to the National Guard in the Champ-de-Mars (p. 281).

On leaving this room, we enter a *SCULPTURE GALLERY*, parallel with the *Galerie des Batailles*, and containing statues and busts of eminent persons of the 17th and 18th centuries. Most of these are by *Rude*, *Houdon*, *Duret*, and other modern masters, but there are also a few by *Prieur*, *Anguier*, and their contemporaries.

We may now return to the *Escalier des Princes*, where, in a recess to the right, is a beautiful group of the Three Graces, by *Pradier*. Thence we may descend either to leave the palace or to visit the S. wing and central part of the ground-floor. It is, however, preferable to proceed first to the second floor. To do so we return to the *Salle du Sacre* (Pl. V; p. 293), cross it obliquely to the door in the corner (Pl. F), and thus regain the *Escalier de Marbre* (Pl. A). The *Escalier de la Reine* ascends hence to the —

Second Floor. The door at the head of the staircase, inscribed 'Attique Chimay', leads to a series of small rooms above the *Appartements de Marie Antoinette* (p. 298; Pl. a-k). The *Attique du Nord* has been already described (p. 295).

ATTIQUE CHIMAY. 1st Room (Pl. a). Sea-pieces and naval battles, by *Gudin*, *Crépin*, and *Isabey*. In an adjoining room are some good paintings by *Philippoteaux*, *Bergeret*, *Révoil*, and *Biard*. — 2nd Room (Pl. b). Portraits of members of the Orleans family, by *Winterhalter* (d. 1873) and *Ingres*. — We now pass through the door near the window. — 3rd Room (Pl. c). To the right, **Bonnat*, Thiers as President of the Republic, C. de Montalivet, the senator. *Philippoteaux*, Battle of Montebello (1859). *Isabey*, Body of Napoleon I. brought to France; *Bellangé*, Capture of the Mouzaia (1840), Battle of the Alma (1854); *Bellangé* and *Douzats* (1862), Review in the Tuileries under the First Empire (1810); at the end, Portrait of Victor Hugo, after *Bonnat*; *B. Ulmann*, Thiers at a meeting of the Chamber of Deputies. — 4th and 5th Rooms (Pl. d, e). Portraits of the Bonapartes by *Gros*, *H. Scheffer*, *Hébert*, *Gérard*, *Robert-Lefevre*, and *Dubufe*. To the right of the fireplace: **David*, Bonaparte, First Consul, crossing the St. Bernard in 1800 (an imaginative work). — Adjoining this room are six cabinets containing portraits of eminent Frenchmen, etc. In the 6th.: *H. Vernet*, The Duke of Orléans (Louis Philippe) setting out for the Hôtel de Ville (1830).

We now regain the staircase-vestibule, which is adorned with marble busts (Rossini, etc.). Opposite is a door leading to the *ATTIQUE DU MIDI*, a series of rooms, which visitors formerly entered after having seen the *Salle de 1830* (see above), and which contains a *GALLERY OF PORTRAITS* of celebrated persons from the 13th cent. downwards (S. wing, above the sculpture-gallery of the first floor).

1st Room. *Heim*, Picture representing a lecture delivered by Professor Andrieux, with 46 portraits of eminent authors, actors, and actresses. — 2nd Room. On the right, *Gérard*, Charles X.; several other portraits of members of the Bourbon family; *Schlesinger*, Sultan Mahmoud Khan II.

(d. 1839); to the left, **Paul Delaroche*, Pope Gregory XVI. (d. 1846); (entrance-wall), *Wilkofsky*, Portrait of Horace Vernet (d. 1863). — 3rd Room. *Galerie des Portraits de l'Empire et de la Restauration*. *Rouget*, Napoleon I. showing the infant king of Rome to the dignitaries of the Empire; Empress Josephine. *Gros*, Count Fournier-Sarlovèze (d. 1827); *Guérin*, after *Gérard*, Empress Marie Louise. — We next enter the 4th Room, divided into two sections by a partition, situated above the Escalier des Princes (Pl. E), and called the *SALLE DES RÉSIDENCES ROYALES*, from the views of palaces, châteaux, and royal pleasure-grounds which it contains. — 5th Room, *SALLE DES ANGLAIS*. *Queen Victoria and *Prince Albert (d. 1861), painted in 1842 by *Winterhalter*; Ernest Augustus, King of Hanover (d. 1851), Pitt, Fox, and others. — 6th Room. On the right: *Gérard*, Lætitia Ramolino, mother of Napoleon I.; below, Emp. Paul I. of Russia (d. 1801); Mirabeau; Mme. Lebrun, the artist (d. 1842); to the left, Duchess of Orleans; Washington; *Mme. Lebrun*, Marie Antoinette and her children. — 7th Room. Above the fire-place, Louis XV. when a child. — 8th Room. To the right, *Michiel van Musscher* (Dutch painter, d. 1705), Portraits of himself and family; to the left, *H. Lehmann*, Diana of Poitiers; after *Largillière* (d. 1746). Town Council of Paris (original in the Louvre, Collection La Caze); to the right, *Ary Scheffer*, Henri IV. — 9th Room. Portraits of kings and princes of the 15th and 16th centuries.

We now return to the first floor, and descend by the *Escalier des Princes* (Pl. E; p. 299) to the ground-floor.

Ground Floor of the S. Wing. We first visit the rooms to the right, which contain the *GALERIE DE L'EMPIRE*, consisting of 13 saloons devoted to the campaigns of 1796-1810. Many of the pictures and sculptures in these rooms were removed for the sittings of the Chamber of Deputies in 1871-79 and have not been replaced.

1st Room (1796). Unimportant works. — 2nd Room (1797). *Lethière* (1802), Conclusion of peace at Leoben. — 3rd Room (1798). *Girodet-Trioson*, Revolt in Cairo. *Guérin*, Napoleon pardoning the rioters at Cairo. — 4th Room (1802-1804). *Hennequin*, Napoleon distributing the crosses of the Legion of Honour in the camp at Boulogne (1804). — 5th Room (1804). *Sérangei*, Napoleon at the Louvre after his coronation, receiving deputations from the army. — 6th Room (1805). Small pictures of scenes from the first campaign of the Grande Armée. — 7th Room. *Salle des Pas-Perdus* of the *Chambre des Députés*, formerly containing busts of members of the imperial family. — 8th Room (1805). *Meynier*, Marshal Ney restoring to the 76th Regiment of Foot its colours found in the arsenal at Innsbruck. **Debret* (1806), 'Napoléon rend honneur au courage malheureux', the words used by the emperor in saluting a waggon containing wounded Austrians in Italy. — 9th Room (1805). *Gros* (1812), Interview of Napoleon with the Emperor Francis I. of Austria during the bivouac on the day after the battle of Austerlitz, 3rd Dec., 1805. 'Je vous reçois dans le seul palais que j'habite depuis deux mois', were the words with which Napoleon addressed Francis. 'Vous tirez si bon parti de cette habitation, qu'elle doit vous plaire', was the reply. — 10th Room (1806, 1807). *Meynier* (1810), The French army entering Berlin, 27th Oct., 1806. *Berthon*, Napoleon receiving the deputies of the senate in the palace at Berlin. — 11th Room (1807). *Gosse* (1810), Interview of Napoleon with the King and Queen of Prussia, at Tilsit. — 12th Room (1808). *Regnault* (1810), Marriage of Prince Jerome with the Princess Frederica of Wurtemberg. — 13th Room (1809, 1810). *Debret* (1810), Napoleon addressing his German troops before the battle of Abensberg. *Rouget* (1836), Marriage of Napoleon with the Archduchess Marie Louise of Austria, 1810.

SALLE DE MARENGO (1800), so called from a picture by *C. Vernet*, now in the Salle du Sacre (p. 298). *Thévenin* (1806), The French army crossing the St. Bernard.

The adjoining *SALLES DES MARINES* (I-IV), containing sea-pieces by *Gudin* and others, are now occupied by the President of the Chamber of Deputies and are not shown to the public.

The GALLERY OF SCULPTURES, parallel with the Galerie de l'Empire, chiefly contains *Statues* and *Busts* of celebrities of the republic and empire, and generals who fell in battle.

To the right of this gallery is the former CHAMBRE DES DÉPUTÉS, containing, above the chair of the president, a large painting by *Coudet*, the Opening of the States General on 5th May, 1789. This hall is also used for the Congress, i.e. the united meeting of the senate and the chamber of deputies.

We now leave the S. Wing by the Cour des Princes (see Plan, p. 292). Those who are fatigued may omit the central part of the ground-floor, which is comparatively uninteresting, and pass directly into the gardens (p. 303).

Central Part of the Ground Floor. Here we turn to the left, cross a passage leading to the gardens, traverse several vestibules, and reach a series of rooms devoted to the *Admirals, Constables, and Marshals of France* (Pl. I-IX and 1-8).

Room I. Portraits of French admirals from 1270 to 1844. Between the windows: Anne of Austria, by *Steuben* (over life-size). — Room II. Constables of France from 1060 to 1621. On the back-wall, two equestrian portraits: Olivier, Sire de Clisson (d. 1407), by *Emile de Lansac*; Louis de Champagne, Count de Sancerre (d. 1402), by *Ziegler*. — Room III. Marshals of France from 1391 to 1565. On the back-wall, equestrian portraits: Lohéac (d. 1486), by *Féron* (1835); Pierre de Rohan (d. 1514) and Gian Giacomo Trivulzi, Marquis of Vicevano (d. 1519), both by *Monvoisin* (1835); Jacques de Cbabannes (d. 1525), by *E. de Lansac*. A few marshals are commemorated by inscriptions instead of portraits. — Room IV. Marshals from 1339 to 1656. — Room V. Marshals of the 17th cent.: Henri de la Tour d'Auvergne, Vicomte de Turenne (d. 1675), by *Mauzaisse*. — Room VI., with fine rococo decorations, once the library of Marshal Condé. On the back-wall: "Equestrian portrait of Count Rantzau (d. 1650), by *Alaux* (1834).

Room VII. (corner-room). Marshals of the 16th and 17th cent.: Charles de Mouchy, Marquis d'Hocquincourt (d. 1658), by *Caminade*; Count de Miossens (d. 1676), by *Mauzaisse* (1833). By the windows of this and the following rooms are several plaster casts of funereal monuments. — Room VIII. (Salle Dorée). Marshals of the 17th and 18th cent.: Frédéric Armand, Duke of Schomberg, properly Schönburg, who served successively in the armies of the Netherlands, France, Brandenburg, and England, and fell at the battle of the Boyne in 1690 (French school-piece of the 17th cent.). On the back-wall: Equestrian portrait of François Henri de Montmorency, Duke of Luxembourg (d. 1695), by *Wachsmutt*; Count de Tourville (d. 1701), by *Eug. Delacroix*. — Room IX. On the back-wall: "Sébastien le Prestre, Seigneur de Vauban (d. 1707), the celebrated military engineer, by *Larivière*. Passing through the door on the left we now reach the —

SALLE DES ROIS, which contains modern portraits of the 67 monarchs of France from Clovis I. (d. 510) to Napoleon III. (d. 1873). — In the centre: Half-figure of Louis XII. (d. 1515), in bronze, by *Lor. da Mugiano*; Bronze statue of Napoleon I., by *E. Seurre*.

The adjoining SALLE DES RÉSIDENCES contains views of the royal châteaux of France. — On the other side of the vestibule are four SALLES DE TABLEAUX-PLANS, with representations of sieges and conquests of the years 1627-32. — From the vestibule we pass to the right into the —

GALERIE LOUIS XIII., embellished with statues of Louis XIII. and Anne of Austria, by *Guillain*.

Many of the battle-pieces on the walls are copies, but the following are original: Battle of Rocroy (1643), with Marshal Condé in the middle,

by *Schnetz*; Louis XIV. receiving satisfaction from Pope Alexander VII. through Cardinal Chigi in 1664, by *Ziegler*. — At the end of this gallery are several other SALLES DES MARÉCHAUX.

Room 1. Marshals of the 18th century. To the left, Duke Maurice of Saxony (Marshal Saxe; d. 1750), natural son of Augustus the Strong, King of Saxony, and the Countess of Königsmark; Count Löwendal (d. 1750), natural son of Frederick III. of Denmark, successively in the Austrian, Saxon, Russian, and French service; both portraits by *Couder*. — Room 2. Marshals of the second half of the 17th century. Immediately to the right, Louis Fr. Armand du Plessis, Duc de Richelieu (d. 1788; great-nephew of the Cardinal), by *Couder*. Charles de Rohan, Prince de Soubise (d. 1789), who was defeated by Frederick the Great in 1757, a contemporary French work. — Room 3. (corner). Marshals of the reign of Louis XVI. and of the Empire, Luckner, guillotined in 1794, by *Couder*; *Joachim Murat, Grand Duke of Cleve and Berg (d. 1815), by *Gérard*. — Room 4. Marshals of the Empire. The artistic value of the portraits here is small; the best is to the left, Joseph Lefebvre, Duke of Dantzig (d. 1820), by *Davin-Mirvaux*. — Room 5. Marshals of the Empire. Claude Vict. Ferrin, Duc de Belluno (d. 1841), by *Gros*; *Laurent, Marquis de Gouvion St. Cyr (d. 1830), by *H. Vernet*; Prince Poniatowski (d. 1813), by *Vauchelet*; Marshal Clarke, Duc de Feltre (d. 1818), by *Descamps*; Count Molitor (d. 1841), by *H. Vernet*. — Room 6. Marshals and Admirals of the reign of Louis Philippe. — Room 7. Marshals and Admirals of the reign of Napoleon III. — Room 8. 'Guerriers Célèbres', not marshals, from Godfrey de Bouillon (d. 1190) onwards. Dumouriez, general of the Revolution and the Empire (d. 1823), by *Bouillard*; adjacent, B. C. Joubert, general of the Republic, who fell in 1799 in an engagement with Suvaroff, by *Bouchot*.

The door near the vestibule of the chapel leads to the Gardens.

The *Gardens (comp. Map, p. 287) at the back of the Palace of Versailles, with their small park and ornamental sheets of water, are partly at least in the same condition as when first laid out by *Le Nôtre* (d. 1700), the most famous landscape-gardener of his time. A more artificial style than that of *Le Nôtre* can hardly be conceived. His chief object seems to have been to subject nature to the laws of symmetry, and to practise geometry, architecture, and sculpture upon lawns, trees, and ponds. On the other hand the grounds are interesting on account of their quaint, solemn, old-fashioned appearance, which harmonises admirably with the heavy and formal architecture of the palace, and is in perfect keeping with the notions of art which prevailed in the time of Louis XIV. The greater part of the grounds, which are not very extensive, may be surveyed from the terrace of the palace. They are adorned with numerous statues and vases, some of which are copies from celebrated antiques, and others originals of the 17th and 18th centuries. The playing of the GRANDES EAUX always attracts vast crowds of spectators, and on these occasions trains run between Paris and Versailles every 5 min. in the middle of the day. This imposing spectacle, which it costs 8-10,000 fr. to exhibit, generally takes place on the first Sunday of every month from May to October, and is always advertised long beforehand in the newspapers and street placards. The best way to avoid the crush is to proceed to Versailles early, and to leave it immediately after the playing of the fountains, as most of the spectators remain till a later hour. The fountains play between 4 and 5 o'clock, but not simultaneously.

The order is as follows (marked by a red line on the Plan, p. 287). First the Petites Eaux — viz. those of the *Bassin de Latone*, the **Salle des Rocailles* (Pl. 1), the **Bosquet de la Colonnade* (Pl. 2), the *Bassin d'Apollon*, the *Bassin d'Encelade* (Pl. 3), that of the *Obélisque* (Pl. 4), and the *Bains d'Apollon* (Pl. 5). Next the Grandes Eaux, which begin to rise about 5 o'clock, — viz. those of the *Allée d'Eau*, the *Bassin du Dragon*, and the *Bassin de Neptune*. The jets of these are about 7½ ft. in height, but they do not play for more than 20 minutes. A good place should if possible be secured in time. The visitor unacquainted with the grounds had better follow the crowd.

Among the principal sculptured groups are those in the *Parterre d'Eau*, in front of the palace, and the *Parterres du Midi* and *du Nord* (p. 305), to the right and left, such as the Ariadne and the statue of Napoleon I. (by *Bosio*), both in the *Parterre du Midi*. Near the steps descending to the lower part of the garden, are two large basins, the *Fontaine de Diane* to the right, and the *Fontaine du Point du Jour* to the left, both adorned with groups of animals in bronze and other good sculptures. To the right: Two lions fighting with a boar and a wolf, by *Van Clève*; Noon or Venus, by *G. Marsy*; Evening or Diana, by *Desjardins*; Air, by *Le Hongre*. To the left: Bear and tiger, a stag and dog, by *Houzeau*; Spring, by *Magnier*; Water, by *Legros*.

This point commands a survey of the huge, monotonous façade of the palace, 456 yds. in length (with 375 windows). The building, however, presents a more pleasing appearance when seen from the *Pièce d'Eau des Suisses*, a large sheet of water to the S. of the *Parterre du Midi*. On this side two flights of marble steps, 103 in number, and 22 yds. in width, descend to the *Orangery*. The orange-trees, about 1200 in number, are dispersed throughout the gardens in summer. One of them is said to be upwards of 450 years old. Adjoining the Swiss pond is a poor equestrian statue of Louis XIV., by *Bernin*, transformed by *Girardon* into a *Marcus Curtius*. Beyond the pond extends the *Bois de Satory*.

The former *Potager* or vegetable-garden, near the *Pièce des Suisses*, on the side next the town was converted in 1873 into a *School of Horticulture*.

At the foot of the steps which descend beyond the *Parterre d'Eau* is situated the large **Bassin de Latone*, constructed by *B. Marsy*, consisting of several steps of red marble, on which there are gilded frogs, lizards, and tortoises spouting water against a fine group in white marble of Latona with Apollo and Diana. According to the myth, Latona having besought Jupiter to chastise the peasants of Lycia for having refused her a draught of water, the god metamorphosed them into frogs (*Ovid's Metamorph. vi. 313-381*).

The *Statues* in the *Pourtour de Latone* are among the finest in the garden. On the right as we approach from the palace is a singular statue representing Melancholy, by *La Perdrix*, the book, purse, and bandaged mouth being allusions to the proneness of scholars, misers, and taciturn persons to this mood. Then *Antinous*, *Captive Barbarian*, a *Faun*, *Bacchus*, *Faustina* as *Ceres*, *Commodus* in the character of *Hercules*, *Urania*, and *Ganymede*. On the other side, as we return towards the palace, are the *Dying Gladiator*, *Apollo Belvedere*, *Urania*, *Mercury*, *Antinous*, *Silenus*, *Venus Kallipygos*, *Captive Barbarian*, *Fire*, and *Lyric Poetry*.

At the end of the *Tapis Vert*, a long lawn beginning near the basin of Latona, is the *Bassin d'Apollon*, with a group of the sun-god in his chariot, environed with tritons, nymphs, and dolphins (known as the 'Char Embourbé'). The figures, by *Tuby*, after *Lebrun*, are in lead. The cruciform *Canal* to the W. of the basin of Apollo, about 1 M. in length, extends to near the *Grand Trianon* (p. 306).

To reach the *Grand Trianon* hence we follow the avenue immediately to the right of the railing; the other is not open all the way.

There are several other basins and groups of statuary in different parts of the grounds, which are worthy of a visit when the fountains play. (On days when the fountains are not playing visitors are allowed to inspect these basins only if accompanied by a guide, procured at the *Tapis Vert*.) On the S. side, on our right as we return towards the palace, are the **Bosquet de la Colonnade* (Pl. 2), containing several basins of marble, and adorned in the centre with the Rape of Proserpine, in marble, by *Girardon*, after *Lebrun*. Farther on are the *Salle des Marronniers* (Pl. 2), with statues of Antinous and Meleager, and antique busts; the *Bosquet du Roi* and the *Bassin du Miroir*, near which is the *Bassin de l'Hiver* or *de Saturne* in the *Allée de l'Hiver*. Then the *Bosquet de la Reine*, where the affair of the diamond necklace is said to have taken place. Here are bronze figures of the Medicean Venus and a Fighting Gladiator. In the broad avenue descending hence is a basin with a Bacchus and small satyrs, in lead, by the brothers *Marsy*. On our left as we again descend are the *Salle de Bal* or *des Rocailles* (Pl. 1), with a cascade and a group of Cupid and a Satyr, and the *Quinconce du Midi* (concerts given here in summer; terminal figures after *Poussin*).

On the N. side, or to the left of the *Tapis Vert* as we re-ascend, are the *Bassin d'Encelade* (Pl. 3), where the giant, half-buried beneath Etna, spouts forth a jet of water 74 ft. in height; the *Obelisk* (Pl. 4), a fountain deriving its name from the form of the *Cent Tuyaux*, or hundred jets of water; the *Bassin du Printemps*, in the transverse walk in the centre; the *Bosquet des Dômes*, lower down on the right (the 'dômes' themselves which furnished the name have been removed); the *Quinconce du Nord*, the *Bassin de l'Été*, the *Rond Vert*, and the **Bosquet des Bains d'Apollon* (Pl. 5). A grotto in this last 'bosquet' contains a fine group by *Girardon* and *Regnaudin*, representing Apollo attended by nymphs. There are also two groups of the Steeds of Apollo, at the sides, by *Guérin* and the brothers *Marsy*.

We now regain the *Parterre du Nord* (comp. p. 304), which is arranged similarly to that on the S. side. Among the sculptures here are a Knife-grinder, a Venus (stooping) by *Coyzevox*, and the *Fontaine de la Pyramide*, by *Girardon*.

Beyond the *Parterre du Nord*, to the N., is another sloping parterre, at the beginning of which is the *Bath of Diana*, a square basin, with lead-reliefs of **Diana* and her nymphs bathing, by

Girardon; adjacent are statues of Anger, by *Houzeau* and a Flute-player, by *Jouvenet*. Then the *Allée d'Eau* or *des Marmousets*, consisting of 22 groups, with three children in each, in basins, and supporting goblets whence the water descends into the *Bassin du Dragon* (the dragon restored in 1890 by Tony Noël), and thence to the **Bassin de Neptune*, the largest in the grounds. The latter is adorned with five groups in metal: Neptune and Amphitrite, by the elder *Adam*; the Ocean, by *Le Moyne*; Proteus guarding the flocks of Neptune, by *Bouchardon*, and two dragons, each bearing a Cupid, by *Girardon*.

Near the Bassin de Neptune, is the *Bosquet de l'Arc de Triomphe* (Pl. 6), recently restored, with a statue of France between Spain and Germany, by *Coyzevox* and *Tuby*. The other statues have been brought hither from bosquets that have been removed: *Æsop* and Cupid; Galatea, by *Tuby*; Flora, by *Magnier*; Break of Day, by *Legros*; Arion, by *Raon*, and Meleager. To the left (W.) is the *Avenue de Trianon*, leading to the two Trianons (see below).

The **Grand Trianon**, a handsome villa of one story, in the form of a horse-shoe, situated about $\frac{3}{4}$ M. to the N. W. of the terrace of the palace, was erected by Louis XIV. from plans by *Mansart* for Madame de Maintenon. It is reached by the Avenue de Trianon, which begins at the Bassin de Neptune (see above). The villa is open at the same times as the Palace of Versailles (p. 290), but visitors are conducted through it by an attendant, whose attempts at hurrying should not be yielded to. It contains several richly-furnished apartments, and a few good works of art by Mignard, Lebrun, and Boucher.

The SALON DES GLACES contains a table, of which the top, made of single piece of oak, is 9 ft. across. In the SALON DE FAMILLE is a table given by Charles IV. of Spain to Napoleon I. The GRANDE VESTIBULE, in which the famous trial of Marshal Bazaine took place in 1873, contains a group in marble by *Vinc. Vela* (1862), representing France and Italy exchanging the kiss of peace, presented to the Empress Eugénie by the ladies of Milan. In the next room, to the right, is an Olympia by *Etez*. Other rooms contain Japanese and Sèvres porcelain, some fine malachite vases given to Napoleon I. by Alexander I. of Russia, paintings by *Boucher*, etc. In one of the PETITS APPARTEMENTS DE NAPOLEON I. is a mosaic table from Rome. — The custodian points out the chief curiosities.

The *Grand Trianon Garden*, which is unattractive and in a state of neglect, is open from 8 a.m. to 4 or 5 p.m.

To the right of the Grand Trianon is a **MUSÉE DES VOITURES* (open at the same times as the Trianon), being a collection of state-carriages from the time of the first Empire to the baptism of the Prince Imperial in 1856, sledges of Louis XIV., sedan-chairs, etc. A collection of harness from the time of Louis XIV. to the present day is arranged in glass-cases.

The **Petit Trianon**, a little to the N.E. of the other, erected by Louis XV. from the plans of *Gabriel*, was a favourite resort of Marie Antoinette. It is tastefully fitted up, and contains paintings by *Natoire*, *Pater*, *Watteau*, etc. (open as the Grand Trianon).

A visit should be paid to the *JARDIN DU PETIT TRIANON, which is tastefully laid out in the English style and contains some fine exotic trees, an artificial lake, a 'Temple of Love', and a 'hamlet', where the court-ladies played at peasant life.

FROM VERSAILLES TO ST. GERMAIN-EN-LAYE. — 1. By the *Chemin de Fer de Grande-Ceinture*, 14 M., in $\frac{3}{4}$ -1 $\frac{1}{4}$ hr. (fares 2 fr. 20, 1 fr. 80, 1 fr. 50 c.). — The train starts from the Gare des Chantiers (p. 287), threads a short tunnel, and passes near the Pièce d'Eau des Suisses (p. 304). Fine view of the palace from behind.

4 M. St. Cyr, with a celebrated military school, attended by 750-800 pupils from 16 to 20 years of age and furnishing 350 officers to the army every year. The school now occupies the 'Maison d'Education' established here by Mme. de Maintenon, for which Racine composed his 'Esther' and 'Athalie'. St. Cyr is also a station on the Ligne de Bretagne. — 5 $\frac{1}{2}$ M. *Bailly*. — Beyond (7 M.) *Noty-le-Roi* the train enters the forest of Marly (p. 312). Short tunnel, beyond which a junction line diverges to the right to the railway to St. Germain viâ Marly-le-Roi (p. 311). — 8 $\frac{1}{2}$ M. *Le Joutet-d'Eau*. On quitting the wood we enjoy a fine view to the right. — 10 $\frac{1}{2}$ M. *Marcel-Marly*. Hence to *St. Germain* (W. station), see p. 312.

2. By the *Chemin de Fer de l'Ouest*, as far as Asnières (comp. p. 285), and thence by the line to St. Germain (see p. 313), in 1 $\frac{1}{2}$ hr. (through-fares 1 fr. 75, 1 fr. 45 c.).

From Versailles to the *Valley of the Bièvre*, see p. 333.

14. From Versailles to Rambouillet.

19 $\frac{1}{2}$ M. RAILWAY from the Gare des Chantiers in $\frac{1}{2}$ -1 hr. (fares 3 fr. 75, 2 fr. 85, 2 fr. 5 c.). — From Paris (Gare Montparnasse), 30 M., in 1-1 $\frac{1}{2}$ hr. (fares 5 fr. 90, 4 fr. 45, 3 fr. 20 c.).

Beyond a short tunnel and the gardens of Versailles, the line to St. Germain (see above) diverges to the right. Fine view, on the same side, extending to the Forest of Marly (p. 312). — 3 M. *St. Cyr* (see above); the station of this line is near the military school. Farther on, the line to Cherbourg diverges to the right, and we pass, on the same side, the fort of St. Cyr and the pond of St. Quentin, one of the reservoirs for the fountains of Versailles. — 7 M. *Trappes*. About 3 M. to the S.S.E. lie the scanty remains of the ancient *Abbaye de Port-Royal*, a favourite retreat, from 1625 to 1656, of men of learning and religion, around whom clustered some of the most illustrious younger men of the day, such as Pascal and Racine. The attachment of the society to Jansenism led to its dispersion and to the destruction of the convent. — Near (10 M.) *La Verrière* we pass, on the right, an ancient house of the Templars, with a Gothic chapel of the 13th cent.; to the left, a small lake. A public conveyance plies every morning to (5 M.) *Dampierre* (p. 340) and (7 $\frac{1}{2}$ M.) *Chevreuse* (p. 339). — 13 M. *Les-Essarts-le-Roi*. From (15 $\frac{1}{2}$ M.) *Le Perray* an excursion may be made to Vaux-de-Cernay (p. 340; 4 $\frac{1}{2}$ M. to the E.); viâ *Auffargis* and the valley of the Rû des Vaux. — We now traverse a small wood, beyond which the church of Rambouillet comes into view on the right.

19 $\frac{1}{2}$ M. **Rambouillet** (*Lion d'Or, Croix Blanche*, Rue Nationale,

near the château), a town with 5633 inhab., known for its old château, where Francis I. died in 1547. The château afterwards belonged to Charles d'Angennes, husband of the celebrated Marquise de Rambouillet (d. 1665), and was acquired for the crown by Louis XVI. Charles X. signed his abdication here in 1830.

The Rue de l'Embarcadère, to the left as we quit the station, leads to (5 min.) the Place de la Foire, whence we may enter the Small Park (see below).

The *Château* or *Palais National*, reached by the Rue Nationale and the avenues in the park beyond the ornamental water, consists of a number of incongruous buildings, surrounding an old crenelated tower. Neither exterior nor interior is of any special interest. The long building at the entrance is a preparatory school for infantry soldiers.

The great attraction of Rambouillet is the **Parks* of the château, which are the finest in the environs of Paris, surpassing the gardens of Versailles in size, variety, and natural beauty, and containing many charming and secluded walks. In front of the château is a *Parterre*, adjoined by the *Small Park*. The sheet of water in the latter is diversified by several islets (boat 50 c. per hr. for each pers.). To the right, beyond this lake, is the *Parc Anglais*, which we reach most directly by skirting the left margin of the lake, and passing through a magnificent avenue of Louisiana cypresses, said to be unique in Europe. The English Park contains streams of water, a chalet, and a hermitage. To the right of this park, to the N.E. of the lake, is a *Dairy* constructed by Louis XVI., with a temple and an artificial grotto. Beyond, at the top of the avenue, is a *Farm*, where Napoleon I. kept the first merino sheep brought from Spain to France. To the right, between the Parc Anglais and the N. part of the town, extends the *Great Park*, which covers 3000 acres and contains numerous avenues of noble trees.

The *Church* of Rambouillet, at the end of the Rue de la République, is a modern Gothic edifice, built in 1868.

15. From Paris to St. Cloud, Sèvres, and Meudon.

To St. Cloud. *Railway* (Rive Droite) see pp. 285, 286. Fare 80 or 55 c. The *Ligne des Moulineaux* from the Gare St. Lazare or the *Gare du Champ-de-Mars* (to be removed to the Esplanade des Invalides), is preferable: 9½ or 5½ M., in 34 or 25 min., fare 80 or 55 c. and 65 or 45 c. In St. Cloud the station is in the lower part of the town, at the bridge. — *Steamboats* (p. 22), pleasant when not crowded, every ¼ hr. in summer, but less frequently at other seasons. Fare 20 c., on Sundays and holidays 30 c.; from Suresnes to St. Cloud (2 M.) 25 c. The journey takes 1 hr. with, and 1¼ hr. against the stream. — *Tramway (TA)* from the Quai du Louvre, starting every ½ hr., in 1-1¼ hr.; fare 50 c., outside 35 c.

To Sèvres. *Railway*, either on left bank to Sèvres (pp. 286, 287), or by the *Ligne des Moulineaux*, as above. The latter is preferable; 10 or 6½ M., in 39 or 20 min., fare 1 fr. or 55 c. and 65 or 45 c. — *Steamboats*, as to St. Cloud. — *Tramway* from the Quai du Louvre (comp. Appendix) in 1-1¼ hr., stopping at Sèvres near the bridge, opposite the porcelain-fac-

ST. CLOUD & SÈVRES

Echelle de 1:25,000

A vertical scale bar with markings at 500 and 1000. The bar is oriented vertically, with the 500 mark at the bottom and the 1000 mark at the top. The bar itself is a thin horizontal line with small vertical tick marks along its length. The numbers 500 and 1000 are printed to the right of the bar.



tory. The tramway from Paris to Versailles also passes Sèvres. Fare to Sèvres 50 c., outside 35 c.

To Meudon. *Railway* (Rive Gauche) see pp. 286, 287. Fare 80 or 55 c. — *Ligne des Moulineaux* (see above) to *Bas-Meudon*, in 44 or 15 min.; fare same as to Sèvres. — *Steamboats* as to St. Cloud and Sèvres. The steamboat-station is *Bas-Meudon*; it is preferable to walk from Sèvres.

RAILWAY ROUTES. *Ligne de Versailles (Rive Droite)*, see p. 285. The station at St. Cloud is situated above the town, which is reached by steep streets, in the new quarter of *Montretout* (p. 311).

Ligne des Moulineaux (from the St. Lazare station). — To (6 M.) *Puteaux*, see p. 285. The line diverges to the left of the Versailles line and descends to the Seine, traversing a long tunnel. — $7\frac{1}{2}$ M. *Suresnes-Longchamp* is the station for Suresnes and the race-course of Longchamp in the Bois de Boulogne (p. 159). $9\frac{1}{2}$ M. *Pont-de-St. Cloud* (see below).

Ligne des Moulineaux (from the Gare du Champ-de-Mars). This line follows the left bank of the Seine to Sèvres. Beyond *Javel*, still within the city-limits, it passes under the E. end of the Point-du-Jour viaduct (p. 257). Outside the fortifications, to the left, is Issy (p. 286). — $2\frac{1}{2}$ M. *Les Moulineaux*, a dependency of Meudon. The station is near the bridge of *Billancourt*, to the right. — 3 M. *Bas-Meudon* (p. 313). — $4\frac{1}{2}$ M. *Pont-de-Sèvres*, in a cutting near the porcelain-factory (p. 312). Thence the line skirts the park of St. Cloud (to the left), passes Boulogne (to the right), and beyond a cutting and tunnel reaches ($5\frac{1}{2}$ M.) *Pont-de-St. Cloud*.

The STEAMBOAT starts from the *Pont Royal*, on the Louvre side. Table of stations, etc., in the Appendix. The trip is very pleasant. Among the most conspicuous objects on the banks are the *Chambre des Députés*, the *Invalides*, the *Eiffel Tower*, and the buildings in the *Champ-de-Mars* to the left, and the *Trocadéro* to the right. We pass under the *Ponts de Solférino*, *de la Concorde*, *des Invalides*, *de l'Alma*, *d'Iéna*, *de Passy*, *de Grenelle*, and *du Point-du-Jour*, the last two on the *Ile des Cygnes*, at the lower end of which is *Bartholdi's* statue of Liberty enlightening the world (p. 162). Fine view to the left, on quitting Paris, of the hills of Meudon and St. Cloud.

The TRAMWAY ROUTE as far as Auteuil has been described at p. 287. The tramway-line to Versailles diverges to the left at the *Porte de St. Cloud*. The line to St. Cloud passes, *viâ Billancourt*, to *Boulogne*, a town with 30,000 inhab., which possesses a handsome church of the 14th and 15th cent., recently restored and provided with a spire. There are numerous 'blanchisseries' here. The tramway-car now crosses the Seine, on the left bank of which rises St. Cloud.

The tramway to Sèvres follows the high-road to Versailles *viâ Billancourt* (office, *Route de Versailles*, No. 39), beyond which it crosses the Seine. The terminus is near the bridge, beside the porcelain factory. *Sèvres*, see p. 312.

St. Cloud (*Restaurants* at the bridge and in the Grande

Avenue, most of them expensive; *Belvédère*, Quai de St. Cloud, moderate charges; *Café-Restaurant de la Gare*, at the bridge, déj. 2½, D. 3 fr.), a small town with 5400 inhab., which owes its name to a monastery founded here by St. Clodoald, grandson of Clovis. Owing to its situation near Paris the place soon acquired importance, and for the same reason it was much exposed to danger during the mediæval wars. Thus in 1346 it was burned by the English, and again in 1411 by the Armagnacs. Henri III., when besieging Paris in 1589, pitched his camp at St. Cloud, and was assassinated here by Jacques Clément. During the Prussian siege of Paris in 1870-71, the town of St. Cloud, which had been almost entirely deserted by its inhabitants, was partly occupied by the Germans, and repeatedly bombarded from Fort Valérien. The château, the spacious barracks near it, and many of the houses in the town, were completely burned down in October, 1870. No town in the environs of Paris suffered so severely during the war, or presented so melancholy an appearance after its termination.

The *Palace*, now a ruin, was erected in 1572 by a wealthy citizen. In 1658 it was purchased and rebuilt by Louis XIV., and presented by him to his brother the Duke of Orleans. In 1782 it was purchased by Louis XVI. for Marie Antoinette. In one of the saloons of the château, called the *Salle de l'Orangerie*, the Council of Five Hundred once held their meetings. On 9th Nov., 1799, Bonaparte with his grenadiers dispersed the assembly, and three days later caused himself to be proclaimed First Consul. To these reminiscences of the first rise of his power was probably due the marked preference which the emperor always manifested for St. Cloud. On 3rd July, 1815, the second capitulation of Paris was signed at the château, in which Blücher's headquarters were established. Here, too, on 25th July, 1830, Charles X. issued the famous proclamations abolishing the freedom of the press, dissolving the Chambers, and altering the law of elections, which caused the revolution of July. St. Cloud afterwards became the principal summer-residence of Napoleon III.

The *Church* of St. Cloud is a handsome modern edifice in the Romanesque style of the 12th century, with a lofty spire. The choir is adorned with mural paintings by J. Duval-le-Camus, representing scenes from the life of St. Clodoald. The church also contains some fine stained glass and decorations in grisaille.

Opposite the church are the remains of the abbey where St. Clodoald was interred, and adjacent is a handsome modern *Hôtel de Ville*.

In order to reach the *PARK, which is the great attraction of St. Cloud, we pass through the iron gate to the left of the bridge and follow the avenue on the bank of the Seine. (On the right of this avenue are several cafés, and bake-houses of 'gaufres', a kind of cake.) We soon arrive at the *Grande Cascade*, divided by an avenue into the *Haute* and the *Basse Cascade*, designed by Lepautre and Mansart, and adorned with statues of the Seine and the Marne by Adam. The fountains generally play in summer on the second Sunday of each month, from 4 to 5 o'clock, and also during the fête of St. Cloud on the last three Sundays in September, at the same

hours. The '*Jet Géant*', or great jet, to the left of the cascades, rises to a height of 136 ft.

Skirting the 'cascades', we soon reach the foot of the ruins of the palace, behind which is a fine old garden called the *Trocadéro*, commanding a number of pleasing views.

The *Allée du Château*, which ascends above the ponds, opposite the ruins, leads to the summit of a small hill (5 min. from the palace), which commands an admirable *View. Far below flows the Seine; to the left is the bridge of St. Cloud; beyond it the Bois de Boulogne; lower down is the small town of Boulogne; to the right is Meudon, farther distant is the Arc de l'Etoile; in the background Montmartre; from among the houses of Paris rise St. Vincent-de-Paul, the dome of the Invalides, the Palais du Trocadéro, the Eiffel Tower, the domes in the Champ-de-Mars, St. Sulpice, the Panthéon, the dome of the Val-de-Grâce, and other buildings. Before the war of 1870 the top of this hill was occupied by the *Lanterne de Démosthène*, or 'de Diogène', as it was popularly called, a lofty tower erected in imitation of the Monument of Lysicrates at Athens.

The broad central avenue (right) which diverges from the site of the tower leads to ($\frac{3}{4}$ M.) *Ville d'Avray*, a station on the Versailles railway (p. 286). The *Allée du Château*, which we have been following, leads in 5 min. more to the small town of Sèvres. Visitors to the porcelain-manufactory take the footpath descending to the left (S.E.).

Beyond the Chemin de Fer de Versailles (p. 309) is the handsome modern quarter of St. Cloud.

To the right of this quarter lies *Montretout* (see p. 309), where in 1870 the Prussians established a redoubt, connected with the heights of *Buzanval*. It was taken by the Parisian troops on 19th Jan., 1871, but afforded them little advantage.

FROM ST. CLOUD TO ST. GERMAIN-EN-LAYE viâ Marly-le-Roi, 15 M., railway in 1 hr. — The first part of this line, which diverges from the Versailles railway, is uninteresting, but it afterwards affords a pleasant view of the Seine and St. Germain. Beyond ($1\frac{1}{2}$ M.) *Garches* the train passes the château of *Villeneuve-l'Étang*, the race-course of *La Marche*, and the *Hospice Brezin*, an institution for old workmen. Tunnel. — $3\frac{1}{2}$ M. *Vauresson*. Then a tunnel. To the left, a stud-farm and the *Château of Beauregard*. We then obtain a good view to the right. — 5 M. *Bouival-La-Celle-St. Cloud*; the village of La-Celle-St. Cloud is prettily situated near a small wood. Bouival, see p. 314. To the left is the Aqueduct of Marly (see below). — 6 M. *Louveciennes*, a village with numerous large villas. — The train now passes through a tunnel and some cuttings, and crosses the road and tramway-line from Rueil to Marly-le-Roi (p. 314) by a viaduct 980 ft. long and 145 ft. high. Good view of St. Germain.

$7\frac{1}{2}$ M. *Marly-le-Roi*, with a celebrated château, built by Louis XIV., and destroyed in the Revolution. The remains include the *Abreuvoir*, a large basin near the tramway-station, and parts of the extensive garden-walls. The small *Park*, the nearest entrance to which is at the end of the avenue ascending to the right from the *Abreuvoir*, affords a pleasant walk. The main road, crossing the site of the château and commanding a fine view, ascends to the *Aqueduct of Marly*, constructed under Louis XIV. to bring to Versailles the water raised by the hydraulic machine at Marly (p. 314). It is 700 yds. long and 75 ft. high. The adjoining road leads from St. Germain to Versailles (p. 287). On the other

side is Louveciennes (p. 311). The N.E. half of the *Forest of Marly*, beyond l'Étang-la-Ville (see below), also affords picturesque walks. The part adjoining Marly is exposed and is kept as a game-preserve for the president of the republic. It contains a fort and several batteries. The entire forest, 6 M. long and 2½ M. broad, is surrounded with walls. There are gates at the top of the park and at the end of the village, beyond the church. To the right of the latter is the villa of *Victorien Sardou*, the dramatist. — 8 M. *L'Étang-la-Ville*, situated in a valley. We reach the Forest of Marly from this point in ¼ hr. by turning to the left; but the next station, *St. Nom-la-Bretèche*, is within the forest itself. The line joins the *Grande Ceinture* line in the Forest of Marly. — 11 M. *Marcel-Marly*, beyond which is the *Forêt de St. Germain*. From (13 M.) *St. Germain-Grande-Ceinture*, 1 M. from the château, the line makes a wide curve to (15 M.) *St. Germain-Ouest*, the terminus, beside the château.

Sèvres (*Café-Restaurant de la Terrasse*, Grande Rue 27, déj. 2½, D. 3 fr.; arrange prices on ordering; *Estaminet Parisien*, same street, No. 61), with 7620 inhab., is one of the most ancient places in the environs of Paris. The celebrated —

***PORCELAIN MANUFACTORY** has been the property of government since 1756, and employs about 180 hands. It now occupies a new building at the S.E. corner of the park of St. Cloud, near the bridge. The façade is adorned with a large porcelain mosaic, and at the entrance is a bronze statue, by Barrias, of *Palissy*, a reproduction of the statue in Paris (p. 251).

The *Workshops* are open to visitors daily (12 to 4 or 5), by cards of admission obtained on written application to the *Secrétariat des Beaux-Arts*, Rue de Valois 3 (Palais-Royal), Paris. Foreign visitors may often procure admission through the attendants in the exhibition-galleries (fee). The processes of painting and enamelling are not shown. — The *Exhibition Rooms*, which contain numerous specimens of the products of the manufactory, and the *Musée Céramique*, are open to the public daily from 12 to 4 or 5 o'clock. Entrance to the museum on the side next the river, in the central pavilion. Umbrellas and walking-sticks are left at the entrance (no fee). The small handbook sold at the entrance is antiquated and simply a history of the manufactory. — The *Musée Céramique*, a collection founded in 1800 by Alexander Brongniart (d. 1847) and enlarged by Rivereux, comprises objects of every kind relating to the history of porcelain-making, and specimens of modern pottery, faience, and porcelain from all parts of the world. The collection, however, is chiefly interesting to connoisseurs.

Sèvres contains nothing else to interest the visitor. Ascending the Avenue de Bellevue to the left beyond the porcelain-manufactory, we pass the old château which formerly contained the manufactory and is now restored as a *Normal School* for female teachers. We soon reach *Bellevue* (rail. station, see p. 287), which owes its origin to a château of Mme. de Pompadour, now in ruins. Numerous handsome villas have recently been erected here, but they unfortunately too often interrupt the fine views of the Seine. The best point of view is at the N.E. end of the *Avenue Mélanie*.

The Grande Rue de Bellevue, which crosses the last-named avenue, leads to the railway-station, $1\frac{1}{4}$ M. from the main street of Sèvres, and to ($\frac{1}{2}$ M.) —

Meudon (*Restaurants* in the Avenue de Meudon and at the upper station), a small town with 7620 inhab., of which Rabelais was curé in 1545-53 (bronze bust in Meudon proper). It consists of Meudon proper, on the slope of the hill which is crowned by the château; of a new quarter near the station of Meudon, with numerous prettily-situated villas; of *Bas-Meudon*, on the opposite bank of the Seine, with several manufactories; of *Les Moulineaux*, also on the bank of the Seine, to the E., with a railway-station (p. 309); of *Le Val*, a little higher up; and of *Fleury*, still higher, with a large orphanage (p. 287).

The *Château of Meudon*, rebuilt by the Dauphin in 1695, and afterwards occupied by the Empress Marie Louise, the King of Rome, and lastly Prince Napoleon, was set on fire by a shell and reduced to a heap of ruins during the Prussian bombardment of Paris in 1871. It has since been partly restored and is now an *Observatory*. The garden was laid out by Le Nôtre. At the beginning of the terrace below it, which affords a beautiful *View of Paris, is a *Monument du Centenaire*, a symbolical bronze bust by Courbet, erected in 1889. In 1870 the Prussians planted a powerful battery here, which completely commanded Boulogne, Billancourt, Auteuil, Grenelle, Vaugirard, and Issy. The park contains workshops for the manufacture of military balloons.

The *Wood of Meudon*, on the heights between Meudon and the valley of Sèvres and Chaville-Viroflay, is intersected in all directions with pleasant paths (finger-posts). On the E. it is adjoined by the charming *Bois de Chamart*. Part of the wood of Meudon is enclosed as the park of the château and is not open to the public.

16. From Paris to St. Germain-en-Laye.

13 M. *Chemin de Fer de l'Ouest*. Trains start from the Gare St. Lazare (p. 23; booking-office in central portion) every hour, or oftener, from 7.35 a.m. to 12.35 a.m., and from St. Germain every hour from 6.55 a.m. to 9.55 p.m., after which another starts at 11 p.m. — The journey occupies 27-50 minutes. Fares 1 fr. 65, 1 fr. 35 c.; no reduction on return-tickets. — Another and longer line runs via *St. Cloud* and *Marly-le-Roi*; 24 M. in $1\frac{1}{2}$ - $1\frac{3}{4}$ hr.; fares 2 fr. 35, 1 fr. 70, 1 fr. 15 c. Comp. p. 314).

The *Steamboat Journey* from Paris to St. Germain-en-Laye is pleasant but rather long ($3\frac{1}{2}$ hrs., return 4 hrs.); fare 3, in the reverse direction 2 fr.; return-fare $4\frac{1}{2}$ fr. The steamer, named the '*Touriste*', starts from the Pont Royal (left bank) at 10.30 a.m., and leaves Le Pecq at 5 p.m. (in Sept. 4 p.m.) for the return-journey. Déjeuner on board 4 or 6, D. 5 or 7 fr. Stations: *Suresnes* (p. 285), *Asnières* (p. 285), *St. Denis* (p. 318), *Argenteuil* (p. 326), *Chatou* (p. 314), *Bougival* (p. 314), and *Le Pecq* (p. 315), which lies at the lower end of St. Germain.

From Paris to *Asnières*, see p. 285. The Versailles line here diverges to the left, and that to Argenteuil (p. 326) to the right. Farther on, to the right, beyond ($5\frac{1}{2}$ M.) *La Garenne-Bezons*, di-

verges the line to Rouen, Havre, and Dieppe (see p. 365). — $7\frac{1}{2}$ M. *Nanterre* is a village (5600 inhab.), where, according to tradition, Ste. Geneviève, the patron-saint of Paris, was born in 422 (p. 237). A 'Rosière' festival is held here on Whit-Sunday. Steam-tramway, see below.

$8\frac{3}{4}$ M. *Rueil* (*Hôtel-Rest. du Lion d'Or*), a small town with 9364 inhabitants. The Empress Josephine is interred in the little church, recently restored in the Renaissance style, in which a monument was erected to her memory by her children Eugène Beauharnais (d. 1824), and Queen Hortense (d. 1837), mother of Napoleon III. The statue, by *Cartellier*, represents the empress in a kneeling posture. Queen Hortense is also interred in this church, and a monument of similar design, executed by *Bartolini* of Florence, was erected to her in 1846. The handsome organ-loft, by *Baccio d'Agnolo* of Florence (15th cent.), was presented by Napoleon III.

FROM RUEIL TO ST. GERMAIN, 6 M., steam-tramway in connection with the railway (fares 1 fr. 5, 65 c.). [The steam-tramway may also be taken direct from Paris (Place de l'Etoile in $1\frac{1}{2}$ hr., fares 1 fr. 60, 1 fr. 15 c.), viâ *Neuilly*, *Courbevoi*, *Rond Point de la Défense*, *Rond Point des Bergères*, and *Nanterre*.] Beyond Rueil there are 14 intermediate stations, of which we mention the most important.


$1\frac{1}{4}$ M. *La Malmaison*, with the château in which the Empress Josephine resided after her divorce in 1809 and where she died in 1814. After the battle of Waterloo, Napoleon retired to the château of Malmaison, but quitted it on the approach of the Prussian troops on 29th June, 1815. It is now private property.

3 M. *Bougival* (*Cafés-Restaurants de Madrid* and *Pignon*), a prettily-situated village, on the left bank of the Seine, much frequented by rowing parties. Part of the *Church*, which possesses a handsome Romanesque bell-tower, dates from the 13th century. A fine view is obtained on the road from Bougival to Celle (p. 311). On the opposite bank of the Seine are *Croissy* and *Chatou* (see below).

$3\frac{3}{4}$ M. *La Machine*, a suburb of Marly, named from the hydraulic machine by which Versailles and St. Cloud were supplied with water. The old machinery, constructed at a time (1686) when mechanical science was in its infancy, consisted of 14 water-wheels, each 38 ft. in diameter, 221 pumps, and ponderous iron and woodwork, and is said to have cost 4 million francs. This huge and formidable apparatus was replaced in 1855-59 by a stone dyke, 6 iron wheels, and 12 forcing-pumps, by means of which the water is driven up in a single volume to the reservoir, situated $\frac{3}{4}$ M. from the river and 505 ft. above it. The quantity of water thus raised averages 33,550 cubic ft. per hour. The steam-engine in front is no longer used. Visitors are admitted to inspect the works (fee).

At ($4\frac{1}{4}$ M.) *Port Marly* the tramway-line to ($1\frac{1}{4}$ M.) Marly-le-Roi (p. 311) diverges to the left. The main line follows the high-road to St. Germain, to the S. side of which it ascends, traverses the Place Royale and the Rue Gambetta, and halts in the Place du Château. 6 M. *St. Germain*, see p. 315).

The train crosses the Seine, which is divided here by an island into two arms. $9\frac{3}{4}$ M. *Chatou*, the station also for (1 M.) *Croissy* (omnibus to Bougival, 2 M.; see above). — $10\frac{1}{2}$ M. *Le Vésinet* consists mainly of a group of pleasant villas, erected in a kind of park. To the left of the railway is a Convalescent Home for women; about 1 M. farther on, to the right, is a steeplechase course. — 12 M.



Le Pecq. The train now recrosses the Seine, here divided into two arms by an island, and ascends a steep gradient (1 : 29), passing over a viaduct and through two tunnels, to —

13 M. St. Germain-en-Laye. — Hotels-Restaurants. ***PAVILLON HENRI IV. ET DE LA TERRASSE** (Pl. 9; F, 4), at the beginning of the terrace (see below), 1st class, with a beautiful view (Thiers died here on 3rd Sept., 1877); **DU PRINCE DE GALLES**, to the right of the church (Pl. 4; E, 3); **DE L'ANGE-GARDIEN**, Rue de Paris 74, behind the barracks (table-d'hôte déj. 2½, D. 3 fr.). — **Cafés-Restaurants.** *Crenier*, near the Gare de l'Ouest (Pl. E, 3); *Pavillon Louis XIV.* (table d'hôte), Place de Pontoise (Pl. E, 2), with a garden, closed in winter.

Cabs. Within the barriers, per drive 1¼ fr., on Sun. and holidays 1½ fr.; per hour 2 and 2½ fr. Beyond the barriers, within a radius of 9½ M., 2½ and 3 fr. per hour.

St. Germain, a quiet town with 16,312 inhab., is indebted for its importance to the fact that it was long a favourite summer residence of the kings of France, who were first attracted to the spot in the 12th century by the beauty of its situation. Its lofty and healthy site and its attractive walks render it a favourite summer-resort, and have induced a number of English families to reside here.

The **Château** (Pl. E, 3) was formerly known as the *Vieux Château*, in contradistinction to the *Château Neuf*, of which the Pavillon Henri IV. (Pl. 9; F, 4) is now the sole relic. Early in the middle ages the French kings possessed a fortress on this site commanding the Seine. The chapel, which is still in existence, was built by Louis the Pious. During the wars with England the castle was destroyed. It was restored by Charles V., but the present building, whose gloomy strength contrasts strikingly with the cheerful appearance of contemporaneous edifices, dates from the time of Francis I., who here celebrated his nuptials with Claudia, daughter of Louis XII. Henri II. built the adjacent *Château Neuf*, which continued to be a favourite royal residence till the time of Louis XIV., who was born here in 1638. After Louis XIV. had established his court at Versailles (p. 288) the château was occupied for 12 years by the exiled king James II., who died here in 1701 and was interred in the church. The *Château Neuf* was almost entirely taken down in 1776. Napoleon I. established a school for cavalry-officers in the old château, and it was afterwards used as a military-prison. It is now being restored in accordance with the original plans of A. Ducerceau, the architect of Francis I.; and the part in the Place du Château, adjoining the railway-station, alone awaits completion.

The ***MUSÉE DES ANTIQUITÉS NATIONALES**, which the château now contains, embraces an interesting collection of objects dating from the dawn of civilisation in France down to the period of the Carolingians. These are suitably arranged, and provided with explanatory notices. The museum is open to the public on Sun. from 10.30 a.m., on Tues. and Thurs. from 11.30 a.m., to 4 or 5 p.m., and to strangers on other days (Mon. excepted) by special permission.

In the fosse to the right of the entrance is a dolmen, found in 1872 at Conflans-Ste. Honorine (p. 342). — Below we give a short summary of the most interesting objects, referring for details to the excellent catalogue, published in 1887 (4½ fr.). The usual entrance to the museum is by the first door to the left in the court, but in wet weather by a small door to the left of the vestibule, which leads to Room S. (see below). Those who wish to follow a strictly chronological order must begin with the first floor. Explanatory labels.

GROUND FLOOR. Rooms S and R, to the left of the principal entrance: Casts of medallions and bas-reliefs from the Arch of Constantine at Rome; models of Roman engines of war; ancient war-chariots, etc. — Rooms A, B, and D, to the right of the entrance: Casts of bas-reliefs from the Arc d'Orange and the Julian tomb at St. Remy, near Arles. Room B also contains a medallion of a mosaic found at Autun in 1830, representing Bellerophon and the Chimæra. — We now return to the entrance, and ascend the handsome brick and stone staircase to the entresol.


ENTRESOL. Room XIX. Gallic mile-stones and geographical inscriptions. — Room XX. Celtic and Roman inscriptions; sepulchral stones. — Room XXI. Gallic mythology; altars, statues, and reliefs, of rough workmanship, but great historical interest. — Rooms XXII & XXIII, on the other side of the staircase. Sculpture relating to the Roman legions in Gaul. By the pillars and in the passage, tombstones and funeral urns (original). — Room XXIV. Inscriptions. — Rooms XXV. & XXVI. Sculptures illustrating Gallic costumes, arts, and pursuits.

FIRST FLOOR. Rooms I-III, to the right, contain objects of the pre-historic or bone and flint period. Room I: Cut flints of immense antiquity, and fossilised bones of animals either altogether extinct or no more found in France. Cases 1-15 contain objects found in alluvial deposits and the open country; Cases 16-33 contain tools and ossifications from caverns, the first shelter of primæval man. In the middle, casts of the heads of the rhinoceros (*r. tichorinus*), tiger (*felis spelæa*), great cave-bear (*ursus spelæus*), urus (*bos primigenius*), the long-haired elephant (18-20 ft. high), and the so-called Irish elk (*Megaceros hibernicus*; 9-10 ft. high); also a tusk and a molar of the mammoth (*elephas primigenius*). In Case 12 are different types of flint implements (from *St. Acheul*, from *Moustier* in Dordogne, etc.). — Room II. Models of dolmens and 'menhirs' (1/20 of the real size); implements of the polished-flint period; plan of the Allées de Carnac, in Bretagne; bone implements and ornaments. — Room III. Dolmen from the tumulus of Gav'rinis (Morbihan), Bretagne, and casts of the unexplained characters from the tumulus. To the left of the mantelpiece is placed an interesting collection of flint arrow-heads.

Adjoining this room is the *Galerie de Mars* or *Galle des Fêtes*, occupying the whole height of the first and second stories next to the church, and not yet restored. It is also called the *Salle de Comparaison*, as it contains objects from different countries. At present, however, it is mainly devoted to objects to be afterwards placed in the other rooms, and may be passed over by hurried visitors. The cases to the right and left of the entrance contain a collection of Romano-Gallic earthenware (better in RR. XIV-XVI), while the other cases contain arms and armour from different sources, objects in iron and bronze, etc. Casts of the Igel column and other Roman and Celtic monuments.

Returning to Room III, we ascend thence by a short staircase adjoining the *Galerie de Mars* to the —

SECOND FLOOR, where we begin on the side next the church. — To the left, in the turret, is the *Salle Numismatique*, containing Gallic, Gallo-Roman, and Merovingian coins, trinkets, Merovingian pottery and arms, etc. In the first case to the left, in the middle, are ornaments in gold and silver. The corresponding case on the other side contains Merovingian fibulæ and other objects in bronze, gold, and glass. Characteristic features of the barbaric art of this epoch are the inlaying of gold on glass



and the use of precious stones. — *Room IV.* Lacustrine and flint period (epoch of the lake-dwellings): polished flints, polished bone implements, objects in wood, vases. By the second window to the right: bread, grain, fruit, and cloth found in the lake-dwellings on the Lake of Constance. — *Room V.* Objects of the bronze period. In the glass-case in the centre are about a thousand different articles found in a vault at Larnaud (Jnra). — *Room VI.* Gallic antiquities of the early historic period. Weapons in iron and objects of other kinds, found in burial-places (tumuli), including fragments of war-chariots. In the 2nd case, Gallic helmets; in the 20th (in the middle), fine bronze vases, bracelets, necklaces (torques), etc.

Room VII., on the other side of the staircase. Continuation of the Gallic antiquities: objects from the burial-places of the *Marne*; clay vessels; bracelets, rings, necklaces, brooches, vases, and belts in bronze; weapons and knives in bronze, etc. — *Room VIII.* Objects from the burial-ground of *Chassemy*, in the department of Aisne. — *Room IX.* Specimens of Gallic tombs; reconstruction of a Burial in a chariot, found in 1875 at *La Gorge Meillet* (Marne), with the chief below and an attendant above. The original objects found in this tomb are in Case 2, to the left. — We now return to the —

FIRST FLOOR. *Room XIII.* Roman conquest of Gaul. To the left, Roman soldier armed with the pilum; in the centre, large relief-plan of *Alise (Alésia)*, and of the siege of that town by Cæsar; models of besieging engines (Case 24); objects found in the fosses of Alise, including a fine *Vase in chased silver (in the glass-case behind the plan). — *Room XIV.* Gallo-Roman pottery; vases and figures in white clay. — *Room XV.* Pottery; vases with red glazing and reliefs; bronze vases, statuettes, and fibulæ; extensive collection of glass. — *Room XVI.* Pottery; objects in bronze and iron.

The *Church* of St. Germain, situated opposite the château, contains a simple monument in white marble, erected by George IV. of England to the memory of James II. (p. 315). The monument was afterwards restored by order of Queen Victoria.

In the small *Place* to the right of the façade of the château is a *Statue of Thiers* (Pl. E, 4), by Mercié, erected in 1880 (see p. 315).

The *Hôtel de Ville* (Pl. 7; E, 3), in the Rue de Pontoise, near the station, contains a small collection of pictures on the second floor (open daily, except Mon., 10-4). It includes specimens of Teniers, Lucas van Leyden, Titian, Gerard Dou, and De Crayer.

The *TERRACE (Pl. F, G, 2, 1) and the beautiful *FOREST constitute the great charm of St. Germain. The terrace extends for 1½ M. along the E. slope of the vine-clad hill at a considerable height above the Seine, and commands a magnificent survey of the valley, the winding river, and the well-peopled plain. The middle distance resembles a huge park sprinkled with country-houses. The nearest village is Le Pecq, beyond which is Le Vésinet. Montmartre is visible on the horizon, but the rest of Paris is concealed by Mont Valérien, to the right. Also to the right, on the hill, is the aqueduct of Marly (p. 311). To the left, beyond the corner of the park of Vésinet, the tower and cathedral of St. Denis are faintly distinguishable, while on the intermediate hills lies Montmorency.

The beautiful forest of St. Germain, about 11,000 acres in extent, is kept in admirable order, and affords pleasant and shady walks in every direction. The popular *Fête des Loges*, which takes place in the forest on the first Sunday after Aug. 30th and on the two following

days, derives its name from *Les Loges*, a country-seat 2 M. distant from the town, erected by Anne of Austria, wife of Louis XIII., and now a school for daughters of members of the Legion of Honour. The Pontoise road, striking to the right beyond Les Loges, leads to (3 M.) *Achères* (see below). It crosses the road from Poissy to Maisons (see below), which lies about 2 M. to the right of the point of intersection. Fine view on quitting the wood.

FROM ST. GERMAIN TO MAISONS-LAFFITTE (*Argenteuil*), 10½ M., railway (*Grande Ceinture*) in 35-80 min. (fares 2 fr. 5, 1 fr. 55, 1 fr. 15 c.). This section of the railway describes a wide curve through the Forest of St. Germain. An omnibus runs direct to (4 M.) Poissy eight times daily, starting from the main station (fare 50 c.) to (4½ M.) Maisons-Laffitte (70 c.), etc. — 2½ M. *St. Germain-Grande-Ceinture* (p. 307). — 5 M. *Poissy* (*Hôtel de Rouen*); the station is to the E., at the opposite end of the town to that of the Rouen railway (p. 365). — 8 M. *Achères*; the village lies 1½ M. to the N.W., near the race-course of St. Germain. Railway to Pontoise, see p. 342. Our line now coincides with the Rouen line (p. 365) till the Seine is crossed. — 10½ M. *Maisons-Laffitte*, see p. 341. The railway continues to the left to *Argenteuil* (p. 326).

From St. Germain to *Versailles*, see p. 307.

17. From Paris to St. Denis, Enghien, and Montmorency, and back to Paris viâ Argenteuil.

The trains between Paris and these places follow the *Ligne Circulaire de la Gare du Nord à la Gare de l'Ouest* (18 M.). Through-tickets are issued at low rates but do not allow of a break in the journey.

a. From Paris to St. Denis.

4½ M. CHEMIN DE FER DU NORD. Trains start from the Gare du Nord in the Place Roubaix (see p. 24), 4 times an hour or oftener (three trains-tramways at 10,30, and 50 min. past each hour from Paris and from St. Denis). The journey occupies 10-15 minutes. Fares 85, 65, 40 c.; return-tickets 1 fr. 30, 85, 70 c.

TRAMWAYS. Two lines run to St. Denis, one starting from the lower end of the Rue de Lafayette (Pl. B, 21; *II*), the other from the Boul. Haussmann (Rue de Rome; Pl. B, 18; *II*). These lines are very convenient, but the routes are uninteresting; the former traverses La Chapelle, with its malodorous manufactories.

1¼ M. *La Chapelle-Nord-Ceinture*, also a station on the Chemin de Fer de Ceinture (p. 24). The huge goods station of the Chemin de Fer du Nord is situated here. A little beyond the fortifications the Soissons railway diverges to the right. — 2½ M. *La Plaine-Voyageurs*. The trains-tramways also stop at *Le Landy* and *Pont de la Révolte*.

4½ M. **St. Denis**. — *Hôtel du Grand-Cerf*, Rue de Paris and Place aux Gueldres, to the S. — *Café-Restaurant de la Marine*, at the station. — The terminus of the tramway from the Rue Taitbout, is in the Place de la Caserne, to the N. of the Rue de Paris; that of the tramway from the Boul. Haussmann in the Place aux Gueldres.

St. Denis, an uninteresting town with 48,000 inhab., now surrounded with manufactories, is celebrated as the burial-place of the kings of France. The railway-station is ¾ M. from the cathedral. To reach the latter we cross the Canal de St. Denis (p. 186) and

follow the Rue du Chemin de Fer, and then the Rue Compoise. At the beginning of the latter stands the new *Parish Church*, built by Viollet-le-Duc in the style of the 13th cent. and completed in 1867. We then cross the Rue de Paris, which intersects the town from N. to S. To the left is the *Hôtel de Ville*, in the Renaissance style, built in 1883.

The *CATHEDRAL, popularly known as LA BASILIQUE, is open the whole day. The royal tombs are shown on week-days every $\frac{1}{2}$ hr. between 8.30 a.m. and 5.30 p.m. (except during service). Admission to the interior of the church is free; to the treasury and crypt $\frac{1}{2}$ fr., but the attendants also expect a small gratuity.

A chapel was erected here about the year 275 above the supposed grave of St. Dionysius, or St. Denis, the first bishop of Paris (p. 189). To this chapel pilgrims flocked from far and near. *Dagobert I.* (d. about 638) substituted a large basilica for the chapel, and handed it over to the Benedictine monks, for whom he also built an abbey at the same place. This church was repeatedly restored, particularly by *Pepin the Little* (d. 768); and at length *Suger*, the celebrated abbot of St. Denis (1121-51) and adviser of Louis VI. and Louis VII., determined to erect a more handsome edifice, in the construction of which no part of the old church was to be retained except the central crypt and a few columns. Suger's building marks the beginning of the Gothic tendency in architecture, the development of which from the Romanesque style can be traced here, though perhaps not in all details. The façade, completed in 1140, shows the round arch still maintaining its ground along with the pointed arch which afterwards entirely replaced it. The choir, consecrated in 1144, is surrounded by radiating chapels, a feature of the Romanesque style, and at the same time exhibits the Gothic buttress system in an advanced stage of development. A thorough restoration, necessitated partly by the subsidence of the foundations and partly by the effects of a fire, was carried out from 1230 onwards by the abbots *Eudes Clément* and *Matthieu de Vendôme*, in the pure Gothic style now dominant. The upper part of the choir, the whole of the nave, and the transept were entirely rebuilt. During the 14th cent. additional chapels were erected in the N. aisle and the E. wall of the S. transept. From this period the church remained unaltered till 1792, when it was so ruined during the Revolution that a traveller of the period speaks of it as a 'désert riche en décombres, habité seulement par des oiseaux de proie'. The renovations under Napoleon I., the Restoration, and the July Monarchy were not in good taste, and did not even render the building secure. Under Napoleon III., however, who entrusted the work of restoration to *Viollet-le-Duc*, one of the greatest Gothic architects of modern times, the church regained much of its ancient magnificence.

Under the Carlovingian dynasty the monks of St. Denis are found concerning themselves with political as well as with spiritual matters.

When *Pepin the Little* took possession of the throne of France in 751 he sent *Fulrad*, Abbot of St. Denis, to Rome, to procure the papal confirmation of his title. Three years later *Pope Stephen II.* took refuge here from the Lombards, and anointed Pepin's sons *Charles* and *Charlemagne*. Here, in presence of his nobles, Pepin handed over his dominions to his sons before he died. The members of the house of Capet also favoured this abbey. *Louis VI.* (d. 1137), whose best adviser was the penetrating, sagacious, and liberal abbot *Suger*, solemnly adopted the *Oriflamme* ('auriflamme', from its red and gold colours), or standard of St. Denis, as the banner of the kings of France. It was suspended above the altar, whence it was removed only when the king took the field in person. Its last appearance was on the unfortunate day of Agincourt (p. xvi). *Abélard* (p. 177) dwelt in this abbey during the 12th cent., until he became abbot of Paraclete near Nogent-sur-Seine. During the absence of *Louis VII.* on a crusade in the Holy Land (1147-49) *Suger* became the administrator of the kingdom, and used his power to increase the dependence of the nobility on the throne. Among the other merits of this renowned abbot, who possessed the confidence of the whole nation, and died at St. Denis in 1151, is that of having collected and continued the chronicles of the abbey. The *Maid of Orleans* hung up her arms in the church of St. Denis in 1429. In 1593 *Henri IV.* abjured Protestantism in this church, and in 1810 *Napoleon I.* was married here to the Archduchess Marie Louise.

The Church of St. Denis is chiefly important and interesting as the BURIAL CHURCH OF THE FRENCH KINGS, nearly all of whom from *Dagobert I.* (d. 638) are interred here with their families. The numerous monuments of the early period have perished during the frequent alterations or rebuilding of the church. *Louis IX.* (1226-70) erected a number of mausoleums and monuments with recumbent figures in the choir to the memory of his ancestors, and from his time down to *Henri IV.* (d. 1610) monuments were erected to all the monarchs, as well as to several princes and eminent personages. After *Henri's* death the coffins of his successors were merely deposited in the royal vault. When the first Revolution broke out, the Convention resolved that the tombs should be destroyed, in accordance with the motion of *Barrière* (31st July, 1793): — 'La main puissante de la République doit effacer impitoyablement ces épitaphes superbes et démolir ces mausolées qui rappelleraient des rois l'effrayant souvenir'. By a singular coincidence, the work of desecration was begun on 12th Oct., 1793, the anniversary of the day on which, one century before, *Louis XIV.* had caused the demolition of the ancient tombs of the emperors at Spire. *Hentz*, the agent employed by the Convention, was, moreover, a namesake of the superintendent of the work of destruction at Spire. In order the more speedily to accomplish the work, the wall of the crypt was broken through, and the bodies of the illustrious dead of a thousand years, from *Dagobert* (d. 638) to *Louis XV.* (d. 1774), besides other celebrated personages, were thrown into 'fosses communes' dug in the neighbourhood.

On the restoration of the church in 1806, *Napoleon* decreed that the crypt should be used for his own burial and that of his successors; but one member only of his family, the young *Napoléon Charles*, son of his brother *Louis*, was interred here. The body, however, was afterwards conveyed to St. Leu (p. 346).

In 1817, *Louis XVIII.* caused the remains of his ancestors, as well as those of *Louis XVI.* and *Marie Antoinette*, who had been interred in the churchyard of the Madeleine, to be replaced in the crypt. He himself (d. 1821), the *Duc de Berry*, who was assassinated in 1820, and several of his children were the last of the Bourbons interred here.

Napoleon III., as already mentioned, had again destined this church to be the resting-place of the French emperors, but he also died and was interred in a foreign country (1873).

The preservation of the tombs which have survived these disastrous vicissitudes was chiefly due to the exertions of the indefatigable *Alex. Lenoir* (p. 247), who caused them to be transferred to the Musée des Petits-Augustins, now the Palais des Beaux-Arts. Unfortunately, however,

all the metal monuments had already been melted down. When Louis XVIII. ordered the monuments to be restored to the church in 1817, they were placed in the crypt, but repeated alterations in their arrangement have since taken place. Numerous monuments from other churches preserved in the Musée Lenoir were erected here. During the work of restoration under *M. Viollet-le-Duc* they were all placed as nearly as possible in their original positions, but there are still several monuments not properly belonging to St. Denis.

The *West Façade* formed part of the building consecrated by Abbot Suger in 1140. It contains three recessed portals decorated with sculptures, which, however, have been so altered and supplemented, that their original character is scarcely traceable. Those of the S. portal represent the Months, and St. Dionysius in prison, after a painting in the Louvre (p. 125); those of the central bay, the Last Judgment, and the Wise and Foolish Virgins; and those of the N. portal, St. Dionysius on his way to Montmartre and the signs of the Zodiac. The battlements along the top of the façade were erected for defensive purposes during the 14th century. Behind them rises the high-pitched roof of the nave, surmounted by a statue of St. Dionysius. On the right and left are two towers, neither of which ends in a spire; that on the left has been taken down so far as to be on a level with the top of the façade. — The statues of princes and the Martyrdom of St. Dionysius on the portal of the N. transept are in better preservation, but it is impossible to obtain a near view of them.

THE INTERIOR, entered by one of the three modern bronze doors in the W. façade, consists of nave and aisles, crossed by a simple transept. Length 354 ft., breadth 130 ft. The dim twilight of the *Vestibule*, which dates from Suger's time, and is borne by heavy columns, forms a striking contrast to the airy and elegant *Nave* of the 13th cent., with its thirty-seven large windows, each 33 ft. high, its handsome triforium-gallery, and its lofty columns. The stained-glass windows were placed here in the reign of Louis Philippe. Those in the nave represent kings and queens of France down to St. Louis; in the N. transept are events from the crusades and from the life of St. Louis; in the S. transept, Napoleon I., Louis XVIII., and Louis Philippe; in the choir, the martyrdom of St. Denis, and the history of the church. The stained-glass windows in the aisles, and those introduced into the choir-chapels by Viollet-le-Duc, particularly the latter, are more in keeping with the style of the building. The only ancient stained-glass window is one on the left in the *Chapel of the Virgin*, with the genealogy of Christ; at the bottom, to the left, the Abbot Suger is represented. The same chapel contains a mosaic pavement of the 12th cent., and an altar of the 14th cent., with antique sculptures of scenes from the life of Our Lord.

The *High Altar* is a modern imitation of the style of the 13th century. Behind it stands the altar of St. Denis and his fellow-martyrs (p. 322).

We now proceed to inspect the monuments in detail, beginning with those in the left or N. transept.

N. SIDE. *Tombs of the Family of St. Louis.* — **Tomb of Louis XII.* (d. 1515) and his consort *Anne de Bretagne*, probably executed in the first half of the 16th cent. by *Jean Juste* of Tours, and measuring 19½ ft. in length, 9½ ft. in breadth, and 10 ft. in height. The monument is in the Renaissance style, and, like several others in the church, bears considerable resemblance to the fine monument of Giangaleazzo Visconti in the Certosa di Pavia. The king and queen are represented on the sarcophagus in a recumbent posture, executed in a rude, realistic manner, and again in a kneeling attitude above. The monument is surrounded by twelve arches, richly decorated, beneath which are statues of the Twelve Apostles. At the corners are allegorical figures. On the pedestal are reliefs of the entry of Louis XII. into Milan (1499), his passage of the Genoese mountains (1507) his victory over the Venetians at Agnadello (1509), and their final submission. — Then, to the right, the fine truncated column by *Barth. Prieur*, commemorating *Henri III.* (d. 1589). From this point we see, to the right of the high-altar, the tomb of *Dagobert I.* (d. 638), an interesting monument of the 13th cent., with curious allegorical figures representing the king's soul leaving his body and its reception in heaven, a recumbent statue of Dagobert (modern), and erect statues of Sigebert, Dagobert's son (modern), and Queen Nantilde (13th cent.). — **Tomb of Henri II.* (d. 1559) and his queen *Catherine de Médicis* (d. 1589), the masterpiece of *Germain Pilon*, executed in 1564-83 (13 ft. high, 12 ft. long, and 10 ft. broad). This fine work consists of white marble, adorned with twelve columns and twelve pilasters, and with bronze statues of the four cardinal virtues at the corners. The deceased are represented twice, by nude marble figures on the tomb, and by bronze figures, full of vitality, in a kneeling posture above the entablature. Behind are monuments of the family of Valois, to see which properly we ascend some steps.

To the left, another monument to *Henri II.* and *Catherine de Médicis* (see above); recumbent marble figures on a bronze couch. It is said that in her old age the queen disapproved of the nude figures on the other monument, and caused these robed and elderly effigies to be executed.

The chapels round the choir, which we now pass, contain no monuments; but the chapel of the Virgin has ancient stained-glass windows, a mosaic pavement dating from the 12th cent., and sculptured scenes from the life of Christ. We now pass behind the altar of St. Denis and his fellow-martyrs, SS. Rusticus and Eleutherus, known as the *Confession de St. Denis*, another piece of modern workmanship, containing reliquaries. On one side is a representation of the Oriflamme (p. 320).

The SACRISTY, to the S. of the choir, is adorned with ten modern paintings relating to the history of the abbey: *Monstau*, Coronation of Marie de Médicis; *Debay* (after *Gros*), Charles V. and Francis I. visiting the abbey; *Menjaud*, Death of Louis VI.; *Guérin*, Philip III. presents the abbey with the Relics of St. Louis; *Barbier*, St. Louis receiving the Oriflamme (p. 320); *Landon*, St. Louis restoring the burial-vaults; *Meynier*, Charlemagne at the consecration of the church; *Garnier*, Obsequies of King Dagobert; *Monstau*, Preaching of St. Denis; *Heim*, Discovery of the remains of the kings in 1817.

The TREASURY is contained in a room adjoining the Sacristy on the left. Of the valuable articles which were formerly kept here St. Denis itself now possesses none, although a few are preserved in the treasury at Notre-Dame, the Galerie d'Apollon at the Louvre, and elsewhere. The present contents are almost all modern, and their number has been so diminished by a daring robbery in 1882, that a visit to them is of little interest. — The greatest artistic value among the remaining objects is possessed by a copper altar-piece, in repoussé work, of the 13th cent., on the left wall. On the right wall are a gilt copper cross (divided lengthwise into two sections, which are hung apart from each other), dating from the 13th cent., and another silver altar, of the period of Louis XIV. In the glass-case is a large modern monstrance, in the style of the 13th century.

S. SIDE. Opposite the Sacristy: The interesting *Tombstone of Frédégonde* (d. 597), which was formerly in the Church of St. Germain-des-Prés. The figure of the queen is represented by a kind of mosaic, formed of small pieces of differently coloured marble mingled with minute pieces of copper. The hands and feet are of the colour of the stone itself, the shape only being indicated by the lines of the mosaic, and seem to have been originally painted. Some authorities consider the tombstone contemporaneous with the queen, who lived in the 6th cent., while others, with more probability, refer it to the 11th or 12th century. — We now descend a flight of steps to the right of which is the entrance to the —

CRYPT, which was built by *Suger* for the bones of the three holy martyrs. It lies immediately under the apse, and has a choir encircled with chapels corresponding exactly with those of the church above. The central part of the crypt, under the sanctuary, is occupied by the burial-vault of the Bourbons, which was formed by Henri II. and now contains the coffins of the following royal and princely personages: *Louis XVI.*, *Marie Antoinette*, *Louis XVIII.*, *Adelaide* and *Victoire de France*; the *Duc de Berry* and two of his children; *Louis Joseph* and *Louis Henri Joseph*, the last two princes of the house of Condé; lastly, *Louis VII.*, formerly in the Abbey of Barbeau near Melun, and *Louise of Lorraine*, wife of Henri III., from the Eglise des Capucins in the Place Vendôme. The remains brought back by Louis XVIII. in 1817 from the 'fosses communes' (p. 320) are placed in a double vault at the end of the ambulatory, where the names of the deceased are inscribed on two large black marble slabs. — Adjacent is the 'Caveau Impérial', constructed by Napoleon III. as the burial-vault of his dynasty, but quite untenanted. — In the crypt-chapels and by the external wall of the central part of the crypt are a few indifferent statues, including a *Statue of Marie Antoinette*, a kneeling figure in a ball dress; a *Statue of Louis XVI.*,

by Gaulle; a *Statue of Diana of France*, of the 16th cent.; four colossal allegorical figures intended to form part of a monument to the Duc de Berry; and monuments to Henri IV., Louis XIII., Louis XIV., Louis XV., etc.

On the other side of the flight of steps, to the right of the choir: *Monument of Du Guesclin*, 'comte de Longueville et Connestable de France' (d. 1380), one of France's most heroic warriors in her contests with England. In the left eye is indicated the wound which the constable received in battle. The tomb of his companion-in-arms, the Constable *Louis de Sancerre* (d. 1402) is close by. — *Statue of Charles V.* (d. 1380), formerly in the Eglise des Célestins, a master-work of the 16th century. — *Tomb of Renée de Longueville* (d. 1515), a daughter of François II., Duke of Longueville, who died at the age of seven years; also from the Eglise des Célestins. — In the choir, to the right, are several less important monuments; and on the other side of the altar, the *Monuments of Blanche* and *Jean*, children of St. Louis, of enamelled copper, the figures in repoussé work, probably executed at Limoges; Blanche's monument formerly stood in the abbey of Poissy, Jean's in that of Royaumont. — To the left, **Monument of Francis I.* (d. 1547), with kneeling figures of the king, his wife Claude, and their three children on the entablature, and scenes from the battles of Marignano and Ceresole, in relief, on the pedestal. This monument is in the same style as that of Louis XII., and is still finer. It is said to be the joint production of *Philibert Delorme*, *Germain Pilon*, and *Jean Goujon*. — **Urn*, containing the heart of Francis I., originally destined for the Abbey des Hautes Bruyères near Rambouillet, a masterpiece in the Renaissance style by the otherwise little-known sculptor *Pierre Bontemps*. — *Monument of Louis d'Orléans* (d. 1407) and *Valentine de Milan* (d. 1408), erected by their grandson, Louis XII., in the Eglise des Célestins, and *Monument of Charles d'Etampes* (d. 1336), a masterpiece of the 14th century, with statues of the deceased and 24 statuettes of apostles and martyrs.

The extensive building which adjoins the church was erected by Louis XIV. and Louis XV. on the site of the old *Abbey*. Since 1815 it has been the seat of the '*Maison d'Education de la Légion d'Honneur*', a school affording a free education to daughters of officers on active service down to the rank of captain, and of civilian members of the Legion of Honour occupying a corresponding social position. The privilege is granted only for one daughter of each member, but the other children, or the grand-daughters, sisters, nieces, and cousins of those entitled to the privilege, are admitted for an annual payment. The pupils, who number upwards of 500, are uniformly dressed in black, and the discipline is of an almost military character. Strangers are not admitted.

In the Seine, beyond the railway, is the *Ile St. Denis*, and on the opposite bank is the *Plaine de Gennevilliers*, with the village of that name, 2½ M. from St. Denis (p. 61).

b. From St. Denis to Enghien and Montmorency.

RAILWAY to (3 M.) *Enghien* in 12-15 min. (60, 45, 35 c.); from Enghien to (2 M.) *Montmorency* in 7 min. (55 or 35 c.).

A short way beyond St. Denis the main line of the *Chemin de Fer du Nord* (R. 21) diverges to the right. Our line passes *Fort de la Briche* (p. 346). To the left flows the Seine. — 6 M. (from Paris) *Epinay*, a village of 2362 inhabitants. — Railway to Beaumont, see pp. 345, 344.

FROM EPINAY TO NOISY-LE-SEC, 8 M., Grande Ceinture Railway. The chief station is (5½ M.) *Le Bourget* (p. 350). — At *Noisy-le-Sec* (4823 inhab.) the Grande Ceinture Railway joins the *Chemin de Fer de l'Est*. See *Baedeker's Northern France*.

The Grande Ceinture Railway also runs from Epinay to (3½ M.) *Argenteuil* (p. 326), skirting the Seine.

7½ M. (3 M. from St. Denis) **Enghien** (*Hôtel des Bains*; *Bellevue*; *Hôtel de la Paix*; *Jeanson's Restaurant*), a small watering-place (2426 inhab.) with a cold sulphur-spring, a park, a lake, and a race-course. The grounds afford pleasant walks, and are a favourite resort of the Parisians.

The distance from Enghien to Montmorency in a direct line is only 1¼ M., but the train makes a detour and passes *Soisy*. Fine views.

Montmorency. — **Hotels.** HÔTEL DE FRANCE ET DE L'ÉTRANGER, at the station; CHEVAL BLANC, Place du Marché.

Cafés-Restaurants. *Chalet des Fleurs*, at the station; *Trois Mousquetaires*, near the Hermitage.

Horses from 1¼ fr. per hr., bargaining advisable on Sun. and holidays. *Asses* ¾-1¼ fr. per hr.

Montmorency, an ancient town with 4900 inhab., is charmingly situated on a hill covered with orchards. It is another favourite summer-resort of the Parisians, chiefly owing to its beautiful forest (see below). The town proper is poorly built, but the quarter adjoining the railway-station and the forest consists of tasteful villas and shady avenues. The *Church*, with its small but conspicuous spire, dates from the 14th cent. and contains the tombs of two Polish generals. On the side of the town next to Enghien, Rue du Temple 18, is an interesting house in a mixed Gothic and Renaissance style, with fine sculptures.

Montmorency was once the residence of Rousseau, who spent two years (1756-58) in the house called the '*Ermitage de Jean Jacques Rousseau*', and there wrote his *Nouvelle Héloïse*. It is situated on the N. side of the town, at the end of the Rue Grétry, and is recognisable by its reddish walls (visitors not admitted). This unpretending abode was fitted up for the philosopher's use by the Countess d'Epinay, in order to prevent his return to Geneva. During the Revolution the Hermitage became national property, and was for a time occupied by *Robespierre*. In 1798 it was purchased by the composer *Grétry*, who died here in 1813. His heart was interred in the garden, where a monument was erected to his memory, but in consequence of a law-suit was afterwards removed to Liège, his native place. An allusion to this is contained in the inscription.

THE FORBST OF MONTMORENCY, which begins to the S.E. of the Hermitage and extends to the N.W. for a distance of 5½ M., with a breadth of 1¼-2½ M., covers a very irregular tract, the highest

point of which is 600 ft. above the sea. Three of the hills, at Montmorency, Montlignon (see below), and Domont, have lately been crowned with forts. The forest consists mainly of chestnuts and has been left to a great extent in a natural state, a fact which adds to its attractions but makes it difficult for the stranger to find his way. Some of the higher points command charming views. The pleasantest route, well-marked and easy to follow, ascends beyond the station and skirts the S. slopes, which afford fine views, to *Andilly*, 1½ M. to the N.W. From the hill just above this village, the prospect extends to the heights of Montmartre, Mont Valérien, and St. Germain-en-Laye. On this plateau stands the *Fort of Montlignon*, named after a neighbouring village. Riders generally prolong the excursion to the *Croix Blanche* (restaurant), a point a little farther to the N., which may also be reached direct from Montmorency. We descend thence to the W. to the (15-20 min.) *Carrefour du Pont d'Enghien* (Rendez-vous de Chasse, restaurant), whence a path leads to (10 min.) the *Château de la Chasse*, with the scanty ruins of a castle of the 14th cent., surrounded by ponds and moats. This spot is about 4 M. to the N.W. of Montmorency and nearly in the centre of the forest. — Another favourite point is the *Châtaigneraie*, a group of magnificent chestnuts, ¾ M. from the station and not far from the Hermitage.

c. From Enghien to Paris via Argenteuil.

11 M. RAILWAY in 45-50 min.; fares 1 fr. 95, 1 fr. 45, 1 fr. 10 c.

The train passes the *Lac d'Enghien* on the left and the race-course of Enghien (p. 325) on the right. Fine view on the same side. On a height in the distance rises the tower of the *Château de la Tour*, above *St. Prix* (1 M. from St. Leu, see below). — 2 M. *Ermont*. Railway to Pontoise and to Valmondois, see R. 18.

The line now turns to the S. Beyond (2½ M.) *Sannois* the train descends between the hills of *Orgemont* on the left and *Sannois* and *Cormeilles* on the right to the valley of the Seine.

4 M. (from Paris 13½ M.) **Argenteuil** (*Soleil d'Or*, with restaurant, near the bridge), an ancient town with 12,809 inhab., lies on the right bank of the Seine and is the headquarters of pleasure-boat sailing on that river. The wine of Argenteuil is mediocre, but its asparagus is justly celebrated. The *Church*, a modern Romanesque structure by Ballu, with a lofty tower, boasts of possessing the seamless robe of Our Saviour, presented to it by Charlemagne. Adjacent to the *Gare de l'Ouest* lies the station of the *Ligne de Grande Ceinture* (for Maisons, Epinay, etc.; see pp. 318, 326).

FROM ARGENTEUIL TO CONFLANS-SÈTE. HONORINE (Mantes), 9½ M., new railway, not yet opened. This line diverges to the left from the Ermont line and beyond a deep cutting runs along a high embankment among the vineyards of Argenteuil. To the right stretch the fortified heights of *Sannois* (440 ft.) and *Cormeilles* (545 ft.), commanding a fine view, to the W., of the valley of the Seine. In the distance is the hill of the Hautil, between the Seine and the Oise. — 3½ M. *Cormeilles-en-Parisis*,

a large village picturesquely situated on the S.W. slopes of the hill of the same name. Near the church (13-15th cent.; modern tower) is a bust of Daguerre (1787-1851), a native of Cormeilles. We traverse another deep cutting and two viaducts above the valley in which lies the village of *La Frette*, on the bank of the Seine. To the right are the curious *Butte de la Tuile* (390 ft.) and *Montigny*, prettily situated at the end of the heights of Cormeilles. — $5\frac{1}{2}$ M. *Herblay*, a large village with a conspicuous church (12th cent.), on the steep right bank of the Seine, opposite the wood of St. Germain-en-Laye. There is another station about $1\frac{1}{2}$ M. to the N.E., see p. 341. Farther on we traverse an uninteresting plain.

$9\frac{1}{2}$ M. *Conflans*. From the station, which is $\frac{1}{2}$ M. to the N. of the town (p. 342), a branch line is to be extended to the Pontoise line at Eragny (p. 342). The main line enters a cutting farther on, crosses the line from Paris to Pontoise, viâ Achères, and afterwards the Oise, etc.

We now cross the Seine, 6 M. *Colombes* (14,254 inhab.); $6\frac{1}{2}$ M. *Bois-de-Colombes*; $7\frac{1}{2}$ M. *Asnières* (p. 285). — 11 M. ($18\frac{1}{2}$ M.) *Paris* (Gare St. Lazare, p. 23).

18. From Paris to Fontainebleau.

37 M. CHEMIN DE FER DE LYON. The journey occupies $1\frac{1}{2}$ -2 hrs. (fares 7 fr. 25, 5 fr. 40 c., and 4 fr.; return-tickets 9 fr., 6 fr. 80, 4 fr. 95 c.). — The station (Pl. R, G, 25, 28; p. 23) is in the Boulevard Diderot.

Those who visit Fontainebleau should devote a whole day to the excursion, leaving Paris by an early train (views on the left side). One hour will probably suffice for a visit to the palace and garden, after which a drive or walk to the Gorges de Franchard will occupy 2-3 hrs., and a visit to the Fort de l'Empereur 1 hr. more. Time will then be left to dine at Fontainebleau before returning to Paris.

At ($1\frac{1}{4}$ M.) *Bercy-Ceinture*, a station within Paris, we cross the Ligne de Ceinture. — Beyond ($3\frac{3}{4}$ M.) *Charenton* (p. 214), the lunatic asylum of which is seen on a height to the left, we cross the *Marne*, near its confluence with the Seine. On the left bank of the *Marne* lies *Alfortville* (p. 214). To the left rises the fort of *Charenton*, commanding the Seine and the *Marne*. $4\frac{1}{2}$ M. *Maisons-Alfort*, a village with 7034 inhab., some distance beyond which we cross the Ligne de Grande Ceinture (pp. 24, 338).

$9\frac{1}{2}$ M. *Villeneuve-St. Georges*, a place of some importance, with 4315 inhab., and a suspension-bridge over the Seine, is picturesquely situated on the slope of a wooded hill to the left. Above the village is a new fort. Villeneuve is also a station on the Ligne de Grande Ceinture (p. 338). — The beautiful green dale of the *Yères*, a small but deep river, bordered with rows of willows and poplars, is now traversed. Picturesque country-houses, small parks, and thriving mills are passed in rapid succession. — 11 M. *Montgeron*. — 13 M. *Brunoy*, before reaching which the train crosses the *Yères*. The chain of hills and the plain are studded with innumerable dwellings. The train now crosses a viaduct 413 yds. long and 100 ft. in height, commanding a beautiful view, and then enters the plain of *La Brie*. — $16\frac{1}{4}$ M. *Combs-la-Ville*. — $19\frac{1}{2}$ M. *Lieusaint*. — 24 M. *Cesson*. Near Melun the Seine is again reached and crossed.

28 M. *Melun* (*Grand Monarque*, Rue du Miroir, near St. Aspais;

diligence to Barbison, see p. 335), which lies about $\frac{1}{2}$ M. from the station, the capital of the Département de Seine et Marne, an ancient town with 12,560 inhab., is picturesquely situated on an eminence above the Seine.

Melun is the *Melodunum* mentioned by Cæsar as having been captured by his lieutenant Labienus. The Normans also laid it waste five times in the 4th cent.; and after it had become a royal residence it was again several times captured: by Charles the Bad of Navarre in 1358; by Du Guesclin in 1359; by the English in 1420, after an obstinate resistance by the inhabitants, who succeeded in expelling the invaders ten years later; and by Henry IV. in 1590.

The handsome Avenue Thiers and the Rue St. Ambroise lead from the station to an island, on which, to the right, rises the *Church of Notre Dame*, built in the 11th cent. but afterwards remodelled and recently restored. The transepts are surmounted by two Romanesque towers. The interior, the most interesting portion of which is the choir; contains some excellent old paintings: in the right aisle, Descent from the Cross, by *Jordaens*, after Rubens; Infant Moses, by *Primaticcio*; in the choir, an early copy of Raphael's large Holy Family. In the right aisle there is also a good funereal monument (15th cent.).

The principal street on the other side of the island skirts the back of the *Church of St. Aspais*, on the apse of which is a modern medallion of Joan of Arc, by Chapu, erected to commemorate the expulsion of the English in 1430. The church dates from the 16th century. The exterior is richly decorated, while the interior deviates from the usual form in having double aisles terminating in apses. The choir has some fine old stained glass and six handsome marble medallions of apostles and church-fathers, dating from the 17th century. The right aisle contains two ancient paintings, a Last Supper and the Hebrew Children in the Fiery Furnace; in the left aisle is a large modern painting of Christ, by H. Schopin. Fine organ-case.

The Rue du Miroir, in front of St. Aspais, ascends to the upper part of the town, in which are situated the *Belfry of St. Barthélemy*, erected in the 18th cent., and the *Préfecture*, in the style of Louis XIII.

A few yards to the W. of St. Aspais is the Rue du Marché-aublé, through which and the following street we reach the *Hôtel de Ville*, a handsome Renaissance edifice, part of which is ancient. In the interior is a small museum and a library. The court is embellished with a *Statue of Amyot* (1513-93), bishop of Auxerre and translator of Plutarch. The bishop was a native of Melun. Behind the Hôtel de Ville lies a tasteful public garden.

By the Rue de l'Hôtel de Ville we reach the *Place St. Jean*, with its ornamental fountain, erected in 1864. — Farther on, on an eminence above the right bank of the Seine, lies the park of the *Château de Vaux-le-Pénil* (18th cent.), which affords pleasant walks.

The *Château de Vaux-Praslin*, a gorgeous structure of the 18th cent., lying about 4 M. from Melun, in the same direction, is reached by the

FORÊT DE FONTAINEBLEAU

1:100,000

0 500 1000 2000 3000

Mètres.

(Le Bas Bréau)
Barbison
Mare à Piat

Caverne
des Brigands
Vallée
de la Soie
(Tour Denebourg)

Gorges
d'Aprenant
Hauteurs
de la Soie
Les Monts
Girard
Le gros Totaux

ARBONNE

Rochers et Gorges
de
Franchard
Rocher des Zramet

La Queue de Vache

Rocher de la Touche

Bois Rond

Gorge aux Archers

Plaine et Plâtiers

de la Haute Barne

Gorge aux Loups

Le Long Rocher

Marlotte

CHAILLY

Barbison

Macherin

Gorges

et

Vallée d'Aprenant

Les Monts Girard

Plaine de Macherin

Milieu

Buttes de Franchard

Le Chêne Brûlé

Rochers et Gorges de Franchard

Le Chêne Brûlé

Le Chêne Brûlé

Le Chêne Brûlé

Le Chêne Brûlé

Le Chêne Brûlé

Le Chêne Brûlé

Le Chêne Brûlé

Le Chêne Brûlé

Le Chêne Brûlé

Le Chêne Brûlé

Le Chêne Brûlé

Le Chêne Brûlé

Le Chêne Brûlé

Le Chêne Brûlé

Le Chêne Brûlé

Le Chêne Brûlé

Le Chêne Brûlé

Le Chêne Brûlé

Le Chêne Brûlé

Le Chêne Brûlé

Le Chêne Brûlé

Le Chêne Brûlé

Le Chêne Brûlé

Le Chêne Brûlé

Le Chêne Brûlé

Le Chêne Brûlé

Le Chêne Brûlé

Le Chêne Brûlé

Le Chêne Brûlé

Le Chêne Brûlé

Le Chêne Brûlé

Le Chêne Brûlé

Le Chêne Brûlé

Le Chêne Brûlé

Le Chêne Brûlé

RECLOSSES

FONTAINEBLEAU

Le Mont Morillon

Rocher des Demoiselles

Mont aux Bœufs

Les Grands Feuillets

La Canche

Guilleminette

Les Erables et Dénégé

Marchais Olivier

Ventes aux Perches

Les Clos Baron

Clos au Roy

Ventes Lapiot

Les Clos Baron

Clos au Roy

Ventes Lapiot

Les Clos Baron

Clos au Roy

Ventes Lapiot

Les Clos Baron

Clos au Roy

Ventes Lapiot

road ascending to the right from the Place St. Jean. The château, which is surrounded by an immense park, was erected at a cost of 720,000*fr.* by *Nicolas Fouquet*, 'surintendant des finances' under Louis XIV. The owner was in the habit of entertaining the king here at costly fêtes, which eventually led to his ruin, as the enormous expenses could only be met by a dishonest use of the public funds. The interior, which contains paintings by *Lebrun* and *Mignard*, may be inspected on application to the proprietor.

Beyond Melun we see the Château de Vaux-le-Pénil (p. 328) on the left. Then, after affording several picturesque glimpses of the valley of the Seine on the same side, the train reaches (32 M.) *Bois-le-Roi* and enters the forest of Fontainebleau.

37 M. Fontainebleau. — The station is about 1½ M. from the palace (omnibus 30 or 50 c.).

Hôtels. *HÔTELS DE FRANCE ET D'ANGLETERRE, DE L'AIGLE NOIR*, and *DE L'EUROPE*, all near the palace (arrange prices on ordering); *DE LA VILLE DE LYON ET DE LONDRES*, Rue Royale 21, pens. 12 fr.; *DU LION D'OR*, Rue des Bons-Enfants 25; *DE LA CHANCELLERIE*, Rue Grande 2, near the palace; *DU CADRAN-BLEU*, Rue Grande 9, déj. 3, D. 3½, D. à part 4 fr.; *HÔTEL-PENSION LAUNOY*, Boul. de Magenta 37, near the palace; *DU NORD ET DE LA POSTE*, Rue de France 27, R. 2½-3, déj. 2½-3, D. 3-3½, pens. 7½-8 fr.

Restaurants. *Perruillat*, Rue des Bons-Enfants 23, opposite the Jardin de Diane (déj. 2½, din. 3 fr.); *Nigrin*, Rue Grande 112, a little cheaper; *Restaur.-Fâtisserie*, Rue de la Paroisse 5, opposite the church (déj. 1¾, D. 2 fr.). — **Cafés.** *Naudin*, Rue des Bons-Enfants 33; *Cadran Bleu*, see above; *de l'Hôtel-de-Ville*, Rue Grande 23; *Henri II.*, Rue Grande 65; etc.

Carriages. Per drive in the town, 2 pers., 1 fr. 25 c., on Sun. 1 fr. 50 c., 4 pers. 2 fr. and 2¼ fr. To the station, 2 pers. 1½, 4 pers. 2 fr. (½ fr. extra 'à domicile'). Per hour: in the town 2 and 3 fr.; in the forest 2½ and 3 fr. for the first hour, and 2 and 2¼ fr. for each additional hour; carriage with 5 seats 4 and 3 fr. Luggage 30 c. per 33lbs. (30kil.). The tariff does not hold during the races.

Post and Telegraph Office, Rue du Château 22.

Fontainebleau, which like Versailles chiefly owes its origin to the palace, is a quiet place with broad, clean streets, and 13,340 inhabitants. With the exception of the palace, the only buildings of any importance are the modern Church and *Hôtel de Ville* in the Rue Grande. The Place du Palais-de-Justice, at the back of the church, is adorned with a bronze statue, by Godin, of *General Damesme*, a native of Fontainebleau, who was killed at Paris by the insurgents in June, 1848.

***Palace.** The château or palace of Fontainebleau, situated on the S.W. side of the town, is said to occupy the site of a fortified château founded by Louis VII. in 1162. It was *Francis I.* (d. 1547), however, who converted the mediæval fortress into a palace of almost unparalleled extent and magnificence. The exterior is less imposing than that of some other contemporaneous edifices, as the building, with the exception of several pavilions, is only two stories in height; but the interior, which was decorated by French and Italian artists (Fontainebleau school, see p. 89) in the style of Giulio Romano, is deservedly much admired. *Henri IV.* (d. 1610) made considerable additions, but since that period it has undergone little alteration. It was a favourite residence of *Napoleon I.*, but after the Restoration it was much neglected. *Louis Philippe* and *Napoleon III.* spent large sums of money in restoring it.

Several historical associations attach to the Palace besides those relating to Napoleon, Pius VII., and Queen Christina which are mentioned afterwards. On 4th June, 1602, Henri IV. caused his companion in arms Marshal Biron to be arrested here on a charge of high treason, to be beheaded in the Bastille a month later. Here, in 1685, Louis XIV. signed the Revocation of the Edict of Nantes, by which Henri IV. had granted toleration to the Protestants in 1598. The Grand Condé died here in 1686, and it was in this palace that the sentence of divorce was pronounced against the Empress Josephine in 1809.

The palace is shown daily from 10 to 5 o'clock in summer and from 11 to 4 in winter, gratis. The custodian who shows the apartments is to be found at the entrance, or in the principal court, or in the offices to the left of the railing.

This extensive pile of buildings contains five different courts — the *Cour du Cheval Blanc* or *des Adieux*, the *Cour de la Fontaine*, the *Cour Ovale* or *du Donjon*, the *Cour des Princes*, and the *Cour de Henri IV.* or *des Offices*.

The *Cour du Cheval Blanc*, by which we enter, the largest of these, is separated from the street and the Place de Ferrare or de Solferino by a railing, and derives its name from a statue it formerly contained. It is sometimes called the *Cour des Adieux* from having been the scene of Napoleon's parting from the grenadiers of his old Guard on 20th April, 1814, after his abdication. Here, too, on 20th March, 1815, on his return from Elba, the emperor reviewed the same troops before marching with them to Paris.

The wing to the right of the *Cour du Cheval Blanc* is occupied in summer by M. Carnot, president of the republic.

The central part of the palace is approached by the massive *Escalier du Fer-à-Cheval*, so named from its horseshoe form. Visitors generally enter here, on the left side, and we shall briefly describe the route usually followed by the custodians.

The *Chapelle de la Trinité*, on the ground-floor to the left, has a fine ceiling, painted by Fréminet, an imitator of Michael Angelo. The altar-piece is by J. Dubois; the statues by G. Pilon. In this chapel Louis XV. was married in 1725, and the Duc d'Orléans (p. 156) in 1837, and Napoleon III. was baptised here in 1810.

A broad staircase ascending thence leads to the —

Appartements de Napoléon I., on the side of the garden next to the Orangery, which consist of an antechamber; secretary's room; bath-room, with mirrors adorned with paintings, which are said to have been brought from the apartments of Marie Antoinette at the Trianon; room in which Napoleon signed his abdication on 4th April, 1814, on the small round table in the centre; study, with a ceiling by Regnault, representing Law and Justice; bedroom with a chimney-piece of the time of Louis XVI., Napoleon's bed, a clock adorned with antique cameos, given to Napoleon by Pius VII., the cradle of the King of Rome, fine furniture and bronzes, etc.

To the left is the **Salle du Conseil*, of the period of Louis XV., decorated by Boucher, and containing furniture covered with

tapestry-work from Beauvais. Large table, the top of which is a single piece. Then the **Salle du Trône*, with a handsome ceiling, containing a chandelier in rock crystal and wainscoting executed in the reigns of Louis XIII. and Louis XIV. We next enter the boudoir of Marie Antoinette, with two fine ivory vases, her **Bedroom* adorned with hangings presented by the city of Lyons, and two rooms containing vases from Sèvres.

We now reach the *Galerie de Diane*, or *de la Bibliothèque*, a hall 88 yds. in length, constructed under Henri IV. and restored by Napoleon I. and Louis XVIII. It is adorned with paintings representing mythological scenes, by *Blondel* (d. 1853) and *A. de Pujol* (d. 1861). It contains the library (35,000 vols.) and a number of curiosities, including Monaldeschi's coat of mail.

Under the *Galerie de Diane* is the old *Galerie des Cerfs*, which is now converted into a 'garde-meuble' and is not shown to visitors. It was in this room in 1657 that Queen Christina of Sweden, while a guest at the French court after her abdication (1654), caused her unfortunate equerry and favourite Count Monaldeschi to be put to death after a pretended trial for treason. Louis XIV. expressed his strong disapprobation of this proceeding, but took no farther steps in the matter, and Christina continued to reside at Fontainebleau for two years longer. Monaldeschi is interred in the small church of *Avon*, a village on the E. side of the park, about 1 M. from the palace.

We are next conducted to the *Salons de Réception*, adjoining the Cour Ovale (p. 333). The antechamber is embellished with Gobelins tapestry, and the following apartment with tapestry from Flanders (myth of Psyche), as well as that of Francis I., which contains a handsome chimney-piece of the 16th century and some ebony reliquaries of the time of Louis XIII. — The *Salon Louis XIII.*, in which that king was born, was adorned with paintings by *Ambroise Dubois* (d. 1615) from the story of Theagenes and Charicles. The *Salles de St. Louis* contain fifteen pictures relating to the life of Henri IV., and over the chimney-piece a statue and a portrait of the same king. In the *Salon aux Jeux* is a clock of Louis XIV. The *Salle des Gardes*, the last of this series, looks towards the Cour de la Fontaine (p. 333). It contains a handsome chimney-piece, partly by *G. Pilon*, adorned with a bust of Henri IV., statues of Power and Peace, an ancient ceiling, and a fine modern flooring. A passage to the left leads to the —

Escalier du Roi, or grand staircase, adorned with paintings after Primaticcio by *Nic. dell' Abbate*, and restored by *A. de Pujol*. The subjects are from the life of Alexander. The Cour Ovale (p. 333) is well seen from the landing.

The *Appartements de Mme. de Maintenon*, which we next enter are less interesting. In the salon is some tapestry worked by the ladies of St. Cyr and a cabinet by Buhl. — Thence a passage leads to the —

**Galerie d'Henri II.*, or *Salle des Fêtes*, a hall 33 yds. long and 11 yds. in width. It was constructed by Francis I., richly deco-

rated by Henri II., and successfully restored by Louis Philippe. The initial letter of Henri II. frequently recurs, together with a crescent and the letter *D*, the emblem and initial of Diana of Poitiers. The mythological frescoes by *Primaticcio* and his pupil *Nic. dell' Abbate* have been restored by *Alaux*, and have thus lost much of their originality. At the end of the hall is a handsome chimney-piece. The windows afford a pleasant survey of the gardens.

Retracing our steps to the Salon St. Louis, we turn to the left into the *Galerie de François I.*, 70 yds. in length and 6½ yds. in width, which extends from the Cour de la Fontaine (see below) to the vestibule of the Fer-à-Cheval (p. 330). To the left of the entrance is a jewel-casket in Sèvres, of the time of Louis Philippe. The gallery is embellished with fourteen large compositions by *Rosso Rossi*, representing allegorical and mythological scenes relating to the history and adventures of Francis I. The paintings are separated from each other by bas-reliefs, caryatides, trophies, and medallions. The winged salamander, being the king's heraldic emblem, and his initial *F* frequently recur.

The *Vestibule d'Honneur* possesses two handsome oaken doors of the time of Louis XIII., and four modern doors in the same style. — To the left are the *Appartements des Reines Mères* and of *Pius VII.* They were once occupied by Catherine de Médicis (p. 87); by Anne of Austria (d. 1666), mother of Louis XIV.; and afterwards by Pius VII., who was a prisoner here from June, 1812, to Jan., 1814.

We pass through an antechamber with chairs and hangings in Cordovan leather and a magnificent Louis XIII. reliquary, a second antechamber with tapestry (Story of Esther), and a room with Gobelins tapestry and furniture covered with stuffs from Beauvais, to the bedroom of Anne of Austria, which is also hung with Gobelins tapestry. Beyond this are two small rooms (portrait of Pius VII. after *David*, in the first), the pope's bedroom, and another apartment with Gobelins tapestry. The last of these rooms is near the fish-pond (p. 333). We then enter an antechamber, and the 'Galerie des Fastes', so called from a project of decorating it with paintings of the history of Fontainebleau. It contains a few ancient pictures of secondary importance.

Lastly we reach the *Galerie des Assiettes*, which is sometimes shown to visitors first. It derives its name from the quaint style in which it was decorated by order of Louis Philippe with plates of porcelain bearing views of royal residences. It is also called *Galerie des Fresques* from the frescoes by A. Dubois which have been transferred hither from the Galerie de Diane.

On the ground-floor, to the right, in the main building is a **Chinese Museum*, open at the same hours as the palace. The entrance is in the Cour de la Fontaine (p. 333), reached by a large door to the right of the Fer-à-cheval staircase.

Room I. Perfume-censers; jardinières in cloisonné enamel; copper dragons and pagoda; basreliefs in jasper; lacquer panels; etc. In the

glass-cases: crown of the king of Siam; handsome ewer; etc. — Room II. Wooden pagoda; valuable jewels, including a belt presented by Louis XV. to the Siamese ambassadors; jewel of the order of the elephant; mandarin's collar in jade, etc. This room also contains statues by Schœnewerk and Cordier, and portraits by C. Vanloo of Louis XV. and Maria Leczinska. — Room III. Palanquin; gongs; weapons and armour; flags, etc.

Gardens. The principal entrance is by the *Cour de la Fontaine*, to the right of which there is a *Pond* with a pavilion. The carp in this pond are still a source of interest and amusement to visitors.

On the right lies the *Jardin Anglais*, planted under Napoleon I.

On the left, at the end of the *Avenue Maintenon*, which leads to the forest, rises the *Porte Dorée*, dating from the reign of Francis I., as the salamander in the armorial bearings indicates. It is adorned with old frescoes, now restored. This forms one of the entrances to the *Cour Ovale*, or *du Donjon*, a court 80 yds. long and 34 yds. in width, the oldest in the palace. It has undergone various alterations and has lost its original form, but is still interesting on account of its fine colonnades of the early French Renaissance; the capitals of the pillars are especially fine. It is not open to the public. To the E. is a curious gate, covered with a dome, called the *Porte Dauphine*, or the *Baptistère*, from the fact that Louis XIII. was baptised here.

Beyond the pond is the *Parterre*, a second public garden, designed by Le Nôtre in the reign of Louis XIV., containing a square pond and a round one. Farther on is the *Canal* (1320 yds. long), formed by order of Henri IV., with bronze and marble statues and groups in front of it. To the left is the *Park*, with a *Labyrinth* and the famous *Vinery* of the palace. The building on the right of the canal, the former *Vénerie*, is now occupied by the *Ecole d'Application de l'Artillerie et du Génie*, removed hither from Metz.

The ***Forest of Fontainebleau**, which is about 50 M. in circumference and covers an area of 42,500 acres, is justly regarded as the most beautiful in France. On the N.E. side it is bounded by the sinuosities of the Seine. The ground here is of a very varied character, the rock formation consisting chiefly of sandstone which yields most of the paving stones of Paris. The magnificent timber and picturesque gorges of the forest afford numerous pleasant walks, and there are good paths in every direction.

The best plan of the forest is the admirable *Carte topographique de la forêt et des environs de Fontainebleau* by Denecourt (d. 1874), a local celebrity, who spent a considerable part of his life and of his patrimony in exploring and studying the forest, and in rendering its finest points accessible by footpaths. The map in the Handbook is a reduced copy of Denecourt's. All points where paths cross each other are provided with finger-posts. It should be observed that the blue marks, which M. Denecourt has caused to be placed on trees and rocks, indicate the way to the most picturesque points. The red marks are connected with the forest administration, and point in the direction of the town. — Those who stray from the beaten paths should be provided with 'alcali volatil' for use in the case of adder-bites.

The finest point of view near Fontainebleau is the ***Tour Dene-**

court (*Fort de l'Empereur*), which is reached in $\frac{1}{2}$ hr. from the railway-station. We ascend the road to the left by the restaurants at the station; cross the railway, follow it to the right, soon turning to the left at a laboratory of vegetable biology, and follow the broad, sandy path, leading to the height on which the 'Fort' is situated. This 'fort' is a belvedere, built in the form of a miniature fortress, which commands a picturesque view for nearly 40 miles round. The Eiffel Tower in Paris is seen. From Fontainebleau we reach the tower in about $\frac{3}{4}$ hr., via the Rue Grande, the Melun road, and the ($\frac{13}{4}$ M.) Chemin de Fontaine-le-Port, to the right, where a post indicates the way to the Tour Denecourt (comp. the Map). Nearer the town, to the right of the Melun road, is the *Croix de Calvaire*, commanding a view of Fontainebleau, which is not visible from the Tour Denecourt.

The *Race-Course* and *Drill-Ground* of Fontainebleau lies in the *Vallée de la Solle*, to the left of the road from Melun; and between that road and the road from Paris (see below) are the *Nid de l'Aigle* and the *Gros Fouteau*, two of the finest groups of trees in the forest ($\frac{1}{4}$ M. from the town).

Visitors seldom extend their excursion beyond the *Rochers et Gorges de Franchard*, $2\frac{1}{2}$ M. from the town (carr., p. 329). Near the Barrière de Paris, at the N.W. angle of the town, at the end of the Rue de la France, we follow the broad road diverging to the left from the high-road to Paris (which leads to the Gros Fouteau and the Nid de l'Aigle, see above). Carriages turn to the left at the Route Ronde. Pedestrians quit the road after 35 min. by a path to the left (Route de la Fosse Rateau), from which after 5 min. another footpath diverges to the right, leading through the forest in 5 min. more to the *Restaurant de Franchard* (dég. 3, D. $3\frac{1}{2}$ fr.), the most frequented spot in the environs of Fontainebleau.

The celebrated *Rochers et Gorges de Franchard*, a rocky basin overgrown with trees and bushes, about $2\frac{1}{2}$ M. in circumference, begin about 5 minutes' walk to the W., at the *Rochers des Ermites* and the '*Roche qui pleure*', a little beyond the ruins of an ancient monastery (now a forester's house). The water which trickles from this 'weeping rock' is popularly believed to be a remedy for diseases of the eye; but its appearance is not inviting. The top of the rock commands a good survey of the gorge: in the distance to the N. are visible the *Gorges d'Apremont*, another rocky wilderness (see below). The visitor may now return to the town by the same route.

An excursion (5 hrs.) to the *Gorges d'Apremont* and the fine timber of the neighbouring *Bas-Bréau* is not less interesting than the above (comp. the Map). Between the Rochers d'Apremont and the *Monts Girard*, another chain of hills, extends the *Dormoir*, a plain partly wooded, and partly covered with rocks and heath, one of the most beautiful parts of the forest, and a favourite sporting rendezvous. In the upper part of the Gorges d'Apremont is

BANLIEUE DE PARIS

Echelle de 1: 800,000

Kilomètres
0 10 20 30





situated the *Caverne des Brigands*, said once to have been the haunt of bandits. The man who lives in a rustic hut here sells refreshments at high prices, and also souvenirs of the forest. Farther to the N. is the high-road to Paris, already mentioned, which leads, in the direction of Fontainebleau, past the *Hauteurs de la Solle* to the Gros Fouteau (p. 334), etc. — The Bas Bréau is nearer the station of Bois-le-Roi (p. 329; $1\frac{1}{4}$ hr.) than the station of Fontainebleau. — *Barbison* (Hôtel des Artistes; Siron-Blatrix), about $\frac{3}{4}$ M. to the W., contains a colony of artists.

A diligence plies several times a day to Barbison ($1\frac{1}{4}$ hr., fare 1 fr.) from Melun (p. 327; comp. the Indicateur).

Among the interesting points in the S. part of the forest may be mentioned the *Rocher d'Avon*, near the palace-park, between the road to Moret and that to Marlotte, and the *Gorge aux Loups* and the *Long Rocher*, near the verge of the forest. — The village of *Marlotte* (Hôtel Mallet), $\frac{3}{4}$ M. farther on and $5\frac{1}{2}$ M. from Fontainebleau, is, like Barbison, a favourite resort of artists. The nearest station is *Montigny*, on the line to Montargis, $\frac{3}{4}$ M. to the E., whence we may return to Fontainebleau viâ *Moret*.

19. Sceaux and the Valleys of the Bièvre and the Yvette.

The following excursion is recommended in favourable weather to all lovers of nature, especially to those who are good walkers. At least an afternoon should be devoted to it, in order to allow time for a visit to Sceaux and Robinson (see below).

a. From Paris to Sceaux.

1. By Tramway.

The tramway-cars start from the *Place St. Germain-des-Prés* (p. 251), which is easily reached with 'correspondance' from any part of Paris (comp. the Appx.). The terminus is at *Fontenay-aux-Roses* (p. 336). The distance is $5\frac{1}{2}$ M., traversed in 1 hr. 5 min.; fares 60 or 30 c. On Sun. and holidays the cars are often overcrowded. From the terminus we have fully 1 M. to walk to Sceaux by a pleasant road.

Starting from the *Place St. Germain-des-Prés* (Pl. R, 19; IV; see p. 251), the tramway follows the wide Rue de Rennes to the Gare Montparnasse (p. 262). It then turns to the left into the Boul. Montparnasse and immediately afterwards to the right into the Boul. Raspail, which skirts the Cemetery of Montparnasse. Beyond the *Place Denfert-Rochereau* (with the Gare de Sceaux, p. 242, on the left), we traverse the Avenue d'Orléans to the church of St. Pierre-de-Montrouge (p. 243), and then the Avenue de Châtillon, by which we quit Paris. — Outside the gate lies *Malakoff*, a village with 8118 inhabitants.

Châtillon (2389 inhab.) lies at the foot of a plateau, which commands a good view of Paris. A little to the W. is Clamart (p. 286).

About $\frac{3}{4}$ M. to the E. of Châtillon lies *Bagneux* (1500 inhab.), with numerous villas and an interesting church, dating in part from the 13th century. Châtillon and Bagneux were both included in the German lines in 1870-71. On 13th Oct., 1870, the French made a vigorous attack on the German troops posted here, and after a sharp contest succeeded in taking

possession of Bagneux, which, however, they evacuated on the same evening. Monuments in memory of those who fell on this occasion have been erected both at Bagneux and at Châtillon.

At the S.W. end of Châtillon the road divides. We follow the left branch to **Fontenay-aux-Roses** (2935 inhab.), a favourite point for a walk from Paris, 1 M. to the S.E. of Châtillon, and the terminus of the tramway-line. It is surrounded with fields of strawberries and violets, in both of which it carries on a brisk trade. A fine view of Paris is enjoyed from the N. side of the large Place where the car stops.

To reach the railway-station (see below) we descend the Rue Boucicaut farther on; but it is shorter to go from Fontenay to Sceaux by the road than by the railway. To the right, as we descend the street, is the *Maison Boucicaut*, a handsome modern structure; to the left is *Ste. Barbe-des-Champs*, a small dependancy of the college of that name in Paris. Farther on, beyond a *Normal School* for female teachers, the road forks. The right branch leads to (1 M.) Sceaux (p. 337) viâ the ($\frac{1}{2}$ M.) station of Fontenay; the left to ($\frac{1}{2}$ M.) Bourg-la-Reine (p. 337).

The direct route to ($\frac{1}{4}$ M.) *Robinson* (p. 337) diverges to the right from the road from Châtillon, before the Place de Fontenay. At the first fork we keep to the left (Rue de Châtenay). On reaching the road from Sceaux to Robinson, we keep to the right.

The road to the right at the above-mentioned fork leads to the ($\frac{1}{2}$ M.) little village of *Plessis-Piquet*, prettily situated on the side of a hill, and separated from the Bois de Meudon and ($\frac{1}{4}$ M.) Clamart by the small plain through which runs the road to Châtillon.

2. By Railway.

7 M. *Ligne de Sceaux, Orsay, et Limours*. The station is in the Place Denfert-Rochereau (Pl. G, 20; see p. 23). Trains leave Paris hourly from 8 a.m. to 11 p.m., and Sceaux hourly, starting at the half-hours or a little later. Fares 1 fr. 20, 80, 60 c.

The line crosses the streets of Paris by means of several viaducts, traverses the park of Montsouris (p. 243), and intersects the fortifications. — $\frac{3}{4}$ M. *Sceaux-Ceinture*, the junction for the Chemin de Fer de Ceinture (see Appx.). To the left are *Fort Bicêtre* and the large lunatic asylum and hospice of that name. Numerous quarries and market-gardens on both sides. The small pyramidal wooden structures cover the mouths of deserted quarries, in which mushroom-rooms are now cultivated.

$\frac{3}{2}$ M. *Arcueil*, a village (6465 inhab.) in the valley of the *Bièvre*, with a church of the 13-15th centuries. The *Ecole Albert-le-Grand*, in the Grande-Rue, an ecclesiastical establishment, was managed in 1870-71 by Dominican monks, several of whom were massacred by the Communists. It contains a mortuary chapel, with a statue of P. Captier, by Bonnassieux.

To the left, visible both on reaching and quitting the station, is the large *Aqueduct of Arcueil*, consisting in fact of two aqueducts, one above the other, with a total height of 135 ft. The name of the village is derived from an ancient aqueduct (*Arculi*) constructed here by the Romans, on the

site of which Jacques Debrosse (1613-24) built another aqueduct, 440 yds. long, for the purpose of conveying water from the village of *Rungis* to the garden of the Luxembourg. In 1868-72 a second aqueduct was placed on the top of this, and, though the masonry is not so good as that of Debrosse, it is still a notable piece of engineering. — A road to the left of the Aqueduct ascends to *Villejuif*.

Beyond Arcueil the fortified heights of *Villejuif* (see above; *Redoute des Hautes-Bruyères*) come into sight. Farther on Bagneux (p. 335), Fontenay-aux-Roses (p. 336), and the fort of Châtillon (p. 335) are seen to the right. To the left are *L'Hay* and *Chevilly*, also scenes of contests during the siege of Paris.

4½ M. *Bourg-la-Reine*, where the line to the upper valley of the Bièvre and to Limours diverges to the left (p. 338). Farther on, to the left, is the *Lycée Lakanal*. — 5½ M. *Fontenay-aux-Roses* (p. 336); the station is nearer to Sceaux than to Fontenay. — The train now ascends in numerous sharp curves to —

7 M. *Sceaux* (*Hôtel de l'Etoile-du-Nord*; *Restaurant du Parc*, near the station), a small town with 3443 inhab., pleasantly situated upon a hill amid charming scenery. The *Château of Sceaux*, built by Colbert, afterwards became the property of the Duc du Maine, son of Louis XIV. and Mme. de Montespan. During the first half of the 18th cent. it was celebrated for the brilliant fêtes given here by the Duchesse du Maine to the little court of wits and 'grands seigneurs' she assembled around her. The château was destroyed at the Revolution. A small piece of the *Park* has been preserved (to the right of the station) and is open to the public; it affords a fine view of the valley of Fontenay. Florian (1755-1794), the poet and fabulist, is buried in the cemetery of Sceaux. A bust of Florian and one of the Provençal poet Auhanel (1828-1886) are placed here.

The prettiest walk from Sceaux is to Robinson, a group of houses charmingly situated at the foot of a wooded hill 1 M. from the station, and reached by following the high-road (omn. 30 c.). It possesses numerous garden-cafés, with platforms placed amid the branches of the large chest-nuts, and in fine weather it is thronged with pleasure-seekers. A house with a tower on a height a little beyond Robinson commands an admirable view of the valley of the Bièvre. Horses and asses may be hired at Sceaux (horses 2-3 fr. per hr., asses 1-1½ fr.).

h. From Sceaux to the Valley of the Bièvre (Versailles).

1. Through the Bois de Verrières.

The Bois de Verrières is a favourite resort of riders, who reach it from Robinson by the road passing the above-mentioned house with the tower. The first part of the route is, however, monotonous and devoid of shade, and the pedestrian route by the lower road is preferable. Walkers traverse the wood and descend to the valley, whence they may return by train.

The lower road leads from Robinson towards the S. and passes (½ M.) *Aulnay* and (1½ M.) *Châtenay*. Just beyond the latter village we reach the high-road from Versailles to Choisy-le-Roi, which descends to the left to the railway-station of (¼ M.) *Berny* (p. 338) and ascends to the right to the Bois de Verrières.

The Bois or Buisson DE VERRIÈRES covers a small plateau
BAEDEKER. Paris. 10th Edit. 22

which commands the valley of the Bièvre on the E. and S. and has consequently been fortified with six redoubts. Its main axis, from Châtenay to Bièvre, is not above $2\frac{1}{2}$ M. long. Various points in it afford charming views of the valley. Equestrians generally proceed to *Malabry* (Inn), about $1\frac{1}{4}$ M. from Châtenay, and thence to the so-called '*Obelisk*', a circular clearing in the wood, where the chief forest-paths converge. Walkers reach this point directly by ascending from Châtenay along the road to Igny and then turning to the left. Proceeding in the same direction beyond the clearing we reach the margin of the plateau, where it overlooks the most attractive part of the valley. On the other side we obtain a view of a pretty little side-valley, with the ruins of the old *Abbaye aux Bois*. To the right of the above-mentioned road to Igny lies the village of *Bièvre*, where we descend into the valley (see below).

2. By Railway.

RAILWAY from *Bourg-la-Reine* (p. 337) to *Massy-Palaiseau*, on the Ligne de Grande-Ceinture, 5 M.; from Massy to *Versailles*, $9\frac{1}{2}$ M. Through-trains, of which there are few, run from Bourg-la-Reine to Versailles in 50-80 min. (fares 2 fr. 95, 2 fr. 20, 1 fr. 65 c.). Bourg-la-Reine is $1\frac{1}{4}$ M. from Sceaux by road.

Bourg-la-Reine, see p. 337. Short tunnel. — $1\frac{1}{4}$ M. *Bermy*, with a race-course; $2\frac{1}{2}$ M. *Antony*. To the right we obtain a view of the Bois de Verrières. — 4 M. *Massy*. — At (5 M.) *Massy-Palaiseau* our line joins the Ligne de Grande-Ceinture. — Railway to Limours, see p. 339.

FROM MASSY-PALaiseau TO VALENTON, $11\frac{1}{2}$ M. This somewhat uninteresting section of the Ligne de Grande-Ceinture has stations at *Wissous*, *Rungis* (p. 337), *Orly*, and *Villeneuve-le-Roi*, beyond which it crosses the Ligne d'Orléans, the Seine, and the Ligne de Lyon. *Valenton* is a junction near the last-named line, at which this section of the Ligne de Grande-Ceinture joins that from Champigny (p. 215) and Sucy-Bonneuil (p. 215; $2\frac{1}{2}$ M.) to Villeneuve-St. Georges, which is situated 2 M. to the S. (see p. 327).

FROM MASSY-PALaiseau TO JUVISY, 9 M., railway in $\frac{1}{2}$ hr. (fares 1 fr. 85, 1 fr. 35, 95 c.). — 2 M. *Champlan*. — 3 M. *Longjumeau*, a manufacturing town with a church of the 12th and 15th centuries. — $7\frac{1}{2}$ M. *Savigny-sur-Orge*, with a fine château of the 15th and 18th centuries. Our line here joins the railway from Paris to Orléans. — 9 M. *Juvisy* is also a station on the Ligne de Grande-Ceinture, which runs hence to (4 M.) *Villeneuve-St. Georges* (p. 327).

Beyond the Bois de Verrières the Ligne de Grande-Ceinture traverses the prettiest part of the VALLEY OF THE BIÈVRE, with its verdant meadows and luxuriant woods. — 8 M. *Bièvre*, beautifully situated on the slope of a plateau. Among the fortified hills to the left of the valley lie the *Étang de Saclay*, the *Étang du Trou Salé*, and other ponds which furnish the water for the fountains at Versailles. — 9 M. *Vauboyen*; $10\frac{1}{2}$ M. *Jouy-en-Josas*. Farther on the train turns to the right and ascends by a lofty viaduct. To the left is the *Aqueduct of Buc*, 530 yds. long and 70 ft. high, built in 1686 to convey water to Versailles from the ponds between the valleys of the Bièvre and the Yvette. Soon after our line joins the Ligne de Bretagne. — $14\frac{1}{2}$ M. *Versailles*, Gare de Chantiers (p. 287).

c. From the Valley of the Bièvre to the Valley of the Yvette.

Railway from Massy-Palaiseau to (10 M.) *St. Remy-lès-Chevreuse*, by a continuation of the line from Paris viâ Bourg-la-Reine (p. 338), in 40-50 min. (fares 2 fr. 5, 1 fr. 55, 1 fr. 15 c.). — *Chevreuse* is about $1\frac{1}{2}$ M. from the station, and $2\frac{1}{2}$ M. farther on is *Dampierre*, to both of which places public conveyances ply (see below). *Vaux-de-Cernay* lies about 3 M. from *Dampierre*.

Those who do not wish to walk and who do not object to public conveyances may make this excursion as follows: leave Paris at 1 p.m., and on arriving at *St. Remy* take the omnibus to *Chevreuse*; after visiting the ruined chateau, take the omnibus, which starts at 4.15 p.m. for the station of *Laverrière* on the line from Paris to Chartres (Chemin de Fer de l'Ouest), quit the vehicle at *Dampierre*, walk thence to (3 M.) *Vaux-de-Cernay*, and return in time to catch the omnibus starting from *Dampierre* at 9 p.m. for *St. Remy*, in connection with the last train to Paris. Omnibus-fare to *Chevreuse* 40, to *Dampierre* 70 c., or, if through-tickets from or to Paris are taken, 20 and 50 c. — Special permission is required both to visit the chateau at *Dampierre* and the ruins at *Vaux-de-Cernay* (see below).

Massy-Palaiseau, see p. 338. — $1\frac{1}{4}$ M. *Palaiseau*, an ancient place which owes its name to a royal palace ('palatium'), now destroyed. In the Place de la Mairie is a bronze statue of *Barra*, a boy-volunteer killed by the Vendéens in 1793. To the right is a new fort. — The train now enters the pretty *Valley of the Yvette*, which is flanked by wooded hills. — 5 M. *Orsay*, a large village to the left. — 7 M. *Gif*. — Then to the right, before the next station, the ruins of *Chevreuse* become visible. — 10 M. *St. Remy-lès-Chevreuse*, the station for *Chevreuse*, *Dampierre*, and *Vaux-de-Cernay*.

The railway, turning to the S., now quits the valley of the Yvette and ascends another picturesque vale to (3 M.) *Boullay-lès-Troux*. The terminus is reached at ($2\frac{1}{2}$ M. farther) *Limours*, a place of little importance.

The road, passing through the village of *St. Remy*, crosses the Yvette and turns to the left. A shorter and pleasanter footpath leads along the railway-line to the left, passes the *Château de Courbetin*, and soon comes in sight of the ruins.

Chevreuse (*Hôtel du Grand-Courrier*, Rue de la Mairie 23), a small and poorly-built village, is the capital of a barony, afterwards a duchy, various holders of which have distinguished themselves as soldiers, courtiers, or scholars.

The *Ruined Chateau* is quite unimportant in itself, but it lends picturesqueness to the distant views of the town and valley, while its terrace commands a fine survey in the direction of *Dampierre*. The ruins occupy the extremity of a small plateau, 260 ft. above the town, whence they are reached by a fatiguing, sandy path. They consist mainly of a massive donjon of unhewn limestone and two towers of hewn stone, now covered with ivy. The smaller tower is not seen from the foot of the hill or from the terrace. The interior is uninteresting.

The *Church*, built, like many of the edifices of the district, of rough limestone, has a tasteful interior, with some fair mural paintings by M. de Courbetin. Opposite the S. portal is an ogival

Romanesque doorway and a few other remains of a *Priory*, now used as a storehouse.

The road from Chevreuse to Dampierre, though picturesque, is almost entirely destitute of shade. On the right rise wooded hills, and on the heights to the left is the handsome modern *Château de Beviliers*. The *Château de Mauvière*, near the left side of the road farther on, dates from the 18th century. We now turn to the right, skirt the long wall concealing the château of Becquencourt, and, beyond a mill on the Yvette, reach the village of Dampierre.

Dampierre (*Hôtel de l'Yvette*; omnibus, see p. 339) is noted for its magnificent **Château*, belonging to the ducal family of Luynes, which has obtained an honourable distinction from the rich archæological collection now in the Bibliothèque Nationale at Paris (p. 195). The château, built for the most part in the 17th cent. by H. Mansart and restored in 1840 by Duban, is a huge structure of brick and stone, rising between a fine 'cour d'honneur' and an extensive park in a small valley, the confining hills of which limit the view in every direction. Admission to the château and park may be obtained on Fridays, from 1 to 5 o'clock, on written application to the Duchesse de Luynes, who usually spends the summer at the château (address before July, 51 Cité de Varenne, Paris). Among the art-treasures retained in the château are an ivory, gold, and silver statue of Minerva by Simart (a quarter-size reproduction of the colossal chryselephantine statue of Minerva in the Parthenon), the celebrated Sleeping Penelope by Cavellier, and a silver statue of Louis XIII. by Rude. — The neighbouring *Church* contains the burial vault of the Ducs de Luynes.

The route to Vaux-de-Cernay, leaving the château in the direction of the church, ascends the valley of the streamlet of the same name to the S. In less than $1\frac{1}{4}$ M. we diverge from the road, and continuing in a straight direction, pass the hamlet of *Garnes*. At the *Moulin des Rochers* we reach another carriage-road, which leads first to the left, then to the right, not far from Cernay-la-Ville (p. 341), and follows the other side of the valley. Walkers, however, find a shorter and pleasanter path leading along the bank of the stream from the Moulin des Rochers, and passing two other mills. We next skirt the long *Etang de Cernay* and in about $\frac{1}{4}$ hr. more reach the picturesquely-situated hamlet of *Vaux-de-Cernay*, noted for its ancient abbey.

The *Abbaye des Vaux-de-Cernay*, situated near the pond, was founded in 1128. The ruined church, in the Romanesque style, with its portal and S. aisle, the vaulting of which is still entire, is the most interesting part extant. The remains now belong to Baron Nathaniel de Rothschild, who has converted some of the better-preserved buildings to his own use. Visitors are admitted by special permission only, for which application may be made to 33 Rue du Faubourg St. Honoré, in Paris. Adjacent are two parks.

The village of *Cernay-la-Ville* (Hôtel Margat), reached on the E. or opposite side from Vaux, by the carriage-road which is joined by that from Dampierre (p. 340), is frequented, like Barbison and Marlotte, by artists, who have left their mark in a curiously decorated room in the hotel. The return viâ Cernay-la-Ville to Dampierre is a detour of 2 M.

20. From Paris to the Valley of the Oise.

a. From Paris to Pontoise.

18-22 M. RAILWAY in $\frac{3}{4}$ -1 hr. (fares 3 fr. 55, 2 fr. 65, 1 fr. 95 c.), either from (1) the *Gare du Nord*, viâ St. Denis, Enghien, and Ermont; or from (2) the *Gare St. Lazare*, viâ Asnières, Argenteuil, and Ermont; or from (3) the *Gare St. Lazare*, viâ Asnières, Achères, and Conflans. The return-tickets of the Ligne du Nord are also available viâ Argenteuil, and vice versâ, but not viâ Achères. Those who have time should go on as far as Beaumont and return by one of the two lines described farther on.

1. VIÂ ST. DENIS OR ARGENTEUIL. — From Paris to (9 M.) *Ermont*, where the single line begins, see pp. 319-326. Ligne de Valmondois, see pp. 346, 345.

To the right is seen the château of *La Tour*, rising from the Forest of Montmorency on a height in the distance; to the left, the *Hills of Corneilles* (p. 326). — $11\frac{1}{2}$ M. *Franconville*. The village is about $\frac{1}{2}$ M. to the S. of the station, and 1 M. from Corneilles (p. 326). We next see the fort of *Corneilles*, at the W. end of the chain of hills. — 13 M. *Herblay-Montigny*. These two places are about 2 M. to the S., the former on the new line from Paris to Mantes (p. 327). — 15 M. *Pierrelaye*. Farther on, a junction-line branches off to the right, and on the same side we have a fine view of Pontoise. To the left our line is joined by that from Achères (see below). The train crosses the *Oise*. — $18\frac{1}{2}$ M. *Pontoise* (p. 342).

2. VIÂ ACHÈRES. — From Paris to (3 M.) *Asnières*, see p. 285. The Ligne de Versailles branches off to the left (p. 285), and the Ligne d'Argenteuil to the right (p. 327). — $5\frac{1}{2}$ M. *La Garenne-Bezons*, where the line to St. Germain-en-Laye (R. 16) diverges to the left. To the right is the prison of Nanterre, and farther on Argenteuil, and the heights of Montmorency, Sannois, and Corneilles; to the left, Mont Valérien. We again cross the Seine. — 8 M. *Houilles*. To the left we see St. Germain with its terrace. From this point to Achères our line coincides with the Ligne de Grande-Ceinture (p. 318). To the right is the château of Maisons. We again cross the Seine.

$10\frac{1}{2}$ M. **Maisons-Laffitte** (*Hotels and Cafés* near the station), a village with 4380 inhabitants. The *Château* here, erected by Mansart in the 17th cent., was once the property of the Comte d'Artois (Charles X.). It was afterwards presented to Marshal Lannes by Napoleon I., and eventually purchased by M. Laffitte, the banker, who robbed it of its greatest charm by parcelling out the grounds in building lots. The villas here are in great request as summer-quarters among the financial magnates of Paris. In the vicinity is a *Race Course*. On the opposite bank lies the prettily-situated *Sartrouville*.

From Maisons-Laffitte to St. Germain-en-Laye and Argenteuil by the Grande-Ceinture, see p. 318.

We next pass through the lower part of the forest of St. Germain. — $13\frac{1}{2}$ M. *Achères* (Buffet). The station is about $1\frac{1}{2}$ M. from the village, which lies near the St. Germain race-course. Here our line diverges to the right from those of the Grande-Ceinture and Rouen, both of which pass (3 M.) Poissy (p. 318). Farther on we again cross the Seine, near its confluence with the *Oise*. Fine view of Conflans to the right. — 16 M. *Conflans-Andrésey*. The large village of *Conflans-St. Honorine*, about $\frac{1}{2}$ M. from the station, is prettily situated on an eminence on the right bank of the Seine, and is dominated by a large square *Tower*, sole relic of a fortified château. The *Church* (12-16th cent.), from which we obtain a good view, is also on the height, and behind it is a fine modern *Château*. The place derives its name from the fact that it is situated at the confluence of the Seine and the Oise. The latter is crossed here by a suspension-bridge (toll 5 c.). To reach ($1\frac{1}{2}$ M.) *Andrésey*, we cross the bridge and turn to the left. — New line from Paris to Mantes viâ Conflans, see p. 326.

Our line again follows for a short distance the left bank of the Oise, which a little farther on makes a detour of 6 M. — 19 M. *Eragny-Neuville*, whence a junction-line runs to the new line to Mantes.

22 M. (19 M.) *Pontoise* (*Hôtel de la Gare*, *Hôtel de Pontoise*, both at the station), a town with 7192 inhab., picturesquely situated on a height on the right bank of the Oise. The town dates from the days of the Romans, and from an early period played a somewhat important part in French history, owing to its position as capital of the Vexin (Vellocasses) and its proximity to Paris. It was frequently involved in the wars of the kings of France with the kings of England and the dukes of Normandy, and also in the civil struggles of later date. The only remains of its fortifications are the walls of the ancient château, which protected the town on the side next the river.

On leaving the station, we see facing us, on an eminence, the *Church of St. Maclou*, with a handsome flight of steps in front of it. At the top of the steps is a marble statue, by Lemot, of *General Leclerc* (1772-1802), brother-in-law of Napoleon I. and a native of Pontoise. The church is a Gothic edifice of the 12th cent., reconstructed in the 15-16th centuries. The most striking features of the exterior are the tower, terminating in a lantern in the Renaissance style, and the beautiful Flamboyant rose-window in the W. façade. The *Chapelle de la Passion*, to the left on entering, contains a **Holy Sepulchre*, in the style of the Renaissance, with 8 statues and groups of the Resurrection and the Holy Women. The *Stained-glass Windows* also date from 1545, with the exception of those adjoining the tomb, which are modern. Opposite the pulpit is a Descent from the Cross, by Jouvenet, and the choir contains some rather heavy wood-carvings of the Renaissance.

The road to the left, at the end of the square, leads to the

Promenade, at the end of which is a mound commanding a fine view. — The *Church of Notre Dame*, in the lower part of the town, dating from the 16th cent., contains the tomb of St. Gautier (Wal-ter), a curious monument of 1146, with a statue of the saint. — Above the railway is a *Stone Bridge*, commanding a good view of the town and connecting it with St. Ouen-l'Aumône (see below). Between the two bridges is a large *Hospital*.

From Pontoise to Dieppe, viâ Gisors, comp p. 359 and see *Baedeker's Northern France*.

b. From Pontoise to Beaumont.

12 M. RAILWAY in $\frac{1}{2}$ - $\frac{3}{4}$ hr. (fares 2 fr. 45, 1 fr. 85, 1 fr. 35 c.).

The train recrosses the Oise and enters *St. Ouen-l'Aumône*. Farther on, to the right, is the *Château de Maubuisson*, on the site of the notorious Cistercian abbey of that name. It includes a huge barn and a tower of the 13th or 14th cent. (at one corner of the park). — $\frac{3}{4}$ M. *St. Ouen-l'Aumône* station, the junction for the branch-line mentioned at p. 341. We again cross the Oise. — 4 M. *Auvers*, a prettily situated village with an interesting church of the 12-13th cent. (interior restored). About 1 M. to the right, on the other bank of the river, lies *Méry* (p. 345). — $\frac{5}{2}$ M. *Valmondois*, the junction of a line to Paris viâ Ermont (see p. 345). — *Mériel* and the *Abbaye du Val*, see p. 345.

A branch-line runs hence through the valley of the *Sausseron* to (4 M.) *Nesles*, with an interesting church of the 12th cent., and to (9 M.) *Epiais-Rhus*.

$\frac{7}{2}$ M. **L'Isle-Adam** (*Ecu de France*, near the bridge), a pleasant little town of 3337 inhab., on the left bank of the Oise, which here forms two islands. The station is at *Parmain*, on the right bank, connected with the town by two stone bridges. L'Isle-Adam owes its name to the larger of the islets, on which stood a château belonging latterly to the Prince de Conti (see below). The town is well-built and contains many tasteful villas. The fine avenue to the left, beyond the church and the Hotel de Ville, ascends to a wood of the same name.

The CHURCH, in a straight line with the station, is a Renaissance edifice, with a handsome portal of 1537, lately restored and flanked with a tower of the same date. The **Pulpit*, executed by a German artist in 1560, is richly adorned with statuettes and inlaid work. The choir, the aisles, and the new Lady Chapel (to the right) contain some good modern stained glass. The stalls, dating from the 16th cent., have curious reliefs on their misericords. In a chapel to the left is an altar-piece in carved wood, representing the Passion (15th cent.). An adjoining chapel, opposite the Lady Chapel, contains the remains of the monument of Prince de Conti (1717-76), destroyed, like his château, at the Revolution. The beautiful figure of a weeping woman is a plaster reproduction of one by Moitte. — The *Hôtel de Ville*, alongside of the church, and the *Clergy House*, at the back of it, are handsome modern buildings in a similar style.

The small *Château*, which has replaced that of the Prince of Conti, contains some interesting paintings including what is said to be the original of the small Holy Family by *Raphael*, that in the Louvre (p. 118; No. 1499) being thus a copy.

The *Wood of l'Isle-Adam*, covering a chain of hills with a maximum height of 620 ft., affords numerous pleasant walks. The railway from Beaumont to Ecouen (see p. 345) skirts its other side, the nearest stations being *Presles* (4 M.) and *Montsoult* (6 M.).

The valley now expands and ceases to be picturesque. — The church of ($9\frac{1}{2}$ M.) *Champagne* has a fine spire of the 13th century.

12 M. **Beaumont** (*Hôtel des Quatre-Fils-Aymon*, facing the bridge), a small town with 3000 inhab., picturesquely situated, $\frac{1}{2}$ M. from the railway, on a height on the left bank of the Oise. The **Church*, reached by a lofty flight of steps, is an interesting building of the 13th cent., with double aisles surmounted by galleries. The pillars are round, like those of Notre-Dame at Paris, and have fine foliated capitals. The choir is much smaller than the nave. The lateral tower terminates in the Renaissance style.

Passing the church-tower, following the streets to the right, and turning again to the right at the *Hôtel de Ville*, we reach the *Place du Château* or *Promenade*, adjoining which is part of the old wall of the château, with round towers at the corners. The *Promenade* affords an extensive but somewhat monotonous view of the valley of the Oise.

From Beaumont to *Creil*, see p. 349; to *Hermes*, see *Baedeker's Northern France*.

b. From Beaumont to Paris.

1. *Viâ Montsoult*.

23 M. RAILWAY in $\frac{3}{4}$ -1 $\frac{1}{4}$ hr. (fares 4 fr. 55, 3 fr. 40, 2 fr. 50 c.).

This is part of the direct line from Paris to Beauvais and Amiens. The train crosses the Oise and ascends the picturesque valley of one of its affluents. — 2 M. *Nointel*.

To the left is the *Forest of Carnelle*, affording numerous pleasant walks. The *Poteau de Carnelle* (690 ft.), its highest point, is about $\frac{1}{4}$ M. from Nointel and $\frac{1}{4}$ M. from Presles (see below). There is a 'Tour d'Observation', commanding an extensive view. The 5th avenue to the right in coming from Nointel (the third from Presles) leads to the S.E. to ($\frac{3}{4}$ M.) the *Poteau de St. Martin* (about $\frac{3}{4}$ M. from the village of that name; p. 345). About 1 M. to the S.W. is the *Pierre Turquoise*, a kind of leafy arbour, 38 ft. long and 10 ft. wide (to the left; sign-post). About $\frac{1}{2}$ M. lower down is a wide alley leading to the right to ($\frac{3}{4}$ M.) the station of Presles. To reach the ($\frac{1}{2}$ M.) *Château de Franconville* (p. 345) from the *Pierre Turquoise*, we retrace our steps to (7 min.) a footpath leading to the right to (7 min.; sign-post) the plain of St. Martin.

$3\frac{1}{4}$ M. *Presles*. To the left is seen the magnificent **Château of Franconville*, recently rebuilt by the Duc de Massa. The nearest station to it is (1 M.) Belloy, on the Luzarches line (see below). To the right is the *Forest of L'Isle-Adam*. — $7\frac{1}{2}$ M. *Montsoult*, the station for the two villages of *Montsoult* and *Maffliers*, situated about $\frac{2}{3}$ M. to the W. and to the N.W., at the beginning of the forest of L'Isle-Adam. There is also an interesting château at Montsoult, commanding a fine view.

FROM MONTSOULT TO LUZARCHES, 7 M., railway in 25-40 min. (fares 1 fr. 45, 1 fr. 10, 80 c.). — $2\frac{1}{2}$ M. *Belloy-St. Martin*. Belloy, to the right, contains an interesting church dating from the 15th century. *St. Martin-du-Tertre*, to the left, is picturesquely situated on an eminence on the S.E. border of the forest of Carnelle (p. 344). To the left is the *Château de Franconville*, mentioned on p. 344. — The train now enters a cutting, beyond which we have a fine *View to the left of the valley of the Oise. — About $1\frac{1}{2}$ M. to the N. of ($4\frac{1}{2}$ M.) *Viarmes* (Cheval Blanc) are the remains of the abbey of *Royaumont*, dating from the 13th cent., now occupied as a convent and not open to visitors. — 7 M. *Luzarches* (*Hôtel St. Damien*), a small town in a pleasant situation. A little to the N.E. is the forest of Coye, which extends to the forest of Chantilly (p. 348). About 2 M. to the S. is the château of *Champlâtreux*, built in the 17th and 18th centuries.

10 M. *Domont*, on the N. slope of the forest of Montmorency, is commanded by a fort. — 12 M. *Ecouen-Ezanville*. The *Château* of Ecouen, to the left, is a handsome edifice of the 16th cent., built by Jean Bullant for the Constable Anne de Montmorency, like the oldest part of the château at Chantilly (p. 347). It is now used as a school for daughters of members of the legion of honour of lower rank than are provided for at St. Denis (p. 324). Visitors are not admitted. The park and a fort occupy the top of the hill on which the town is situated. The road on the other side, commanding a fine view in the direction of Paris, descends to *Villiers-le-Bel* (3930 ft.; p. 346) and (2 M.) *Sarcelles*.

$13\frac{1}{2}$ M. *Sarcelles-St. Brice*. — 14 M. *Groslay*. — $15\frac{1}{2}$ M. *Deuil-Montmagny*. — At (17 M.) *Epinay*, we join the Pontoise line to *St. Denis* and *Paris* (see p. 325).

2. Viâ Valmondois and Ermont.

25 M. RAILWAY in $1\frac{1}{4}$ - $1\frac{1}{2}$ hr. (fares 5 fr. 55, 4 fr. 15 c., 3 fr.).

From Paris to (6 M.) *Valmondois*, see p. 343. Beyond Valmondois the train quits the Pontoise line and crosses the Oise. To the left a view of the park of the château of *Stors*. — $7\frac{1}{2}$ M. *Mériel*.

The ruined *Abbaye du Val*, 1 M. to the E., presents various features of interest to archaeologists and others. It is reached by the road which ascends the Oise, traversing the village, and then skirting the small railway used to transport the stones from the quarries higher up to the left. We then turn to the left, and $\frac{1}{4}$ M. farther on follow the road leading to the left across the fields. At the lowest point we turn to the right, through an arched gate, and reach the abbey just beyond a small house, where permission to view the interior of the ruin is obtained. The abbey, like many others, was suppressed in 1791, and was afterwards converted into a manufactory. The chief remains consist of an imposing edifice of the 12th cent., successfully restored, containing the refectory and chapter-house on the ground-floor and the dormitory above, the last a large vaulted apartment, divided into two by a row of fine columns. At one side is an octagonal turret, in front of which is one of the walks of the old cloisters. On the elevated ground opposite are the remains of two vaulted structures, the larger by the side of the road. Beyond the fields and hills (now stripped bare) of the abbey extends the forest of *L'Isle-Adam* (p. 344).

$9\frac{1}{2}$ M. *Méry*, with a splendid view; the village lies $\frac{1}{2}$ M. below the station. — 11 M. *Bessancourt*. — 12 M. *Taverny*, to the left, at the foot and on the slope of a hill joining the forest of Montmorency and commanding a fine view. The *Church*, halfway up the

hill, dates from the 13th and 15th cent. and is one of the handsomest in the environs of Paris. Above the S. portal is a fine rose-window in the Flamboyant style. The interior contains a handsome stone altar in the style of the Renaissance and wood-carvings of the same period (by the S. door), representing the martyrdom of St. Bartholomew. Taverny is continued by St. Leu.

13 M. *St. Leu-Taverny*. The château of St. Leu, once belonging to Louis Bonaparte, King of Holland, and afterwards occupied by the last Prince of Condé (d. 1830), has disappeared; its site is marked by a simple monument to the prince. The modern *Church*, much improved by Napoleon III., contains the tombs of Carlo Bonaparte (d. 1783), father of Napoleon I., Louis Bonaparte (d. 1846), and two sons of the last. The monument of Louis is in the apse, behind a railing.

15 M. *Ermont-Halle*. — 16 M. *Ermont*. From Ermont to Paris, see pp. 326, 318.

21. Chantilly and its Environs.

a. From Paris to Chantilly.

63 M. CHEMIN DE FER DU NORD (station, Pl. B. 24; see p. 24), express-trains in 45-55 min., ordinary trains in 1 hr. 5 to 1 hr. 30 min. (fares 5 fr. 5, 3 fr. 75, 2 fr. 80 c.; return-tickets 7 fr. 50, 5 fr. 70, 4 fr. 75 c.).

As the park at Chantilly is open only on Sun. and Thurs. afternoon, those who wish to combine with this excursion visits to points in the valley of the Oise (R. 20) must begin with the latter. Including the return *via* Senlis and a visit to Ermenonville, two days are required.

From Paris to (4½ M.) *St. Denis*, see p. 318. Branch-line to Enghien (Montmorency, St. Leu, etc.), see p. 325. Beyond the canal of St. Denis (p. 186) rise the forts *du Nord* and *de la Briche*. — 7 M. *Pierrefitte-Stains*. Beyond Pierrefitte to the left, is the fortified *Butte Pinçon* occupied by the Germans in 1870-71. To the right, farther on, is the new fort of Stains or Garge.

9½ M. *Villiers-le-Bel-Gonesse*. *Villiers-le-Bel* is 2 M. from the station, with which it is connected by a steam-tramway (30 c.). An omnibus (30 c.) also runs hence to (1½ M.) *Gonesse*, which has a fine church of the 12-13th centuries. — 12½ M. *Goussainville*. — 15 M. *Louvres*. — 19 M. *Survilliers*.

A diligence plies hence (1 fr.) to *Mortefontaine (Hôt. de la Providence)*, a village 4½ M. to the E., with a *Château* and fine *Park* (visitors admitted), which belonged at one time to Joseph Bonaparte. *Mortefontaine* is 6 M. from Ermenonville (p. 350), 8 M. from Senlis (p. 349), and 9½ M. from Chantilly (p. 347).

The train now enters the *Forest of Coye*. — 22½ M. *Orry-Coye*, 1¼ M. from *Orry-la-Ville* (omnibus) to the S.E., and 1¾ M. from *Coye*, to the N.W. From the station we may walk through the wood to (15-20 min.) the *Etang de la Reine-Blanche* (p. 348; comp. the Map), and thence to Chantilly.

The train crosses the valley of the *Thève* by a handsome stone *Viaduct* of 15 arches, 330 yds. long, and 130 ft. high, commanding

a fine view. To the right are the *Etang* and the *Château de la Reine-Blanche* (p. 348). Beyond the viaduct the train enters the *Forest of Chantilly* (p. 348).

25½ M. Chantilly. — *HÔTEL DU CYGNE ET DU GRAND CERF*, to the left of the church; *HÔTEL D'ANGLETERRE*, at the other end of the Grande Rue; *HÔTEL DE LA GARE*. — *Café de Paris*, Rue de Paris; others at the beginning of the Grande Rue and at the station. — *Post and Telegraph Office* at the Hôtel de Ville. — No tariff for cabs; arrange price beforehand.

Chantilly, a town with 4200 inhab., was famous especially in the 17th and 18th cent. as the residence of the Condés, and as the scene of the magnificent fêtes given by the 'Grand Condé' to Louis XIV., which Mme. de Sévigné mentions in describing the death of Vatel. The town presents a thronged and busy scene during the race-meetings, which are held thrice a year, in May, September, and October. It contains large establishments for the breeding and training of race-horses. The silk lace to which the name of Chantilly is given is now made chiefly in the department of Calvados. The population includes about 400 English, and there is a small English church.

Quitting the station, we observe the forest opposite, through which we may return after seeing the town. To the left lie the town, which contains nothing noteworthy, and the *Pelouse*, or race-course, about 125 acres in area. To the right, near the forest, farther on, are situated the *Grand Stands* for spectators, and to the left are the extensive *Stables* (18th cent.) of the Condés (open on Thurs. and Sun., 2-4).

The **CHÂTEAU*, separated from the race-course by some sheets of water, consists of two main divisions. The château proper, to the left, includes the *Châtelet*, built in the 16th cent., close to the border of the lake, and the larger *Château Moderne*, behind. The latter, replacing the building destroyed at the Revolution, was erected by the Duc d'Aumale, the heir of the Condés, to whom a decree of the National Assembly in 1872 gave back the ancestral property of which he had been deprived during the second empire. The other portion of the château, separated from the former by a broad slope leading to the park, is the *Château d'Enghien*, a heavy-looking erection of the 18th century.

The Château, with its magnificent collections, was presented in 1836 to the Institut de France by the Duc d'Aumale, under reservation of the usufruct; and since the expulsion of the duke it has remained closed.

At the entrance of the château proper stands a statue, by P. Dubois, of the *Constable Anne de Montmorency* (1493-1567), who built most of it, as well as the *Château d'Ecouen* (p. 345).

The **Park* is open to the public on Sun. and Thurs. from 12 to 4 or 5, and is reached by a massive flight of steps descending from the slope mentioned above. It was laid out by Le Nôtre, who afterwards designed the gardens of Versailles in the same style, and is embellished with fine parterres and ornamental pieces of water. The chief of the latter is the *Canal de la Manche*, which is formed by the *Nonette*, and extends to the lower part of the town. The chief statues (Le Nôtre, Molière, Bossuet, Condé, La Bruyère) are placed round the first basin. The park beyond

the canal is not open to the public. To the left is an *English Garden*, and to the right a *Hamlet*, as at Versailles; while farther on, beyond the canal, are the little châteaux of *La Nonette* and *St. Firmin* (not accessible to the public). The *Parc de Silvie*, to the right and partly behind the Château d'Enghien, has most completely retained the 17th cent. aspect.

The road round the outside of the park is uninteresting. The top of the Vertugadin, on the side next Vineuil, commands a pretty view; thence we may join the railway at Senlis.

The FOREST OF CHANTILLY, which covers an area of 6125 acres, is well kept and provided with numerous guide-posts, but it occupies for the most part a flat site, and most of the roads and paths are covered with a thick layer of sand that renders walking disagreeable and fatiguing. The paths skirting the railway to (1 hr. from the station) the Etang de Comelle (see below) are, however, better. The paved Route de Louvre and another road to the right lead in about 1 hr. from the château to the *Carrefour du Table*, an open space where 12 roads meet, with a large stone table in the centre. The Route du Connétable, starting from the race-course near the château, is very sandy, and is kept purposely soft by the horse-trainers. The entrance to the avenue is embellished with two lions. — The *Etang de la Reine Blanche* or *de Comelle* is a long-shaped sheet of water, fed by the Thève, a small tributary of the Oise, lying between the Forest of Chantilly and the Forest of Coye. Near the lower end is the *Château de la Reine Blanche*, a small modern Gothic hunting-lodge on the site of an ancient château once occupied by Queen Blanche, mother of St. Louis. A little farther on is the large railway-viaduct, mentioned at p. 346. The nearest station to the pond is Orry-Coye (p. 346), at which, however, the express trains hardly ever stop.

At (3 M. from Chantilly) *St. Leu-d'Esserent* we may join the railway from Creil to Paris via Beaumont (see below). To reach it we follow first the road from Paris to Amiens, afterwards diverging to the left (comp. the Map).

b. From Chantilly to Paris via Creil and Beaumont.

At (6 M.) *Creil* we change carriages, and join the railway descending the valley of the Oise. From Creil to *Beaumont*, 13 M., thence to Paris 23 M. via *Montsoult*, 25 M. via *Valmondois-Ermont*, or 29 M. via *Pontoise-Ermont*. From Ermont we may also take a ticket to the Gare St. Lazare.

Beyond Chantilly the train crosses the valley of the *Nonette* by a second *Viaduct*, 484 yds. in length and 72 ft. in height, consisting of 36 arches, and commanding a fine view. To the left, the *Château de Laversine*, belonging to Baron G. de Rothschild. The train then passes through a cutting, traversing the quarries of *St. Mazimin*, which yield excellent building stone, and soon crosses the *Oise*. To the right is a handsome modern château. To the left is the line to Beaumont (p. 349); and in the same direction are seen the village and manufactories of *Montataire* (5370 inhab.), commanded by a handsome church of the 12th and 13th, and a château of the 15th century.


32 M. *Creil* (*Buffet*; *Hôtel de la Gare*), a town with 7420 inhab., is an important station on the Chemin de Fer du Nord, being the

CHÂTEAU ET PARC
de
CHANTILLY.

1:19,000

0 100 200 300 Mètres

Carte de Vincennes



Forêt de Vincennes

junction of five different lines (see *Baedeker's Northern France*). The town, prettily situated on the Oise, contains a *Parish Church*, a building of the 12-15th cent., and the ruins of the *Church of St. Evremont* (12th cent.) on an island, now the property of a porcelain-manufactory.

The line to Beaumont and Paris, identical for a short distance with that from Chantilly, afterwards follows the right bank of the Oise. — $4\frac{1}{2}$ M. *St. Leu-d'Esserent*, with a conspicuous church, chiefly of the 12th cent.; the largest of the three towers is Romanesque. — 6 M. *Précy*; 10 M. *Boran*.

13 M. *Persan-Beaumont*. — *Beaumont* and thence to Paris, see R. 20.

c. From Chantilly to Paris viâ Senlis and Crépy-en-Valois.

To *Senlis*, 8 M.; thence to *Crépy-en-Valois* 14 M., where carriages are changed. From *Crépy to Paris* (Gare du Nord), 38 M.

I. From Chantilly to Crépy-en-Valois.

This line diverges to the right of that to Creil beyond the viaduct over the valley of the Nonette (p. 348). The train stops at *St. Maximin*, to the S. of the village of that name, noted for its building-stone, and at *Vineuil*, to the N. of the park of Chantilly (p. 347). — $4\frac{1}{2}$ M. *St. Firmin*, to the N.E. of the village, which also lies near the park. The tower of Senlis cathedral appears to the right.

8 M. *Senlis* (*Hôtels du Grand Cerf, du Nord, de France*, Rue de la République, Nos. 21, 28, 27), the Roman *Civitas Sylvanectensium*, situated on the Nonette, is a pleasant little town with 7200 inhab., which is frequently mentioned in mediæval history. Until the Revolution it was the seat of a bishopric founded by St. Rieul or Regulus.

The Gothic *Cathedral*, a handsome building of the 12-16th centuries, has a fine façade and two square towers, one of which is 250 ft. in height. The side-portals are in the Flamboyant Gothic style. The interior is worth inspection. In the chapel to the left of the nave is an antique marble bas-relief.

Opposite the portal is a house in the grounds of which are some remnants of the *Roman Walls* (towers) and of the *Royal Palace* of the Merovingians. To the left of the house, farther on on the right, is an ancient Gothic portal, the former entrance to the palace.

The former *Bishop's Palace*, with an ancient early-Gothic chapel, lies to the right of the choir of the cathedral.

In the neighbourhood, to the right, is the former *Church of St. Frombourg*, now a stable. The nave is a fine Gothic edifice of the 12th century. The neighbouring *Church of St. Pierre* (12-16th cent.) is now a market; one of its towers is surmounted by a spire, the other by a dome.

The Rue de la République descends towards the Nonette. On the left is the large *Palais de Justice*, behind which is a small *Musée Municipal*, in a street to the left, which leads also to the theological

Collège de St. Vincent, which has superseded the abbey of that name. The abbey-church (chiefly 12th cent.) has been preserved.

Traces of a *Roman Amphitheatre* have been recently discovered, near the town, to the left of the road to Chantilly.

Ermenonville (see below) lies 8 M. to the S.E. of Senlis.

The train beyond Senlis passes seven stations, of which the chief are (12½ M.) *Barbery* and (16½ M.) *Auger-St. Vincent*

22½ M. *Crépy-en-Valois* (*Hôtel de Bannière*), a town with 3400 inhab., was the ancient capital of a district which belonged from the 14th cent. to a younger branch of the royal family of France. Of the interesting old collegiate church of *St. Thomas*, the façade (13th cent.) and a tower and spire (15th cent.) still remain.

Railways to *Soissons* and to *Compiègne* viâ Verberie, see *Baedeker's Northern France*.

II. From Crépy-en-Valois to Paris.

3½ M. *Orimoy*; 8 M. *Nanteuil-le-Haudouin*; 12 M. *Le Plessis-Belleville*.

From *Le Plessis-Belleville* a diligence (1 fr.) plies to *Ermenonville* (*Hôtel Lefèvre*), a village 3 M. to the N.W., near the forest of the same name. It is known as the spot where J. J. Rousseau died and was buried in 1778, six weeks after his arrival to enjoy the retreat offered to him by the Marquis de Girardin. The Château, now the property of Prince Radziwill, is at the E. end of the village, and is shewn in the absence of the proprietor. The Park, intersected by the road which continues the principal street of the village, was one of the finest laid out in the 18th cent., and is more in the English style than in that of *Le Nôtre*. The most interesting part is the *Grand Parc*, to the left of the road and in front of the château. The *Ile des Peupliers*, in a lake here, contains the empty tomb of Rousseau, his remains having been removed to the *Panthéon* (p. 238) in 1794. — The road passing in front of the château leads to *Senlis* (p. 349), 8 M. to the N.W. *Mortefontaine* (p. 346) lies 6 M. to the W. of *Ermenonville*.

16½ M. *Dammartin*; the small town lies 13¼ M. to the N.W. on a hill (omnibus 40 c.). About 1¼ M. to the S. (omnibus 30 c.) is the *Collège de Juilly*, founded in the 17th cent. by the fathers of the Oratory. Among its alumni have been many celebrated men.

We next pass the stations of *Thieux-Nantouillet*, (2½ M.) *Mitry-Claye*, (24 M.) *Villeparisis*, and, after skirting the *Canal de l'Ouse* (p. 186), *Vaujours*. Between (27 M.) *Sevan-Livry* and (29 M.) *Aulnay-lès-Bondy*, the *Forêt de Bondy* appears on the left.

From *Aulnay-lès-Bondy* a branch-line runs to (12 M.) *Bondy*, on the line to *Nancy*; see *Baedeker's Northern France*.

32 M. *Le Bourget-Drancy*. *Le Bourget*, to the right, was the scene of sanguinary struggles between the French and Germans on Oct. 28-30th and Dec. 24th, 1870, in which the former were repulsed. A monument to the French soldiers has been erected. We here cross the *Ligne de Grande-Ceinture*. — 34 M. *Aubervilliers-la-Courneuve*. *Aubervilliers*, an uninteresting village to the right, is connected with *Paris* by a tramway (see Appx.). — To the right appears *St. Denis*, the road to which we cross at the station *Pont de Soissons*, where we also join the main *Ligne du Nord*. — 36 M. *La Plaine-St. Denis*. Then the station of *La Chapelle-Nord-Ceinture*.


38 M. *Paris* (Gare du Nord, p. 24).

BOULOGNE s.m.

1 : 16,000

0 50 100 200 300 400 500 600 700 800

Mètres



ROUTES FROM LONDON TO PARIS.[†]

22. By Folkestone, Boulogne, and Amiens.

255 M. By TINAL EXPRESS TRAINS (see advertisements in 'Bradshaw'), from Charing Cross or Cannon Street, in 8-10 hrs., average sea-passage 2¼ hrs.; fares 2l. 17s. 6d. and 2l. 3s. 6d.; return-tickets valid for one month 4l. 18s. 3d. and 3l. 18s. 3d. Passengers with single tickets may break their journey at the principal stations, and spend seven days on the route. Night-service at reduced fares, 2nd class 33s., 3rd class 22s. 6d. (tickets available for three days only); return-tickets available for 14 days, 50s. 3d. and 34s. 9d. Registered luggage is not examined before arrival at Paris.

By *Steamboat from London to Boulogne* daily during the season (see advertisements in 'Bradshaw') and thence to Paris by railway, a journey of 14-17 hrs. exclusive of detention at Boulogne, where the trains do not correspond with the steamers; river-passage about 6 hrs., sea-passage 4-5 hrs.; fares 26s. 6d., 22s., 16s.; tickets available for three days. This is the cheapest, and in favourable weather the pleasantest route.

Boulogne-sur-Mer. — Hotels. Near the baths: HÔTEL DU PAVILLON IMPÉRIAL (Pl. a; D, 1), HÔTEL DE LA MARINE & DE BRIGHTON (Pl. b; D, 2), in the Boul. Ste. Beuve (Nos. 98 & 40); HÔT. FOLKESTONE (Pl. c; D, 2), HÔT. DE PARIS (Pl. d; D, 2), HÔT. WINNSOR (Pl. e; D, 2), Quai Gambetta (Nos. 74, 66, & 62). In the town: HÔTEL DES BAINS ET DE BELLEVUE (Pl. f; E, 3), Quai des Bains and Rue Victor Hugo; HÔT. CHRISTOL (Pl. g; E, 3), Place Frédéric Sauvage 14; HÔT. DE L'UNIVERS (Pl. h; E, 3), HÔTEL MEURICE (Pl. i; E, 2), HÔT. DU NORN (Pl. k; E, 3), Rue Victor Hugo (Nos. 26, 35, 25); BRITISH HOTEL (Pl. l; E, 3), Rue Faïdherbe 27; H. DU LOUVRE, Place Bellevue, near the station; etc. There are also numerous *maisons meublées, pensions*, and furnished apartments.

Restaurants. *Casino* (déj. 4; D, 5 fr.); *Restaur. Poirmeur*, on the E. jetty; **Hôtel de Flandre*, Quai Gambetta 52 (déj. 2, D, 2½ fr.); also at the above-named hotels and at the railway-stations.

Cafés. *Grand Café de Boulogne, Continental*, Rue Adolphe Thiers 35 and 31; *Seigne*, opposite the theatre.

Cabs. From 6 a.m. to midnight, per drive 1½ fr., per hour 2 fr.; from midnight to 6 a.m. 2 fr. and 2½ fr.; outside the town, per hr. 2½ fr.

Tramway to the Casino from the Place Dalton (Pl. F, 3), 15 c.; to the New Harbour Works from the Coin-Menteur (Pl. E, 3), 10 c.

Baths. *Sea-baths* 1½ fr., including machine and towels; subscription for 12 baths 9 fr. Hydropathic baths at the Casino. Fresh water and Sea baths at the Hôtel des Bains.

Post and Telegraph Offices, Rue du Pot-d'Étain 12 (Pl. E, 3).

British Vice-Consul, *Capt. R. N. Surplice*, Rue Wissocq 14. — **American Vice-Consul,** *M. Flageollet*, Rue de la Gare. — **Bankers,** *Adam & Co.*, Rue Victor Hugo 6. — *Merridew's Library*, Rue Victor Hugo 60.

Physicians. *Dr. Carr*, Rue Faïdherbe 69; *Dr. Philip*, Rue Victor Hugo 33; *Dr. Docker*, homeopath, Rue Maignan 13. — **Dentists.** *Mr. Hillman*, Rue Ad. Thier 29; *Mr. Manton*, Grande Rue 14; *Mr. J. Mac-Conaghey*, Rue Victor Hugo 44.

English Churches. *British Episcopal Church*, Rue du Temple; chaplain, Rev. Archdeacon Maule, LL.D., 95 Rue de la Paix. — *Holy Trinity*, Rue de la Lampe; Rev. E. R. Parr, M. A., 7 Boul. Daunon. — *St. John's*, Rue des Vieillards; Rev. J. H. Fry. The Sunday services at the three churches are at 11 and 7.30. — *New Wesleyan Methodist Church*, 70 Grande Rue; Rev. W. Barkell; services at 11 and 7.

[†] For farther details see *Baedeker's Northern France*.

Boulogne-sur-Mer, so called to distinguish it from Boulogne-sur-Seine near Paris, the *Bononia* (?) or *Gessoriacum* of the Romans, is an important seaport town, the capital of the Département Pas-de-Calais, situated at the mouth of the *Liane*, with a population of 46,000, of whom over 1000 are permanent English residents. The town may be said to combine a certain degree of English comfort with French taste. Its numerous schools enjoy a high reputation.

The *Basse-Ville* lies on a slight eminence on the right bank of the *Liane*. The principal thoroughfares are the *Grand' Rue*, a broad street leading past the Market-square to the Haute Ville; the *Rue Victor Hugo* and *Rue Ad. Thiers*, where the best shops are situated, and the *Rue Faidherbe*, a long street which runs from the sluice bridge to the *Tintellerie's Gardens* (public).

The *Museum* (Pl. F, 3), in the *Grand' Rue*, contains interesting ethnographical and historical collections, Gallo-Roman and Egyptian antiquities, and a picture gallery (open in summer daily, except Tues., 11-4; in winter on Sun., Wed., Thurs., and Sat.). The *Public Library*, on the second floor, contains 55,000 vols. and some interesting MSS.

At the top of the *Grand' Rue*, in the garden of the Sous-Préfecture, is a colossal bust of Henri II., by *David*, commemorating the restoration of the town to France by the English in the reign of that monarch (1550). Close by stands a bronze statue of *Mariette Bey*, the eminent Egyptologist, who was a native of Boulogne (1821-81).

The *Haute-Ville*, enclosed by ramparts (13th cent.), is entered by three gateways: the *Porte des Dunes*, near the Sous-Préfecture, the *Porte de Calais*, and the picturesque *Porte Gayole*. The *Hôtel de Ville* (Pl. G, 3) was erected in 1734 on the site of an ancient castle, where the crusader Godfrey de Bouillon was born in 1065.

The church of *Notre-Dame* (Pl. G, 2), a building in the degraded Italian style, erected in 1827-66, occupies the site of a Gothic church which was destroyed in 1793. Handsome high-altar in mosaic work, and richly ornamented Lady Chapel. Curious crypt (adm. 1 fr.). The lantern which surmounts the dome is crowned with a colossal statue of the Virgin, which forms the most conspicuous point in the whole town. Extensive *View, comprising the 'dunes', the plateau traversed by the railway to Calais, in the foreground Napoleon's Column, and in the distance, in clear weather, the white cliffs of the English coast. The entrance to the staircase is by a door to the right, at the S. portal (adm. 1 fr.).

The *Château* (Pl. G, 2), in which Louis Napoleon was confined after the attempted insurrection of 1840, is the ancient citadel of Boulogne, and dates from the 13th century. It is now converted into barracks (no admission).

The *Theatre* (Pl. E, 3), in the *Rue Monsigny*, is a fine building in the Grecian style, capable of holding 1100 persons.

The *Harbour*, especially the W. part near the *Douane*, and the

steamboat-quay, with the principal hotels, present a very busy scene. The commercial importance of the harbour is increasing, and since 1879 extensive operations (to cost 1,400,000l.) have been going on with a view of enlarging and deepening the port. Boulogne stands next to Marseilles, Havre, and Bordeaux among the seaports of France. At the end of the harbour is the *Casino* or *Etablissement de Bains* (Pl. D, 1, 2), which is admirably fitted up. Adm. $\frac{1}{2}$ -1 fr. (for the whole day 3 fr.), less to subscribers. The garden is always open to visitors, but non-subscribers pay 20 c. for admission on concert-days.

The *Pier*, or *Jetée de l'Est* (Pl. B, C, 1, 2), which extends 650 yds. into the sea, is a favourite evening-promenade. The opposite (W.) pier is 200 yds. longer. Both are provided with lighthouses.

The *Fish Market* is held early in the morning in the *Halle* (Pl. E, 3). The fishermen and their families occupy a separate quarter. *la Beurrière*, on the N. side of the town, and form one-sixth of the population. They are remarkable for their adherence to the picturesque costume of their ancestors, and they differ considerably in character and customs from the other inhabitants of the town. Their wives, who are called *Matelottes*, exercise unlimited sway on shore, whilst the sea is the undisputed domain of the husbands.

Boulogne possesses about 250 fishing-boats, which extend their voyages during the herring-fishery as far as the Scottish coast and Iceland, and in favourable seasons realise as much as 400,000l.

In 1804 Napoleon I. assembled an army of 172,000 infantry and 9000 cavalry on the table-land to the N. of Boulogne, under the command of Marshals Soult, Ney, Davoust, and Victor, and collected in the harbour a flotilla of 2413 craft of various dimensions, for the purpose of invading England and establishing a republic there. The troops were admirably drilled, and only awaited the arrival of the fleets from Antwerp, Brest, Cadiz, and the harbours of the Mediterranean, which had been in the course of formation for several years for this express purpose. Their union was prevented by the English fleet under Sir Robert Calder; and the victory of Nelson at Trafalgar, on 22nd Oct., 1805, completed the discomfiture of the undertaking.

NAPOLEON'S COLUMN, or the *Colonne de la Grande-Armée*, a Doric column, constructed by Marquise, 172 ft. in height, situated 2 M. from Boulogne on the road to Calais (comp. Pl. G, 1), was founded in 1804 to commemorate the expedition against England, the first stone being laid by Marshal Soult in the presence of the whole army. The first empire left the monument unfinished, and in 1821 Louis XVIII. caused the work to be resumed, intending that the column should commemorate the restoration of the Bourbons; but it was not completed till 1841, when its original destination was revived. The summit is occupied by a statue of the emperor, one of *Bosio's* finest works. The pedestal is adorned with reliefs in bronze, representing emblems of war. The view from the top resembles that commanded by the dome of Notre-Dame (custodian $\frac{1}{2}$ fr.).

FROM BOULOGNE TO PARIS.

159 M. CHEMIN DE FER DU NORD. Express in $4\frac{1}{4}$, other trains in $6\frac{1}{2}$ hrs. (fares 31 fr. 25, 23 fr. 45, 17 fr. 20 c.).

Quitting the handsome station of Boulogne, the train traverses the valley of the Liane. The country soon becomes flat and uninteresting. 3 M. *Pont-de-Briques*; $5\frac{1}{2}$ M. *Hesdigneul*.

9 M. *Neufchâtel*. Beyond ($17\frac{1}{2}$ M.) *Etaples* the train crosses the *Baie de la Canche* by a viaduct. $20\frac{1}{2}$ M. *St. Josse*; $32\frac{1}{2}$ M.

Verton, the station for the (4 M.) small sea-bathing place of *Berck*; 28 M. *Conchil-le-Temple*; 34 M. *Rue*.

40½ M. *Noyelles* is situated in the midst of a dreary expanse of sand. — In the vicinity the *Somme* was crossed by Edward III. before the battle of *Crécy* in 1346. — Branch-line to the right to (8½ M.) *Cayeux*, viâ (4 M.) *St. Valéry-sur-Somme*, whence William the Conqueror set out for England in 1066. Another branch line runs to (5 M.) *Le Crotoy*.

49 M. *Abbeville* (*Hôtel de la Tête-de-Bœuf*; **Hôt. de la Gare*) is a cloth-manufacturing town, with 19,837 inhab., on the *Somme*, and connected with the sea by means of a canal. The principal building is the unfinished Church of *St. Vulfran*, founded in the 15th century. The Flamboyant portal of the Church of *St. Gilles* is also interesting. The *Musée Boucher-de-Perthes* chiefly consists of prehistoric antiquities. In the Place d'Armes is a bronze statue of *Lesueur*, the composer (d. 1837), by *Rochet*; and the Place Courbet is embellished with a statue, by *Falguière* and *Mercié*, of *Admiral Courbet* (d. 1885), who was born at *Abbeville*.

From *Abbeville* a branch-line runs to (58½ M.) *Béthune*, viâ *St. Riquier*.

The scenery becomes more picturesque as the train ascends the fertile valley of the *Somme*. — 54½ M. *Pont-Remy*. — From (59½ M.) *Longpré* branch-lines diverge to *Le Tréport* and *Canaples*. — 64 M. *Hangest*; 68½ M. *Picquigny*, with the ruins of a stronghold of the 16th cent.; 71½ M. *Ailly-sur-Somme*; 72½ M. *Dreuil*; 75½ M. *St. Roch*. — The train now threads two short tunnels.

76½ M. *Amiens*. — *Hotels*. *HÔTEL CONTINENTAL* (Pl. a; F, 4), Rue des Trois-Cailloux 60, R. from 3 fr.; *HÔTEL DU RHIN* (Pl. b; G, 4), *Hôtel de l'Univers* (Pl. d; G, 4), both in the Rue Noyon, the street opposite the station, and somewhat expensive; *ECU DE FRANCE* (Pl. f; G, 4), in the same street, less pretending; *HÔTEL DE FRANCE ET D'ANGLETERRE* (Pl. c; E, F, 4), Rue de la République 9, nearer the centre of the town; *HÔTEL DU COMMERCE* (Pl. e; F, 4), Rue des Jacobins; *HÔT. DE LA PAIX*, Rue Duméril (Pl. E, 4); *HÔTEL DE LA CROIX BLANCHE*, Rue de Beauvais 44 (Pl. E, 4).



Restaurants. At the *Hôtel Continental* and the *Ecu de France*; *Restaur. de l'Est*, opposite the station, D. 3¼ fr. — *Cafés*. *Taverne Lorraine*, *Cercle des Voyageurs*, both in the Rue des Trois-Cailloux.

Amiens, the ancient capital of Picardy, now that of the Department of the *Somme*, with 80,288 inhab., and one of the principal manufacturing towns in France, is situated on the *Somme* and its affluents the *Arve* and the *Selle*. These streams form numerous canals, which are invaluable for the industrial purposes of the town. The principal manufactures are linen, woollen stuffs, silk thread, cashmeres, and velvet. The lower part of the town, with its canals and narrow streets, is the manufacturing quarter, while the central part contains the best shops; the new town is separated from both these quarters by handsome boulevards. In 1802 the Peace of *Amiens* between France and England was concluded here. On 20th Nov., 1870, the Prussians defeated the French near *Amiens*, and entered the town on the following day.

The exit from the station is in the boulevards, opposite the Rue

AMIE NS

1 : 15,300





de Noyon, which we follow to the PLACE ST. DENIS (Pl. F, G, 4), embellished with a bronze statue of *Ducange*, the eminent linguist (born at Amiens in 1610; d. 1688). The Rue Victor Hugo leads hence to the right, passing the modern *Palais de Justice*, to the —

*CATHEDRAL (Pl. F, 3), one of the most imposing Gothic churches in Europe, erected in 1220-1288 by the architects *Robert de Luzarche*, *Thomas de Cormont*, and his son *Renault*. Length 470 ft., length of transept 213 ft., width of nave 144 ft. The heaviness of the building is insufficiently relieved by the lofty spire over the transept, 392 ft. in height, or 145 ft. above the roof, re-erected in 1529. The two uncompleted towers of the W. façade belong to the 13th (the lower) and 15th cent., the former being 181 ft., the latter 210 ft. in height, but like the central spire they are too small for the edifice. The principal W. Portal, one of the finest parts of the building, was completed towards the end of the 14th century.

The *FACADE contains three lofty recessed porches, richly adorned with reliefs and statues. '*Le beau Dieu d'Amiens*' is an admirable figure of the Saviour which separates the doors of the central portal. Above the portals are a handsome gallery, niches containing twenty-two colossal statues of kings of Judah, a magnificent rose-window 38 ft. in diameter, and still higher a gallery connecting the towers.

The *INTERIOR consists of nave, transept, aisles, and choir, all flanked with chapels. The nave rises to the very unusual height of 147 ft., being surpassed in this respect by the cathedral of Beauvais alone. The vaulting is borne by 126 remarkably bold columns, tapering towards the top. The stained glass in the rose-windows, triforium, and choir is ancient. The organ-loft dates from 1425, but has been modernised. The bronze monuments of the two bishops who founded the church, one on each side of the nave, are fine works of the 13th century. The wall of the choir is adorned with reliefs representing, on the N. side the history of John the Baptist, on the S. side the life of St. Firmin, sculptured in 1489 and 1530. Behind the high-altar is the '*enfant pleureur*', a much admired, but overrated weeping angel, by Blasset. At the entrance to the choir are large marble statues of St. Vincent de Paul and S. Carlo Borromeo. The transept contains some interesting reliefs, painted and gilded, of the beginning of the 16th century.

The *Choir Stalls, 110 in number, are fine specimens of carving executed in 1508-22. There are no fewer than 3650 figures. The subjects are Scriptural, and also represent different worldly occupations.

The traveller should not neglect to visit the *Triforium*, which commands a good survey of the interior of the church, and ascend thence to the external galleries and the tower.

At the back of the church rises a statue in bronze of *Peter the Hermit* (Pl. F, 3), or Pierre of Amiens, the promoter of the first crusade.

The *Musée de Picardie (Pl. E, 4), in the Rue de la République, is open on Sun., Tues., Thurs., 12 to 4 or 5 (at other times for a fee). The collections on the ground-floor include mediæval carvings; Roman antiquities (tomb-reliefs, leaden coffins, bronzes, glass); a fine mosaic found at Amiens in 1857, with interesting arrangement of colours; faïence from Nevers and Beauvais; a few Greek antiquities (statue of Diana; mosaic of Apollo); and a collection of modern sculptures. On the first floor are about 250 French paintings, chiefly of the beginning of the present century (David, Gérôme, etc.). — In the same street is the *Bibliothèque Communale* (Pl. E, 4).

In a street running parallel with the Boul. du Mail, to the N., is a monument called the *Illustrations Picardes* (Pl. F, 4), consisting of a figure of Picardy, surrounded with statues and busts of eminent natives of that province. — On the W. side of the town is the pleasant *Promenade de la Hotoie* (Pl. A, B, 2, 3).

A branch-line connects Amiens with *Rouen* (in 2-3 $\frac{3}{4}$ hrs.).

Beyond Amiens we cross the *Arve*. 79 $\frac{1}{2}$ M. *Longueau* (Buffet), junction of a line to *Arras* (*Lille*). Near (82 $\frac{1}{2}$ M.) *Boves* is a ruined château in which Henri IV. often resided with the beautiful Gabrielle d'Estrées. Fine view of the valley of the *Noye*. — 89 M. *Ailly-sur-Noye*. — 93 $\frac{1}{2}$ M. *La Faloise*. — From (99 $\frac{1}{2}$ M.) *Breteuil-Gare* a branch-line leads to the (4 $\frac{1}{2}$ M.) small town of *Breteuil* (3154 inhab.). At the village of *Folleville*, 4 M. to the N. of Breteuil, are the ruins of a château, and a late-Gothic church containing a monument by Ant. della Porta. A view of these buildings is obtained from the railway, soon after *La Faloise* is quitted.

104 M. *St. Just-en-Chaussée*, the centre of a hosiery-manufacturing district, and the junction of lines to Beauvais and *Douai*.

117 $\frac{1}{2}$ M. *Clermont de l'Oise* (*Hôtel des Deux Epées*), a town with 5529 inhab., pleasantly situated on a hill, is commanded by an ancient castle now used as a prison for women. Above the town rises the church of *St. Samson*, of the 14th and 16th centuries. The *Hôtel de Ville*, dating in part from the 14th cent., is said to be the oldest in the N. of France. The country here is well-peopled and picturesque. Branch-lines to Compiègne and to Beauvais.


122 $\frac{1}{2}$ M. *Liancourt-sous-Clermont*, with 4286 inhab., is a manufacturing town. Part of an old château of the dukes of Rochefoucauld-Liancourt is still standing here. It was rebuilt by Jeanne de Schomberg in 1640, and has a beautiful park. The church contains two good marble monuments. By the desire of Henri IV., Gabrielle d'Estrées was married to a certain Seigneur de Liancourt, a man of deformed person and deficient intellect, on condition that he should never see her again after the ceremony.


127 M. *Creil*, beyond which the train skirts the *Oise*. Large porcelain-factory on an island in the river.

From Creil to (159 M.) Paris, see R. 21.

23. By Dover, Calais, and Amiens.

283 M. By EXPRESS (see 'Bradshaw'), starting from Charing Cross, Cannon Street, Victoria, Holborn Viaduct, and St. Paul's stations, in 8-11 $\frac{1}{2}$ hrs.; sea-passage 1-1 $\frac{3}{4}$ hr.; fare 3*l.* 1*s.* 6*d.* and 2*l.* 6*s.* 6*d.*; tickets available for seven days, with option of halting at Dover, Calais, and Amiens; return-tickets, valid for one month, 4*l.* 18*s.* 3*d.* and 3*l.* 18*s.* 3*d.* — 'Club Trains' (1st cl. only; 15*s.* extra) leave London every afternoon except Sun., returning from Paris every afternoon except Sat., performing the journey in less than 8 hrs. — Night-service at lower fares, 2nd class 33*s.*, 3rd class 22*s.* 6*d.* (tickets available for three days only); return-tickets, available for 14 days, 50*s.* 3*d.* and 34*s.* 9*d.* — The London, Chatham, and Dover Railway (Victoria, Holborn Viaduct, and St. Paul's stations) also issues mixed tickets





(first-class rail and second-class steamboat) for the night-service at 42s., return-tickets 63s. — Luggage should be registered before leaving England, to avoid examination at Calais.

Calais. — **Hotels.** *TERMINUS, at the Gare Maritime; *DE LA GARE CENTRALE, at the Central Station; MEURICE, Rue de Guise; DESSIN, Rue Neuve; HÔTEL SAUVAGE; HÔTEL DU COMMERCE; DE LONDRES, Rue de la Cloche; DE FLANDRE. — **Restaurants.** At the *Maritime* and *Central Stations*. Sainsard, Rue de la Cloche; Sauvage, Rue de Guise; *Railway Restaurant*. — **Cafés:** de Bellevue, de France, du Globe, Place d'Armes. — *Sea-Bathing:* to the N. of the Bassin de Retenue.

British Consul, E. W. Bonham, Esq., 1 Rue de Croy; Vice-consul, W. Thomsett, Esq., Rue des Thermes 21. — **United States Consul,** M. Vendroux, Rue Leveux 20.

English Church, Rue du Moulin-Brulé; minister, Rev. M. H. Umbers, M. A. — **Wesleyan Chapel,** Rue du Temple. Services in both at 11 a.m. and 6.30 p.m.

Calais, a town with 58,710 inhab., including *St. Pierre-lès-Calais*, with which it was united in 1885, and a fortress of the first class, derives its chief importance from its harbour and its traffic with England, to which it is the nearest port on the French coast. Dover is 18 M. distant. About 260,000 travellers pass through the town annually. Calais contains about 1500 English residents, chiefly engaged in its extensive lace-manufactories.

The old *Hôtel de Ville*, in the Place d'Armes, the handsomest edifice in the town, was erected in 1740 on the site of an older building of which the tower still remains (15th cent.). It is adorned with busts of the *Duc de Guise*, 'libérateur de Calais en 1558', and *Richelieu*, the founder of the citadel in 1634. Since the union of the towns, the municipal offices have been removed to a new building. — The church of *Notre-Dame*, on the E. side of the town, dating from the 12th and chiefly from the 14th cent., has been modernised. The handsome marble altar, an Assumption by *Zeghers* (1628), and a Descend from the Cross by *Rubens* may be inspected.

The *Harbour*, the entrance to which is between two piers, has of late years been considerably deepened, and works are still in progress. There is a large new tidal-harbour or avant port with handsome stone quays, the N. side of which is set apart for the Dover Mail and passenger steamers. Here is the new *Gare Maritime*, with the Terminns Hotel (see above) on the upper floor. The new *Central Station*, a handsome building, stands on the site of the old fortifications, between the old town of Calais and the former suburb of *St. Pierre* (see above). The new floating basin with an area of 27 acres, opened in 1889, the dry dock and other facilities for shipping will contribute to increase the commercial importance of the town and port.

The chalk cliffs and the castle of Dover are visible from the harbour in clear weather. On the E. quay of the old tidal-harbour rises a marble *Column* commemorating the restoration of Louis XVIII. On the other side is an *Etablissement des Bains*. The faubourg of *Courgain*, between the column and the town, is inhabited by fishermen.

FROM CALAIS TO BOULOGNE. Passengers from England find the train for Paris waiting at the Gare Maritime. $13\frac{1}{4}$ M. *Calais-Ville* (central station, see above); 3 M. *Fontinettes*, still within the new fortifications of Calais. 5 M. *Frethun*; $11\frac{3}{4}$ M. *Caffiers*. — 17 M. *Marquise*, a small town with marble quarries, is 7 M. from *Cap Gris Nez*, the nearest point to the English coast, and the proposed starting-point of the submarine tunnel between France and England.

26 M. *Boulogne*, and thence to Paris, see R. 22.

24. By Newhaven, Dieppe, and Rouen.

By EXPRESS from Victoria and London Bridge stations (see 'Bradshaw') in 10 (day-service, summer only) or 11 hrs. (night service, all the year round); single tickets, available for seven days, 34s. 7d., 25s. 7d., 18s. 7d.; return-tickets, available for one month, 58s. 3d., 42s. 3d., 33s. 3d., available for 2 months, 63s. 9d., 46s. 1d., 36s. 3d.; sea-passage 4-5 hours. Luggage should be registered at London or Newhaven in order to avoid examination at Dieppe; in returning, luggage registered to London is examined at Newhaven. This route from London to Paris is one of the cheapest and most interesting.

Dieppe. — **Hotels.** HÔTELS ROYAL (Pl. a; C, 1), BRISTOL (Pl. b; C, 1), DE LA PLAGE (Pl. c; D, 1), DES BAINS (Pl. d; D, 1), DU RHIN ET DE NEWHAVEN (Pl. e; C, 1), GRAND HÔTEL FRANÇAIS (Pl. é; B, 1); DES ÉTRANGERS (Pl. f; D, 1), GRAND HÔTEL (Pl. g; E, 1), all in the Rue Aguado, facing the sea and somewhat expensive (déj. 4, D. 5 fr.). — GRAND HÔTEL DU NORD ET VICTORIA (Pl. h; E, 2), GR. HÔT. DE LONDRES (Pl. i; D, 2), Quai Henri IV., opposite the steamboat-wharf; DE LA PAIX (Pl. j; C, 2), Grande Rue 212; DE ROUEN (Pl. k; C, 2), Rue de la Barre; CHARLOT D'OR (Pl. l; C, 2), same street; DE PARIS (Pl. m; C, 1), Place de la Comédie; *HÔT. DE COMMERCE (Pl. n; D, 2), Place Nationale (D. $3\frac{1}{2}$ fr.); GLOBE (Pl. o; D, 2), Rue Duquesne. Travellers are recommended to ascertain the prices beforehand. — *Furnished Apartments* are also easily found in the Rue Aguado.

Restaurants. *Café-Restaurant du Casino*, on the beach, see below; *Au Faisan Doré*, Grande Rue 74 (déj. 2, D. $2\frac{1}{2}$ fr.); *Hôtel des Arcades*, Arcades de la Bourse, déj. $1\frac{3}{4}$, D. 2 fr.; *Buffet*, at the Gare Maritime.

Cafés. *Café Suisse*, Grande Rue 1, and in the Arcades; *Café de Rouen*, *Café des Tribunaux*, both at the other end of the Grande Rue.

Cabs with seats for two pers. $1\frac{1}{4}$ fr. per drive (after midnight 2 fr.), 2 or $2\frac{1}{2}$ fr. per hr.; with four seats $1\frac{1}{2}$ - $2\frac{1}{2}$ and $2\frac{1}{2}$ -3 fr. respectively.

Steamboats to Newhaven twice a day in summer, daily in winter.


British Vice-Consul, *H. W. Lee-Jortin, Esq.*

English Church, Rue Asseline; services on Sun. at 11 and 7 (in summer 7.30). Chaplain, *Rev. Jas. Hamilton, M. A.*

The *Carved Ivory* and *Lace* of Dieppe are specialties of the place.

Dieppe, with 23,000 inhab., is situated in a valley formed by two ranges of lofty white chalk-cliffs, at the mouth of the *Arques*, which forms a harbour capable of containing vessels of considerable size. The estuary was formerly called the '*Deep*', from which the town derives its name. In spite of the vicinity of Havre, Dieppe still carries on a considerable trade in coals with England and in timber with Norway and Sweden. Fish is, however, the staple commodity of the place. Dieppe is also a fashionable watering-place, being annually visited by numerous English, as well as French families.

The *Gare Maritime* (Pl. E, 2) and the *Steamboat Quays* are on the N. side of the *Avant Port*, or outer harbour. To the S.W., beyond



the *Bassins Duquesne* and *Bérigny*, lies the *Central Station* (Pl. C, 3); and to the E., between the Bassin Duquesne, and the suburb of *Le Pollet* (Pl. E, 3), inhabited by sailors and fishermen said to be of Venetian origin, are several new basins, opened in 1887.

Along the N. side of the town, between the sea and the Rue Aguado, in which are the principal hotels, stretches *La Plage* (Pl. C, D, E, 1), a handsome marine park or promenade, $\frac{2}{3}$ M. long. At its W. extremity is the *Casino* or *Etablissement de Bains* (Pl. C, 1), the principal attraction for visitors, a handsome brick and glass structure replete with every convenience and including a small theatre (adm. in the forenoon 50 c., afternoon 1 fr., evening or whole day 3 fr.; less for subscribers). In front of it are placed about 200 small tents, used as dressing-rooms, from which the bathers descend into the water, accompanied by a *guide-baigneur*, if necessary. In fine weather the scene is very amusing, and novel withal to the English visitor.

On a precipitous white cliff at the W. extremity of the Plage rises the handsome *Castle* (Pl. B, 1, 2), with its massive walls, towers, and bastions, erected in 1435 as a defence against the English. In 1694, however, it was unable to resist the cannonade of the English fleet, then returning from an unsuccessful attack on Brest, and the unequal contest resulted in the total destruction of the town. The view from the castle is very extensive.

The church of *St. Remy* (Pl. 5; C, 2), not far from the castle, in a mixed style of the 16th and 17th cent., contains huge round columns and some good sculptures. — The church of *St. Jacques* (Pl. 4; C, D, 2), the patron-saint of fishermen, in the *Place Nationale*, is an interesting florid Gothic edifice dating from the 12-16th centuries. It contains numerous rich sculptures and stained-glass windows. Near the church is the *Statue of Duquesne* (Pl. 15; D, 2), erected in 1844, a celebrated admiral and native of Dieppe (d. 1687). — To the E. of the entrance to the harbour is the modern Gothic church of *Notre-Dame-de-Bon-Secours* (Pl. F, 2). The *Musée* (Pl. 11; C, 1) contains antiquities found in the neighbourhood.

The most interesting point in the environs of Dieppe is the ruined castle of *Arques* (*Hôtel du Château*; **Henri IV.*, unpretending), situated 4 M. to the S. E., and memorable as the scene of a victory gained by Henri IV. over the League in 1589. The excursion may be made by train or by omnibus (there and back 2 fr.). The *View from the castle embraces the valleys of the *Arques*, the *Béthune*, and the *Eaulne*.

Other excursions may be made to *Varangeville*, *Puys*, *Cité de Limes* or *Camp de César*, and *Berneval*, all on the coast.

FROM DIEPPE TO PARIS.

125 $\frac{1}{2}$ M. RAILWAY viâ Ronen in 3 $\frac{3}{4}$ -7 $\frac{1}{3}$ hrs. (fares 20 fr. 75, 15 fr. 60, 11 fr. 45 c.). — Another line leads viâ *Neufchâtel*, *Gournay*, *Gisors*, and *Pontoise* (in 4-5 $\frac{1}{2}$ hrs.; fares the same).

Soon after quitting Dieppe the train passes through a tunnel, upwards of 1 M. in length, and then enters the valley of the *Scie*, which it crosses 22 times. After passing several unimportant stations, it reaches (32 M.) *Malainay* (p. 368), where the Rouen-Havre and

Dieppe lines unite. From this point to Rouen the district traversed is cheerful and picturesque, abounding in cotton and other factories.

38 M. Rouen. — **Hotels.** *HÔTEL D'ANGLETERRE (Pl. a; C, D, 3, 4), Cours Boieldieu 7-8; HÔTEL D'ALBION (Pl. b: C, 4), Quai de la Bourse 16; HÔTEL DU NORD (Pl. c; C, 3), Rue de la Grosse-Horloge 91; HÔTEL DE PARIS (Pl. d; D, 4), Quai de Paris 51; *HÔTEL DE FRANCE (Pl. e; D, 2), Rue des Carmes 99; all these of the first class, R. 2½-12 fr. (enquiry should be made beforehand), L. ¾-1, A. ¾-1, déj. à la carte, D. 3½-4½ fr. — Less pretending: HÔTEL DE LA POSTE (Pl. f; C, 2), Rue Jeanne d'Arc 72, R. 2 fr., A. 50 c.; DE LA CÔTE-DE-BALEINE (Pl. g; D, 3), Rue du Bac 18-20; LISIEUX (Pl. h; D, 3), Rue de la Savonnerie 4; *HÔTEL DU DAUPHIN ET D'ESPAGNE (Pl. i; D, 3), Place de la République; VICTORIA (Pl. j; C, 1), near the station on the right bank, unpretending.

Restaurants. **Mennechet*, Rue Jacques-le-Lieur 10, behind the Hôtel d'Angleterre, expensive; *Pomet*, Quai de Paris 34; *Guilmet*, Rue des Charrettes 46, also behind the Hôtel d'Angleterre (déj. 1½, D. 1¾ or 2 fr.); *de Paris*, Rue de la Grosse-Horloge 95 (same charges); *Halbout*, Rue Grand Pont.

Cafés. *Thillard*, Cours Boieldieu 5; *Boieldieu*, *Victor*, in the theatre; *Houdard*, Quai de Paris 58; *de l'Univers*, Place Notre-Dame.

Tramways traverse some of the principal streets and also extend to the suburbs: fares 10-50 c. — *Omnibus* to Bon-Secours, starting from the stone bridge, 60 c.; to Bois Guillaume 60 c.

Cabs (*'Citadines'*) 1½ fr. per drive, 2 fr. per hour; at night (12-6 a.m.) 2½ or 3 fr.; each trunk 20 c.

Post and Telegraph Offices, Rue Jeanne d'Arc 45 (Pl. C, 2).

British Consul, *Major W. P. Chapman*, Rue Thiers 65. — **American Consul**, *Chas. Williams, Esq.*, Rue Thiers 38.

English Church Service in *All Saints' Church*, Ile de la Croix, by the stone bridge; services on Sun. at 11 and 3. Chaplain, *Rev. Rob. Douglas, M. A.* — *Westeyan Church* at the corner of the Rue Grand Pont and the Rue Madeleine; services on Sun. at 11 and 6.30.


Rouen, the Roman *Rotomagus*, formerly the capital of Normandy, now that of the Department of the Seine-Inférieure, with 107,000 inhab., exclusive of the suburbs, is a very important cotton manufacturing place, sometimes not very aptly called the Manchester of France. It is the richest of French cities in mediæval architecture, though the recent construction of handsome streets like those of Paris has swept away several of the monuments of antiquity that had been spared by the Huguenot wars and the Revolution. The old walls of the town, which bade defiance to Henry V. of England in 1415 and to Henri IV. of France in 1592, have been converted into boulevards planted with trees.

The city is bounded on the S. by the Seine, which is here upwards of 300 yds. in breadth, and which separates Rouen from the suburb of *St. Sever* (Pl. C, D, E, 4, 5). The quays extend along the bank for 1½ M. The *Pont de Pierre* (Pl. D, 4), constructed in 1829, passes over the lower end of the *Ile Lacroix*, where there is a statue of *Corneille*, a native of Rouen (d. 1684), by David d'Angers. [The house in which he was born is No. 4, Rue de Corneille, Pl. B, 3; his dwelling-house, now public property, is situated at *Petit Couronne*, 5½ M. to the S.W.] Farther down the river is the *Pont Boieldieu* (Pl. D, 4), a handsome iron bridge, erected in 1885-88. *Le*

ROUEN

1 : 20,000





Cours Boieldieu (Pl. C, D, 4), a small promenade opposite the latter, is adorned with a statue of the composer *Boieldieu* (d. 1834). Adjacent are the *Théâtre des Arts* (Pl. 12; D, 3, 4) and the *Bourse*, the latter a building of the 18th century. At the end of the quay is the *Douane* (Pl. C, 4). In front of the *Gare d'Orléans* (Pl. C, D, 5), on the opposite bank, is a statue of the *Abbé de la Salle* (1651-1716), the founder of the society of 'Frères de la Doctrine Chrétienne'.

The **Cathedral*, or *Notre-Dame* (Pl. D, 3), the principal parts of which date from 1207-80, is one of the grandest Gothic edifices in Normandy, although remarkably unsymmetrical in plan. The central portal of the W. façade, towards the Place, was erected by Cardinal d'Amboise, the favourite minister of Louis XII., at the beginning of the 16th cent., and profusely decorated in the florid style. The sculptures over the chief entrance, of no great merit, represent the Genealogy of Christ, with the Beheading of John the Baptist on the left, and the Virgin and saints on the right. The two unfinished towers of the façade are of unequal height. The **Tour de Beurre*, the loftier and more beautiful, 230 ft. in height, derives its name from having been erected with the money paid for indulgences to eat butter during Lent. The central spire over the transept, having been ignited by lightning and burned down in 1822, was replaced by a most unsightly tower of cast iron, 465 ft. in height. A spiral staircase ascends to the summit. The two side-portals, dating from the 15th cent., are of great interest, especially that on the N., called the **Portail des Libraires* from the book-stalls that once occupied the court.

The INTERIOR of the church (447 ft. in length; transept 177 ft. in length; nave and aisles 105 ft. in width; 92 ft. in height) is in the early pointed style, and possesses three fine rose-windows in the nave and transepts. Part of the stained glass dates from the 13th century. The first chapel on the right, in the Tour de Beurre, contains a large altar-piece, representing the Crucifixion and the Martyrdom of St. Stephen, and also several monuments of the 13th and 14th centuries. The last chapel on the S. side of the nave contains the tomb of *Rollo* (d. 927), first Duke of Normandy, and the corresponding chapel on the N. side that of his son *William, Longue-Épée* (d. 943). The *Chapelle du Christ*, adjoining the high-altar, contains an ancient mutilated figure in limestone, 7 ft. in height, of *Richard Cœur-de-Lion* (d. 1199), discovered in 1838; his heart is interred below. Its original resting-place in the choir is indicated by a small marble tablet. *Henry II.* of England (d. 1189) is also buried in the choir.

To the right in the beautiful **Chapelle de la Vierge* is the magnificent **Monument of Cardinal George d'Amboise* and his nephew, who was also a cardinal, by *Roland Leroux*, erected in 1525. To the left is the handsome **Monument of the Duc de Brézé* (d. 1530), grand seneschal of Normandy, erected by his widow, the celebrated *Diana of Poitiers* (d. 1566), mistress of *Henri II.*, and attributed to *Jean Cousin* and *Jean Goujon* (p. 106). — The altar-piece, an Adoration of the Shepherds, is by *Ph. de Champagne*.

**St. Maclou* (Pl. E, 3), 'un diminutif de St. Ouen', as it has been called, is a very rich example of the florid Gothic style of the 15th century. The modern spire was completed in 1869. The exquisitely carved reliefs on the wooden doors are ascribed to *Jean Goujon*.

***St. Ouen* (Pl. D, E, 2), one of the most beautiful Gothic churches

in existence, surpasses the cathedral, both in extent and in excellence of style. It was founded in 1318, and completed towards the close of the 15th century. The original plan having been followed throughout, the edifice exhibits a rare harmony of design. The **Tower* over the transept, 268 ft. in height, is surmounted by an octagonal open-work lantern, terminating in a gallery (**View*).

The rich *Façade* contains three portals adorned with numerous statues and reliefs. The S. '**Portail des Marmousets*', so called from the figures of the animals with which it is adorned, deserves minute inspection. The reliefs over the door represent the Death and Assumption of the Virgin. Above this portal is a magnificent rose-window, still higher is an arcade with eleven statues, and the whole is crowned with a pediment bearing a statue of *St. Ouen* (d. 678), archbishop of Rouen. The towers have recently been completed, although not in strict harmony with the rest of the edifice.

The proportions of the interior (453 ft. in length, 84 ft. in width; transept 138 ft. in length; 106 ft. in height) are remarkably pleasing. The walls appear to be almost entirely displaced by the numerous windows, 135 in number, all filled with stained glass. The unusually lofty triforium is exceedingly beautiful. In the nave and transepts are three fine rose-windows, also filled with stained glass.

The verger (1 fr.) shows the choir-chapels, and points out several spots which command fine views of the interior. The whole of the interior is reflected in the bénitier near the W. door.

At the back of the church and the adjoining Hôtel de Ville is a pleasant garden to which the public are admitted. The *Chambre aux Clercs*, a Norman tower of the 11th cent., adjoins the church on this side, and probably formed part of an earlier church.

The *Hôtel de Ville* (Pl. D, E, 2), on the N. side of the church, a building in the Italian style, was formerly part of the monastery of *St. Ouen*. In front of the edifice rises the *Equestrian Statue of Napoleon I.*, by Vital-Dubray.

Behind the statue of Napoleon is the *Rue Thiers*, leading to the *Jardin Solférino*, at the S.E. corner of which stands the new —

Musée (Pl. C, 2), opened in 1888, containing a collection of Italian, Dutch, and modern French pictures, besides sculptures and a ceramic collection. The *Musée* is open daily from 10 (on Mon. from 12) to 4 or 5.

The *Municipal Library* (open daily 10-5), in the building at the back of the *Musée*, contains 130,000 printed vols., 2500 MSS., 2700 coins and medals, about 2000 portraits of eminent natives of Normandy, and a collection of engravings.

The adjacent church of *St. Laurent* (Pl. D, 2), dating from the 15-16th cent., with a fine tower, is now used as a magazine. The church of *St. Godard* (Pl. D, 2), partly of the 16th cent., contains admirable modern stained-glass windows and mural paintings.

The *Tour de Jeanne d'Arc* (Pl. C, 1), in the Rue de Jeanne d'Arc, is a relic of a citadel erected by Philip Augustus in 1204, which was the scene of the trial of Joan of Arc; the tower in which she was

imprisoned was pulled down in 1809. — The church of *St. Patricia* (Pl. C, 2), a little to the W. of the Jardin Solférino, contains the finest *Stained glass in Rouen, some of it dating from the 16-17th centuries. The allegorical window at the end of the N. aisle, attributed to *Jean Cousin*, is considered the best.

The **Palais de Justice* (Pl. C, D, 2, 3), in the late florid Gothic style, resembles the handsome town-halls of Belgium, although consisting of a single story only. The central part of the edifice and the projecting wings form an entrance-court, enclosed by a railing. The left wing, the *Salle des Procureurs* or *des Pas-Perdus*, erected in 1493, is a spacious hall with an open roof, once used as an exchange. The central part was erected six years later, for the *Cour de l'Echiquier*, the supreme tribunal of Normandy, which under Francis I. was styled 'parlement'. The assizes are now held here. The concierge lives in the right wing, a modern addition.

The TOUR DE LA GROSSE HORLOGE, or *Beffroi* (belfry; Pl. C, 3), was erected in 1389. The bridge across the street, and the arch which unites the tower with the old Hôtel de Ville, date from 1527.

Farther to the W. is the PLACE DE LA PUCELLE (Pl. C, 3), the traditional scene of the burning of Joan of Arc in 1431. About 24 years later she was declared innocent of the crime of witchcraft by a papal bull, and the French, who it is well known had been her betrayers, being now masters of Rouen, erected a cross to her memory on the spot where she had suffered. The place is now occupied by a paltry figure over a fountain. It is believed, however, that the exact spot of the execution was a little higher up, in the *Place du Vieux-Marché* (Pl. C, 3), where the *Théâtre Français* now stands.

The adjoining *HÔTEL DU BOURGTHÉROULDE (Pl. C, 3), which was erected at the close of the 15th cent., in the style of the Palais de Justice, contains a number of reliefs, one of which represents the interview on the 'Field of the Cloth of Gold' (1520). The graceful hexagonal tower is decorated with sculptures from Scriptural subjects. The building is now occupied by the Comptoir d'Escompte, and is open to the public on week-days (on Sun. apply to the concierge).

To the S.E. of this point, at the corner of the Rue aux Ours and the Rue Jeanne d'Arc, is the handsome *Tour St. André* (Pl. C, 3), a relic of an old church. It stands in a small square, on one side of which the front of a timber dwelling of the 16th cent. has been re-erected. To the S. is the church of *St. Vincent* (Pl. C, 3), a pretty Gothic building of the 16th cent., with a 17th cent. tower. The Rue Jeanne d'Arc ends, to the S. of this point, at the Quai de la Bourse.

At the end of the Rue de la République is the large *Fontaine Ste. Marie* (Pl. D, 1), erected by Falguière in 1879. To the left is an old convent, now containing the *Museum of Antiquities* (Pl. D, 1), which is open on Thurs. and Sun., 12-4 (at other times 1 fr.).

The collections consist chiefly of sculptures and wood-carvings of the middle ages; stained-glass windows and other articles from churches and

suppressed monasteries; Roman mosaics and other antiquities; weapons; fine iron-work; coins, medals, etc.

The *Muséum d'Histoire Naturelle*, the entrance to which is a little lower down, is open daily, 10 to 4 or 5 (on Mon. from 12). The collection of birds on the second floor is particularly worthy of notice.

Descending from the Hôtel du Bourghthéroulde to the Quai du Havre, we follow the quay to the *CÔTE STE. CATHERINE (405 ft.; Pl. G, 3), which rises at the E. end of the city, immediately beyond the *Champ-de-Mars*. The ascent takes $\frac{1}{2}$ hour. The summit is occupied by a few fragments of a fortress, which Henri IV. caused to be demolished, and commands an extensive view.

A still finer prospect may be enjoyed from the new pilgrimage-church of *Notre-Dame de Bon-Secours*, or simply ***Bon-Secours** as it is usually called, situated on the lofty bank of the river, 2 M. above Rouen. The view embraces the city, the course of the river for many miles above and below Rouen, and in the distance the rich and verdant pastures of Normandy.

A pleasant steamboat-excursion may be taken to *La Bouille*, a small but busy town, $12\frac{1}{2}$ M. below Rouen. The *Château de Robert le Diable*, the scanty ruins of which occupy the top of a neighbouring height, affords a charming view of the wooded hills, the valley of the Seine with its white chalk-hills, and in the distance Rouen with the cathedral.


FROM ROUEN TO PARIS. Passing by means of three tunnels under the Boulevards St. Hilaire and Beauvoisine, and the Côte Ste. Catherine, the train crosses the Seine, affording a beautiful view of Rouen to the right. To the left, on the hills which rise from the river, stands the church of *Bon-Secours*. At ($39\frac{1}{4}$ M.) *Sotteville* is an English church. From (44 M.) *Oissel* a branch-line runs to *Elbeuf* (Grand-Hôtel; Univers), 6 M. distant, a cloth-manufacturing town, with 22,100 inhabitants. Beyond Oissel the train crosses the Seine. — $48\frac{1}{2}$ M. *Pont de l'Arche*, where the Seine is again crossed, above the influx of the *Eure*, is the junction of a line to *Gisors*; it possesses a fine church of the 15th century. — 56 M. *St. Pierre-du-Vauvray*, whence a branch-line diverges to *Louviers* (Hôtel du Mouton), a town of 10,550 inhab. with large cloth-factories. The train now penetrates the chalk-hills by means of two tunnels.

The station of (64 M.) *Gaillon* lies opposite the village of *Courcelles*. The château of Gaillon, erected in 1500, and now used as a prison, was one of the finest in Normandy, and a favourite residence of Francis I. The lofty façade has been removed to the court of the Ecole des Beaux-Arts at Paris (p. 247).

On the right bank of the Seine, near (3 M.) *Les Andelys* (Grand Cerf), are the ruins of the castle of *Gaillard*, erected by Richard Cœur-de-Lion to command the navigation of the Seine and protect Normandy against the French monarchs. It afterwards became a state-prison, and in 1314 was the scene of the murder of Margaret of Burgundy, wife of Louis X. (see p. 244). It was destroyed by Henri IV. in 1663, along with the castles of several dangerous Norman barons.

$75\frac{1}{2}$ M. *Vernon* (Hôtel d'Evreux), with 8164 inhab., once a strongly-fortified town, possesses a conspicuous tower, erected in





1123 by Henry I. of England. The *Church* is an interesting building of the 12-15th centuries. The château of *Bizy* in the vicinity was once the property of Louis Philippe. Branch-lines to Gisors and to *Pacy-sur-l'Eure* diverge here. To the left are the ruins of the castle of *Châteauneuf*, constructed by Philip Augustus.

The long tunnel between *Bonnières* and *Rolleboise* cuts off the wide circuit which the river describes here.

At the château of (84 M.) *Rosny*, Sully, the celebrated minister of Henri IV., was born in 1559. It was afterwards the property of the Duchesse de Berri, who resided in it from 1818 to 1830.

92½ M. **Mantes** (*Hôtel du Grand Cerf*), a picturesque town with 6600 inhab., is surnamed '*La Jolie*'. The lofty towers of the Gothic church of **Notre-Dame*, dating from the end of the 12th cent., are conspicuous objects in the town. The portal is richly sculptured. The old tower of *St. Maclou*, 14th cent., is also interesting. It was at Mantes that William the Conqueror received by a fall from his horse the injury of which he afterwards died at Rouen (1087). — New line to Paris viâ *Argenteuil*, see p. 327.

The line continues to skirt the banks of the Seine, and frequently commands fine views. Several unimportant stations.

108 M. **Poissy** (*Buffet; Hôtel de Rouen*), a town with 6400 inhab., was the birthplace of St. Louis (b. 1226), who frequently styled himself '*Louis de Poissy*'. Here in 1561 a conference was assembled by order of the States General, with a view to adjust the differences between the Roman Catholic and Protestant parties. Their deliberations, however, led to no result, owing to the strong condemnation of the Calvinists by the Sorbonne. — The principal church is a fine building of the transition-style of the 12th century. Poissy is also a station on the Ligne de Grande Ceinture (p. 318).

111 M. *Achères*, in the forest of St. Germain (p. 342), the junction of the direct line to Dieppe (viâ Pontoise, p. 342). At (114 M.) *Maisons-Laffitte* (p. 341) the Seine is again crossed. Near (120 M.) *Colombes* the line recrosses the Seine. St. Germain with its palace is a conspicuous object on the hill to the right.

The Seine is crossed for the last time at *Asnières* (p. 285), where the lines to Argenteuil and Versailles diverge. The train passes *Clichy*, intersects the fortifications of Paris, and beyond a short tunnel under the Place de l'Europe reaches the Gare St. Lazare at —

125¼ M. **Paris**. Conveyances, see p. 1.

25. By Southampton, Havre, and Rouen.

By RAILWAY from Waterloo Bridge Station to Southampton in 2¼ hrs. ('boat-train' at 9.45 p.m.; see advertisements in 'Bradshaw'); by STEAMBOAT to Havre every Mon., Wed., and Frid. in 9-10 hrs.; by EXPRESS from Havre to Paris in 4½ hrs. (quick trains, 6 hrs.; ordinary trains, 7½-7¾ hrs.). Omnibus from the quay to the station at Havre not included in the fare. Single tickets, available for seven days, 33s. and 24s.; return-tickets, available for one month, 55s. and 39s. Luggage may be registered direct to Paris. — This route is pleasant in fine weather.

By STEAMBOAT from London to Havre direct once a week (see advertisements of General Steam Navigation Co.), average passage, including 5-6 hrs. in the Thames, 18 hrs.; fares 13s. and 9s.; return-tickets available for one month, 20s. 6d. and 14s.

Le Havre. — **Hotels.** *HÔTEL FRASCATI* (Pl. B, 4), on the beach, far from the centre of the town, R. from 3, L. $\frac{3}{4}$, A. 1, déj. 4, D. 5 fr.; **DE L'EUROPE* (Pl. c; C, 3), Rue de Paris 121; *DE BORDEAUX* (Pl. d; C, 3), Place Gambetta; *DE NORMANDIE* (Pl. e.; C, 3), Rue de Paris 106; *D'ANGLETERRE* (Pl. f; C, 2), Rue de Paris 124 and 126, R. 2-5, déj. $2\frac{3}{4}$, D. $3\frac{3}{4}$ fr.; *CONTINENTAL* (Pl. b; C, 4), opposite the Jetée; *RICHELIEU* (Pl. h; C, 3), Place Richelieu, near the office of the railway-omnibus; *AIGLE D'OR* (Pl. j; C, 4), Rue de Paris 32, mediocre, R. $2\frac{1}{2}$, déj. $3\frac{1}{2}$, D. $3\frac{1}{2}$ fr.; *HÔTEL DES ARMES DE LA VILLE* (Pl. k; C, 4), Rue d'Estimaucville 29.

Restaurants. At the *Hôt. de Bordeaux* (see above); *Tortoni*, in the Arcades of the Place Gambetta, déj. 3, D. 4 fr.; *Plat d'Argent*, Place Richelieu, déj. $1\frac{3}{4}$, D. $2\frac{1}{4}$ fr., beer or cider included.

Cafés. *Tortoni*, see above; *de l'Opéra*, also in the Place Gambetta; *Guillaume Tell*, Place de l'Hôtel-de-Ville. — *Café Chantant de l'Alcazar* (Pl. C, 2), Rue Thiers 17 ($\frac{3}{4}$ - $1\frac{1}{2}$ fr.).

Cabs. In the town, per drive 1 fr. 25 c., per hr. 2 fr. (after midnight 2 and $\frac{1}{2}$ fr.); in the environs 2 & $2\frac{1}{4}$ fr.

Post and Telegraph Office (Pl. C, D, 2), Bonl. de Strasbourg 108 and 110.

Steamboats, starting from the Grand Quai (Pl. C, D, 4), to Honfleur, Trouville, Caen, Southampton, London, New York, etc.

British Consul, *J. Bernal, Esq.*, Boulevard François Premier 55. — **American Consul**, *Oscar F. Williams, Esq.*

English Church, Rue de Mexico; services at 11 and 7.30 (4 p.m. in winter). Chaplain, *Rev. Howard S. Chesshire, M. A.*, Rue Ste. Adresse 31. — **Wesleyan Methodist Chapel**, Rue de l'Hôpital; minister, *Rev. G. Whelpton*.

Le Havre, formerly called *Havre-de-Grâce*, from a chapel of Notre-Dame-de-Grâce founded by Louis XII. in 1509, was fortified by Francis I. in 1516. It is now the seaport for Paris, and next to Marseilles the most important in France (112,000 inhab.). The buildings and the commercial prosperity of the town are of very recent origin. Its situation at the mouth of the Seine is extremely advantageous. The industrial importance of the town is mainly derived from its ship-building yards and sugar-refineries.

The RUE DE PARIS, intersecting the town from S. to N., is the centre of traffic. It begins at the W. end of the *Grand Quai* (Pl. C, 4), where passengers from England disembark, crosses the *Place Gambetta* (Pl. C, 3), with the *Theatre*, and ends at the *Place de l'Hôtel-de-Ville*. Near the beginning is the church of *Notre-Dame* (Pl. C, 4), built in the 16th cent. in a style showing the transition from Gothic to Renaissance forms. The BOULEVARD DE STRASBOURG (Pl. F-A, 2) stretches from the *Railway-Station* (Pl. F, 2), on the E., to the sea, on the W., passing the *Palais de Justice*, the *Sous-Préfecture*, the *Bourse* (Pl. D, 2, 3), a fine Renaissance edifice, finished in 1880, and the handsome modern *Hôtel de Ville* (Pl. C, 2).

The old fortifications have been demolished, but the town and harbour are commanded by new forts erected on the heights of *Ingouville* and *Ste. Adresse* (p. 367).

The extensive HARBOUR and Docks (Pl. C-G, 2-5) deserve a visit. The chief dock is the *Bassin de l'Eure* (Pl. E, F, 3, 4, 5), 50 acres in area, constructed in 1846-1856, where the huge Trans-

atlantic steamers lie. The *Bassin Bellot*, recently constructed to the E., is even larger. The *Bassin du Roi* (Pl. C, D, 3, 4), excavated in 1669, is connected with the *Bassin du Commerce* (Pl. C, D, E, 3), adjoining which is the *Bassin de la Barre*. The *Bassin Vauban* (Pl. F, G, 2, 3) is another large dock, a little to the N. There is also a well-protected '*Avant Port*', or outer harbour. The *Canal de Tancarville*, opened in July, 1887, was constructed to connect the Seine directly with the harbour, and to enable ships to escape the 'barre' or tidal wave in the estuary.

In 1796, *Admiral Sir Sidney Smith*, in an unsuccessful attempt to capture a French vessel, close to the guns of the citadel, was stranded on the shallows of the estuary of the Seine, and taken prisoner by the French.

Opposite the harbour rises the *Musée-Bibliothèque* (Pl. C, 4), in front of which are statues by David d'Angers of *Bernardin de St. Pierre* (author of '*Paul et Virginie*', to which the reliefs refer) and *Casimir Delavigne*, the dramatist, both natives of Havre. The Museum (open on Sun., Tues., and Thurs., 10 to 4 or 5) contains stuffed animals, casts, pictures, coins, etc., and a library of 30,000 volumes.

The **Jetée du Nord* (Pl. B, 5), or N. pier, near the *Hôtel Frascati*, terminating in a lighthouse, commands a fine view, and is a favourite promenade. Numerous boats here afford the visitor an opportunity of enjoying an excursion by water.

As Havre itself contains little to interest travellers, those who have a few hours at their disposal should ascend the height on which *Ingouville*, a town with 12,000 inhab., is situated. *Ingouville*, and *Graville*, another contiguous town, were united with Havre in 1856, and contain many handsome villas and gardens. The **View* embraces the town with its forest of masts, the estuary of the Seine, and the sea. A tramway, starting from the Boulevard de Strasbourg, runs to *Ste. Adresse* (*Hôtel des Phares*; *Casino Marie-Christine*), a favourite little bathing-place $2\frac{1}{2}$ M. to the N.W. Visitors should alight at the '*Quatre Chemins*' (20 or 10 c.) or the *Rue des Bains* (35 or 30 c.), and proceed to the lighthouse, *Phares de la Hève*, which commands a fine view.

Steamers ply twice daily from Havre in 1 hr. (fares 3 fr., 1 fr. 50, 75 c.) to *Trouville-sur-Mer* (*Hotels des Roches-Noires, de Paris, Bellevue, de la Plage*, on the beach; *Tivoli, Bras d'Or*, in the town), pleasantly situated at the mouth of the *Touques* and now the most fashionable watering-place on the coast of Normandy. Pop. 6300. The season lasts from June to Oct., and is at its height in Ang., when living here is extremely expensive. The *Casino* or *Salon* is a large and handsome structure, with concert-rooms, ball-rooms, and a fine terrace on the shore. The beach is excellent. A number of handsome villas have sprung up in the environs. — *Deauville* (*Hôtel du Casino*) and a number of less pretending watering-places sprinkled along the coast also afford good summer-quarters (see *Baedeker's Northern France*).

FROM HAVRE TO PARIS.

142½ M. RAILWAY in 4½-7½ hrs. (fares 28 fr. 10, 21 fr. 5, 15 fr. 45 c.). — STEAMBOAT up the Seine to Rouen daily in 7-8 hrs. (fares 5 and 4 fr.), tedious, but scenery very pleasing at places.

The railway-station at Havre is near the Cours de la République. On quitting the station we observe *Graville*, with its curious church of the 11th cent., on the high ground to the left.

4 M. *Harfleur*, the first station, once an important seaport, has long since yielded up its traffic to Havre. Its harbour has been filled up by the deposits of the *Lézarde*, which falls into the Seine here. In 1415 the town was taken by Henry V. of England, to whom the foundation of the fine Gothic church is attributed. From Harfleur a branch-line runs to (2¼ M.) *Montivilliers*, an industrial town with an old abbey-church. — Beyond (15½ M.) *Beuzeville-Bréauté*, from which a branch-line runs to (8½ M.) *Lillebonne* (Hôtel de France), the train crosses a lofty viaduct.

19½ M. *Bolbec-Nointot* is the station for *Bolbec*, a thriving manufacturing town with 12,000 inhab., 2 M. to the S.

26¼ M. *Yvetot* is another manufacturing place, with 8000 inhab., the ancient counts or soi-disants kings of which are thus playfully described by Béranger: —

‘Il était un roi d’Yvetot,	Dormant fort bien sans gloire,
Peu connu dans l’histoire,	Et couronné par Jeanneton
Se levant tard, se couchant tôt,	D’un simple bonnet de coton’.

30 M. *Motteville* is connected with the Dieppe railway by a branch-line to *Clères* (16 M.). Another branch runs to *St. Valéry-en-Caux*, frequented as a bathing-place. The pleasant village of (36 M.) *Pavilly* is commanded by the restored château of *Esneval*. The train quits the undulating and fertile table-land of the *Pays de Caux*, and descends to the viaduct of *Barentin*, 570 yds. in length, and 100 ft. above the level of the valley. From (37 M.) *Barentin* a branch-line runs to (18 M.) *Caudebec*. The train soon enters a tunnel, nearly 1½ M. in length, beyond which it reaches (44½ M.) *Malaunay*, where the Dieppe line diverges. From this point to Rouen, and to Paris (142½ M. from Havre), see pp. 359-365.

LIST

of the most important Artists mentioned in the Handbook, with a
note of the schools to which they belong.

Abbreviations: A = architect; P. = painter; S. = sculptor; c., ca. = circa, about; Fr. = French; Bol. = Bolognese; Flor. = Florentine; Ferr. = Ferrarese; Lomb. = Lombardic; Neap. = Neapolitan; Rom. = Roman; Ven. = Venetian, etc.

The Arabic numerals enclosed within brackets refer to the art notices throughout the Handbook, the Roman figures to the Introduction.

- Abbate, Nic. dell'*, Lomb. P.; 1512-71.
Adam, Jean-Vict., Fr. P., Paris, pupil of Meynier & Regnault; 1801-66.
Adam, Lamb.-Stigisb., Fr. S., Nancy; 1700-59.
Aizelin, Eug., Fr. S., Paris, pupil of Ramey & Dumont; b. 1821.
Alaux, Jean, Fr. P., Bordeaux, pupil of Vincent; 1786-1864.
Albano, Franc., Bol. P., pupil of Carracci; 1578-1660.
Albertinelli, Mariotto, Flor. P., pupil of Rosselli and Fra Bartolommeo; 1474-1515.
Allegri, see Correggio.
Amaury-Duval, Eug.-Emm., Fr. P., Paris, pupil of Ingres; 1808-85. — (p. xxxviii).
Amerighi, see Caravaggio.
Androuet, see Dncreceau.
Angelico (Fra), da Fiesole, Flor. P.; 1387-1455.
Ange, Roger, Fr. A.; 15-16th cent.
Anguier, François, Fr. S., Eu; 1604-1669. — (p. 108).
—, Michel, Fr. S., brother of the last; 1612-86.
Antigna, J.-Pierre-Alex., Fr. P., Orleans, pupil of P. Delaroche; b. 1818.
Antonello, see Messina.
Audran, Gérard, Fr. engraver, Lyons; 1640-1703.
—, Claude, Fr. P., brother of the last; 17th cent.
Bakhuizen, Ludolf, Dutch P., Emden, pupil of A. van Everdingen; 1631-1708.
Ballu, Théodore, Fr. A., Paris; 1817-85.
Baltard, Victor, Fr. A., Paris; 1805-74.
Balze, Jean-El.-Paul, Fr. P., pupil of Ingres; b. 1815.
—, Jean-Ant.-Raymond, Fr. P., brother of the last; b. 1813.
Barbarelli, see Giorgione.
Barbieri, see Guercino.
Baroccio, Federigo, Rom. P.; 1528-1612.
Barrias, Félix-Jos., Fr. P., Paris, pupil of L. Cogniet; b. 1822.
—, Louis-Ernest, Fr. S., Paris, pupil of Cavalier & Joffroy; b. 1841. — (p. xl).
Bartholdi, Fréd.-Aug., Fr. S., Colmar; b. 1834.
Bartolommeo (Fra), Baccio della Porta, Flor. P.; 1475-1517.
Barye, Ant.-Louis, Fr. S., pupil of Bosio and Gros; 1796-1875. — (p. xl).
Bassano, Jacopo (da Ponte), Ven. P., 1510-92.
Bastien-Lepage, J., Fr. P., Damvillers (Meuse); 1848-85.
Baudry, Paul-Jacq.-Aimé, Fr. P., La Roche-sur-Yon, pupil of Sartoris & Drolling; 1828-86. — (pp. xxxvii, xxxviii).
Beham or Böhm, Hans Sebald, Ger. P., Nuremberg; 1500-50?
Bellangé, Jos.-Louis-Hipp., Fr. P., pupil of Gros; 1800-66.
Bellini, Gentile, Ven. P., 1426?-1507.
—, Giovanni, Ven. P., brother of the last; 1427-1516.
Beltraffio or Boltraffio, Giov.-Ant., Milanese P., pupil of L. da Vinci; 1467-1516.
Benouville, Franç.-Léon, Fr. P., Paris, pupil of Picot; 1821-59. — (p. xxxvii).
Berchem or Berghem, Nic., Dutch P., Haarlem; 1624-85.
Berge, Aug. Charles de la, Fr. P.; 1807-42.
Berrettini, see Cortona.
Bida, Alex., Fr. P., Toulouse, pupil of Delacroix; b. 1823. — (p. xxxviii).
Blondel, Merry-Jos., Fr. P., Paris, pupil of Regnault; 1781-1853.
Boilly, Louis Léop., Fr. P.; 1761-1845.
Bol, Ferd., Dutch P., Dordrecht, pupil of Rembrandt; 1610?-81.
Bologna, Giov. da, also called *Jean (Boullogne) de Douai*, S., Douai, pupil of Michael Angelo; 1524-1608.

- Bonheur, Rosa*, Fr. P., Bordeaux; b. 1822. — (p. xxxix).
- Bonifazio* or *Bonifacio*, three Ven. painters; ca. 1540-1580.
- Bonnassieux, Jean-Marie*, Fr. S., pupil of Dumont; h. 1810.
- Bonnat, Léon-Joseph-Florentin*, Fr. P., Bayonne, b. 1833, pupil of Cogniet. — (pp. xxxvii, xxxviii).
- Bordone, Paris*, Ven. P., 1500-70.
- Borgognone, Ambrogio da Fossano*, Lomb. P.; 1455?-1524?.
- Bosio, Fr. Jos.*, S., Monaco, pupil of Pajon; 1769-1845. — (p. 119).
- Botticelli, Aless.* or *Sandro (Filipepi)*, Flor. P., pupil of Fra Filippo Lippi; 1447-1510.
- Bouchardon, Edme*, Fr. S., Chaumont, pup. of Coustou the Younger; 1698-1762.
- Boucher, Franc.*, Fr. P., pupil of Lemoine; 1704-70. — (p. xxxi).
- Bouguereau, Ad.-Will.*, Fr. P., La Rochelle, pup. of Picot; b. 1825.
- Boulogne, Bon.* or *de Boullongne*, Fr. P., Paris; 1649-1717.
- , *Louis*, Fr. P., brother of the last; 1654-1733.
- Boullongne*, see *Valentin*.
- Bourgeois, Charles-Arthur*, living Fr. S., Dijon, pupil of Duret & Guillaume. — (p. xl).
- Bourguignon, Le*, see *Courtois*.
- Brascassat, Jacques-Raymond*, Fr. P., Bordeaux; 1804-67.
- Breton, Jules-Adolphe*, Fr. P., pup. of Drolling; h. 1827. — (p. xxxviii).
- , *Em.-Adélar*, Fr. P., brother and pupil of the last.
- Breughel*, see *Brueghel*.
- Brion, Gustave*, Fr. P., Alsace; 1824-1877. — (p. xxxviii).
- Briosco, Andr.*, surn. *Riccio*, Ital. S., Padua; h. after 1450.
- Brongniart, Alex.-Théod.*, Fr. A., Paris; 1739-1813.
- Bronzino, Angelo di Cosimo*, Flor. P., pupil of Pontorno; c. 1502-72.
- Brouwer, Adr.*, Flem. P., Oudenaerde, pupil of Fr. Hals; c. 1605-38.
- Bruant, Libéral*, Fr. A.; d. 1697.
- Brueghel, Peeter*, or *Brueghel the Elder* ('*Peasant Brueghel*'), Flem. P., Breda; c. 1520-69.
- , *Jan*, surn. '*Velvet Brueghel*', Flem. P., Brussels, son of the last; 1568-1625.
- Bullant, Jean*, Fr. A., S.; d. 1578.
- Buonarrotti*, see *Michael Angelo*.
- Buonvicino*, see *Moretto*.
- Cabanel, Alex.*, Fr. P., Montpellier, pupil of Picot; 1823-89. — (p. xxxviii).
- Cabat, Louis*, Fr. P., Paris, pupil of Flers; h. 1812. — (p. xxxix).
- Calcar, Johann von*, P. of the Ven. School, pupil of Titian; 1510-46.
- Caliari*, see *Veronese*.
- Canaletto, Ant. Canale*, Ven. P.; 1697-1768.
- Canova, Ant.*, Ital. S.; 1757-1822.
- Caravaggio, Michelangelo Amerighi da*, Lomb. & Rom. P.; 1569-1609.
- Carpaccio, Vittore*, Ven. P.; 1470?-1519.
- Carpeaux, Jean-Bapt.*, Fr. S., Valenciennes, pupil of Rude & Duret; 1827-75. — (p. xl).
- Carracci, Lodovico*, Bol. P., pupil of Tintoret; 1555-1619.
- , *Agostino*, Bol. P.; 1558-1601.
- , *Annibale*, Bol. P., brother of Agostino, pup. of Lodovico, 1560-1609.
- , *Ant.*, Bol. P., son of Agostino, pup. of Ann. C.; 1583-1618.
- Carrier-Belleuse, Alb.-Ern.*, Fr. S., pupil of Dav. d'Angers; 1824-87.
- Carrucci*, see *Pontorno*.
- Cartellier, Pierre*, Fr. S., Paris; 1757-1831.
- Cavellier, Pierre-Jules*, Fr. S., Paris, pupil of David d'Angers, b. 1814. — (p. xl).
- Cellini, Benvenuto*, Fl. S. and goldsmith; 1500-72.
- Cerceau, du*, see *Ducerceau*.
- Cesari, Jos.*, Rom. P.; c. 1560-1640.
- Chalgrin, J.-Fr.-Thér.*, Fr. A., Paris, pup. of Servandoni; 1739-1811.
- Champaigne, Phil. de*, Fr. P., Brussels; 1602-74. — (p. xxx).
- Chapu, Henri-Mich.-Ant.*, Fr. S., pup. of Pradier & Duret; 1833-91. — (p. xl).
- Chardin, J.-B. Siméon*, Fr. P., Paris; 1699-1779. — (p. xxxi).
- Charlet, Nicolas*, Fr. P., Paris; 1792-1845. — (p. xxxix).
- Chassériau, Théod.*, Fr. P., pupil of Ingres; 1819-56.
- Chaudet, Ant.-Denis*, Fr. S., Paris 1763-1810. — (p. 109).
- Chenavard, Paul*, Fr. P., Lyons; h. 1806. — (p. xxxvii).
- Chintreuil, Ant.*, Fr. P.; h. 1816.
- Cigoli, Luigi Cardi da*, Flor. P.; 1559-1613.
- Cima*, see *Conegliano*.
- Cimabue, Giov.*, Flor. P.; 1240?-1302?.
- Clésinger, J.-B.-Aug.*, Fr. S., Besançon; 1814-83.
- Cloet* or *Cloet, Franc.*, surn. *Jehannet*, Fr. P., Tours; 1500?-72. — (p. xxxix).
- Cogniet, Léon*, Fr. P., pupil of Guérin; 1794-1881.
- Coignet, Jules-Louis-Philippe*, Fr. P., Paris, pupil of Bertin, 1798-1860. — (p. xxxvi).

- Colombe, Michel*, Fr. S.; 1430?-1512? — (p. 106).
- Comte, Charles*, Fr. P., Lyons, pup. of Fleury; b. 1815. — (p. xxxvi).
- Conegliano, Cima or Giov. Batt. da*, Ven. P.; d. 1517?
- Constable, B. A. J.*, Engl. P., 1776-1836.
- Cornu, Séb.-Melch.*, Fr. P., Lyons, pupil of Ingres; 1804-71.
- Corot, J.-B. Camille*, Fr. P., Paris; 1796-1875.
- Correggio. Ant. Allegri da*, Lomb. P.; 1494?-1534.
- Cortona, Pietro Berrettini da*, Flor. A. and P.; 1596-1669.
- Cortot, Jean-Pierre*, Fr. S., Paris; 1787-1843.
- Costa, Lor.*, Ferr. P.; 1460-1535.
- Couder, Louis-Ch.-Aug.*, Fr. P., Paris, pup. of David & Regnault; 1789-1873.
- Courbet, Gustave*, Fr. P.; 1819-77. — (p. xxxviii).
- Court, Jos.-Dés.*, Fr. P., Rouen, pupil of Gros; 1798-1865.
- Courtois, Jacq., le Bourguignon*, Fr. P.; 1621-1676.
- Cousin, Jean*, Fr. P., S., A., & engraver; d. ca. 1589.
- Coustou, Nic.*, Fr. S., Lyons; pup. of Coyzevox, 1668-1733. — (p. 109).
- , *Guill.*, Fr. S., Lyons, brother of the last and pup. of Coyzevox; 1678-1746. — (p. 109).
- , *Guill.*, Fr. S., Paris, son of the last; 1716-77.
- Couture, Thomas*, Fr. P., Senlis, pupil of Gros & P. Delaroche; 1815-79. — (p. xxxvi).
- Coyppel, Noël*, Fr. P., Paris; 1628-1707.
- , *Ant.*, Fr. P., son of the last; 1661-1722.
- , *Noël-Ant.*, Fr. P., son of Noël C.; 1692-1734.
- Coyzevox, Ant.*, Fr. S., Lyons; 1640-1720. — (p. 108).
- Craesbeke, Joost van, or Craesbeeck*, Flem. P.; 1608-41.
- Craeyer or Crayer, Gasp., de*, P., Antwerp; 1582-1669.
- Cranach, Lucas, the Elder*, Ger. P.; 1472-1553.
- Crauk, Gust.-Ad.-Dés.*, Fr. S., Valenciennes, pup. of Pradier; b. 1827.
- Credi, Lor. di*, Flor. P., 1459-1537.
- Cuijff or Cuyff, Aalbert*, Dutch P., Dordrecht; 1605-91.
- Curson, Paul-Alf. de*, Fr. P., Poitiers, pupil of Drolling & Cabat; b. 1820.
- Daubigny, Ch.-Frang.*, Fr. P., Paris, pupil of Delaroche; 1817-78. — (p. xxxix).
- Dauzats, Adrien*, Fr. P., Bordeaux, pupil of Gué; 1804-1868.
- David, Jacques-Louis*, Fr. P., Paris, pup. of Vien; 1748-1825. — (p. xxxii).
- David d'Angers, Pierre-Jean David*, Fr. S., Angers; 1789-1856. — (p. xxxix).
- David de Bruges, Gérard*, P.; 1450?-1523.
- Debay, J.-B.*, Fr. S., pupil of Chaudet; 1779-1863.
- Debrosse, Jacques*, Fr. A.; d. 1621.
- Decamps, Alex.-Gabr.*, Fr. P., Paris; 1803-60. — (p. xxxvi).
- Delacroix, Ferd.-Vict.-Eug.*, Fr. P., Charenton, pupil of P. Guérin; 1799-1863. — (p. xxxiii).
- Delaplanche, Eug.*, Fr. S., Paris, pupil of Duret; 1836-91.
- Delaroche, Paul*, Fr. P., Paris, pupil of Gros; 1797-1856. — (p. xxxv).
- Delaunay, Jules-Elie*, Fr. P., Nantes, pup. of Flandrin; b. 1823.
- Delorme, Philibert*, Fr. A., Lyons; 1518?-77?
- Denner, Bath.*, Ger. P., Hamburg; 1685-1747.
- Deseine, Louis-Pierre*, Fr. S., Paris; 1759-1822.
- Desjardins, Martin (van den Bogaert)*, S.; 1640-94.
- Desportes, François*, Fr. P.; 1661-1743.
- , *Claude-Frang.*, Fr. P., son and pupil of the last; 1695-1774.
- Detaille, Edouard*, Fr. P., Paris, pup. of Meissonier; b. 1848. — (p. xxxix).
- Devéria, Eug.*, Fr. P., Paris, pup. of Girodet; 1805-65. — (p. xxxvi).
- Diaz de la Peña, Narcisse*, Fr. P., Bordeaux; 1807-76. — (p. xxxvi).
- Dieboldt, Georges*, S., Dijon, pupil of Ramey & Dumont; 1816-61.
- Domenichino, Domenico Zampieri*, Bol. P., pup. of the Carracci; 1531-1641.
- Donatello*, Flor. S.; 1383-1466.
- Doré, Gust.-Paul*, Fr. P. & designer, Strassburg; 1832-83.
- Dosso, Giov. Lutero*, also called *Dosso Dossi*, Ferr. P.; c. 1479-1546.
- Douai, Jean de*, see Bologna.
- Dou or Dow, Ger.*, Dutch P., Leyden; 1598-1675?
- Drevet, Pierre*, two engravers, father and son, of Lyons; 1664-1739, 1697-1739.
- Drolling, Martin*, Fr. P., Alsace 1752-1817.
- Drouais, Fr.-Hub.*, Fr. P., Paris 1727-75.
- Duban, Fél.-Louis-Jacq.*, Fr. A., Paris; 1797-1870.
- Dubois, Paul*, Fr. S., Nogent-sur-Seine; 1829-1833. — (p. xi).
- Dubufe, Louis-Edouard*, Fr. P., Paris, pup. of Delaroche; b. 1818.
- Duc, Jos.-Louis*, Fr. A.; b. 1802-79.

- Ducerceau* or *du Cerceau*, *Jacques Androuet*, Fr. A.; 1540-?.
Ducq or *Duc*, *Jean le*, Dutch P., The Hague; 1636-95.
Dujardin or *du Jardin*, *Karel*, Dutch P., Amsterdam; 1635?-78.
Dumont, *Jacques-Edme*, Fr. S., Paris, pupil of Pajou; 1761-1844. — (p. xl).
Dupré, *Jules*, Fr. P., Nantes; 1812-89. — (xxxix).
Duran, *Carolus*, Fr. P., Lille, pup. of Souchon; b. 1837. — (p. xxxix).
Dürer, *Alb.*, Ger. P., Nuremberg; 1471-1528.
Duret, *Francisque*, Fr. S., Paris, pup. of Bosio; 1804-65. — (p. xxxix).
Duval-le-Camus, *Jules-Alex.*, Fr. P., Paris, pup. of Delaroche & Drolling; 1817-77.
Dyck, *Antonius van*, P., Antwerp, pupil of Rubens; 1599-1641.
Etez, *Ant.*, Fr. S., Paris, pupil of Dupaty & Pradier; 1810-88.
Eyck, *Jan van*, early Flem. P.; 1390?-1441.
Fabrizio, *Gentile*, da, Umbr. P.; c. 1370-1450.
Falguière, *Jean-Alex.-Jos.*, Fr. S., P., Toulouse, pup. of Jouffroy; b. 1831.
Féron, *Firmin-Eloi*, Fr. P., Paris, pupil of Gros; 1802-76.
Ferrari, *Gaudenzio*, Lomb. P.; 1484-1550.
Feti, *Dom.*, Rom. P.; 1589-1624.
Feyen-Perrin, *Aug.*, Fr. P., pupil of L. Cogniet & Yvon; 1829-88.
Fictoor or *Victoor*, *Jan*, Dutch P., pupil of Rembrandt; ca. 1640-62.
Fiesole, *Fra[Angelico] da*, see *Angelico*. — *Mino da*, Flor. S.; 1400-86.
Filipepi, see *Botticelli*.
Flandrin, *Hippolyte*, Fr. P., Lyons, pup. of Ingres, 1809-64. — (p. xxxvi).
 —, *Jean Paul*, Fr. P., Lyons, brother of the last and pupil of Ingres; b. 1811.
Flinck, *Govaert*, Dutch P., Cleve; pupil of Rembrandt; 1616-60.
Fontaine, *Pierre-Franç.-Léon.*, Fr. A., Pontoise; 1762-1853.
Fouquet or *Fouquet*, *Jean*, Fr. P., Tours; c. 1415-77? or 83. — (p. xxix).
Foyatier, *Denis*, Fr. S.; 1793-1863.
Fragonard, *Jean-Hon.*, Fr. P., Grasse, pupil of Boucher, 1732-1806. — (p. xxxi).
 —, *Alex.-Evariste*, Fr. P., son of the last; 1783-1850.
François, *Franç.-Louis*, Fr. P., Plombières, pupil of Corot & Gigoux; b. 1814. — (p. xxxix).
Franchville or *Franqueville*, *Pierre*, Fr. S., Cambrai, pup. of Giov. da Bologna; 1548-1618? — (p. 108).
Francia, *Franç. (Raibolini)*, Bol. P.; 1450-1517.
Franciabigio, *Francesco Bigio*, Flor. P.; 1482-1525.
Franck, *Fr.*, the *Elder*, Flem. P.; 1544-1616.
 —, *Fr.*, the *Younger*, Flem. P., son and pupil of the last; 1580-1642.
Frémiet, *Emm.*, Fr. S., Paris, pupil of Rude; b. 1824.
Fréminet or *Fréménel*, *Martin*, Fr. P., Paris; 1567-1619.
Fromentin, *Eug.*, Fr. P., La Rochelle, pupil of Cabat; 1820-76. — (p. xxxviii).
Fyt, *Jan*, P., Antwerp; 1606-61.
Gabriel, *Jacques-Ange*, Fr. A.; 1710-82.
Gallait, *Louis*, Belg. P., Tournai; 1816-87.
Garofalo, *Benv. Tisio*, Ferr. P.; 1481-1559.
Garnier, *Jean-Louis-Charles*, Fr. A., Paris; b. 1825.
Gatteaux, *Jacques-Edouard*, Fr. S., Paris; b. 1758.
Gellée (Cl.), see *Lorrain*.
Gérard, *Franç.*, Baron, Fr. P., pupil of David; 1770-1837. — (p. xxxii).
Géricault, *Jean-Louis-André-Théod.*, Fr. P., Rouen, pupil of Guérin; 1791-1824. — (p. xxxiii).
Gérôme, *Jean-Léon*, Fr. P., Vesoul; b. 1824. — (p. xxxviii).
Ghirlandajo or *Grillandajo*, *Dom. del*, Flor. P.; 1449-94.
 —, *Ben.*, Flor. P., brother and pupil of the last; 1458-97.
 —, *Ridolfo*, Flor. P., son of Dom. G.; 1483-1561.
Gigoux, *Jean-Franç.*, Fr. P., Besançon; b. 1809.
Giordano, *Luca*, surn. *Fapresto*, Neapol. P., pup. of Ribera and Corotone; c. 1632-1705.
Giorgione, *Giorgio Barbarella*, Ven. P., pup. of Bellini; 1478-1511.
Girardon, *Franç.*, Fr. S., Troyes; 1628-1715.
Giraud, *Pierre-Franç.-Eug.*, Fr. P., Paris, pupil of Hersent & Richomme; 1806-81.
 —, *Séb.-Ch.*, Fr. P., Paris; b. 1819.
 —, *Victor*, Fr. P., Paris, pup. of Picot & Eug. G. (his father); 1835?-71.
Girodet-Trioson (*Anne-Louis Gir. de Roucy-Trioson*), Fr. P., Montargis, pup. of David; 1764-1824. — (p. xxxiii).
Glaize, *Aug.-Barth.*, Fr. P., Montpellier, pup. of Devéria; b. 1812.
Gleyre, *Charles-Gabriel*, Fr. P., Che-

- villy (Switzerland), pnp. of Hersent; 1807-1874. — (p. xxxvii).
- Gossaert*, see *Mabuse*.
- Goujon, Jean*, Fr. S. & A., Paris; 1520?-72? — (p. 106).
- Goyen, Jan van*, Dutch P., Leyden; 1595-1656.
- Gozzoli, Benozzo*, Flor. P.; 1420-98.
- Greuze, J.-B.*, Fr. P.; Tournus; 1725-1805. — (p. xxxii).
- Gros, Ant.-Jean*, Baron, Fr. P., Paris, pupil of David; 1771-1835. — (p. xxxii).
- Guadin, Théod.*, Fr. P., Paris, pupil of Girodet; 1802-80.
- Guercino, Il (Giov. Franc. Barbieri)*, Bol. P.; 1590-1661.
- Guérin, Pierre-Narc.*, Baron, Fr. P., Paris, pupil of J.-B. Regnault; 1774-1833. — (p. xxxii).
- Guido Reni*, Ital. P.; 1575-1642.
- Guillain, Simon*, Fr. S. & engraver, Paris; 1581 or 92-1679. — (p. 107).
- Guillaume, Claude-J.-B.-Eug.*, Fr. S., Montbard, pupil of Pradier; b. 1822. — (p. xl).
- Guillaumet, Gust.*, Fr. P., Paris, pup. of Picot and Barrias; 1840-87.
- Gumery, Ch.-Alph.*, Fr. S., Paris; 1827-71.
- Hals, Frans*, Flem. P., Malines; 1584-1666.
- Hamon, Jean-Louis*, Fr. P., St. Loup (Brittany), pup. of Delaroche & Gleyre; 1821-74. — (p. xxxviii).
- Harpignies, Henri*, Fr. P., Valenciennes, pup. of Achard; b. 1819.
- Hébert, Ern.-Ant.-Aug.*, Fr. P., Grenoble, pupil of Delaroche; b. 1817. — (p. xxxvii).
- Heem, Jan Davidz de*, P., Utrecht; 1600(?) - 1674.
- Heim, Franc.-Jos.*, Fr. P., Belfort, pupil of Hersent; 1787-1865.
- Helst, Barth. van der*, Dutch P., Haarlem; 1613(?) - 70.
- Henner, J.-J.*, Fr. P., Alsace, pupil of Drolling & Picot; b. 1829.
- Herrera, Franc.*, the Elder, Span. P.; 1576-1656.
- Hersent, Louis*, Fr. P., Paris, pnp. of J.-B. Regnault; 1777-1860.
- Hesse, Nic.-Aug.*, Fr. P., Paris, pupil of Gros; 1795-1869.
- , *Alex.-J.-B.*, Fr. P., Paris, pupil of Gros; 1806-79.
- Heyden (Heijde)*, *J. van der*, Dutch P., Gorkum; 1637-1712.
- Hiolle, Ern.-Eug.*, Fr. S., Valenciennes, pnp. of Jouffroy; 1834-86.
- Hittorf, Jac.-Ign.*, A., Cologne, pupil of Fr.-Jos. Bellanger in Paris; 1793-1867.
- Hobbema, Meindert*, Dutch P.; 1638-1709.
- Holbein, Hans, the Younger*, Ger. P., Augsburg; 1497-1543.
- Hondecoeter, Melchior d'*, Dutch P., Utrecht; 1636-95.
- Honthorst, Ger. van*, Dutch P.; 1590-1666.
- Hooch or Hoogh, Pieter de*, Dutch P.; 1632-81.
- Houdon, Jean-Ant.*, Fr. S., Versailles; 1741-1823. — (p. 109).
- Huet, Jean-Bapt.*, Fr. P., pupil of Leprince; 1745-1811.
- , *Paul*, Fr. P., Paris, pupil of Gnérin and Gros; 1804-69.
- Ingres, J.-A.-Dom.*, Fr. P., Montauban, pupil of David; 1780-1867. — (p. xxxv).
- Isabey, Louis-Gab.-Eug.*, Fr. P., Paris, pupil of his father, J.-B. Isabey, the designer; 1804-86.
- Jacquemart, Mlle. Nélie*, Fr. P., Paris, pupil of L. Cogniet; b. 1845. — (p. xxxvii).
- Jehannet*, see *Clouet*.
- Jobbé-Duval, Armand-Marie-Félix*, Fr. P., pup. of P. Delaroche; 1821-89.
- Jordaens, Jac.*, P., Antwerp; 1593-1678.
- Jouffroy, Franc.*, Fr. S., Dijon, pupil of Ramey the Younger; 1806-82. — (p. xxxix).
- Jouvenet, Jean*, Fr. P., Rouen; 1644-1717. — (p. xxx).
- Juste de Tours, Jean*, Fr. S.; d. ca. 1535.
- Kauffmann, Angelica*, Ger. P., Coire 1741-1807.
- Keller*, two brothers of Zürich, sculptors at the court of Louis XIV.
- Labrousse, Pierre-Franc.-Henri*, Fr. A.; 1801-75.
- Lafosse or La Fosse, Ch. de*, Fr. P., Paris; 1636-1716.
- Langlois, Jean-Ch.*, surn. *Le Colonel*, Fr. P., pupil of Girodet, Gros, & H. Vernet; 1789-1870.
- Largillière, Nic.*, Fr. P., Paris; 1656-1746. — (p. xxxi).
- Larivière, Phil.-Ch. de*, Fr. P., Paris, pupil of Guérin, Girodet, & Gros; 1798-1876.
- Lassus, J.-B.-Ant.*, Fr. A., Paris; 1807-57.
- Laurens, Jean-Paul*, Fr. P.; b. 1838.
- Le Brun or Lebrun, Ch.*, Fr. P., Paris, pupil of S. Vouet; 1619-90. — (p. xxx).
- , *Elise-Louise Vigée*, Fr. P., Paris; 1755-1842.
- Lefebvre, Jules-Jos.*, Fr. P.; b. 1836.
- Lefuel, Hector Martin*, Fr. A., Versailles; 1810-81.

- Lehmann, Ch.-Ern.-Rod.-Henri*, P., Kiel, pupil of Ingres; 1814-82.
- Leleux, Adolphe*, Fr. P., Paris; b. 1812. — (p. xxxviii).
- , *Armand*, Fr. P., Paris, brother of the last and pup. of Ingres; b. 1818.
- Lemaire, Phil.-Henri*, Fr. S., Valenciennes, pupil of Cartellier; 1798-1880.
- Lemercier, Jacques*, Fr. A., Pontoise; 1590-1660.
- Lenepveu, Jules-Eug.*, Fr. P., Angers, pupil of Picot; b. 1819.
- Le Nôtre* or *Lenôtre, André*, A. and landscape-gardener, Paris; 1613-1700.
- Lepère, J.-B.*, Fr. A., Paris; 1762-1844.
- Leprince, A.-Xavier*, Fr. P., Paris; 1799-1826.
- Lescot, Pierre*, Fr. A., Paris; 1510-71.
- Le Sueur*, or *Lesueur Eustache*, Fr. P., pup. of Vouet; 1617-55. — (p. xxx).
- Lethière, Guill.-Guillon*, Fr. P., pupil of Doyen; 1760-1832.
- Leveau, Louis*, Fr. A.; 1612-70.
- Léry, Emile*, Fr. P., Paris, pup. of A. de Pujol & Picot; b. 1826. — (p. xxxviii).
- Libri, Girolamo dai*, Ven. P.; 1474-1556.
- Lievens* or *Livens, Jan*, Dutch P., Leyden; 1607-72 (?).
- Lippi, Fra Filippo*, Flor. P.; 1412-69.
- Loison, Pierre*, Fr. S., pupil of David d'Angers; b. 1821.
- Loo, van*, see Vanloo.
- Lorrain, Claude Gellée*, surn. *Cl. le L.*, Fr. P., studied in Italy; 1600-82. — (p. xxx).
- Lotto, Lor.*, Ven. P.; 1480-1554 (?).
- Luini, Bern.*, Mil. P.; 1470(?) - 1530(?).
- Mabuse, Jan van* or *Gossaert*, Flem. P., Maubeuge; 1470?-1532.
- Maes*, or *Maas, Aert* or *Arnold van*, Flem. P., Gouda, pupil of Teniers; 1620-1634.
- , *Nic.*, Dutch P., Dordrecht; 1632-1693.
- Maillet, Jacques-Léon.*, Fr. S., Paris, pupil of Pradier; b. 1823.
- Mainardi, Bastiano*, Flor. P.; d. 1515?
- Maindrone, Et.-Hipp.*, Fr. S., pup. of David d'Angers; 1801-81. — (p. xl).
- Majano, Ben. da*, Flor. A. & S.; 1442-97.
- Mansard* or *Mansart, Franç.*, Fr. A., Paris; 1598-1666.
- , *Jules-Hardouin*, Fr. A., Paris, nephew of the last; 1645-1708.
- Mantegna, Andrea*, Ital. P., Padua; 1431-1506.
- Marcellin, Jean-Esprit*, Fr. S., Gap, pup. of Rude; 1821-1884.
- Marchal, Ch.-Franç.*, Fr. P., Paris, pupil of Drolling; 1825-77.
- Marilhat, Prosper*, Fr. P., Auvergne, pupil of Roqueplan; 1811-1847.
- Marochetti, Ch.*, S., Turin, pupil of Bosio; 1805-67.
- Marsy, Balh. & Gasp.*, two Fr. sculptors of Cambrai; 1624-74 & 1628-81.
- Matout, Louis*, Fr. P., Charleville; 1813-88.
- Matsys* or *Massys, Quinten* or *Quentin*, Antwerp P.; 1466-1531.
- Meer, Jan van der, van Haarlem*, Dutch P.; 1628-91.
- , *J. van der, of Delft*, Dutch P.; 1632-96?
- Meissomier, Jean-Louis-Ern.*, Fr. P., Lyons; 1815-91. — (p. xxxvii).
- , *Juste-Aurèle*, A., S., P. & designer; b. at Turin in 1695, d. at Paris in 1750.
- Memming, Hans*, early Flem. P.; ca. 1430-95.
- Mercié, Antonin*, Fr. S., Toulouse, pupil of Jouffroy & Falguière; b. 1845. — (p. xl).
- Messina, Antonello da*, Neapol. P.; 1410 (?) - 93 (?).
- Metsu, Gabriel*, Dutch P., Leyden; 1630-67 (?).
- Meulen, Ant.-Fr. van der*, Brussels, P. of battle-scenes to Louis XIV.; 1634-90.
- Meynier, Ch.*, Fr. P., Paris, pupil of Vincent; 1768-1832.
- Michael Angelo Buonarroti*, A., S., & P., Florence; 1475-1564.
- Mieris, Frans van, the Elder*, Dutch P., Leyden; 1635-81.
- , *Willem van*, Dutch P., Leyden, pupil of the last; 1662-1747.
- Mignard, Pierre*, Fr. P., Troyes; 1610-95. — (p. xxxi).
- Millet, Jean-Franç.*, Fr. P., pup. of P. Delaroche; 1815-75. — (p. xxxviii).
- , *Aimé*, Fr. S., Paris, pupil of David d'Angers; b. 1816.
- Mino da Fiesole*, see Fiesole.
- Montagna, Bartolommeo*, Ven. P.; d. 1523.
- Montereau, Pierre de*, Fr. A.; d. 1266.
- Mor, Moor, or Moro, Antonis de*, Dutch P., Utrecht; 1512-1576/8.
- Moreau, Gustave*, Fr. P., Paris; pup. of Picot; b. 1826. — (p. xxxviii).
- , *Louis-Gabriel*, Fr. P., Paris; 1740-1806.
- , *Mathurin*, Fr. S., Dijon, pupil of Ramey & Dumont; b. 1822. — (p. xl).
- Moretto da Brescia (Aless. Bonvicino)*, P., Brescia; 1498-1555.

- Mollez, Victor-Louis*, Fr. P., Lille, pupil of Picot; b. 1809.
- Murillo, Bartolomé-Esteban*, Span. P.; 1616-82.
- Nanteuil (Ch. - Franç. - Leboeuf)*, Fr. S., Paris, pupil of Cartellier; 1792-1865.
- , *Robert*, engraver, Reims; 1630-1698.
- Natoire, Ch.-Jos.*, Fr. P., Nîmes, pupil of Lemoine; 1700-77.
- Neer, Aart van der*, Dutch P., Amsterdam; 1619 (?) - 82 (?).
- Neuville, Alphonse de*, Fr. P., St-Omer, pup. of Picot; 1835-85. — (p. xxxix).
- Oggionno, Marco da*, Lomb. P., pup. of Leon. da Vinci; 1470 (?) - 1540 (?).
- Ostade, Adr. van*, Dutch P.; 1610-85.
- , *Izaak van*, Dutch P., brother and pupil of the last; 1621-49.
- Ottin, Aug.-Louis-Marie*, Fr. S., Paris, pup. of David d'Angers; 1811-90.
- Oudry, J. B.*, Fr. P., Paris; 1686-1755.
- Pagnest, A.-L.-Claude*, Fr. P.; 1790-1819.
- Pajou, Augustin*, Fr. S., Paris, pupil of Lemoine; 1730-1809.
- Palissy, Bern.*, potter; 1510? - 89. — (p. 143).
- Palma Vecchio, Jacopo*, Ven. P.; 1470-1528.
- Panini, Giov.-Paolo*, Lomb. P.; 1695-1768.
- Papety, Dom.-Louis-Féréol*, Fr. P., Marseilles; 1815-49.
- Percier, Ch.*, Fr. A., Paris; 1764-1838.
- Perraud, Jean-Jos.*, Fr. S., pupil of Ramey & Dumont; 1821-76. — (p. xi).
- Perrault, Claude*, Fr. A., Paris; 1613-88.
- Perugino (Pietro Vannucci)*, Umbrian P.; 1446-1521.
- Philippoteaux, Henri-Emm.-Félix*, Fr. P., Paris; 1815-1884.
- Picot, Franç.-Ed.*, Fr. P., Paris, pupil of Vincent; 1786-1868.
- Pigalle, J.-B.*, Fr. S., Paris; 1714-85. — (p. 109).
- Pilon, Germain*, Fr. S., 1515? - 90? — (p. 106).
- Pils, Isid.-Adr.-Aug.*, Fr. P., Paris, pupil of Picot; 1813-75.
- Pinturicchio (Bernardino Betti)*, Umbrian P.; 1454-1513.
- Piombo, Sebast. del*, Ven. P.; 1485-1547.
- Pippi*, see Romano.
- Ponce or Ponzio, Paolo*, Flor. S. of the 16th cent. — (p. 106).
- Pontormo, Jacopo Carrucci da*, Flor. P., pup. of A. del Sarto; 1494-1557.
- Polter, Paul*, Dutch P.; 1625-54.
- Pourbus or Porbus, Frans, the Younger*, Antwerp P.; 1570-1622.
- Poussin, Gaspard*, properly *G. Dughet*, Fr. P., Rome, nephew and pup. of the following; 1613-75. — (p. xxx).
- , *Nicolas*, Fr. P., Andelys, Normandy; 1594-1665. — (p. xxx).
- Pradier, J.-J.*, Fr. S., Geneva, pup. of Lemot; 1786-1852. — (p. xxxix).
- Préault, Ant.-Augustin*, Fr. S., Paris; 1809-79.
- Prieur, Barth.*, Fr. S.; d. 1611. — (p. 106).
- Primaticcio, Franc.*, Bol. P.; 1504-70.
- Protais, Paul-Alex.*, Fr. P., Paris; 1826-90.
- Prudhon, Pierre-Paul*, Fr. P., Cluny; 1758-1823. — (p. xxxii).
- Puget, Pierre*, Fr. S., Marseilles; 1622-94. — (p. 107).
- Pujol, Alex.-Denis-Abel*, Fr. P., Valenciennes, pupil of David; 1785-1861.
- Puvis de Chavannes, Pierre*, Fr. P., Lyons, pupil of H. Scheffer & Couture; b. 1824.
- Raffet, Denis*, Fr. P., Paris, pupil of Charlet & Gros; 1804-60. — (p. xxxix).
- Raibolini*, see Francia.
- Ramey, Claude*, Fr. S., Dijon; 1754-1838.
- Raphael (Raffaello Santi da Urbino)*, Ital. P., pupil of Perugino; 1483-1520.
- Regnault, J.-B.*, Fr. P., Paris; 1754-1829.
- , *Henri*, Fr. P., Paris, pupil of Cabanel; 1843-71. — (p. xxxix).
- Rembrandt van Ryn*, Dutch P., Leyden; 1607-69.
- Reni*, see Guido.
- Ribera, José de*, surn. *Spagnoletto*, Span.-Neap. P.; 1588-1656.
- Ribot, Augustin-Théodule*, Fr. P., Breteuil, pupil of Glaize; b. 1823.
- Ricard, Louis-Gust.*, Fr. P., Marseilles; 1824-73. — (p. xxxvii).
- Riccio*, see Brioso.
- Richier, Ligier*, Fr. S., St. Mihiel, pup. of Michael Angelo; 16th cent.
- Rigaud, Hyacinthe*, Fr. P., Perpignan; 1659-1743. — (p. xxxi).
- Robbia, Luca, Andr., & Giov. della*, three Flor. sculptors of the 15-16th centuries.
- Robert, Hubert*, Fr. P.; 1733-1808.
- , *Louis-Léop.*, P., La Chaux-de-Fonds, pupil of Gérard & David; 1794-1835.
- Robert-Fleury, Jos.-Nic.*, Fr. P., Paris, pup. of Girodet, Gros, & H. Vernet; 1797-1890. — (p. xxxvi).

- Robert-Fleury*, Tony, Fr. P., Paris, son of the last & pupil of Delaroche; b. 1837.
- Robusti*, see Tintoretto.
- Romano*, Giulio (Pippi), Rom. P.; 1492-1546.
- Rosa*, Salvatore, Neap. P.; 1615-73.
- Rosso*, Giovanbattista, Flor. P.; 1496-1541.
- Rottenhammer*, J., Ger. P., Munich; 1564-1623.
- Rousseau*, Théodore, Fr. P., Paris; 1812-67. — (p. xxxix).
- Rubens*, Peter Paul, Antwerp P.; 1577-1640.
- Rude*, Franc., Fr. S., Dijon, pupil of Cartellier; 1734-1855. — (p. xxxix).
- Ruisdael* or *Ruysdael*, Jacob van, Dutch P., Haarlem; c. 1625-82.
- Ruysdael*, Salomon van, Dutch P.; Haarlem; d. 1670.
- Saint-Jean*, Simon, Fr. P., Lyons; 1808-60.
- Santerre*, J. B., Fr. P., pupil of Bon Boulogne; 1650-1717.
- Santi*, see Raphael.
- Sarto*, Andrea del (Andrea Vannucchi), Flor. P.; 1487-1531.
- Sassoferrato*, Giov.-Batt. Salvi da, Rom. P.; 1605-85.
- Scheffer*, Ary, P., Dordrecht, pupil of Guérin; 1795-1858. — (p. xxxiv).
- , Henri, P., brother of the last and pupil of Guérin; 1798-1862.
- Schnetz*, Jean-Victor, Fr. P., Versailles, pupil of David, Regnault, Gérard, & Gros; 1787-1870.
- Sesto*, Ces. da, P., Milan, pupil of Leon. da Vinci; d. after 1524.
- Seurre*, Ch.-Marie-Em., Fr. S., Paris, pupil of Cartellier; 1798-1858.
- Sigalon*, Xavier, Fr. P., Uzès, pupil of P. Guérin; 1790-1837.
- Signal*, Em., Fr. P., pupil of Gros; b. 1804.
- Signorelli*, Luca, Tuscan P.; 1444-1523.
- Simart*, Pierre-Ch., Fr. S., Troyes, pup. of Dupaty & Pradier; 1807-57.
- Slingelandt*, P. van, Dutch P., Leyden, pupil of Don; 1640-91.
- Snyders*, Frans, Antwerp P., pupil of P. Brueghel and of H. van Balen; 1579-1657.
- Solario*, Andrea, Lomb. P., pupil of Leon. da Vinci; c. 1448-1530.
- Soufflot*, Jacques-Germain, Fr. A.; 1714-81.
- Spada*, Lionello, Bol. P.; 1656-1622.
- Spagna*, Giov. di Pietro, surn. lo Spagna, Span.-Umbr. P.; d. 1529?
- Spagnoletto*, see Ribera.
- Steen*, Jan, Dutch P., Leyden; 1636-89.
- Steuben*, Ch., P., Mannheim; 1791-1856. — (p. xxxvi).
- Subleyras*, Pierre, Fr. P., Uzès; 1699-1749.
- Sueur*, Le, see Le Sueur.
- Teniers*, David, the Elder, Antwerp P., pupil of Rubens; 1582-1649.
- , David, the Younger, Antwerp P., son & pupil of the last; 1610-94.
- Ter Borch* or *Terburg*, Ger., Dutch P., Zwolle; 1608-81.
- Thulden*, Th. van, Flem. P., pupil of Rubens; 1607-1686.
- Timbal*, Louis-Ch., Fr. P., Paris, pupil of Drolling & Signal; 1822-80.
- Tintoretto*, Jacopo Robusti, Ven. P., pupil of Titian; 1512-94.
- Titian* (Tiziano Vecellio da Cadore), Ven. P.; 1477-1576.
- Tocqué*, Louis, Fr. P., 1696-1772.
- Triqueti*, Henri, Baron de, Fr. S.; 1802-74.
- Troy*, J. F. de, Fr. P., Paris; 1679-1752.
- Troyon*, Constant, Fr. P., Sèvres; 1810-65. — (p. xxxix).
- Tuby* or *Tubi*, J.-B., S.; 1630-1700.
- Uccello*, Paolo, Flor. P.; 1397-1475.
- Valentin*, surn. Jean de Boullongne, Fr. P., Coulommiers; 1600-34.
- Vanloo* or *van Loo*, Jacob, Dutch P.; 1614-70.
- , Jean-Baptiste, Fr. P., Aix; 1681-1745.
- , Ch.-André, Fr. P., Nice, brother and pupil of the last; 1706-1765.
- , Louis-Michel, Fr. P., Toulon, son and pupil of Jean-Baptiste; 1707-1721.
- Vannucchi*, see Sarto.
- Vannucci*, see Perugino.
- Vasari*, Giorgio, Flor. P. & art-historian; 1511-74.
- Vecelli*, see Titian.
- Vela*, Vinc., Ital. S.; b. 1822.
- Velazquez*, Don Diego Rodriguez de Sylva y V., Span. P.; 1599-1660.
- Velde*, Adr. van de, Dutch P., Amsterdam; 1639-72.
- , Willem van de, the Younger, P., Amsterdam; 1633-1707.
- Ver Meer*, see Meer.
- Vernet*, Claude-Jos., Fr. P., Avignon; 1714-89.
- , Ant.-Ch.-Hor., surn. Carle, Fr. P., son of the last; 1758-1835.
- , Em.-Jean-Horace, Fr. P., son of Carle; 1789-1863. — (p. xxxiv).
- Veronese*, Paolo (P. Caliari), Ven. P.; 1528-1588.
- Victoor*, see Pictoor.
- Vien*, Jos.-Marie, Fr. P., Montpellier; 1716-1809.

- Vinchon, Aug.-J.-B.*, Fr. P., Paris; 1789-1855.
Vinci, Leonardo da, Flor. P.; 1452-1519.
Viollet-le-Duc, Eug.-Emm., Fr. A., Paris; 1814-79.
Visconti, Louis, A., pupil of Percier; 1791-1854.
Villon, Ant., Fr. P., Lyons; b. 1833.
Volterra, Daniele Ricciarelli da, Flor. P.; 1509-66.
Vouet, Sim., Fr. P., Paris; 1590-1649. — (p. xxx).
Watteau, Ant., Fr. P., Valenciennes; 1684-1721. — (p. xxxi).
Weenix, J.-B., Dutch P., Amsterdam; 1621-60.
Weyden, Rog. van der, Flem. P., Tournai; c. 1399-1464.
Wouverman, Phil., Dutch P., Haarlem; 1619-68.
 —, *Pieter*, Dutch P., brother and pupil of the last; 1623-83.
Wynants, Jan, Dutch P.; ca. 1641-79.
Yvon, Ad., Fr. P., Eschweiler, pupil of P. Delaroche; b. 1817.
Zampieri, see Domenichino.
Ziegler, Claude-Louis, Fr. P., Langres, pupil of Ingres; 1804-1856.
Ziem, Félix, Fr. P., Beaune; b. 1821.
Zurbaran, Francisco, Span. P., 1589-1662.
-

INDEX.

- Albaye anx Bois 337.
 — de Port-Royal 307.
 — du Val 345.
 Abbeville 354.
 Achères 318. 342. 365.
 Ste. Adresse 367.
 Ailly-sur-Noye 356.
 — sur-Somme 354.
 Alfort 327.
 Alfortville 214. 327.
 Amiens 354.
 Andilly 326.
 Andrésy 342.
 Antony 338.
 Apremont 334.
 Arcueil 336.
 Argenteuil 326.
 Arques 359.
 —, the 358.
 Arve, the 354. 356.
 Asnières 285. 327.
 Aubervilliers-la-Cour-
 neuve 350.
 Auffargis 307.
 Auger-St. Vincent 350.
 Aulnay 337.
 Aulnay-lès-Bondy 350.
 Auteuil 162. 47. Appx.,
 p. 25.
 Auvers 343.
 Avon 331.
 Bagatelle 159.
 Bagneux 335.
 Bailly 307.
 Barbery 350.
 Barbison 335.
 Barentin 368.
 Bas-Bréau 334.
 Beaumont 344.
 Beauregard (chât.) 311.
 Bel-Air, see Appx., p. 25.
 Belleville, 46. 47. Appx.,
 p. 25.
 Bellevue 287. 312.
 Belloy 345.
 Berck 353.
 Bercy-Ceinture 327.
 Berny 337. 338.
 Bessancourt 345.
 Béthune 354.
 Beuzeville 368.
 Bevillers (chât.) 340.
 Bezons 313. 341.
 Bicêtre 270. 243.
 —, Fort 336. 243.
 Bièvre 338. 339.
 —, the 268. 338.
 Billancourt 237. 309.
 Bizy (chât.) 365.
 Bois-de-Colombes 327.
 Bois-le-Roi 328.
 Boissy-St. Léger 215.
 Bolbec 368.
 Bondy 350.
 Bonneuil 215.
 Bonnières 365.
 Boran 349.
 Bougival 314. 311.
 Bouille, La 364.
 Boullay-les-Troux 339.
 Boulogne-sur-Mer 351.
 Boulogne-sur-Seine 309.
 Bourg-la-Reine 337.
 Bourget, Le 350.
 Boves 356.
 Bréanté 368.
 Breteuil 356.
 St. Brice 345.
 Briche, Fort de la, 346.
 325.
 Brie, La 327.
 Brie-Comte-Robert 215.
 Brunoy 327.
 Bry-sur-Marne 213.
 Buc, Aqueduct of 338.
 Butte-Pinçon 346.
 Buzanval 311.
 Calais 357.
 Canaples 354.
 Carnelle, Forest of 344.
 Carrières, Les 214.
 Caudebec 368.
 Caux, Pays de 368.
 Cayeux 354.
 Celle-St. Cloud, La 311.
 Cernay-la-Ville 341.
 Cesson 327.
 Champagne 344.
 Champigny 215.
 Champian 338.
 Champlâtreux 345.
 Chantilly 347.
 Charenton 214. 327.
 Charonne 46. 47. Appx.,
 p. 25.
 Châteauneuf 364.
 Châtenay 337.
 Châtillon 335.
 Chatou 314.
 Chaville 287.
 Chennevières 215.
 Chevilly 337.
 Chevreuse 339. 307.
 Clamart 286. 313.
 —, Bois de 287. 313.
 Clères 368.
 Clermont-de-l'Oise 356.
 Clichy 201. 235. 365.
 Appx., p. 25.
 St. Cloud 309. 286.
 Colombes 327. 365.
 Combs-la-Ville 273.
 Commelle, Etangs de 348.
 Conchil-le-Temple 353.
 Conflans 214. 327. 342.
 — St. Honorine 342.
 Cormeilles 326.
 Cormeilles-en-Parisis
 327.
 Courbevoie 283. 156.
 Courcelles 364. Appx.,
 p. 25.
 Croy 346.
 Creil 348. 356.
 Crépy-en-Valois 350.
 Créteil 215.
 Croissy 314.
 St. Cyr 307.
 Dammartin 350.
 Dampierre 340. 307.
 Daumesnil, Lac 214:
 Deauville 367.
 St. Denis 318.
 —, Canal 186.
 —, Ile 324.
 Deuil 345.
 Dieppe 358.
 Domont 345.
 Dormoir, the 334.
 Dover 356.

- Drancy 350.
 Dreuil 354.
 Ecouen 345.
 Elbeuf 364.
 Empereur, Fort de l' 334.
 Enghien-les-Bains 325.
 Epiais-Rhus 313.
 Epinay 325.
 Bragny-Neuville 342.
 Ermenonville 350.
 Ermont 326. 346.
 Esneval 368.
 Etang-la-Ville (L'), 312.
 Etaples 353.
 Eure, the 364.
 Ezanville 345.
 Faloise, La 356.
 St. Firmin 349.
 Fleury 287. 313.
 Folkestone 351.
 Folleville 356.
 Fontainebleau 328.
 Fontenay-aux-Roses 336.
 337.
 — sons-Bois 213. 215.
 Franchard 334.
 Franconville 341. 344.
 Gaillard 364.
 Gaillon 364.
 Garches 311.
 Garenne, La 313. 341.
 Garnes 340.
 Gennevilliers 61. 321.
 Gentilly, see Appx., p. 25.
 St. Germain-en-Laye 315.
 St. Germain-Grande-Ceinture 312. 318.
 Gif 339.
 Girard, Monts 334.
 Gonesse 346.
 Goussainville 346.
 Grange, Chât. de la 215.
 Gravelle 214.
 Gravelle 368.
 Grenelle 47; see Appx., p. 25.
 Gris-Nez, Cap 357.
 Gros-Bois, Chât. de 215.
 Groslay 345.
 Hangest 354.
 Harfleur 368.
 Haudouin, Le 350.
 Hantes-Bruyères 337.
 Havre, Le 366.
 Herblay 327. 340.
 Hesdigneul 353.
 Houilles 341.
 Ingouville 367.
 Issy 286. Appx., p. 25.
 Ivry 270.
 Javel 309.
 Joinville-le-Pont 213. 215.
 St. Josse 353.
 Jouy-en-Josas 335.
 St. Just-en-Chaussée 356.
 Juvisy 338.
 La Bouille 364.
 — Brie 327.
 — Celle-St. Cloud 311.
 — Chapelle 318. Appx., p. 25.
 — Faloise 356.
 — Frette 327.
 — Garenne 313. 341.
 — Glacière, see Appx., p. 25.
 — Machine 314.
 — Maison-Blanche, see Appx., p. 25.
 — Malmaison 314.
 — Marche 311.
 — Muette 162.
 — Plaine-St. Denis 350.
 — Plaine-Voyageurs 315.
 — Rapée-Bercy, see Appx., p. 25.
 — Tour (chât.) 326. 341.
 — Varenne-Chennevières 215.
 — Verrière 307.
 Lanterne de Démosthène 311.
 Le Bourget 325.
 — Bourget-Drancy 350.
 — Crotoy 354.
 — Haudouin 350.
 — Havre 365.
 — Jouet d'Eau 307.
 — Landy 318.
 — Pecq 315.
 — Perray 307.
 — Tréport 354.
 — Val 313.
 — Vésinet 314.
 Les Andelys 364.
 — Batignolles 47. 202.
 Appx., p. 25.
 — Essarts-le-Roi 307.
 — Moulineaux 309. 313.
 L'Etang-la-Ville 312.
 St. Len-d'Esserent 349.
 St. Len-Taverny 346.
 Levallois 285. Appx., p. 25.
 Lézarde, the 368.
 L'Hay 337.
 Liancourt 356.
 Lieusaint 327.
 Lillebonne 368.
 Limours 339.
 L'Isle Adam 343.
 Loges, Les 313.
 Longchamp 159.
 Longjumeau 338.
 Longpré 354.
 Longueau 356.
 Louveciennes 311.
 Louviers 364.
 Louvres 346.
 Luzarches 345.
 Machine (La), 314.
 Maffliers 344.
 Maisons-Alfort 327.
 Maisons-Laffitte 341. 318.
 365.
 Malabry 338.
 Malakoff 286. 335.
 Malaunay 359. 368.
 Malmaison 314.
 St. Mandé 211. 214.
 Mantes 365.
 Mareil 307. 312.
 Marlotte 335.
 Marly-le-Roi 311. 307.
 —, Forest of 312.
 Marne, the 327.
 Marquise 357.
 St. Martin 345.
 Massy 338.
 Massy-Palaiseau 338.
 Maubuisson, Château de 343.
 St. Maur 215.
 —, Canal de 213.
 St. Maurice 214.
 Mauvière (chât.) 340.
 St. Maximin 349.
 Measnres xxv.
 Melun 327.
 Ménilmontant 46. 47.
 Appx., p. 25.
 Mériel 315.
 Méry 343. 345.
 Meudon 318. 287.
 Minimes, Lac des 213.
 Mitry-Claye 350.
 Money xii.
 Montataire 348.
 Montgeron 327.
 Montigny 327. 335. 341.
 Montivilliers 368.
 Montlignon 326.
 Montmagny 345.
 Montmorency 325.
 Montretout 286. 311.
 Montreuil 210.
 Montrouge 243. 47. Appx., p. 25.
 Montsoult 314.

Moret 335.
 Mortefontaine 346.
 Motteville 368.
 Moulineaux, Les 309. 313.
 Muette, Chât. de la 162.

Nanterre 314.
 Nanteuil 350.
 Nesles 343.
 Neufchâteau 353.
 Neuilly 156.
 Newhaven 358.
 Nogent-sur-Marne 213.
 215.
 Nointel 344.
 Nointot 368.
 Noisy-le-Roi 307.
 Noisy-le-Sec 325.
 St. Nom-la-Bertache 312.
 Nonette, the 348.
 Nord-Ceinture 318.
 Nord, Fort du 346.
 Noye, the 356.
 Noyelles 353.

Oise, the 341. 342.
 Oissel 364.
 Orgemont 326.
 Orly 338.
 Ormoy 350.
 Orry-Coye 346.
 Orry-la-Ville 346.
 Orsay 339.
 St. Ouen 201, and Appx.,
 p. 25.
 St. Ouen l'Aumône 343.
 Ourcq, Canal de l' 186.

Palaiseau 339.
 Parc de St. Maur 215.
 Paris 1.
 Abattoirs 188.
 Académie Française
 244.
 Agricultural Show 154.
 Alcazar d'Été 33.
 American Chapels 44.
 St. Antoine, Faubourg
 47. 67.
 Aquarium 165.
 Arc de Triomphe du
 Carrousel 149.
 — de l'Étoile 155.
 Archives Nationales
 204.
 Arènes de Lutèce.
 Arrival 1.
 Arrondissements 47.
 Artesian Well of Gre-
 nelle 280.
 — of Passy 162.
 Arts et Métiers, Con-
 servatoire des 173.

Paris:
 Association internat.
 des Professeurs 42.
 Assumption, Ch. of the
 85.
 Aubervilliers 188.
 Auction-rooms 75. 195.
 Augustin, Egl. St. 203.
 Autenil 162. Appx.,
 p. 25.
 Avenue d'Antin 155.
 — du Bois de Boulogne
 156. 157.
 — Carnot 156.
 — des Champs-Élysées
 153. 156.
 — de Clichy 201.
 — Daumesnil 214.
 — Friedland 156.
 — des Gobelins 268.
 — de la Grande Ar-
 mée 156. 157.
 — de Montsouris 242.
 — Henri Martin 163.
 — Hoche 156.
 — d'Iéna 156.
 — Kléber 156. 163.
 — Macmahon 156.
 — Malakoff 163.
 — Marceau 156.
 — Montaigne 155. 168.
 — de l'Observatoire 260.
 — de l'Opéra 76.
 — d'Orléans 242.
 — St. Ouen 201.
 — de Paris 287.
 — Parmentier 176.
 — de la République 71.
 184.
 — du Trocadéro 163.
 — Victor Hugo 156.
 — Victoria 60.
 — de Villiers 203.
 — de Vincennes, see
 Appx., p. 25.
 — de Wagram 156.
 Bagatelle, La 159.
 Bal Bullier 34. 260.
 Balls 33.
 Banks 45.
 Banque de France 169.
 Bardo 243.
 Barracks 64. 68. 71. 169.
 Bassin de la Villette
 186. 67.
 Bastille, Place de la 65.
 —, Reproduction of
 the 284.
 Baths 42.
 Batignolles 47. 202.
 Bazaars 38.
 Beaux-Arts, Palais des
 246.

Paris:
 Beer Houses 16.
 Bel-Air, see Appx., p. 25.
 Belleville 46. 187.
 Appx., p. 25.
 Bercy 47.
 St. Bernard 189.
 Bibliothèque Admin-
 istrative 63.
 — Nationale 195.
 — de l'Arsenal 68.
 — Ste. Geneviève 239.
 — Mazarine 245.
 — de la Ville 209.
 Bicêtre 243. 270.
 Bird-market 220.
 Blind Asylum 280.
 Boating 34.
 Bois de Boulogne 157.
 — de Vincennes 211.
 Bon Marché 38. 271.
 Booksellers 40.
 Botanic Garden 267.
 Bottin (directory) 49.
 Bouffes Parisiens 30.
 Boulevards, the Old or
 Inner 63. 46.
 —, the Outer 69. 47. 189.
 —, the New 69.
 — d'Enceinte 69.
 Boulevard Arago 242.
 — Barbès 189.
 — des Batignolles 201.
 — Beaumarchais 67.
 70.
 — Bonne-Nouvelle 72.
 — des Capucines 75.
 — de Clichy 191.
 — de Courcelles 201.
 — du Crime 70.
 — St. Denis 72.
 — des Filles-du-Cal-
 vaire 70.
 — St. Germain 226.
 — Haussmann 75. 200.
 — Henri IV. 67.
 — de l'Hôpital 267.
 — des Italiens 74.
 — de la Madeleine 79.
 — de Magenta 71. 185.
 — Malesherbes 203.
 — St. Marcel 268.
 — St. Martin 71.
 — St. Michel 225.
 — Montmartre 73.
 — Montparnasse 260.
 — Ornano 189; see
 Appx., p. 25.
 — du Palais 216.
 — Poissonnière 72.
 — de Port-Royal 242.
 — Raspail 260. 242.
 — Richard-Lenoir 67.

Paris :

Boulevard de Sébastopol 60. 72. 172.
 — de Strasbourg 72. 185.
 — du Temple 70.
 — Voltaire 71. 175.
 Boulogne, Bois de 157.
 Bourse, la 73.
 — du Commerce 170.
 — du Travail 71.
 Brasseries 16.
 Bridges, see Ponts.
 Bull-fights 32.
 Bullier (Bal) 34. 260.
 Butte-aux-Cailles 46.
 Butte-Montmartre 189.
 Butte-Mortemart 159.
 Buttes-Chaumont, Les 186.
 Cabinet des Médailles et Ant. 199.
 Cabinets de Lecture 41.
 Cabs 19. Appx. p. 32.
 Cafés 17.
 Cafés Chantants 33.
 Canal St. Denis 186.
 — St. Martin 67. 186.
 — de l'Oureq 186.
 Carnavalet, Musée 208.
 Carrefour Montmartre 73.
 — de l'Observatoire 260.
 Carriages 19.
 Carrousel, Arc du 148.
 —, Place du 149.
 —, Pont du 262.
 Casernes 64. 68. 71. 169.
 Casino de Paris 33.
 Catacombs, the 242.
 Cattle Market 187.
 Cemetery of Montmartre 191.
 — Montparnasse 260.
 — of Passy 163.
 — of Père - Lachaise 176.
 — Picpus 210.
 Cercle des Patineurs 160.
 Cercles 34.
 Chambre des Députés 272.
 Chambre des Notaires 61.
 Champ-de-Mars 280.
 Champs-Élysées 153.
 Chapelle, La 47.
 Chapelle Expiatoire 204.
 — St. Ferdinand 156.
 —, Sainte 218.

Paris :

Charonne 46. Appx., p. 25.
 Châteaud'Eau, Placedu 70.
 Châtelet, Place du 60.
 Chaussée d'Antin, Quartier 194.
 —, Rue de la 75.
 Chemin de Fer de Ceinture 24. Appx., p. 25.
 Chemists 36.
 Chevet (Maison) 12.
 Chinese Pavilions 13. 153.
 Church-music 32.
 Churches 51.
 St. Ambroise 175.
 American Episcopal 44.
 Assumption 85.
 St. Augustin 203.
 Baptist 44.
 St. Bernard 189.
 Billettes, des 44.
 Calvinist 44.
 Ste. Clotilde 273.
 Congregational 44.
 St. Denis-du-St. Sacrement 70.
 Ste. Elisabeth 71.
 English 44.
 — Roman Catholic 44.
 Episcopal 44.
 St. Etienne-du-Mont 240.
 St. Eugène 72.
 St. Eustache 171.
 St. François Xavier 280.
 Free Churches 44.
 St. Germain - l'Auxerrois 59.
 — des-Prés 250.
 St. Gervais 64.
 Invalides 278.
 St. Jacques-du-Haut-Pas 241.
 St. Jean-Baptiste 187.
 Jésus 271.
 St. Joseph-des-Carmes 259.
 St. Julien-le-Pauvre 226.
 St. Laurent 185.
 St. Louis 273.
 Lutheran 44.
 Madeleine 79.
 Ste. Marie 65.
 St. Médard 270.
 St. Merri 62.

Paris :

Churches :
 St. Nicolas - des-Champs 175.
 St. Nicolas-du-Char-donneau 241.
 Notre-Dame 221.
 Notre - Dame d'Auteuil 162.
 Notre-Dame-des-Blancs - Manteaux 207.
 — des-Champs 262.
 — de-la-Croix 185.
 — de-Lorette 194.
 — des-Victoires 169.
 Oratoire 53.
 Panthéon 235.
 St. Paul et St. Louis 65.
 St. Philippe 155.
 St. Pierre de Montmartre 190.
 — (Montrouge) 243.
 Presbyterian 44.
 Protestant 44.
 Rédemption 44.
 St. Roch 85.
 Russian 202.
 Sacré Cœur 190.
 Sainte-Chapelle 218.
 Scotland, Church of 44.
 St. Séverin 225.
 Sorbonne 236.
 St. Sulpice 251.
 St. Thomas - d'Aquin 271.
 Trinité 200.
 Val-de-Grâce 241.
 St. Vincent-de-Paul 188.
 Visitation, Church of the 65.
 Wesleyan Chapel 44.
 Cigars 36.
 Circulating libraries 41.
 Circuses 31.
 Cirque d'Été 31. 155.
 — Fernando 31. 191.
 — d'Hiver 31. 71.
 —, Nouveau 31. 81.
 Cité, island 216.
 Clichy 201.
 Clinique d'Accouchement 259.
 Closerie des Lilas 34.
 Ste. Clotilde 273.
 Clubs 34.
 Cluny, Hôt. et Musée de 226.
 Collections, see Musées.
 Collège Chaptal 201.

Paris :

Collège de France 235.
 — Mazarin 244.
 — des Quatre Nations 244.
 — Rollin 189.
 Colonial Museum 154.
 Colonne de Juillet 67.
 — Vendôme 84.
 Communes Annexées 47.
 Compagnie des Pompes Funèbres 177.
 Comptoir d'Escompte 73.
 Concerts 32. 155.
 Conciergerie 219.
 Concorde, Place de la 81.
 Confectionners 19. 36.
 Conjurers 32.
 Conservatoire des Arts et Métiers 173.
 — de Musique 72. 32.
 Consulates 45.
 Corps Législatif 271.
 Congr. d'Assises 218.
 Courcelles Appx., p. 25.
 Cours-la-Reine 168.
 Cours de Vincennes 211.
 Crédit Lyonnais 75.
 Cuisines de St. Louis 219.
 Custom-house xiii. 1.
 Deaf and Dumb Institution 241.
 Decorative Museum 154.
 St. Denis 71.
 Dentists 43.
 Dépôt des Phares 166.
 Dhuis, Reservoir de la 185.
 Diaconesses Protestantes, Maison des 43.
 Diary 52.
 Dinners à Prix-fixe 12. 14. 15.
 Diorama 32. 191.
 Directory 49.
 Distribution of Time 51.
 Dôme Central (Champ de Mars) 283.
 Dôme des Invalides 278.
 Douane 1. 186.
 Drainage 61.
 Druggists 36.
 Dnval, Etablissements 16.
 Ecole Arago 210.
 — des Arts et Manufactures 175.

Paris :

Ecole des Beaux-Arts 246.
 — des Chartes 207.
 — de Droit 239.
 — d'Etat-Major 271.
 — d'Horticulture 304.
 — Massillon 68.
 — de Médecine 226.
 — Militaire 284.
 — des Mines 259.
 — Monge 203.
 — Normale Supérieure 239.
 — de Pharmacie 259.
 — Polytechnique 240.
 — Turgot 175.
 Eden Theatre 30. 79.
 Egonts 61.
 Eiffel Tower 281. 166.
 Eldorado 33. 185.
 Elysée, Palais de l' 153.
 — Montmartre 34. 189.
 Embassies 45. 271.
 Enceinte, the 158.
 English Churches 44.
 Etablissement des Subsidances Militaire 168.
 Etablissements de bouillon 16.
 Etablissements hydrothérapiques 44.
 St. Etienne-du-Mont 240.
 St. Eustache 171.
 Exchange 73.
 Expositions universelles 281.
 Faubourgs 47.
 Faubourg St. Germain 271.
 St. Ferdinand, Chapelle 156.
 Fête des Fleurs 158.
 Fiacles 19.
 Figaro Office 195.
 Flower Market 220.
 Foire au Pain d'Epices 211.
 Folies Bergère 33.
 Fontaine Cuvier 265.
 — Gaillon 75.
 — de Grenelle 271.
 — des Innocents 171.
 — Louvois 195.
 — de Médecis 258.
 — St. Michel 225.
 — Molière 195.
 — Notre-Dame 224.
 — de l'Observatoire 260.
 — du Progrès 282.

Paris :

Fontaine Richelien 195.
 — St. Sulpice 252.
 — de la Victoire 60.
 Fortifications 158.
 Foundling Hospital 242.
 France, Office of La 73.
 Furnished Apartments 3. 9.
 Gambetta Monument 148.
 Garde-Meuble 280.
 Gardiens de la Paix 49.
 Gares 22.
 Gare de l'Arsenal 67.
 — du Champ-de-Mars 23.
 — de l'Est 24. 185.
 — St. Lazare 23. 204.
 — de Lyon 23.
 — Montparnasse 23. 262.
 — du Nord 24. 186.
 — d'Orléans 23. 267.
 — de Sceaux 23. 242.
 — de Strasbourg 24. 185.
 — de Vincennes 24. 67.
 Ste. Geneviève 46.
 St. Germain-l'Auxerrois 59.
 — des-Prés 250.
 St. Gervais 64.
 Gobelins, the 268.
 Goods-agents 26.
 Grand-Montrouge 243.
 Grands Magasins 37.
 Gran Plaza de Toros 32. 157.
 Grenelle, Fontaine de 271.
 —, Artesian Well of 280.
 Grève, Place de 64.
 Grévin, Musée 32. 73.
 Guignol 153.
 Guimet, Musée 166.
 Halle au Blé 179.
 — aux Vins 267.
 Halles Centrales 170.
 Hertford Hospital 43.
 Hippodrome 31. 168.
 — de Longchamp 159.
 History xiv.
 Hôpital du Val-de-Grâce 241.
 — Lariboisière 189.
 — de Lourcine 270.
 — de la Pitié 267.
 — de la Salpêtrière 267.
 — Tenon 184.
 Horse Market 268.
 Horse Races 34.

Paris:

- Horse Show 154.
 Hospice de Bicêtre 243.
 — des Enfants-Assistés 242.
 — Suisse 43.
 — Wallace 43.
 Hospitals 43.
 Hôtels 2.
 Hôtels garnis 3. 9.
 Hôtel Barbette 207.
 — de Béthune 65.
 — de Castille 156.
 — de Cluny 226.
 — Dieu 224.
 — du Figaro 195.
 — Gaillard 203.
 — de Hollande 207.
 — des Invalides 274.
 — Lambert 224.
 — Lamoignon 208.
 — des Monnaies 245.
 — d'Ormesson 65.
 — Pompéien 168.
 — des Postes 24. 170.
 — du Prince Soltikoff 168.
 — de Sens 68.
 — de Soubise 204.
 — de Strasbourg 207.
 — des Téléphones 170.
 — du Timbre 169.
 — la Valette 68.
 — des Ventes Mobilières 75. 195.
 — de Ville 62.
 Houdin, Théâtre 31.
 Ices 19.
 Ile de la Cité 216. 46.
 — des Cygnes 162.
 — St. Louis 224. 46.
 Imprimerie Nationale 207.
 Industrie, Palais de l' 154.
 Institut Catholique 259.
 — de France 244.
 — Pasteur 43.
 — Polyglotte 42.
 — Rudy 42.
 Institution des Jeunes Aveugles 280.
 — des Sourds-muets 241.
 — Ste. Périne 162.
 Invalides, Hôtel des 274.
 —, Egl. des 273.
 St. Jacques, Tour 60.
 St. Jacques-du-Haut-Pas 241.
 Jardin d'Acclimatation 160.

Paris:

- Jardin botanique 267.
 — du Luxembourg 258.
 — du Palais-Royal 57.
 — de Paris 33. 34. 155.
 — des Plantes 263.
 — des Tuileries 151.
 St. Jean-Baptiste 187.
 Jésus, Egl. du 271.
 St. Julien - le - Pauvre 226.
 July Column 67.
 Kiosques 69.
 St. Laurent 185.
 Légion d'honneur, Pal. de la 272.
 Libraries, public, see Bibliothèques.
 Longchamp 159.
 St. Louis, Ile 224. 46.
 Louvois, Font. et Place 195.
 Louvre 86.
 Asiatic Museum 93.
 Bronzes, Ancient 141.
 Campana, Musée 145.
 Chinese Museum 145.
 Collection Dieulafoy 143.
 — of Drawings 141.
 — His de la Salle 142.
 — La Caze 140.
 — Lenoir 144.
 — de Sarzec 143.
 — Thiers 142.
 Egyptian Museum 90.
 Engravings 110.
 Escalier Daru 96.
 — Henri II. 104.
 Ethnographical Museum 147.
 Galerie d'Apollon 136.
 — Denon 95.
 — Mollien 95.
 — des Sept Mètres 120.
 Grande Galerie 121.
 Greek Antiquities 144.
 Jewish Museum 94.
 Marine Museum 146.
 Mediæval and Renaissance Antiquities 142.
 Musée Campana 145.
 — de Chalcographie 110.
 Pavillon Denon 90.
 — del'Horloge (Sully) 141.
 Picture Gallery 111. 146.

Paris:

- Louvre:
 Rotonde d'Apollon 136.
 Salle des Bijoux 138.
 — des Boîtes 148.
 — Daru 133.
 — Duchâtel 119.
 — Henri II. 140.
 — des Sept Cheminées 139.
 Salles Françaises 131.
 — Nouvelles 135.
 Salon Carré 116.
 Sculptures, Ancient 95.
 —, Mediæval and Renaissance 105.
 —, Modern 108.
 Lunatic Asylum 214.
 Lutheran Churches 44.
 Luxembourg, Palais et Jardin du 253.
 Luxor, Obelisk of 82.
 Lycée Charlemagne 65.
 — Condorcet 204.
 — Henri IV. 240.
 — Janson de Sailly 163.
 — Louis-le-Grand 235.
 — —, Petit 259.
 — St. Louis 235.
 — Voltaire 184.
 Madeleine, la 79.
 Madrid 159.
 Magasins 37. 201. etc.
 Mairies 59. 65. 71. etc.
 Maison d'Arrêt de Ste. Pelagie 267.
 Maison Blanche, La, 46; Appx., p. 25.
 — Chardon Lagache 162.
 Maison d'Educat. de la Légion d'Honneur 324.
 Maison de François I. 168.
 — Rossini 162.
 Maisons meublées 3. 9.
 — de santé 43.
 Manège 83.
 Marais, Quartier du 209.
 Marbœuf, Quartier du 155.
 Marché aux Bestiaux 187.
 — aux Fleurs 220.
 — du Temple 71.
 Ste. Marie 65.
 Market, Central 170.
 St. Médard 270.
 Ménilmontant 46. 185.
 Appx., p. 25.

Paris :

St. Merri 62.
Ministère des Affaires
Etrangères 271. 273.
— des Finances 45.
— de la Guerre 271.
272.
— de l'Instruction Pu-
blique 271.
— de Justice 84.
— de la Marine 81.
— des Postes 271.
— des Travaux Publics
271.
Ministerial Offices 45.
271.
Mint 245.
Missions 44.
— Etrangères 271.
Monceaux, Parc 202.
Moncy xii.
Money Changers 46.
Monnaie, La 245.
Montagnes Russes 33.
Montmartre 189, 46. 47.
—, Boulevard 73.
—, Cemetery of 191.
Montparnasse, Ceme-
tery of 260.
Mont de Piété 207.
Montreuil 210.
Montrouge 47. 242.
Montsouis, Park of
243.
Mont Valérien 158. 286.
Monument de la Dé-
fense de Paris 156.
— of Eug. Delacroix
259.
— Bobillot 175.
— of Col. Flatters 243.
— of Gambetta 148.
— of the War of 1870-
71, 281.
Morgne 224.
Mortemart, Butte 159.
Moulin Rouge 33. 34.
Muette, La 162.
Musée d'Anatomie 226.
— des Antiquités Na-
tionales 315.
— des Archives 204.
— d'Artillerie 275.
— des Arts Décoratifs
154. 233.
— Astronomique 260.
— Cambodgien 165.
— Carnavalet 208.
— Céramique 312.
— de Chalographie 110.
— de Cluny 227.
— des Colonies 154.
— des Copies 246. 249.

Paris :

Musée Dupuytren 226.
— Ethnographique
164.
— Forestier 214.
— Galliera 167.
— du Garde-Meuble
288.
— Grévin 32. 73.
— Guimet 166.
— Haüy 280.
— d'Histoire Naturelle
265.
— Historique (Ver-
sailles) 290.
— — de la Ville 208.
— Industriel et Com-
mercial 283.
— Khmer 165.
— du Louvre 86.
— du Luxembourg 255.
— de Mme. de Caën
245.
— des Médailles 199.
— de Minéralogie 259.
— Monétaire 246.
— des Moulages 164.
— de l'Opéra 79.
— Orfila 226.
— Paléographique 204.
— Pédagogique 241.
— de Peinture 111. 256.
260.
— de la Révolution 289.
— de Sculpture Com-
parée 164.
— des Thermes 227.
— de Ville 162.
— des Voitures 306.
Museum of Natural
History 265.
Music 32.
Napoleon I.'s Tomb 279.
Natural History Mu-
seum 265.
Neuilly 156.
Newspapers 41.
New York Herald Read-
ing Room 40.
St. Nicolas-des-Champs
175.
St. Nicolas-du-Char-
donnet 241.
Notre-Dame 221.
Notre-Dame-d'Auteuil
162.
Notre-Dame-des-
Blancs-Manteaux 207.
Notre-Dame-des-
Champs 262.
Notre-Dame-de-la-
Croix 185.

Paris :

Notre-Dame-de-Lo-
rette 194.
Notre-Dame-des-Vic-
toires 109.
Nouveau Cirque 31. 85.
Obelisk of Luxor 82.
Observatoire 260.
—, Fontaine de l' 260.
Oculists 43.
Odéon 29.
Omnibuses 1. 20.
Opera 28. 76.
OpéraComique 29. 75. 61.
Oratoire, l' 58. 44.
Ouen, St. 201. Appx.,
p. 25.
Ouest-Ceinture 286.
Appx., p. 25.
Palais Archiépiscolal
271.
— des Arts-Libéraux
283.
— des Beaux-Arts 246.
— — (Champ de
Mars) 283.
— Bourbon 272.
— du Corps Législatif
272.
— de l'Elysée 153.
— de l'Industrie 154.
— de l'Institut 244.
— de Justice 217.
— de la Légion d'hon-
neur 272.
— du Louvre 86.
— du Luxembourg
253.
— des Machines 283.
— du Quai d'Orsay
272.
— Royal 56.
— des Tournelles 209.
— du Trocadéro 163.
— des Tuileries 149.
Panoramas 32. 155.
Panthéon 235.
Pantin 188.
Parc Monceaux 202.
— Montsouis 243.
— de la Muette 162.
Parcels 25.
Passage Jouffroy 73.
— de l'Opéra 75.
— des Panoramas 73.
— des Princes 75.
— Vivienne 169.
Passports xiii.
Passy 162. Appx., p. 25.
Pâtisseries 19.
St. Paul & St. Louis 65.

Paris:

Pavillon de Hanovre 75.
 — des Travaux Publics 165.
 — de la Ville de Paris 155.
 Pavillons Chinois 158.
 Ste. Pélagie 267.
 Père-Lachaise, Cemetery of 176.
 Petit-Montrouge 243.
 St. Philippe-du-Roule 165.
 Physicians 42.
 Picpus, Cemetery 210.
 Picture - Gallery (Louvre) 111.
 — (Luxembourg) 256.
 — (Versailles) 290.
 Place de l'Alma 168.
 — de la Bastille 65.
 — Baudoyer 65.
 — Blanche 191.
 — de la Bourse 73.
 — du Carrousel 149.
 252.
 — du Château d'Eau 70.
 — du Châtelet 60.
 — de Clichy 201.
 — de la Concorde 81.
 — Denfert - Rochereau 242.
 — de l'Etoile 155.
 — de l'Europe 201.
 — Fontenoy 234.
 — St. Georges 194.
 — de Grève 64.
 — de l'Hôtel-de-Ville 64.
 — d'Iéna 166.
 — d'Italie 270.
 — Ledru-Rollin 176.
 — de la Madeleine 79.
 — Malesherbes 203.
 — Maubert 241.
 — St. Michel 225.
 — Moncey 201.
 — Monge 270.
 — de la Nation 210.
 — de l'Opéra 76.
 — du Palais-Bourbon 273.
 — du Palais-Royal 55.
 — du Parvis Notre-Dame 224.
 — St. Pierre 190.
 — Pigalle 191.
 — des Pyrénées 184.
 — de la République 70.
 — de Rivoli 86.
 — St. Sulpice 252.
 — du Théâtre-Français 58.

Paris:

Place du Trocadéro 163.
 — du Trône 210.
 — Vendôme 84.
 — des Victoires 169.
 — des Vosges 209.
 — Wagram 203.
 Plaza de Toros, Gran 157.
 Point-du-Jour 162. 287.
 Appx., p. 25.
 Pointe St. Eustache 171. 172.
 Policemen 49. 221.
 Pompe à Feu de Chailot 168.
 Pont de l'Alma 168.
 — d'Arcole 64.
 — des Arts 244.
 — d'Austerlitz 263. 23.
 — de Bercy, see Appx. p. 25.
 — du Carrousel 262.
 — au Change 61.
 — de la Concorde 83.
 — de Flandre, see Appx., p. 25.
 — de Grenelle 162.
 — d'Iéna 166.
 — des Invalides 168.
 — St. Michel 225.
 — National, see Appx., p. 31.
 — Neuf 220.
 — Royal 270.
 — des Sts. Pères 262.
 — de Solférino 272.
 — Sully 68. 224.
 Population xxiii.
 Porte Dauphine 157.
 — St. Denis 72.
 — Maillot 157, Appx., p. 25.
 — St. Martin 71.
 Portefeuille Industriel 175.
 Post Office 24. 170.
 Pré Catelan 160.
 Préfecture de Police 220.
 — de la Seine 62.
 Preliminary Drive 49.
 Pré St. Gervais 188.
 Prison de la Conciergerie 219.
 — de la Force 65.
 — des Jeunes Détenus 176.
 — de Ste. Pélagie 267.
 — de la Roquette 176.
 — de la Santé 270.
 Private Apartments 9.
 Protestant Churches 44.

Paris:

Quai de la Conférence 168.
 — Debilly 163.
 — d'Orsay 272.
 Quartier de la Chaussée d'Antin 194.
 — de l'Europe 201.
 — Latin 47. 225.
 — du Marais 209.
 — du Marbœuf 155.
 Race Courses 34. 159. 243. 337. etc.
 Railway Omnibuses 1.
 Railway Stations 22.
 Ranelagh, the 162.
 Reading Rooms 41.
 Réservoirs 190. 243.
 Restaurants 9.
 St. Roch 85.
 Roman Baths 234.
 Roquette, Prison de la 176.
 Rue d'Allemagne 186.
 — St. Antoine 65. 67.
 — du Bac 271.
 — de la Banque 169. 74.
 — de Châteaudun 194.
 — St. Denis 72.
 — Drouot 73. 74.
 — Etienne-Marcel 169.
 — du Faubourg-St. Antoine 67.
 — du Faubourg-St. Denis 72.
 — Fortuny 203.
 — des Francs - Bourgeois 204.
 — d'Hauterive 72.
 — St. Honoré 85.
 — de Lafayette 186.
 — Laffitte 75.
 — du Louvre 59. 170.
 — Monge 224. 241.
 — Montchanin 203.
 — Mouffetard 270.
 — de la Paix 76.
 — des Petits-Champs 169.
 — des Plantes 260.
 — Poissonnière 72.
 — Prony 203.
 — des Pyramides 86.
 — du Quatre Septembre 74. 76.
 — Rambuteau 204.
 — Réaumur 175.
 — de Rennes 251.
 — de Richelieu 73. 195.
 — de Rivoli 58. 83.
 — de la Roquette 176.

Paris:

Rue Royale 80.
 — Soufflot 235.
 — du Temple 64. 71.
 — de Turbigo 71. 172.
 — de la Victoire 194.
 — Vivienne 73.
 Russian Church 202.

Sacré Cœur, Egl. du
 190.

Sainte-Chapelle 218.

Salles de Danse 34.

Salle Wagram 34.

Salon, the 154.

Savonnerie, la 268.

Scala 33. 185.

Séminaire de St. Sul-
 pice 252.

— des Missions Etran-
 gères 271.

Serres de la Ville
 162.

St. Séverin 225.

Sewers 61.

Shops 35.

Skating 34. 160.

Sorbonne, the 238.

Square d'Anvers 189.

— des Arts et Métiers
 72. 172.

— du Carrousel 148.

Cluny 234. 226.

— des Ménages 271.

— Monge 241.

— Montholon 194.

— de Montrouge 243.

— Parmentier 176.

— Richelieu 195.

— de la Trinité 201.

— Vintimille 201.

Statue of Aguesseau
 162.

— of Béranger 71.

— of Berlioz 201.

— of Bernard 236.

— of Bichat 225.

— of Louis Blanc 270.

— of Bobillot 175.

— of Budé 236.

— of Charlemagne 224.

— of Coligny 58.

— of Condorcet 245.

— of Dante 236.

— of Danton 226.

— of Daubenton 161.

— of Daumesnil 211.

— of Diderot 251. 189.

— of Dolet 241.

— of Dumas 203.

— of Gambetta 148.

— of Henri IV. 220.

— of Joan of Arc 86.

Paris:

Statue of Lamartine 162.

— of Larrey 241.

— of Leblanc 173.

— of Ledru-Rollin 176.

— of Liberty 162.

— of Louis XIII. 209.

— of Louis XIV. 169.

— of Marcel 63.

— of Molière 195.

— of Moncey 201.

— of Napoleon 84.

— of Neuville 203.

— of Ney 260.

— of Palissy 251.

— of Papin 173.

— of Parmentier 156.

— of Pascal 60.

— of Pinel 268.

— of Prince Eugene
 275.

— of Raspail 260.

— of Rousseau 239.

— of Sedaine 189.

— of Séguin 201.

— of Shakspeare 201.

— of Le Verrier 260.

— of Villon 241.

— of Voltaire 241. 245.

Steamboats 22.

Street-Criers 48.

Subsistances militaires
 168.

St. Sulpice 251.

Suresnes 160.

Swimming-baths 42.

Synagogues 44. 194.

Tabacs, Manufacture
 des 280.

Tables d'Hôte 15.

Telegraph Offices 26.
 170.

Telephones 26. 170.

Temple, Faubourg du
 47.

—, Marché du 71.

—, Square du 71.

—, Tour du 71.

—, Reproduction of the
 Tour du 165.

Theatres 26.

Théâtre de l'Ambigu
 Comique 31.

— Beaumarchais 31. 70.

— des Bouffes Pari-
 siens 30.

— du Château d'Eau
 31.

— du Châtelet 30. 61.

— de Cluny 31.

— Déjazet 31. 70.

— Eden 31. 79.

Paris:

Théâtre des Folies Dra-
 matiques 31.

— Français 39. 58.

— de la Gaîté 30. 172.

— du Gymnase 29. 72.

— Historique 31.

— des Menus-Plaisirs 31.

— des Nouveautés 30.
 75.

— de l'Odéon 29.

— de l'Opéra 28. 76.

— de l'Opéra-Comique
 29. 75. 61.

— du Palais-Royal 30.
 57.

— de la Porte-St. Mar-
 tin 30.

— de la Renaissance
 30.

— Robert Houdin 31.

— des Variétés 30. 73.

— du Vaudeville 30. 75.

Theatre Offices 26.

Théâtres de Guignol
 153.

Thermes 234.

Thiers, House of A.,
 194.

St. Thomas d'Aquin 271.

Tivoli 34.

Tobacco Manufactory
 280.

Topography 46.

Tour Eiffel 231. 166.

— St. Jacques 60.

— de Jean sans Peur
 172.

— du Temple, Repro-
 duction of, 165.

Tournelles, Palais des
 209.

Tramways 20.

Tribunal de Commerce
 219.

Trinité, Egl. de la 200.

Trinkhalles 69.

Trocadéro, Palais du
 163.

—, Parc du 165.

—, Place du 163.

—, Avenue du 163.

Tuileries, the 149.

—, Jardin des 151.

University 235.

Val-de-Grâce 241.

Vanne, Réservoir de
 la 243.

Vaugirard 47. Appx.,
 p. 25.

Vendôme Column 84.

Paris:

Viaducts 162. 191. 287.
 Viaduc Caulaincourt 191.
 Villette, La 46. 47. 187.
 Vincennes, Bois de 212.
 —, Château de 211.
 St. Vincent-de-Paul 188.
 Voitures 19.
 Weights xxv.
 Wines 40.
 Zoological Garden 254.
 Parmain 343.
 Passy 162. 47. Appx., p. 25.
 Pavilly 368.
 Pecq, Le 315.
 Persan-Beaumont 349.
 Picquigny 354.
 St. Pierre-lès-Calais 357.
 — du Vauvray 364.
 Pierrefitte 346.
 Pierrelaye 341.
 Piple, Chât. du 215.
 Plessis-Belleville, Le 350.
 Plessis-Piquet 336.
 Poissy 365.
 — -Grande-Ceinture 318.
 Point-du-Jour, 162. 287.
 Appx., p. 25.
 Pollet, Le 358.
 Pont de l'Arche 364.
 — de Briques 353.
 — de Flandre, see Appx., p. 25.
 — Remy 354.
 — de St. Cloud 309.
 — de Sèvres 309.
 — de Soissons 350.
 — Viaduc du Point-du-Jour 162. 287.
 Pontoise 342. 341.
 Port Marly 314.
 — Royal Abbaye de 307.
 Prêcy 349.
 Presles 344.
 St. Prix 326.
 Puteaux 285.

Rambouillet 307.
 Reine Blanche, Chât. de la 347.
 St. Remy 339.
 St. Riquier 354.
 Robinson 337.
 St. Roch 354.
 Rolleboise 365.
 Rosny 365.
 Rouen 360.
 Royaumeont 345.
 Rue 353.
 Rueil 314.
 Rungis 338. 337.
 Sannois 326.
 Sarcelles 345.
 Sartrouville 341.
 Sausseron, the 343.
 Savigny-sur-Orge 338.
 Sceaux 337.
 Sceaux-Ceinture 336.
 Scie, the 359.
 Seine, the 22. 46. 360. etc.
 Selle, the 354.
 Senlis 349.
 Sevran-Livry 350.
 Sèvres 312. 286. 287.
 Soisy 325.
 Solle, la 334.
 Somme, the 353.
 Sotteville 364.
 Southampton 365.
 Stains 346.
 Stors 345.
 Sucy en Brie 215.
 Suresnes 160. 285.
 — Longchamp 309.
 Survilliers 346.
 Taverny 345.
 Thève, the 346.
 Thieux-Nantouillet 350.
 Touques, the 367.
 Tour, chât. de la 326. 341.
 Trappes 307.

Trianon, Grand and Petit 306.
 Trouville-sur-Mer 367.
 Tuile, Butte de la 327.
 Val, Abbaye du 345.
 Valenton 338. 215.
 Valérien, Mont 158. 286.
 St. Valéry-en-Caux 368.
 St. Valéry-sur-Somme 353.
 Valmondois 343.
 Vanves 286.
 Vauboyen 338.
 Vaucresson 311.
 Vaugirard 47, see Appx., p. 25.
 Vaujours 350.
 Vaux-de-Cernay 340.
 Vaux-le-Penil (chât.) 328.
 Vaux-Praslin (chât.) 328.
 Vernon 364.
 Verrières, Bois de 337.
 Versailles 287. 286.
 Verton 353.
 Vésinet, Le 314.
 Viarmes 345.
 Ville-d'Avray 286. 311.
 Ville-Evrard 213.
 Villejuif 270. 337.
 Villeneuve-St. Georges 215. 327. 338.
 — l'Etang 311.
 — le-Roi 338.
 Villeparisis 350.
 Villiers-le-Bel 345.
 Vincennes 211.
 Viroflay 286. 287.
 Vitry 270.
 Wissous 338.
 Yères, the 327.
 Yvetot 368.
 Yvette, the 339.

Alphabetical List of the Hotels, Restaurants, and Cafés of Paris mentioned in the Handbook.

The words *Hotel, Restaurant, etc.*, are omitted for the sake of brevity.

Hotels and Maisons Meublées.

Albe (d'), 8.	Chateaubriand, 8.	Gand & de Germanie (de), 6.
Alexandra, 6.	Chantilly (de), 7.	Gare du Nord (de la), 2.
Alma (de l'), 5.	Chatham, 5.	Globe (du), 7.
Ambassadeurs (des), 8.	Chemin de Fer (du), 2.	Grand-Hôtel, 3.
Amirauté (de l'), R. Daunou, 5.	Chemin de Fer de l'Est (du), 2.	Grande-Bretagne (de la), 6.
Amirauté (de l'), R. Duphot, 6.	Chemin de fer de Lyon (du), 2.	Harcourt (d'), 9.
Angleterre (d'), R. Montmartre, 7.	Chemin de Fer du Nord (du), 2.	Haute-Vienne (de la), 7.
Angleterre & des Antilles (d'), 6.	Chemin de fer d'Orléans (du), 2.	Havane (de la), 7.
Anglo-Américain, 2.	Choiseul, 4.	Helder (du), 6.
Anglo-Français, 5.	Choisenl & Egypte (de), 5.	Hollande (de), R. de la Paix, 5.
Antin (d'), 5.	Cité & Bernaud (de la), 7.	Hollande (de), R. Radzivil, 7.
Arcade (de l'), 5.	Claise, 7.	Iles Britanniques (des), 5.
Arts (des), 7.	Cologne (de), 7.	Isly (d'), 8.
Athénée (de l'), 6.	Colonies (des), 7.	Jardin des Tuileries (du), 4.
Bade (de), 6.	Continental, 3.	Jersey (de), 6.
Bâle, 2.	Corneille, 9.	
Balmoral, 5.	Couronne (de la), 4.	
Balzac (villa), 8.		
Bavière (de), 8.	Danube (du), 6.	Lacombe, 7.
Beaujon, 8.	Derby (du), 8.	Laffitte, 6.
Beau-Séjour, 7.	Denx-Cités (des), 7.	Lartisien, 5.
Bedford, 5.	Deux-Mondes (des), 5.	Levant (du), 7.
Belge, 2.	Dominici, 5.	Liban (du), 6.
Belgique & de Hollande, 7.	Doré & des Panoramas, 7.	Lille & d'Albion (de), 4.
Bellevue, 5.		Liverpool, 5.
Bergère, 7.	Empire (de l'), 5.	Londres (de), R. Bonaparte, 8.
Binda, 5.	Espagne & de Hongrie (d'), 6.	Londres (de), R. Castiglione, 5.
Bon Lafontaine (du), 8.	Etats-Unis (des), 5.	Londres & de New-York (de), 2.
Boston (de), 5.	Etrangers (des), R. Racine, 9.	Lord Byron (villa), 8.
Bourse & des Ambassadeurs (de la), 7.		Louis-le-Grand, 5.
Bréban, 7.	Europe (de l'). Bonlev. de Strasbourg 74, 2.	Louvois, 7.
Brésil et d'Orient (du), 6.	Europe (de l'), R. Le Peletier, 6.	Louvre (Gr. Hôt. du), 3.
Brésilien, 7.	Européen, 8.	Lyon (de), 8.
Brighton, 4.		
Bristol, 5.	Famille (de), 8.	Maisons Meublées, 4, 5, 6, 7, 8.
Britannique, 8.	Favart, 7.	Malesherbes, 6.
Buckingham, 6.	Foyot, 8.	Malte (de), 7.
Burgundy, 6.	Français, 2.	Manchester (de), 7.
Byron, 6.	France (de), Cité Bergère 2 bis, 7.	Marine Française (de la), 7.
Caillenx, 2.	France (de), R. du Caire, 8.	Marine & des Colonies (de la), 2.
Calais (de), 5.	France (de), R. Laffitte, 6.	Metropolitan, 4.
Campbell, 8.	France & de Bath (de), 4.	Meurice, 4.
Canada (de), 6.	France & de Bretagne (de), 2.	Meyerbeer, 8.
Capucines (des), 5.	France & de Champagne (de), 7.	Midi (du), 9.
Carmes (des), 9.	Frascati, 7.	Mirabeau, 5.
Castiglione, 5.		
Central, 6.		
Central de la Bourse de Commerce, 4.		

Moderne, 4. 8.	Rapp, 6.	Suez (de), 9.
Monsigny, 6.	Rastadt (de), 5.	Suffren, 8.
Moscou (de), 7.	Rhin (du), Cité Bergère, 7.	Suisse, R. Lafayette, 6.
Musée de Cluny (du), 9.	Rhin (du), Place Vendôme, 5.	Taitbout, 6.
National, 7.	Richelieu, 7.	Tamisi (de la), 4.
Néva (de la), 7.	Richempanse, 6.	Terminur 3. 204.
Newton, 5.	Richer, 7.	Terrasse-Jouffroy (de la), 7.
Nice (de), 7.	Richmond, 6.	Tête, 5.
Nil (du), 6.	Rivoli, 4.	Thérèse, 5.
Normandy (de), 5.	Rome (de) 2.	Tibre (du), 6.
Orient (d'), 5.	Rossini, 6.	Trévise (de), 7.
Orléans (d'), 7.	Rouen (de), R. St. Denis, 8.	Univers (de l'), 2.
Paris (de), Boulev. de Strasbourg, 2.	Rougemont, 7.	Univers & du Portugal (de l'), 7.
Paris (de), R. du Faubourg-Montmartre, 38. 7.	Royal, 8.	Valois (de), 7.
Paris & d'Osborne (de), 4.	Russie (de), 6.	Vendôme, 5.
Pavillon (du), 8.	St. James, 4.	Victoria, Cité d'Antin, 6.
Pays-Bas (des) 6.	St. Laurent et de Mulhouse, 2.	Victoria, R. Rossini 6.
Perey, 5.	St. Pétersbourg (de), 6.	Violet, 5.
Périgord (du), 7.	St. Pierre, 9.	Vivienne, 7.
Pfeiffer 5.	Ste. Marie, 4.	Voltaire, 8.
Port-Mahon (de), 5.	Saints-Pères (des), 8.	Vouillemont, 5.
Prince de Galles (du), 6.	Scribe, 3.	Wagram, 4.
	Sèze (de), 5.	Westminster, 5.
	Strasbourg (de), Boulev. de Strasbourg, 2.	Windsor, 4.

Restaurants and Cafés.

Ambassadeurs (des) 13. 34.	Champeaux, 13.	Foyot, 14.
Américain, 13, 18.	Chaussée d'Antin (de la), 13.	Français (Dîner), B. des Italiens 27. 15.
Anglais, 13.	Cinq Arcades (aux), 14.	—, R. Montmartre 158, 15.
Armenonville (Pavillon d'), 13.	Cirque (du), 13.	France (Café de), 18.
Barbotte, 14.	Commerce, du (Pass. des Panoramas), 15.	France (Rest. de) 13.
Beretta, 14.	Commerce, du (R. St. Denis) 4. 15.	Gaillon, 13.
Bignon, 13.	Congrès (du), 18.	Galleries (des), 15.
Blond (Table d'hôte), 15.	Coq d'Or (Tav. du), 17.	Gaulois (Tav. des), 17.
Blot, 14.	Corazza, 12.	Gillet, 13.
Bœuf à la Mode (au), 13.		Glacier Napolitain, 18. 19.
Bonvalet 13. 15.	Dame Blanche (à la), 19.	Grand Café, 18.
Bouillod (Table d'hôte), 15.	Darras, 15.	Gruber, 15. 17.
Bouillon Boulant, 16.	Désiré Baurain, 13.	Helder (du), 13, 18.
Bouillons Duval, 14. 16.	Dreher (Brass.), 17.	Henri IV, 15.
— Parisiens, 16.	Ducastaing (Brass.), 17.	Hupet, 15.
Boulon (Maison), 15.	Durand, 13, 18.	Imoda, 19.
Bouvier-Vidrequin, 14.	Duval (Etablissements), 16.	Jewish Restaurants 14.
Brébant, 18.	Eden (Brass.) 17.	Julien, 13. 18.
Bruneaux, 15.	Etablissements de Bouillon, 16.	Lapérouse, 14.
Cardinal, 18.	Européen (Dîner), 15.	Larue, 13.
Caron, 14.	Excoffier (Table d'hôte), 15.	Lecomte, 13.
Cascade (de la), 14. 159.		Ledoyen, 13.
Central, 18.		

Légion d'Honneur (de la), 16.	Orléans (d'), 12, 18.	Rougemont, 13.
Lemardelay, 13.	Orsay (d'), 14, 18.	Rouzé, 19.
Léon, 16.	Ory, 13.	Ste. Clotilde, 16.
Lequen, 14.	Paix (de la), 13, 18.	St. Roch, 18.
Lion d'Or, 13.	Palette d'Or (Brass. de la), 17.	Schaeffer, 14.
Lion Rouge (Cabaret du), 17.	Paris (Café de), 13, 18.	Soufflet, 14, 18.
Lipp, 17.	Paris (Dîner de), 15.	Splendide Taverne 13, 17, 18.
Londres (Taverne de), Place Boieldieu, 14.	Paris (Rest. de), 14.	Snède (de), 18.
Lucas, 14.	Pavillon d'Armenonville 13.	Taverne Flamande, 17.
Madeleine, 13.	Pavillons Chinois, 13, 158.	Tavernier Aîné, 15.
Madrid (Café de), 18.	Poissonnière 13.	Terminus (du), 14.
Madrid (Rest. de), 14, 160.	Pont de Fer (du), 18.	Terrasse (de la), 18.
Magny, 14.	Porte Jaune (de la), 14, 213.	Terrasse Jouffroy (de la) 15.
Mail (table d'hôte du), 15.	Porte Montmartre (de la), 18.	Tissot, 14.
Maire, 13.	Porte St. Martin (de la), 15.	Tortoni, 19.
Maison Bonlon, 15.	Pousset, 17.	Tour d'Argent, 14.
Maison Dorée, 13.	Quatre Sergents (aux), 13.	Tournier (Brass.), 17.
Margnery, 13.	Régence (de la), 18.	Univers (de l'), 15.
Mazarin, 18.	Rhénane (Brass.), 17.	Vachette, 18.
Mignon, 14.	Riche, 13, 18.	Variétés, 18.
Moderne, 14.	Richelieu (Déjeuner de), 18.	Véfour (Grand), 12.
Montmartre (Tav.), 17.	Richelieu (Rest.), 15.	Véfour (Petit), 12.
Müller, 17.	Rocher (Dîner du), 15.	Véron, 18.
Musée de Cluny (du), 18.	Rond Point (du), 13.	Vian, 13.
Napolitain, 18, 19.	Rosbif (au), 15.	Vivienne (Table d'hôte) 15.
National (Dîner), 15.		Voisin, 13.
Nations (des), 15.		Voltaire, 18.
Neuve Levi, 14.		Weber, 14, 17.
Noël-Peters, 13.		Zimmer, 17.
Notta, 13.		
Océan (de l'), 16.		

INDEX OF STREETS
AND
PLANS OF PARIS.

CONTENTS.

1. List of the principal streets, public buildings, etc., of Paris.
2. General Plan of Paris, showing the divisions of the large plan and the limits of the special plans.
3. Large Plan of Paris, in three sections.
4. Five Special Plans of the most important quarters of the city.
5. List of the stations of the Chemin de Fer de Ceinture.
6. Plan and List of the omnibus and tramway lines and of the river steamboats.
7. Cab Tariff.

This cover may be detached from the rest of the book by severing the yellow thread which will be found between Nos. I. and II. of the special plans.

List of the Principal Streets, Squares, Public Buildings, etc.

with Reference to the accompanying Plans.

The large Plan of Paris, on the scale of 1 : 20,000, is divided into three sections, of which the uppermost is coloured *brown*, the central *red*, and the lowest *grey*. Each section contains 36 numbered squares. In the accompanying index the capital letters **B, R, G**, following the name of a street or building, refer to the different sections, while the numbers correspond with those on the squares in each section. When the name required is also found on one of the special plans, this is indicated by an italicised Roman numeral. Thus, Rue de l'Abbaye will be found on the red section, square 19; and also on the fourth special map. The capital letters within brackets, placed after the names of the chief streets, etc., indicate the omnibus and tramway-lines which ply in or to these streets (comp. pp. 26-30 of this Appx.).

Names to which *Ancienne, Petite, Saint*, etc., are prefixed, are to be sought for under these prefixes. It should also be observed that the names of streets in Paris are frequently altered. In the special maps some of the house-numbers are inserted at the corners of the longer streets, especially in those cases in which the consecutive odd and even numbers are locally some distance apart. See also footnote at p. 1.

The numbering of the squares is so arranged, that squares in different sections bearing the same number adjoin each other. Thus, square 18 on the brown section finds its continuation towards the S. in square 18 on the red section.

The squares will also be useful for calculating distances, each side of a square being exactly one kilomètre, while the diagonals if drawn would be 1400 mètres or $12\frac{1}{5}$ kilomètre.

The word *Rue* is always omitted in the following index for the sake of brevity; the other contractions will present no difficulty.

	B. R. G.				B. R. G.		
Abattoirs(Villette) <i>AC, TNG</i>	31			Affre	23		
— (rive gauche)	13	23		Agnesseau (d')	II	15	
Abbaye (de l')	IV	19		Alain-Chartier			10
— aux-Bois	IV	16		Albony	III	27	
Abbé-de-l'Épée (de l') <i>IV, V</i>		19		Alembert (d')			17
Abbé-Grégoire	IV	16		Alésia (d')			14
Abbé-Groult (de l')		10		Alexandre-Dumas		31	
Abbeses (des)	20			Alfred-de-Vigny	12		
Abbeville (d')	24			Alger (d')	II	18	
Abel-Leblanc (passage)	28			Alibert	III	27	
Aboukir (d') <i>(N)</i>	III	24		Aliénés (asile clinique d')			20
Acacias (des)	9			Aligre (conr d')	III	20	
Acclimatation (Jardin d')	3			— (rue et place d')		28	
Adolphe-Adam	V	23		Allemagne (d') <i>(AC, TN H)</i>	29		
Affaires Etrang.(min.des) <i>II</i>	14			Alleray (rue & place d')		10	

B. E. G.		B. E. G.	
Alma (avenue, place, & pont de l') (<i>A, TA, TB, TAB, TJ, TS, TL, TM, TS 6</i>) <i>I</i>	12	Ardeunes (des)	29
Alouettes (des)	30	Argenson (d') <i>II</i>	15
Alpes (place des)	23	Argenteuil (d') <i>II</i>	21
Alphand (passage)	23	Argonne (rue & place de l')	28
Alphonse	4	Argout (d') <i>III</i>	21
Alsace (d')	24	Armaillé (d')	9
Amandiers (des)	33	Armorique (de l')	13
Ambassade d'Allemagne <i>II</i>	17	Arquebusiers (des) <i>III</i>	26
— d'Angleterre <i>II</i>	15	Arras (d') <i>V</i>	22
— d'Autriche <i>II</i>	17	Arrivée (de l')	16
— de Russie <i>II</i>	17	Arseual (gare de l')	25
Ambigu (rue & th. de l') <i>III</i>	24	— (biblioth. de l') (<i>U, TC, TL</i>) <i>V</i>	25
Amboise (d') <i>III</i>	21	— (rue & place de l') <i>V</i>	25
Ambroise-Paré	23	Artistes (des)	21
Amélie (rue & passage) <i>IV</i>	14	Arts (des)	4
Amelot <i>III, V</i>	26	— (pont des) <i>IV</i>	20
Ampère	11	Arts-et-Métiers (sq. des) (<i>M, TG, TH, T I</i>) <i>III</i>	24
Amsterdam (d')	18	Asile-Popincourt (rue & passage de l')	26
Amyot <i>V</i>	22	Asnières (porte d')	11
Anatomie (amphithéâtre d')	22	— (route d')	14
Ancienne-Comédie (de l') <i>IV, V</i>	19	Assas (rue d') <i>IV</i>	16
Aucre (passage de l') <i>III</i>	24	Assomption (de l')	5
André-del-Sarte	20	— (église de l') <i>II</i>	18
Anglais (des) <i>V</i>	22	Astorg (d') <i>II</i>	15
— (passage des)	29	Athènes (d')	18
Angoulême (d') <i>III</i>	27	Atlas (de l')	30
Ajou (d') <i>II</i>	18	Auber <i>II</i>	18
— (quai d') <i>V</i>	22	Aubervilliers (d')	26
Annam (d')	33	— (porte d')	25
Anelets (des)	33	Aubigné (d') <i>V</i>	25
Annonciation (de l')	5	Aubriot <i>III</i>	23
— (égl. de l')	8	Aubry-le-Boucher <i>III</i>	23
Autin (d') <i>II</i>	21	Aude (de l')	18
— (avenue d') (<i>TS 5</i>) <i>II</i>	15	Auguste Comte <i>IV, V</i>	19
— (cité d') <i>II</i>	21	Aumaire <i>III</i>	24
Autoiue-Dubois <i>IV, V</i>	19	Aumale (d')	21
Antoiuette	20	Austerlitz (quai & pont d') (<i>AE, TS 8 & 9</i>) <i>V</i>	25
Anvers (place d')	20	Auteuil (rue, gare, porte d') (<i>A, AH, TO</i>)	1
Apenius (des)	16	— (place d') (<i>AH</i>)	4
Appert	6	Avron (d') (<i>TS II</i>)	34
Aqueduc (de l')	26		
Arago (boulev.) (<i>J, K, U; TG</i>)	20		
— (école)	31		
Arbalète (de l')	22	Babylone (de) (<i>AH</i>) <i>IV</i>	16
Arbre-Sec (de l') <i>III</i>	20	Bac (du) (<i>X, Y</i>) <i>II, IV</i>	17
Arc de triomphe du Carrousel (Pl. du Carr.) <i>II</i>	17	Bacon	8
— de l'Etoile (<i>C, AB, TD, TN, TP, TN A, TS 3</i>) <i>I</i>	12	Bagnoux (de) <i>IV</i>	16
Arc-de-Triomphe (de l')	12	Baguiolet (de) (<i>P</i>)	32
Arcade (de l') <i>II</i>	18	— (porte & route de)	36
Archevêché (quai et pont de l') <i>V</i>	22	Baillet <i>III</i>	20
Archives (des) <i>III</i>	23	Bailleul <i>III</i>	20
Archives Nationales <i>III</i>	23	Baillif <i>II, III</i>	21
Arcole (pont & rue d') <i>V</i>	23	Bailly <i>III</i>	24
Arcueil (d')	21	Balaguy	16
— (porte d')	21	Balkaus (des)	35
		Ballu	17
		Baltard (<i>J, TF, TQ</i>) <i>III</i>	20
		Balzac <i>I</i>	12

B. R. G.		B. R. G.	
Banque (de la) (V)	21	Beccaria	28
Banque de France (V) II, III	21	Becquerel	20
— d'Escompte	21	Beethoven	8
Banquier (du)	23	Bel-Air (avenue du) (TS 9)	31
Bara	16	— (station du)	34
Barbanègre	28	Belfort (de)	29
Barbès (boul.) (TI)	23	Belgrand	36
Barbet-de-Jouy	IV 13	Bellart	IV 13
Barbette	III 26	Bellay (du)	V 22
Bargue (rue & passage)	13	Bellechasse (de) (Y, AD) II, IV	17
Baron	16	— (place de)	II 14
Barouillère (de la)	IV 13	Bellefond	21
Barrault (pas.)	23	Belles-Feuilles (des)	I 9
Barrault	21	Belleville (de) (M)	30
Barre (de la)	20	— (boul. de) (TE)	30
Barres (des)	V 23	Bellevue (de)	33
Barthélemy	IV 13	Belliard	22
Basfour (passage)	III 24	Bellièvre	25
Basfroï	29	Bellini	I 8
Bas-Meudon (porte du)	4	Belloni	13
Bassano	I 12	Bellot	26
Basse-du-Rempart (E, X, AB, AC)	II 18	Belloy (de)	I 12
Bassins (des)	I 12	Bel-Respiro (du)	12
Bassompierre	V 25	Belzunce	24
Bastille (de la)	V 25	Bénard	17
— (pl. de la) (E, F, P, R, S, Z, TC, TK, TL, TS 4 & 10) V	25	Bénédictines (couv. de) IV	13
Batignolles (des) (G)	17	Benouville	6
— (boul. des) (G, TD, TP)	17	Béranger	III 27
— (place des) (G)	14	Bercy (de)	V 25
Battoir (du)	V 22	— (boul. & pont de) (TS 9)	28
Bauches (des)	5	— (entrepôts, quai, port, & porte de) (TK)	29
Baudelique	22	Berger	III 20
Baudin	24	Bergère (V)	III 21
Baudoyer (pl.) (rue de Rivoli)	V 23	— (citée)	III 21
Baudricourt	27	Bergers (des)	IV 16
Baume (de la)	II 15	Bérîte	IV 18
Bausset	10	Berlin (de)	V 22
Bayard	II 15	Bernardins (des)	V 22
Bayen	12	Bernard-Palissy	IV 16
Béarn (rue & impasse de) V	26	Berne (de)	18
Beaubourg	III 23	Berri (de)	I 15
Beauce (de)	III 23	Berryer	12
Beau-Grenelle (place)	7	Berthe	20
Beauharnais (citée)	31	Berthier (boulevard)	13
Beaujolais (de)	II, III 21	Berthollet	19
Beaujon (rue & hôpital)	12	Bertin-Poirée	III 20
Beaulieu (pass.)	31	Berton	I 8
Beaumarchais (boul.) (E, F, S)	III, V 26	Bertrand	IV 13
Beaume (de)	IV 17	— (citée)	30
Beaunier	18	Berzélius	13
Beauregard	III 24	Bessières (boulevard)	16
Beaurepaire	III 27	Bestiaux (marché aux) (AC, T 9)	31
Beauséjour (boulevard)	5	Béthune (quai de)	V 22
Beautréillis	V 25	Beudant	14
Beauveau (place)	II 15	Beuret	10
Beaux-Arts (des)	IV 20	Bezout	17
— (école des) (V, AG) IV	17	Bibliothèque Mazarine IV	20
		— Nationale (H)	II, III 21
		Bicêtre (porte de)	24

B. R. G.		B. R. G.	
Bichat	III 27	Boulard	17
Bidassoa (de la)	33	Boulay (rue & passage)	13
Bienfaisance (de la)	15	Boule	26
Bièvre (de)	V 22	Boule-Rouge (de la)	III 21
Billancourt (rue & porte de)	1	Boulets (des)	31
Billetes (temple des) III, V	23	Bouloi (du)	III 21
Billy (quai de) (TA, B, AB) I	12	Bouquet-de-Longch. (du) I	9
Biot	17	Bourbon (passage)	10
Birague (de)	V 26	— (quai)	V 22
Biscornet	V 25	Bourbon-le-Château	IV 19
Bisson	30	Bourdon (boulevard)	V 25
Bitche (place de)	I 9	Bourdonnaix (av. de la) I	11
Bizet	I 12	— (des)	III 20
Blainville	V 22	Bouret	26
Blaise	29	Bourg-l'Abbé (r. & pass.) III	24
Blanche (cité)	14	Bourgogne (de) (Y) II, IV	14
— (rue & place)	17	Bourgon	24
Blancs-Manteaux (des)	23	Bourg-Tibourg (du)	V 23
Blene	21	Boursault	14
Bleus (cour des)	III 24	Bourse (palais de la)	III 21
Blomet (X)	IV 10	— (rue & place de la) (F, I, AB)	II, III 21
Blondel	III 24	— de Commerce	III 20
Blottière	14	— du Travail	III 27
Boccador	I 12	Boutarel	V 22
Bochart-de-Saron	20	Boutebrie	V 19
Boétie (la) (B)	15	Bouvines (avenue & rue de)	31
Bœufs (ancien chemin des)	14	Boyer	33
Boieldieu (place)	II 21	Brady (passage)	III 24
Boileau	1	Brancion (r. et porte)	11
Bois (du)	33	Brantôme	III 23
Bois de Boulogne (av. du) I	9	Braque (de)	III 23
— (passage du)	III 24	Bréa	IV 16
Bois-le-Vent	5	Brèche-aux Loups (r. de la)	31
Boissière	I 9	Bréda (rue & place)	21
Boissonnade	16	Bréguet	V 26
Boissy-d'Anglas	II 18	Brémontier	11
Boiton (passage)	24	Bretagne (de) (D, U)	III 26
Bolivar (M)	30	Breteuil (av. & place de) IV	13
Bonaparte (Q, V, AD, AG) IV	20	Bretonvilliers	III 22
— (quartier)	II 17	Brey	12
Bondy (de)	III 24	Brézin	17
Bon-Marché (magas. du) (V, X, AG, AH)	IV 16	Bridaine	14
Bonne-Nouvelle (boul.) (E, Y)	24	Brignole (de)	I 12
Bons-Enfants (des)	II, III 21	Brisemiche	III 23
Borda	III 24	Brissac	V 25
Borrégo (du)	36	Broca	20
Borromée	10	Brochant	14
Bosquet (avenue) (TS 3) I	11	Brosse (de)	V 23
Bossuet	24	Broussais	20
Botzaris	30	Bruant	26
Bouchardon	III 24	Brune (boulevard)	15
Boucher	III 20	Brunel	9
Boudon (avenue)	4	Bruxelles (de)	17
Boudreau	II 18	Bucherie (de la)	V 22
Bouffes-Paris. (théâtre des) II	21	Buci (de)	IV 19
Boufflers (avenue)	1	Budé	V 22
Bougainville	IV 14	Buffon	V 22
Boulainvilliers (de) (A)	4	— (lycée) (X, AG)	22
Boulangers (des)	V 22	Bugeaud (avenue)	I 6
		Buisson-Saint-Louis (du)	27

B. R. G.		B. R. G.	
Bnot	24	Célestins(quaides) (<i>U, TC</i>) <i>V</i>	22
Burnouf.	27	Cels	16
Bnrq	20	Cendriers (des)	30
Bntte-aux-Cailles (de la)	31	Censier	22
Buttes (des)	23	Cerisaie (de la)	25
Bnttes-Chaumont (parc des)	30	Cérisoles (de)	12
Buzenval (de)	31	Cévennes (des)	7
		Chabanaïs	21
Oabanis	20	Chabrand (cité)	18
Cadet	21	Chabrol (de) (<i>B</i>)	24
Cafarelli	27	Chaillot (de)	12
Cail	23	Chaise (de la)	16
Caillaux (impasse)	27	Chalet (du)	27
Caillié	26	Chalgrin	9
Caillonx (des)	10	Chaligny	28
Caire (pl. & rue du)	24	Châlons (de)	28
Caisse des Dépôts	17	Chamaillards (des)	27
Calais (de)	17	Chambertin	28
Cambacères	15	Chambéry (de)	11
Cambon	18	Chambiges	12
Cambrai (de)	28	Chambre des députés (<i>AF, TL, TM</i>)	14
Cambronne (r. & pl.) (<i>TS 5</i>)	10	Champagny	14
Camon	11	Champ-de-l'Alouette (du)	20
Campagne-Première	16	Champ-d'Asile (du)	17
Campo-Formio (de)	23	Champ-de-Mars (<i>Y, TS 5</i>) <i>I</i>	11
Canal St-Denis	28	— (du)	11
— St-Martin (& rue du)	27	— (stat. du)	8
— de l'Onrcq	29	Champerret (porte de)	8
Canettes (des)	19	Championnet	19
Canivet (du)	19	Champollion	19
Caplat	23	Champs-Elysées(avenue des)	
Capron	17	(<i>A, C</i>)	15
Capucines (boul. & r. des)		Chanaleilles (de)	13
(<i>E, X, AB, AC</i>)	18	Chanez	1
Cardinale	19	Change (pont au)	20
Cardinal-Lemoine(<i>G, K, Z</i>) <i>V</i>	22	Chanoinesse	22
Cardinet	14	Chantiers (des)	22
Carmes (des)	22	Chanudet	14
Carnavalet (musée) (<i>F</i>) <i>V</i>	26	Chapelle (bonlevard de la)	
Carnot (avenue)	12	(<i>TD, TP, TNE</i>)	23
Caroline	17	— (cité & place de la)	23
Caron	26	— (r. & stat. de la) (<i>TH, TN F</i>)	22
Carrières (des)	32	— Expiatoire	18
— (des)	36	Chapon	24
Carrousel (place & pont du)		Chappe	20
(<i>H, X, Y, AG</i>)	20	Chaptal	18
Cascades (des)	33	— (collège)	15
Casimir-Delavigne	19	Charbonnière (de la)	23
Casimir-Périer	14	Chardin	8
Casino de Paris (<i>G</i>)	18	Charente (quai de la)	28
Cassette	16	Charenton (<i>TK</i>)	36
Castellane	18	— (de) (<i>S</i>)	28
Castex	25	— (porte de) (<i>S</i>)	32
Castiglione (de)	18	Charité (hôpital de la) <i>IV</i>	17
Catacombes (entrée des)	17	Charlemagne (lycée)	23
Catalogne	8	— (rue et passage)	23
Catinat	21	Charles V	25
Caulaincourt	20	Charles-Dallery	28
Caumartin	18	Charles-Nodier	20
Cavé	23	Charlot	26
Cavendish	29		

B. R. G.		B. R. G.	
Charolais (du)	28	Ciseaux (des)	IV 19
Charonne (de)	32	Cité (île de la)	V 20
— (boulevard de) (<i>P, TE</i>)	31	— (r. & quai de la) (<i>G, L</i>)	V 23
Charras	18	Cîteaux (de)	28
Charretière	V 19	Civry (de)	1
Chartres (de)	23	Clairault	17
Chasseloup-Laubat	20	Clapeyron	17
Château (du)	17	Claude-Bernard (<i>TQ</i>)	19
Châteaubriand	12	Claude-Decaen	31
Châteaudun (du)	24	Claude-Lorrain	1
— (théâtre du)	III 27	Claude-Pouillet	14
Château-des-Rentiers (du)	26	Claude-Vellefaux	III 27
Châteaudun (de) (<i>B, H, I, AG</i>)	21	Clansel	21
Château-Landon (de)	26	Clavel	30
Châtelain	14	Clef (de la)	V 22
Châtelet (pl. & théâtre du)		Clément	IV 19
(<i>C, G, J, K, O, Q, R, AD,</i>		Clément-Marot	I 12
<i>TC, H, & K</i>)	V 20	Cler (<i>AD</i>)	I 11
Châtillon (avenue de) (<i>TS I</i>)	18	Cléry (de)	III 24
— (porte de) (<i>TS I</i>)	15	Clichy (& porte de) (<i>TN D</i>)	13
Chauchat	II, III 21	— (rue de) (<i>G</i>)	18
Chaudron	26	— (av. de) (<i>H, TN D & E</i>)	17
Chaufourniers (des)	27	— (boul. de) (<i>H, I, TD, TP</i>)	20
Chaume (du)	III 23	— (place de) (<i>G, H, TD, TP,</i>	
Chaumont (porte)	32	<i>TN D & E</i>)	13
Chaussée-d'Antin (de la) (<i>G</i>)	18	Clignancourt (de)	23
<i>II</i>	5	— (porte de)	19
— de la Muette	24	Clisson	26
Chausson (passage)	III 18	Cloche-Perce	V 23
Chauveau-Lagarde	II 18	Cloître-Notre-Dame (du)	V 22
Chauvelot	11	Cloître-St.-Merry (du)	III 23
Chazelles	12	Clopin	V 22
Chemin-Vert (du)	V 29	Clos (du)	35
Chénier	24	Clotilde	V 19
Cherche-Midi (du) (<i>V</i>)	IV 13	Clovis	V 22
Chérubini	II 21	Cloys (des)	19
Cheval-Blanc (passage du)	V 25	Cluny (r. & musée de) (<i>J, L,</i>	
Chevaleret (r. & chemin du)	29	<i>TG, TH, TQ, TS 6 & 7</i>)	V 19
Chevert	IV 14	Cochin	V 22
Chevreuse (de) (<i>B. du M.-P.</i>)	16	— (hospice)	20
— (Issy)	6	Coëtlogon	IV 16
Chine (de la)	33	Colbert (rue & pass.)	II, III 21
Choiseul (rue & passage)	II 21	Coligny (de)	V 25
Choisy (avenue & porte de)	27	Colisée (du)	II 15
Chomel	IV 16	Collège de France (<i>Z, TH</i>)	
Choron	21	<i>V</i>	19
Christiani	23	Colombe (de la)	V 23
Christine	IV, V 20	Colonnes (des)	II, III 21
Christophe-Colomb	I 12	Combes	I 11
Cimarosa	I 9	Comète (de la)	IV 14
Cimetière du Mont-Parnasse		Commandant-Rivière (du)	15
(<i>Q, TS 1 & 2</i>)	16	Commandeur (du)	17
— du Père-Lachaise (<i>P, TE</i>)	32	Commerce (Bourse de)	III 20
— Montmartre (<i>H, TD, TP</i>)	17	— (Chambre de)	III 21
— Montmartre (avenue du)	17	— (Minist. du)	IV 17
Cinq-Diamants (des)	23	Commerce (tribunal de)	V 20
Cirque (du)	II 15	Commines	III 26
Cirque d'Été (<i>A, C</i>)	II 15	Compans (rue & impasse)	33
— d'Hiver (<i>D, E, O, S</i>)	III 27	Comptoir d'Escompte	III 21
— Fernando (<i>I, TD, TP</i>)	20	Conciergerie	V 20
— Nonveau (<i>D</i>)	II 18	Concorde (place & pont de	

B. R. G.

B. R. G.

la) (<i>A, C, AC, AF, TA, TB, TAB, TJ</i>)	11	18	Croix-Nivert (<i>TS 2 & 5</i>)	10	7
Condamine (de la)	17	18	Croix-Ronge (carr. de la) <i>IV</i>	16	16
Condé (de)	19	19	Crouin (passage)	26	26
Condorcet	21	21	Croulebarbe	23	23
— (lycée)	18	18	Crozatier	28	28
Conférence (quai de la) (<i>TA, B & AB, TI</i>)	15	15	Crussol (rue & cité de) . <i>III</i>	27	27
Conflans	36	36	Cugnot	25	25
Conseil d'Etat	20	20	Cujas	19	19
— de Guerre	16	16	Cunial	25	25
Conservatoire (du)	21	21	Cunstine	23	23
— des Arts et Métiers (<i>L, M, T, TG, TH</i>)	24	24	Cuvier	22	22
— de Musique	24	24	Cygne (dn)	23	23
Constantine (de)	14	14	Cygnès (allée des)	7	7
Constantinople (de) (<i>F</i>)	15	15	Dagnerre	17	17
Conti (quai) (<i>V</i>)	20	20	Dalayrac	21	21
Contrescarpe (boul.) (<i>TK</i>) <i>V</i>	25	25	Dames (des)	17	17
— (place)	22	22	Damesme	24	24
Copernic	9	9	Damiette (de)	24	24
Copreanx	13	13	Damoy (passage)	26	26
Coq (du)	23	23	Damrémont	19	19
Coquillière (<i>F</i>)	21	21	Dancourt (place & rue)	20	20
Corbean	27	27	Dangean	4	4
Corbes (passage)	32	32	Dante (du)	19	19
Corbeinean	28	28	Danton	4	4
Cordelières (des)	23	23	Dantzig (de)	11	11
Cormeilles (de)	7	7	Dannbe (place du)	32	32
Corneille	19	19	Darboy	27	27
Cornes (des)	22	22	Darcet	17	17
Cortot	20	20	Darcy	36	36
Corvisart	20	20	Darean	20	20
Cossonnerie (de la)	23	23	Darn	12	12
Cotentin (du)	13	13	Darnbeuton	22	22
Cotte (de)	28	28	Daubigny	14	14
Cottin (passage)	20	20	Danmesnil (av. & pl.) (<i>TS 10</i>)	31	31
Concons (des)	34	34	— (porte & lac)	35	35
Conesuo	17	17	Daunou	18	18
Courat	35	35	Danphine (pl., r., pass.) (<i>O, AD</i>)	20	20
Conrbevoie	1	1	— (porte)	6	6
Conrnelles (de) (<i>AF</i>)	11	11	Dantancourt	17	17
— (boulevard de) (<i>TD, TP</i>)	15	15	Daval	26	26
— (porte de)	11	11	David-d'Angers	32	32
Cour-des-Noues (de la)	32	32	Davonst (boulevard)	34	34
Couronnes (r. & imp. des)	30	30	Davy	16	16
Cours-la-Reine (<i>TA, TB, TAB, TJ</i>)	15	15	Débarcadère (du)	9	9
Courty (de)	17	17	Debelleye	26	26
Contellerie (de la)	23	23	Debilly (quai) (<i>TA, TB, TAB</i>)	12	12
Coutures-St-Gervais (des) <i>III</i>	26	26	Debronsse	12	12
Crébillon	19	19	Decamps	9	9
Crédit Foncier	18	18	Déchargens (des)	20	20
— Lyonnais (<i>E</i>)	21	21	Dechéro	14	14
Crevaux	9	9	Decrès	14	14
Crillon	25	25	Degnerry	27	27
Crimée (de)	29	29	Déjazet (théâtre)	27	27
Croisades (des)	14	14	Delambre	16	16
Croissant (du)	21	21	Delessert	8	8
Croix-des-Petits-Champs (<i>F, I, N, V</i>)	21	21	Delorme (passage)	18	18
			Delouvain	33	33
			Delta (du)	23	23

B. R. G.		B. R. G.	
Demours	11	Dumont-d'Urville	I 12
Denain (boul. de) (<i>K, V, AC</i>)	24	Dunkerque (de)	24
Denfert-Rochereau	IV 19	Dunois	26
— (place) (<i>TG, TS I</i>)	17	Duperré	20
Denoyez	30	Dupetit-Thouars	III 27
Deparcieux	17	Duphot	II 18
Départ (du)	16	Dupin	IV 16
Département (du)	26	Dupleix (place et rue)	I 10
Dépotoir (du)	32	Dupont (cité)	29
Députés (chambre des) (<i>AF, TL, TM</i>)	II 14	Dupuis	III 27
Desaix	I 10	Dupuytren	IV, V, 19
Desbordes-Valmore	5	Duquesne (avenue)	IV 13
Descartes	V 22	Durance (de la)	31
Descombes	8	Duranti	29
Desgenettes	II 14	Durantin	20
Désir (passage du)	III 24	Duras (de)	II 15
Desnouettes	8	Duret	I 9
Desprez	14	Duris	33
Desrenaudes	12	Duroc	IV 13
Deux-Ecus (des)	III 20	Dussoubs	III 24
Deux-Gares (des)	24	Dutot	13
Deux-Ponts (des) (<i>T, Z</i>)	V 22	Duvivier	I, IV 14
Diderot (boulevard) (<i>TM</i>)	V 25	Eaux (passage des)	I 8
Didot	17	Eblé	IV 13
Dier (passage)	13	Echaudé (de l')	IV 19
Dieu	III 27	Echelle (de l')	II 21
Dijon (de)	29	Echiquier (de l')	III 24
Domat	V 22	Ecluses-Saint-Martin (des)	27
Dombasle	11	Ecole Centrale (nouv.)	III 24
Dôme (du)	I 9	— de Droit	V 19
Dominicaines de la Croix	28	— de Médecine	V 19
Domrémy (de)	26	— (rue et place de l')	V 19
Doré (cité)	26	— de Pharmacie	IV 19
Dorian	31	— des Beaux-Arts (<i>V, AG</i>)	IV 17
Dosne	9	— des Mines (<i>TG</i>)	IV 19
Douai (de) (<i>H</i>)	20	— des Ponts-et-Chauss.	IV 17
Douane (hôt. & rue de la)	III 27	— d'Etat-Major	IV 14
Doubles (pont aux)	V 22	— Militaire (<i>V, AD, AH, TS 3 & 5</i>)	IV 10
Doudeauville (rue et pass.)	23	— Normale supérieure	V 19
Douze-Maisons (pass. des)	I 12	— d'Auteuil et J.-B. Say	I 1
Dragon (rue et cour du)	IV 16	— Polytechnique	V 22
Drevet	20	— (de l')	V 22
Droit (école de)	V 19	Ecoles (des) (<i>K, Z, TH</i>)	V 22
Drouot (<i>I</i>)	II, III 21	Ecosse (d')	V 19
Dubail (passage)	III 24	Ecouffes (des)	V 23
Duban	5	Ecuries-d'Artois (des)	II 15
Dubois (passage)	29	Edgar-Quinet	16
Ducange	14	Edimbourg (d')	15
Ducouëdic	17	Edmond-Valentin	24
Duée (de la)	17	Eginhard	V 26
Dufrénoy	6	Eglise (de l')	7
Dugommier	31	Elysée (pal. & rue de l')	II 15
Duguay-Trouin	IV 16	— (passage de l')	20
Duguesclin	I 10	— Montmartre	20
Duhesme	19	Elzévir	III 26
Dulac (passage)	13	Emeriau	I 7
Dulaure	20	Enfants Malades (hôt. des)	IV 13
Dulong	14	Enf.-Rouges (marché d.)	III 26
Dumas (passage)	31	Enfer (boul. d') (<i>TS 1 & 2</i>)	IV 16
Duméril	22		

B. R. G.		B. R. G.	
Enfer (passage d')	16	Fédération (de la)	I 10
Enghien (hospice d')	31	Félicien-David	4
— (d') (T)	24 24	Félicité (de la)	14
Entrepôt (de l')	27	Fénelon (cité)	24
Entrepreneurs (des)	7 7	— (lycée)	V 19
Envierges (rue, cité, & pas- sage des)	30	Fer-à-Moulin (du)	22
Epée-de-Bois (de l')	22	Ferdinand-Berthoud	III 24
Eperon (de l')	V 19	Fermat	17
Epinettes	16	Fermiers (des)	14
Erard	28	Feron	IV 19
Erlanger	1 1	Ferronnerie (de la)	III 23
Ermitage (rue & villa de l')	33	Ferrus	20
Ernestine	23	Fessard (rue & impasse)	30
Esperance (de l')	24	Fêtes (rue & place des)	33
Esquirol	23	Feuillade (de la)	II, III 21
Est (de l')	33	Feuillantines (des)	V 19
Est (gare de l') (B, M, TG, TH, TI)	24	Feuillants (des)	II 18
Estrapade (rue & pl. de l') V	19	Feuillet (passage)	27
Estrées (d') (AH)	IV 13	Feutrier	20
Etat-Major (école d')	IV 14	Feydeau	III 21
Etats-Unis (place des)	I 9	Fidélité (de la)	III 24
Etex	17	Figuier (du)	V 22
Etienne-Dolet (O)	30	Filles-du-Calvaire (boul. & rue des) (D, E, S)	III 26
Etienne-Marcel	III 21	Filles-Dieu (des)	24
Etoile (de l')	I 12	Filles-St-Thomas (des) II, III	21
— (rond-point de l')	I 12	Finances (min. des)	II 20
Etuves	III 23	Flandre (de) (I, TN G)	26
Engène-Delacroix	5	— (pont & route de)	28
Eugène-Gibez	11	Flandrin (boulevard)	6
Euler	I 12	Fleurs (quai aux) (K)	V 22
Eupatoria (d')	30	Fleurus (de)	IV 16
Europe (pl. del') (TN D & E)	18	Florence (de)	17
Evangile (de l')	25	Foin (du)	V 26
Exelmans (boulevard)	1	Folie-Méricourt (de la) III	27
Exposition (de l')	I 11	Folie-Regnault (de la)	29
Eylau (avenue)	I 9	Folies-Dram. (th. des) III	27
Fabert	II 14	Fondary	10
Fabre-d'Eglantine	31	Fontaine	20
Fagon	23	Fontaine-du-But (de la)	19
Faisanderie (de la)	6	— aux-Clercs (de la)	24
Fallempin (passage)	7	— Mulard (de la)	24
Faraday	8	— au-Roi	III 27
Fanbourg - du - Temple (dn) (N)	27	Fontaines (des)	III 24
— Montmartre (du) (J, V) III	21 21	Fontarabie (de)	32
— Poissonnière (du) (T, V)	24 24	Fontary	10
— St-Antoine (du) (T, C) V	28	Fontenoy (place de)	10
— St-Denis (du) (K, TH, TN G & H)	24 24	Fontis (chemin des)	1
— St-Honoré (dn) (D, R, AB)	15 15	Forest	17
— St-Jacques (du) (J)	19	Forez (du)	III 23
— St-Martin (du) (L, TN G)	27 24	Forges (des)	III 24
Fauconnier (du)	V 22	Fortin (avenue)	23
Favart	II, III 21	Fortuny	11
Favorites (des)	10	Fossés-St-Bernard (des)	V 22
Fécamp (de)	32	— St-Jacques (des)	V 19
		Fouarre (du)	V 22
		Fougeat (passage)	10
		Four (du)	16
		Fourcy (de) (Z)	V 23
		Fourneaux (r. & ch. des) IV	13
		Foyatier	20

B. R. G.

B. R. G.

Français (théâtre)	II	21	Gatines (des)	33
Française	III	24	Gandon (ruelle)	27
Francoeur		19	Gauthey	16
François-Gérard		4	Gavarni	8
François-Miron	V	23	Gay-Lussac (<i>J, TQ</i>)	19 19
François Ier (maison de)	II	15	Gaz (rue & impasse du)	26
— (rue & place)	I, II	15	Gazan	21
Francs-Bourgeois (des) (<i>F</i>)	III, V	23	Général-Brunet (du)	32
Franklin (<i>A</i>)	I	8	Général-Foy (du)	15
Frémicourt (<i>I</i>)		10	Genève (de)	28
Frères (Institut des)	IV	13	Gentilly	24
Fresnel	I	12	— (porte et station de)	21
Freycinet	I	12	— (de)	23
Friedland (av. de) (<i>AB, TN</i>)		12	Geoffroy-Didelot	14
Frochot		20	Geoffroy-Langevin	23
Froissart	III	26	Geoffroy-Lasnier	23
Froment		26	Geoffroy-Marie (<i>J</i>)	21
Fromental	V	19	Geoffroy-St-Hilaire (<i>G, K</i>)	22
Fromentin		20	Géorama (du)	17
Fulton		25	George Sand	4
Farstenberg (r. & pl.) <i>IV</i>		20	Gérando	20
			Gérard	23
Gabon (du)		34	Gerbier	29
Gabriel (avenue)	II	15	Gerbillon	16
Gabrielle		20	Gergovie (de)	14
Gaillard		18	Germain-Pilon	20
Gaillon	II	21	Gesvres (quai de) (<i>O, TC</i>)	23
Gaîté (rue & impasse de la)		16	Ginoux	7
— (théâtre de la)	III	24	Girardon	20
Galande	V	22	Gironde (quai de la)	28
Galilée	I	12	Gît-le-Cœur	19
Galliera (r. & musée de)		12	Glacière (de la) (<i>U</i>)	20
Galvani		8	Glaissière (de la)	6
Gambey	III	27	Gluck	18
Ganneron		17	Gobelins (av., rue, & man. des) (<i>U, TQ, TS 6</i>)	23
Garancière	IV	19	Godefroy-Cavaignac	29
Garde-Meuble (<i>TL, TM</i>)	I	11	Godot-de-Mauroy	18
Gardes (des)		23	Gœthe	12
Gare de l'Est (<i>B, M, TQ, TH, TI</i>)		24	Gomboust	18
— de Lyon (<i>R, TM, TS 4</i>)		28	Gourgand (avenue)	11
— de Seaux (<i>J, TQ, TS 1 & 2</i>)		20	Goutte-d'Or (de la)	23
— de Vincennes		25	Gouvion-St-Cyr (boulevard)	8
— d'Orléans (<i>P, T, AE, TM, TS 2, 3, & 9</i>)		25	Gozlin (rue & place)	19
— du Nord (<i>K, V, AC, TH, TI</i>)		24	Gracieuse	22
— Montparnasse (de l'Ouest, rive gauche) (<i>O, TS 1, 2, 3, & 4</i>)		16	Grammont (de)	21
— St-Lazare (de l'Ouest, rive droite) (<i>B, F, X, AI</i>)		18	Grand-Cerf (passage du)	24
— (boul. de la) (<i>TS 7 & 8</i>)		26	Grand-Prieuré (du)	27
— (porte de la)		30	Grande-Armée (avenue de la) (<i>C, TN A</i>)	9
— (quai de la) (<i>AE</i>)		29	Grande-Chaumière (de la)	16
— (de la)		4	Grande-Truanderie (d.l.)	23
Gares (des Deux-)		24	Grandes-Carrières (ch. des)	16
Garibaldi (boul.) (<i>Z</i>)		10	Grands-Augustins (rue & quai des)	20
Gaston-de-St-Paul	I	12	Grands-Champs (des)	34
Gatbois (passage)		28	Grange-Batelière (de la)	21
			Grange-aux-Belles	27
			Gravelle (avenue de)	36
			Gravilliers (des)	24
			Grefulbe	18

B. R. G.

B. R. G.

Grégoire-de-Tours	IV	19	Henri IV (boul. et quai) (U, TC, TL)	V	25
Grenelle (de) (Y, AF) I, IV	14	14	— (lycée)	V	22
— (boul. de) (TS 5)	I	10	Henri-Regnault		18
— (gare et quai de)	I	7	Héricart		7
— (pont et stat. de) (AH)	4	7	Hermel		19
Grenéta	III	24	Hérolde	III	21
Grenier-sur-l'Eau	V	23	Herr		7
Grenier-St-Lazare	III	23	Herschell	IV	19
Grétry	II	21	Hippodrome (A, TA, TB, TAB, TJ, TL, TM, TS 3) I		12
Greuze	I	9	Hirondelle (de l')	V	19
Gribeauval	IV	17	Hoche (avenue)		12
Gros	4	8	Honoré-Chevalier	IV	16
Grotte (de la)		25	Hôpital(boul. & pl. de l') (P) V		25
Guadeloupe (de la)		1	Hôpital-Saint-Louis (de l')		27
Gudin		20	Horloge (quai de l')	V	20
Guénégaud	IV, V	31	Hospices (des)		27
Guénot (cité)		24	Hospitalières-Saint-Gervais (des)	III	23
Guérin-Boisseau	III	24	Hôtel-Colbert (de l')	V	22
Guerre (min. de la) II, IV		17	Hôtel-Dieu	V	23
Guersant	9	9	Hôtel de ville (C, O, Q, T, AD, TC, TK)	V	23
Guichard	5	11	Hôtel-de-Ville (r., quai, & pl. de l') (C, Q, AD, TC, TK) V		23
Guilhem	29	23	Houdart (passage)		30
Guillaume-Tell	11	21	Houdon		20
Guillemites (des)	III	23	Huchette (de la)	V	19
Guimet (musée) (A, B, TJ) I		12	Humboldt		20
Guisarde	IV	19	Huygens		16
Gutenberg	III	21	Iéna (avenue d')		12
Guy-Labrosse	V	22	— (place d') (A, B, TJ) I		12
Guyot	11	23	— (pont d') (TA, TB, TAB) I		8
Guy-Patin	23	24	Immaculée-Conc. (coll. de l')		8
Gymnase (théâtre du)	III	35	Immeubles Industriels (des)		31
Haies (des)		32	Imprimerie Nationale	III	23
Hainaut (du)	II	18	Industrie (pal. de l') (A, C) II		15
Halévy	II	17	Ingres (avenue)		5
Hallé		22	Innocents (des)	II	20
Halle-aux-Vins	V	20	Institut de France	IV	20
Halles - Centrales (D, F, J, TF, TQ)	III	20	— (place de l')	IV	20
Halles (des)	III	20	— Catholique (Z)	IV	16
Hambourg (de)	18	8	— Pasteur		13
Hameau (du)		9	Instruction Publique (ministère de l')	IV	17
Hamelin	I	21	Intérieur (min. de l')	II	15
Hanovre (de)	II	20	Invalides (boul. des) (TS 5)		13
Harlay (de)	V	19	— (hôtel des) (Y, AD)	IV	14
Harpe (de la)	V	26	— (espl. & pont des) II, IV		14
Harvey		23	Irlandais (des)	V	19
Haudriettes (des)	III	18	Islettes (des)		23
Hausmann (boulevard) (TN, TND & E)	II	19	Isly (de l')	II	18
Hautefeuille	V	24	Issy (porte d')		8
Hauteville (d')	III	22	Issy (TS 2 & 5)		6
Haut-Pavé (du)	V	29	Italie (avenue & porte d') (TS 6 & 8)		24
Hautpoul (d')		18	— (boulevard & place d') (P, TS 6 & 8)		23
Havre (du)	II	36			
Haxo		25			
Hébert (place)		21			
Helder (du)	II	17			
Hélène		33			
Henri-Chevreau		9			
Henri-Martin (av.) (TN) I	I				

B. R. G.

B. R. G.

B. R. G.		B. R. G.	
Italiens (boul. des) (<i>E, H</i>)	21	Justice (palais de) (<i>J, K, Q</i>)	20
II, III	30	AI, TG, TH	18
Ivry (<i>TS 7</i>)	27	Justice (min. de la) II	29
— (av. & porte d') (<i>T, Q</i>)	23	Keller	24
Jabach (passage)	22	Kellermann (boulevard)	12
Jacob	17	Képler I	9
Jacquemont	20	Kléber (av.) (<i>B, TN, TP</i>) I	24
Jacques-Cœur	25	Kuss	20
Janson de Sailly (lycée)	6	La Barre (de)	23
Jardin d'Acclimatation	3	Labat	9
— de Paris	15	Labie	15
— des Plantes (<i>P, T, AE, TM, TS 4, 8, & 9</i>)	22	La Boétie (<i>B</i>)	25
Jardinnet (dn)	19	Labois-Rouillon	18
Jardiniers (des)	32	Laborde (r. etsq. de) (<i>AF</i>) II	11
Jardins-Saint-Paul (des)	22	La Bourdonnais (av. de) I	14
Jarente (de)	26	Labrouste	21
Javel (quai de)	4	La Brnyère	16
— (de)	7	Lacaille	18
Jean-Bart	16	Lacaze	22
Jean-Beansire (r. & imp.)	26	Lacépède	16
Jean-de-Beauvais	19	La Chaise (de)	29
Jean-Bologne	5	Lacharrière	17
Jean-Cottin	25	La Condamine (de)	7
Jean-Goujon	15	Lacordaire	16
Jean-Jacq.-Ronsseau (<i>I</i>) III	21	Lacroix	25
Jean-Lantier	20	Lacnée	16
Jean-Nicot	14	Laënnec (hôpital) (<i>X, AG</i>) IV	21
Jean-Robert	23	La Fayette (<i>B, M, AC, TNF, G & H</i>) II	24
Jean-Tison	20	— (place) (<i>V, AC</i>)	21
Jeanne	14	Laferrière (passage)	21
Jeanne-d'Arc (r. & pl.) (<i>TS 7</i>)	26	La Feuillade (de) (<i>I</i>) III	21
Jemmapes (quai de)	27	Lafitte (<i>B, E, H</i>) II, III	21
Jenner	26	La Fontaine (de) (<i>A</i>)	4
Jessaint (rue & place)	23	Laghouat (de)	23
Jen-de-Boule (pass. du) III	27	Lagny (de)	34
Jen-de-Paume	18	Lahire	26
Jeunes-Aveugles (inst. des) I V	13	Lakanal	10
Jennes Détenus (prison des)	29	Lalande	17
Jeûneurs (des)	21	Lallier	20
Joinville (de)	29	Lamarck	20
Joquelet	21	Lamartine	21
Joseph-Dijon	19	— (square)	6
Joubert	18	Lamblardie	31
Jouffroy	11	La Michodière (de)	21
— (passage)	21	La Motte-Piquet (avenue de) (<i>Y, TS 5</i>) I	10
Jour (du)	21	Lancette (de la)	31
Jourdan (boulevard)	21	Lancry (de)	27
Jouvenet	1	Landrien (passage)	11
Jony (de)	23	Langnedoc (de)	22
Juge	7	Lanneau (de)	19
Juifs (des)	23	Lannes (boulevard)	9
Jnigné (de)	12	Lannois	7
Jnillet (colonne de)	25	Lantier	16
Jnles-César	25	La Péronse	12
Julien-Lacroix	30	Laplace	22
Juliette-Lambert	11	Lappe (de)	25
Jnra (dn)	22	La Quintinie	10
Jussienne (de la)	21		
Jussien (r. & pl. de) (<i>G, K</i>) V	22		

B. R. G.		B. R. G.	
Lard (au)	III 20	Lingerie (de la)	II 20
La Reine (cours) (<i>TA, TB, TAB, TJ</i>)	I, II 15	Linné (<i>G, K</i>)	V 22
La Reynie (de)	III 23	Linois (<i>AH</i>)	7
Lariboisière (hôpital)	23	Lions (des)	V 25
La Rochefoucauld (hospice)	17	Lisbonne (de) (<i>A, F</i>)	15
— (de)	21	Litré	IV 16 16
Laromiguière	V 19	Loban (place)	V 23
Las Cases (de)	IV 17	Lobineau	IV 19
Latérale	11	Logelbach (de)	14
Latour-Maubourg (boulev.) (<i>TS 8</i>)	II, IV 14	Loire (quai de la)	29
Latran (de)	V 19	Lombards (des)	III 23
Laugier	11	Londres (de)	18
Laumière (avenue)	29	Longchamp (de) (<i>B</i>)	I 9
Laurent-Pichat	I 9	Loos (de)	III 27
Lauriston	I 9	Lord-Byron	I 12
Lauzun	30	Lorraine (de)	29
Lavandières (des)	III 20	Louis-Blanc	27
Lavoisier	II 18	Louis-Braille	34
La Vrillière (de)	II, III 21	Louis-David	8
Lazaristes (des)	IV 16	Louis-le-Grand (lycée)	V 19
Leblanc	4	Louis-le-Grand	II 18
Lebouis	13	Louis-Philippe (<i>T</i>)	V 23
Lebouteux	14	Louis-Thuillier	V 19
Lebrun	22	Lourcine (de)	20
Lécluse	17	Lourmel	7
Lecourbe (<i>TS 2 & 5</i>)	IV 10	Louvois	II, III 21
Ledru-Rollin (avenue) (<i>P</i>)	V 25	Louvre, (pal., quai, & rue du) (<i>C, D, H, N, V, AG, TA, TB, TAB, TF, TJ, TK</i>)	II, III 20
Lefèvre (boulevard)	11	Lowendal (av. de) (<i>AH</i>)	IV 13
Lefort	19	Lubeck (de)	I 9
Legendre (<i>AJ</i>)	14	Lully	II 21
Légion d'Honneur (pal.)	II 17	Lune (de la)	II 24
Lemaignan	21	Lunéville (de)	29
Lemaire	7	Lutèce (de)	V 20
Lemarrais	1	Luxembourg (du) (<i>Q</i>)	16
Lemercier	17	— (palais & jardin du) (<i>H, J, Q, Z, AF, TG, TQ</i>)	IV 19 19
Lemoine (passage)	III 24	Lyannes (des)	36
Lemoult	7	Lyon (de) (<i>R, TS 4 & 10</i>)	25
Le Nôtre	I 8	— (gare de) (<i>R, TS 4</i>)	28
Léon	23		
Léonard-de-Vinci	I 9		
Léonce-Regnaud	I 12	Mabillon	IV 19
Lepage (cité)	27	Mac-Mahon	11
Le Peletier (<i>H</i>)	II, III 21 21	Macdonald (boulevard)	31
Lepic	20	Madame	IV 16
Leregrattier	V 22	Madeleine (boul., égl., marché, & pl. de la) (<i>A, E, X, AB, AC, AF, TNAB, B & C</i>)	18
Leriché	11	Mademoiselle	10
Lesage	30	Madone (de la)	25
Lesdiguinières	V 25	Madrid (de)	15
Lesueur	9	— (porte de)	3
Letellier	10	Magasins Généraux	33
Letort	19	Magdebourg (de)	8
Levallois-Perret (<i>TN C</i>)	7	Magellan	I 12
Levert	33	Magenta (boulevard de) (<i>K, TI, TN G & H</i>)	24 27
Lévis (rue & place de) (<i>F</i>)	14	Mail (du)	III 21
Lhomond	V 19	Maillot (boulevard)	6
Liancourt	17	— (porte) (<i>C, TN A & AB</i>)	9
Lilas (des)	33		
Lille (de)	II, IV 17		
Lincoln	I 12		

B. R. G.		B. R. G.	
Main-d'Or (conr de la) . . .	28	Maternité (hospice de la) . .	19
Maine (avenue du) (V) IV . .	16	Mathis (AJ)	28
— (place & rue du)	16	Mathnrins (des) II	18
Maison-Dien (de la)	17	Matignon (rue & avenue) II .	13
Maison pompeienne I	12	Maubert (place) (I, TL, TM, TS 6 & 7) V	22
Maistre (de) 17		Manbenge (de) (TN 7) . . .	24
Maitre-Albert V	22	Maublanc	10
Malakoff (TS 1 & 2)	12	Maubuée III	23
— (avenue de) I	9	Mauconseil III	21
Malaquais(quai) (V, AG) IV .	20	Mauve (du) III	23
Malar I	11	Maurice (passage)	29
Malebranche V	19	Mauvais-Garçons (des) . . V	23
Malesherbes (bonlevard) (B, AF, TN AB, B & C) . . II	18	Mayet IV	13
Malher V	26	Mayran	21
Malmaisons (des)	27	Mazagran (rue & imp.) III .	24
Malte (de) III	27	Mazarine IV	20
Malte-Brun	33	Mazas (place) V	25
Mandar III	21	Mazet V	19
Manin 29		Meaux (de)	29
Mansart 17		Méchain	20
Manuel 21		Médéah (de)	13
Manutention (de la) I	12	Médecine (école de) . . . V	19
Maraichers (des) 34		Médecins (de) (H, AF, TG) IV, V	19
Maraix (rue & imp. des) III	27	Méglisserie (quai de la) (O, AD, TC) III, V	20
Marbeau 9		Méhl II	21
Marbeuf (avenue & rue) I . .	12	Meinadier 29	
Marcadet 16		Meissonier 11	
Marceau (avenue) (TS 3) I . .	12	Ménages (square des) . . IV	16
Marché-aux-Bestiaux	31	Ménars II, III	21
Marché-des-Blancs-Manteaux (place & rue dn) III	23	Ménilmontant(boul.de)(TE) — (porte de)	30 36
Marché-de-Montr. (pl. du) . .	17	— (de)	33
Marché-Nenf (quai dn)	19	Mercœur	29
Marché-Saint-Honoré (dn) II .	18	Merlin	29
Mare (de la) 33		Meslay III	24
Marengo (de) II, III	20	Mesnil I	9
Marguettes (des) 34		Messageries (des)	24
Marie (pont) V	22	Messine (avenue de) (AF) .	15
Marie-et-Louise III	27	Metz (de)	24
Marie-Stnart III	24	Menniers (ruelle des) . . .	32
Marie-Thérèse (hosp.)	16	Meyerbeer II	18
Margnan (de) I	12	Mézières (de) IV	16
Marigny (avenue) II	15	Michal	24
Marine (min. de la) II	18	Michel-Ange	1
Mariniers (sentier des)	14	Michel-Bizot	34
Marivaux II	21	Michel-le-Comte III	23
Maroc (rue & place du)	26	Michodière (de la) II	21
Maronites (des) 30		Midi ou Ricord (hôpital du)	19
Marronniers (des) 5		Mignon V	19
Marseille (de) III	27	Mignottes (des) 33	
Marsollier II	21	Milan (de)	18
Martel III	24	Militaire (école) (V, AD, AH, TS 3 & 5) IV	10
Martignac (rue & cité) IV . .	14	Millaud (avenue) V	25
Martin 8		Milton	21
Martin-Bernard	24	Mines (école de) IV	19
Martyrs (des) (I) 20		Minimes (des) (TG)	26
Masséna (boulevard)	30	Ministère de l'Agriculture IV	14
Masseran IV	13		
Massillon V	22		
Masson 20			

B. R. G.

B. R. G.

Ministère de la Guerre <i>II, IV</i>	17	Montmorency (av. & boul. de)	1
— de la Justice <i>II</i>	18	— (de) <i>III</i>	23
— de la Marine <i>II</i>	18	Moutorgueil <i>III</i>	21
— de l'Instruction Publ. <i>IV</i>	17	Mont-Parnasse (du) (<i>Q</i>) <i>IV</i>	16
— de l'Intérieur <i>II</i>	15	— (boul. du) (<i>Q, TS 1, 3, & 4</i>)	16
— des Affaires Etrang. <i>II</i>	14	— (cimet.) (<i>Q, TS 1 & 2</i>)	16
— des Finances <i>II</i>	20	— (gare) (<i>Q, TS 1, 2, 3, & 4</i>)	16
— des Travaux Publics <i>IV</i>	17		16
Miollis	10	Montrenil (porte de)	34
Mirabeau (<i>A H</i>)	4	— (de)	31
Miracles (cour des) <i>III</i>	24	Montrouge (<i>TG</i>)	15
Mirbel (de)	22	— (porte de)	18
Miroménil (de) <i>II</i>	15	Montsouris (av. & parc) (<i>U</i>)	21
Missions-Etrangères <i>IV</i>	16	Mont-Thabor (du) <i>II</i>	18
Mogador <i>II</i>	18	Montyon (de) <i>III</i>	21
Moines (des)	16	Morand	30
Molière (fontaine & rue) <i>II</i>	21	Moreau <i>V</i>	25
— (lycée)	5	Morère	18
Molitor	1	Moret	30
Monceaux (de)	15	Morgue (la)	22
Monceaux (parc de) (<i>AJ, TD, TP, TN AB, B & C</i>)	15	Morillous (des)	11
Moncey	18	Morland (boulevard) <i>V</i>	25
— (place) ou pl. Clichy	17	Mornay <i>V</i>	25
Mondétour <i>III</i>	23	Mortier (boulevard)	36
Mondovi <i>II</i>	18	Moscou (de)	18
Monge (école)	14	Moselle (de la)	29
— (r. & pl.) (<i>V, TS 6 & 7</i>) <i>V</i>	22	Mouffetard (<i>U</i>) <i>V</i>	22
— (square) (<i>V, TH, TS 6 & 7</i>) <i>V</i>	22	Moulin-de-Beurre (du)	13
Monjol	27	Moulin-de-la-Pointe (du)	24
Monnaie (de la) <i>III</i>	20	Moulin-des-Prés (du)	23
Monnaies (hôtel des) <i>IV, V</i>	20	Moulinet (du)	24
Monsieur <i>IV</i>	13	Moulins (des) <i>II</i>	21
Monsieur-le-Prince <i>IV, V</i>	19	Moulin-Vert (rue & imp. du)	17
Monsigny <i>II</i>	21	Moussy (des) <i>III, V</i>	23
Montagne-Sainte-Geneviève (de la) <i>V</i>	22	Mouton-Duvernet	17
Montaigne (av.) (<i>A</i>) <i>I, II</i>	12	Mouzaia (de)	33
Montaigne <i>II</i>	15	Mozart	5
Montalivet <i>II</i>	15	Muette (chât. de la) (<i>TJ, TN</i>)	5
Monthron	17	— (porte de la) (<i>TN</i>)	5
Montcalm	19	Mulhouse (de) <i>III</i>	21
Mont-Cenis (du)	19	Muller	20
Montchanin	14	Murat (boulevard)	1
Mont-Doré (du)	17	Murillo	15
Mont-de-Piété <i>III</i>	23	Murs-de-la-Roquette (des)	29
Montebello (quai de) (<i>I, AE</i>) <i>V</i>	22	Musée de Galliera <i>I</i>	12
Montempoivre (porte de)	34	— Guimet <i>I</i>	12
Montenotte (de)	12	Musset (de)	1
Montesquieu <i>II, III</i>	20	Myrrha	23
Montessuy (de) <i>I</i>	11	Nansouty	21
Montfaucon <i>IV</i>	19	Nautes (de)	28
Montgallet	31	Naples (de)	15
Montgolfier <i>III</i>	24	Nation (de la)	23
Montholon (rue & square) (<i>B, J, T, AC</i>)	21	— (place de la) (<i>TC, TE, TF, TS 9 & 11</i>)	31
Montibœufs (des)	36	National (boulevard)	13
Montlouis	32	— (pont)	29
Montmartre (<i>J, Y</i>) <i>III</i>	21	Nationale	26
— (boulevard) (<i>E, Y</i>) <i>III</i>	21	Nativité (place & église de la)	29
— (cim.) (<i>H, TD, TP</i>)	17	Navarin (de)	21
		Navarre (de) <i>V</i>	22

B. R. G.		B. R. G.	
Navier	16	Oiseaux (anc. mais. des) <i>IV</i>	13
Necker	26	Olier	8
— (hospice)	<i>IV</i> 13	Olive (l')	25
Nemours (de)	<i>IV</i> 27	Olivier-de-Serres	11
Nesle (de)	<i>IV, V</i> 20	Omer-Talon	29
Neuf(Pont) (<i>I, O, AD</i>) <i>III, V</i>	20	Opéra (av. de l') (<i>G, AI</i>) <i>II</i>	21
Neuilly (<i>C, TN A, AB & B</i>)	5	— (passage de l')	21
— (av. de) (<i>C, TN A & AB</i>)	2	— (théâtre & pl. de l') <i>II</i>	18
— (porte de)	3	— Comique (th. de l') <i>II</i>	21
Neuve-des-Boulets	31	Oran (d')	23
Néva (de la)	12	Oratoire (r. & égl. de l') <i>II, III</i>	20
Nevers (de)	<i>IV, V</i> 20	Ordener (<i>AF</i>)	19
Newton	<i>I</i> 12	Orfèvres (quai des) (<i>I</i>) . <i>V</i>	20
Ney (boulevard)	22	Orfila	33
Nice (de)	32	Orillon (rue & impasse de l')	30
Nice-la-Frontière (de)	11	Orléans (av. d') (<i>TG, TSI</i>)	17
Nicolai	32	— (gare) (<i>T, P, AE, TM,</i>	
Nicolas-Flamel	<i>III</i> 23	<i>TS 4, 8, & 9</i>)	25
Nicolet	20	Orléans (porte d')	18
Nicolo	5	— (quai d')	<i>V</i> 22
Niel	11	Orme (de l')	
Nil (du)	<i>III</i> 24	Ormeaux (des)	31
Nitot	<i>I</i> 12	Ormesson (d')	<i>V</i> 26
Nollet	17	Ornano (boulevard) (<i>TI</i>) .	22
Nonnains-d'Hyères (des) (<i>Z</i>)	<i>V</i>	Orsay (quai d') (<i>TL</i>) <i>I, II</i>	11
Nord (gare du) (<i>K, V, AC,</i>	22	Orsel (d')	20
<i>TH, TI</i>)	24	Orteaux (des)	35
Normandie (de)	<i>III</i> 23	Oudinot	<i>IV</i> 13
Norvins	20	Ouest (rue & impasse de l')	
Notre-Dame (église)	<i>V</i> 22	Ourcq (de l')	28
— (pont)	<i>V</i> 23	— (canal de l')	29
— de - Bonne - Nouvelle		Ours (aux) (Et.-Marcel) <i>III</i>	24
(église & rue)	<i>III</i> 24	Paix (de la)	18
— de-Clignancourt (égl.) .	19	Pajol	26
— de-la-Croix (égl.)	30	Pajou	5
— de-la-Gare (égl.)	26	Palais (boulevard du) (<i>J, K,</i>	
— de-Lorette (rue et église)		<i>Q, AI, TG, TH</i>)	20
(<i>H, I, B</i>)	21	Palais-Bourbon (place du) <i>II</i>	14
— de-Nazareth <i>III</i>	24	— des Arts Libéraux	<i>I</i> 11
— de-Recouvrance	<i>III</i> 24	— des Beaux-Arts	<i>I</i> 11
— des-Blancs-Manteaux <i>III</i>	23	— des Machines	<i>I</i> 12
— des-Champs (r. et égl.) <i>IV</i>	16	Palais-Royal	<i>II</i> 21
— des-Victoires (rue, place,		— (place du) (<i>C, D, G, H,</i>	
& église) (<i>F</i>)	<i>III</i> 21	<i>R, X, Y</i>)	<i>II</i> 20
Nouveau Cirque (<i>D</i>)	<i>II</i> 18	Palatine	<i>IV</i> 19
Nouveautés (th. des)	<i>II</i> 21	Palestine (de)	33
Nouvelle-Californie	12	Palestro (de)	<i>III</i> 24
Nys	30	Palikao (de)	30
Oberkampf (<i>O</i>)	<i>III</i> 30	Palmyre	20
Oblin	<i>III</i> 20	Panorama des Ch.-Elys. <i>II</i>	15
Observatoire	19	Panoramas (r. & pass. des) <i>III</i>	21
— (avenue & carrefour de l')		Panoyaux (des)	30
(<i>TG, TS 4</i>)	19	Panthéon (<i>AF</i>)	<i>V</i> 19
Odéon (place, rue & th. de		— (place du) (<i>AF</i>)	<i>V</i> 19
l') (<i>H, Q, Z, AF</i>)	<i>IV, V</i> 19	Pantin (<i>TNH</i>)	31
Odessa (d')	<i>IV</i> 16	— (porte de)	32
Odiot (cité)	<i>I</i> 12	Paon-Blanc (du)	<i>V</i> 23
Offémont (d')	14	Pape-Charpentier	<i>IV</i> 16
Oise (quai de l')	28	Papillon	21
		Paradis (de)	<i>III</i> 24

B. R. G.		B. R. G.	
Parcheminerie (de la) . . . V	19	Peupliers (rue & poternes des)	24
Parc-Royal (du) . . . III	26	Phalsbourg (de) . . .	14
Paris (de) . . . 34	26	Pharmacie (école de) . IV	19
Parme (de) . . . 18	30	Philippe-Auguste (avenue)	31
Parmentier (avenue) . III	30	Philippe-de-Girard . . .	26
Partants (chemin des) . . .	33	Piat	30
Parvis - Notre - Dame (place du) . . . V	22	Picard	29
Pascal (U)	23	Picardie (de) . . . III	27
Pasquier	18	Piccini	9
Passy (pont de) . . . I	8	Picot	9
— (quai de) (TA, TB, TAB) I	8	Picpus (de)	31
— (r. & pl. de) (A, AB, TJ) I	5	— (boulevard de) (TC, TS 9)	31
— (station de) (JT, NT) . . .	5	— (cim., orat., & sémin. de)	31
Pasteur (Institut)	13	Pierre-au-Lard . . . III	23
Pastourel III	23	Pierre-Charron (B) . . . I	12
Patay (de) (TS 7)	27	Pierre-Guérin	1
Paul-Baudry I	12	Pierre-le-Grand	12
Paul-Lelong III	21	Pierre-Leroux IV	13
Paul-Louis-Courier . . . IV	17	Pierre-Lescot III	23
Pauquet I	12	Pierre-Lévéé III	27
Pavée V	23	Pierre-Picard	20
Payen (impasse)	4	Pierre-Sarrazin . . . V	19
Payenne III	26	Pigalle (r. & pl.) (I, TD, TP)	20
Péclet	10	Pinel (rue & place)	26
Pelée (ruelle) III	26	Pitié (hosp. & rue de la) V	22
Pélican (du) . . . II, III	20	Pixérécourt	33
Pelleport 33	36	Plaine (de la)	34
Penthièvre (de) II	15	— (poterne de la)	8
Pépinère (de la) (B) . . . II	18	Plaisance (porte de)	11
Perceval	13	Planchat	31
Perchamps (rue & place des)	4	Plantes (des)	17
Perche (du) III	26	Plat-d'Étain (du) . . . III	20
Percier (avenue) II	15	Plâtre (du) III	23
Perdonnet 23	23	Plumet	13
Pereire (boulevard & place)	11	Poccart	23
Père-Lachaise (P, TE) . . .	32	Point-du-Jour	4
Pergolèse 9	32	— (pont du)	4
Pérignon IV	13	Pointe-d'Ivry (de la) . . .	27
Perle (de la) III	26	Poissonnière III	24
Pernelle III	23	— (boul.) (E, Y) . . . III	21
Pernetty 14	23	Poissonniers (des)	2
Perrault III	20	Poissy (de) V	22
Perrée III	27	Poittevis (des)	19
Perronet IV	17	Poitiers (de)	17
Pétel 10	17	Poitou (de) III	26
Petit 29	10	Poliveau (de)	22
Petit-Musc (du) V	25	Polonceau	23
Petit-Pont V	22	Polytechnique (école) . . V	22
— (rue du) V	22	Pommard (de)	29
Petite-Pierre (de la)	32	Pompe (de la) (AB) . . . I	5
Petite Rue de Paris	11	Ponceau (rue & pass. du) III	24
Petites-Ecuries (rue & passage des) III	24	Poncelet	12
Petits-Carreaux (des) . . . III	21	Poniatowski (boulevard)	32
— Champs (des) . . . II, III	21	Pont (du)	2
— Hôtels (des)	24	Pont-aux-Choux (du) . . . III	26
— Pères (r. & pl. des) II, III	21	Pont-de-Lodi (du) V	20
Pétrarque I	8	Ponthieu (de) I, II	15
Pétruelle 24	8	Pont Louis-Philippe . . . V	23
Peupliers (avenue des)	1	Pont-Neuf (du) (I, J, TF) III	20
		Pontoise (de) V	22
		Ponts-et-Chaus. (éc. des) IV	17

B. R. G.		B. R. G.	
Popincourt	29	Racine	IV, V 19
Portalis (avenue)	15	Radzivil	II, III 21
Porte-Foin	III 24	Raffet	1
Port-Mahon (dn)	II 21	Ragniot (passage)	28
Port-Royal (boul. de) (TS4)	19	Rambonillet (de)	28
Possoz (place)	5	Rambuteau (de) (F, T) III	23
Postes (administr. des) III	21	Rameau	II 21
Postes et télégr. (min. des) IV	14	Ramey (J)	20
Pot-an-Lait (du)	21	Rampon	III 27
Pot-de-Fer (du)	V 22	Ramponneau	30
Poteau (dn)	19	Ranelagh (av. & ruede) (TN)	5
Poterie (de la)	III 20	Raonl (passage)	29
Pouchet	13	Rapée (qnaï de la) (TK) V	25
Ponlet	23	Raphaël (avenue)	5
Ponnetier	V 22	Rapp (avenue)	I 11
Poussin	1	Raspail (boul.) (TS1&2) IV	16 16
Pradier	30	Ratand	V 19
Prairies (des)	35	Ravignan	20
Pré-aux-Clercs (dn)	IV 17	Raynaud (cité)	14
Prêchens (des)	III 23	Raynouard	I 8
Préfecture de la Seine II	17	Réanmnr	III 24
— de Police	V 20	Rébeval	30
Pré-St-Gervais (le)	35	Récollets (des)	III 27
— (porte du)	36	Reculettes (ruelle des)	23
Presbourg (de)	I 12	Regard (du)	IV 16
Présentation (de la)	30	Régis	IV 16
Presles (de)	I 10	Regnault	30
Pressoir (du)	30	Regnier	13
Prêtres-St-Germain-l'Aux. (des)	III 20	Reille (avenue)	21
Prêtres-St-Séverin (des)	V 33	Reine-Blanche (de la)	22
Prévost (passage)	20	Rembrandt	15
Prévôt	V 23	Rémusat (de)	4
Priestley	30	Renaissance (de la)	I 12
Princes (passage des) II, III	21	— (th. de la)	III 24
Princesse	IV 19	Renard (du)	III 23
Prison des Jennes Détenns — de la Roquette	29	Rendez-vous (du)	34
Procession (de la)	13	Rennequin	11
Prony	11	Rennes (de) (H, O, V, AD, TS 1 & 2)	IV 16 16
Pronthon	31	République (av. de la) III	36 27
Pronvaires (des)	III 20	— (place de la) (E, U, AD, TNG & H)	III 27
Provence (de)	II, III 18	Réservoirs (des)	I 8
Providence (de la)	24	Rétiro (cité dn)	II 18
Prud'hon (avenue) (TN)	5	Retrait (dn)	33
Puits-de-l'Ermite (du)	V 22	Reuilly (boulevard de) (TS9)	31
Pnteaux	17	— (porte de)	35
Py (de la)	36	— (de)	28 31
Pyramides (des)	II 18	— (station de)	31
Pyrénées (r. & place des) (O)	33 33	Réunion (passage de la) III	23
Quatre-Fils (des)	III 23	— (rue & place de la)	32
Quatre-Sept. (du)	II 21	— (villa de la)	4
Quatre-Vents (des)	IV 19	Reynie (de la)	III 23
Quinault	10	Rhin (du)	29
Quincampoix	III 23	Ribera	4
Quintinie (de la)	10	Riblette	35
Quinze-Vingts (hospice des)	25	Richard-Lenoir	29
Rabelais	II 15	— (boulevard) (TI) III, V	26
— (lycée)	18	Richard-Wallace (boulevard)	2
		Richelieu (de) (HI) II, III	21
		— (square)	II 21

B. R. G.		B. R. G.	
Richepanse	II 18	Sablonville	5
Richer	III 21	Sabot (du)	IV 16
Richerand (avenue)	III 27	Sacré-Cœur (couv. du)	IV 14
Richomme	23	— (église du)	20
Rigaud	I 9	Saïda (de la)	11
Rigny (de)	II 18	St-Amand	14
Rigoles (rue et cité des)	33 33	St-Ambroise (égl. & r.) (TF)	26
Rimbaut	17	St-Anastase	III 26
Riquet (AJ)	26	St-André-des-Arts (rue & place)	IV, V 19
Riverin (cité)	III 24	St-Antoine (R, Z, TK)	V 25
Rivoli (de) (C, G, H, I, O, R, X, Y, Z, TK)	II, III, V 20	— (hôpital)	28
— (place de)	II 18	St-Augustin	II 21
Rochebrune	29	— (égl.) (B, AF, TNAB, B & C)	15
Rochechouart (J)	21	St-Benoît	IV 17
— (boul. de) (TD, TP)	20	St-Bernard (église)	23
Rocher (du)	15	— (quai) (T, AE, TM)	V 25
Rocroy (de)	24	— (rne, passage, & imp.)	28
Rodier	21	St-Blaise	35
Roger	17	St-Bon	III 23
Rohan (de)	II 20	St-Bruno	23
Roi-de-Sicile (du)	V 23	St-Charles	I 7
Roi-Doré (du)	III 26	St-Claude	III 26
Rollin	V 22	St-Cloud (avenue de)	2
— (collège)	20	— (porte de)	1
Romainville (r. & porte de)	36	St-Denis (G, J, K, AI, TQ)	III 24
Rome (de) (F, TN D & E)	II 18	— (boul.) (E, N, Y)	III 24
— (passage de)	III 24	— (canal)	28
Ronce (passage)	30	— du-St-Sacrement (égl.)	III 26
Rondelet	28	St-Didier	I 9
Ronsard	20	St-Dominique (Y, AD)	I, II 14
Roquépine	II 15	— (passage)	V 11
Roquette (de la) (P)	29	St-Esprit (sém. du)	I 19
Roses (des)	25	St-Etienne-du-Mont (rue & église)	V 22
Rosiers (des)	V 23	St-Engène (église)	III 21
Rossini	II, III 21	St-Eustache (église, place, & impasse) (Halles)	III 21
Rotrou	V 19	St-Fargeau	36 36
Rottembourg	34	St-Ferdinand (chap., rne, & place)	9
Rouelle	I 7	St-Fiace	III 21
Rougemont (rue & cité)	III 21	St-Florentin	II 18
Rouget-de-l'Isle	II 18	St-François-de-Sales	20
Roule (du)	III 20	— (égl.)	11
— (avenue du)	5	St-François-Xavier (place & église) (AH, TS 3)	IV 13
Roussel	12	St-Georges (église)	30
Rousselet	IV 13	— (rue & place) (H)	II 21
Roussin	10	St-Germain (boul.) (H, I, L, O, U, Z, AD, AF, TL, TM, TS 6)	II, IV, V 19
Rouvet	28	— (île)	3
Roy	II 15	— (marché)	IV 19
Royal (pont)	II 17	— de-Charonne (église)	35
Royale (A, AC, AF)	II 18	— des-Prés (église & pl.)	35
Royer-Collard (r. & imp.)	V 19	(H, V, AD, AG, TL, TM, TS 1 & 2)	IV 19
Rubens	23	— l'Auxerrois (égl. & r.)	III 20
Ruisseau (du)	19	St-Gervais (église)	23
Rungis (pl. de)	21	St-Gilles	III 26
Ruty	34		
Ruysdaël (avenue)	15		
Sablière (de la)	17		
Sablonnière (ruelle de la)	10		
Sablons (des)	I 9		
— (porte des)	6		

B. R. G.		B. R. G.	
St-Gothard (du)	20	St-Pierre-de-Chaillet.	12
St-Guillaume IV	17	— de-Montmartre (place & église)	20
St-Hippolyte	20	— de-Montrouge (église)	17
St-Honoré (cloître) <i>II, III</i>	20	— du-Gros-Caillois (égl.) <i>I</i>	12
— (<i>D, G, H, I, R, Y</i>) II	18	— du-Temple (pass.) III	26
— (marché) II	18	— St-Antoine (passage) V	25
St-Hyacinthe V	22	St-Placide IV	16
St-Jacques (<i>J</i>) V	19	St-Roch (égl. & rue) (<i>D</i>) <i>II</i>	18
— (boulevard) (<i>J</i>) 20	20	St-Romain IV	16
— (squ. & tour) III	23	St-Sabin III, V	26
— du-Haut-Pas (égl.) V	19	St-Sauveur III	21
St-Jean-Baptiste-de-Belle-ville (église) 33	33	St-Sébastien III	26
— de-Grenelle (église) 7	7	St-Séverin (rue & église) <i>V</i>	19
St-Jean-de-Dieu (Frères) <i>IV</i>	13	St-Simon IV	17
St-Joseph III	21	St-Sulpice (rue, pl., & égl.) (<i>H, Q, Z, AF, AH</i>) IV	19
— (égl. & chap.) 27	27	— (séminaire de) 6	6
St-Julien-le-Pauvre V	22	St-Thomas-d'Aquin (église, rue, & place) IV	17
St-Lambert 7	7	St-Victor V	22
St-Laurent (église) 10	10	St-Vincent, Montmartre 20	20
— (passage) III	24	— de-Paul (église) (<i>V, AC</i>)	24
St-Lazare (prison) 24	24	— de-Paul (sœurs de) IV	16
— (rue & gare) (<i>B, F, X, AI</i>) II	18	St-Yves	18
St-Leu (église) III	23	Ste-Alice	17
St-Louis (hôpital) III	27	Ste-Anne (rue & pass.) <i>II</i>	21
— (île et pont) V	22	— — Popincourt (pass.)	27
— (lycée) V	19	Ste-Apolline III	24
— aux-Invalides (église) <i>IV</i>	14	Ste-Avoys (passage) III	23
— d'Antin (église) II	18	Ste-Barbe (collège) V	19
— en-l'Île (rue & église) <i>V</i>	22	Ste-Cécile III	24
St-Mandé (avenue & porte de) (<i>T, C</i>) 34	34	Ste-Chapelle (pal. de just.) <i>V</i>	20
St-Marc II, III	21	Ste-Clotilde (église) IV	14
St-Marcel (boul. & égl.) (<i>K, TS 4</i>) 22	22	Ste-Croix-de-la-Bretonnerie (rue & pass.) III, V	23
St-Martin (<i>L, T</i>) III	23	Ste-Elisabeth (r. & égl.) <i>III</i>	27
— (boul. & porte) (<i>E, Y</i>) <i>III</i>	24	Ste-Eugénie	28
— (canal) 27	27	Ste-Euphrasie 19	19
— (marché) III	24	Ste-Félicité (impasse)	10
St-Maur-Popincourt III	27	Ste-Foy (rue & pass.) III	24
St-Médard (r. & église) V	22	Ste-Geneviève (église) V	19
St-Merry (r. & égl.) <i>V, III</i>	23	— (place) V	22
St-Michel (boul.) (<i>J, L, TG, TH, TQ</i>) IV, V	19	Ste-Marguerite (r. & égl.)	28
— (hospice) 34	34	Ste-Marie 20	20
— (pont, place, & quai) (<i>I, J, K, L, Q, AE, AI, TG, TH, TQ</i>) V	19	— (cour & passage) 27	27
St-Nicolas (port) II	20	— des-Batignolles (église) 14	14
— des-Champs (église) 24	24	Ste-Marthe III	27
— du-Chardonnet (église) 22	22	Ste-Opportune (r. & pl.) <i>III</i>	20
St-Ouen (av. & porte de) 16	16	Ste-Pélagie (prison) V	22
St-Paul (rue & pass.) (<i>U</i>) <i>V</i>	25	Ste-Périne (institut. de) 4	4
— Saint-Louis (église) V	25	Saintonge (de) III	26
St-Pétersbourg (de) (<i>TN D & E</i>) 17	17	Sts-Pères (des) (<i>H, AF</i>) <i>IV</i>	17
St-Philibert (avenue) 15	15	— (pont des) II, IV	20
St-Philippe III	24	Salneuve 14	14
— du-Roule (église) (<i>D, R, AB</i>) II	15	Salomon-de-Caus III	24
		Salpêtrière (de la) 26	26
		— (hôpital de la) 25	25
		Sambre-et-Meuse (de) 27	27
		Samson 23	23
		Santé (rue et prison de la) 20	20

B. R. G.		B. R. G.	
Santeuil	22	Sourdis	23
Sartine	21	Sourds-Muets (institut des) .	19
Sauffroy	16	Soyer	2
Saules (des)	20	Spontini	6
Saulnier (passage)	21	Stanislas (rue & passage) .	16
Saumon (passage du)	21	— (collège)	16
Saussayes (des)	15	Steinkergue (de)	20
Saussure	14	Stendhal	32
Sauvage	25	Stéphenson	23
Sauval	21	Stinville (passage)	28
Savoie (de)	20	Strasbourg (rue & gare de)	
Saxe (avenue de)	13	(B, M, TG, TH, TI)	24
Scala (la)	24	— (boulevard de) (B, M,	
Sceaux (gare de) (J, TG, TS 1		TG, TH, TI)	24
& 2)	20	Suchet (boulevard)	2
Sceaux-Ceinture (stat. de)	21	Sud (passage du)	29
Scheffer	8	Suffren (avenue de)	10
Schomberg	25	Suger	19
Schomer	16	Suisses (passage des)	14
Scipion (rue & place)	22	Sully (de)	25
Scribe	18	— (pont)	22
Sébastopol (boulev. de) (M,		Surcouf	14
TG, TH)	24	Suresne (de)	18
Secrétan	30	Surmelin (du)	36
Sedaine	29	Sycomores (avenue des)	1
Séguier	19		
Séguin	25	Tabacs (manufacture des) .	14
Séguir (avenue de)	13	Tacherie (de la)	23
Seine (de)	20	Tage (du)	24
— (quai de la)	29	Taillandiers (des)	29
Sénat (palais du)	19	Taillebourg (avenue de) (TC,	
Sénégal (du)	30	TE, TF, TS 11)	31
Sentier (du)	21	Taillepain	23
Serpente	19	Taitbout (TN, TN F)	21
Sérurier (boulevard)	32	Talma	5
Servan	29	— (cité)	13
Servandoni	19	Tanger (de)	26
Seveste	20	Tanneries (des)	20
Sévigé	26	Tarbé	14
Sèvres (de) (V, A, AG, TS 5)		Tardieu	20
IV	16	Taylor	24
— (porte de)	5	Téhéran (de)	15
Seze (de)	18	Télégraphe (du)	33
Sfax (de)	9	Temple (du) (T, U, AD) .	23
Sibuet	34	— (boul. du) (E, S)	27
Simon-le-Franc	23	— (marché du)	27
Simonet (passage)	23	— (square du)	24
Simplon (du)	22	Téniers	1
Singer	5	Ténon (hôpital)	36
Smala (de la)	7	Ternaux	27
Sœur-Rosalie (avenue)	23	Ternes (av., cité, & porte des)	
Solférino (rue & pont de) .	17	(D)	9
Sommerard (du)	19	Terrage (du)	27
Sontay (de)	9	Terrasse (de la)	14
Sorbier (Q)	33	Terre-Neuve (de)	32
Sorbonne	19	Terres-au-Curé (des)	27
— (pl., r., & pass. de la) .	19	Tertre (place du)	20
Soufflot (AF)	19	Texel (du)	13
Soult (boulevard)	34	Thann (de)	14
Source (de la)	4	Théâtre (du) (J, AH)	7
Sourdière (de la)	18	Théâtre-Français (pl. du) .	21

B. R. G.

B. R. G.

B. R. G.		B. R. G.	
Théâtre Beaumarchais	V . 26	Traktir (de)	I . 9
Th. Déjazet	III . 27	Travaux Pub. (min. des) IV	. 17
Th. de l'Ambigu	III . 24	Traversière	V . 25
Th. de la Gaité	III . 24	Treillard	15
Th. de la Porte-St-Martin III	. 24	Trémolle (de la)	I . 12
Th. de la Renaissance III	. 24	Trévis (de) (J)	21
Th. de l'Odéon	V . 19	— (cité)	III . 21
Th. de l'Opéra	II . 18	Trézel	16
Th. de l'Opéra-Comique II	. 21	Tribunal de commerce	V . 20
Th. des Bouffes-Parisiens II	. 21	Trinité (passage de la) III	. 24
Th. des Folles-Dramat. III	. 27	— (r. & égl. de la) (B, G)	18
Th. des Nouveautés	II . 21	Trocadéro (av. du) (A, TJ) I	. 9
Th. des Variétés	III . 21	— (stat. de l'av. du) 6
Th. du Château d'Eau III	. 27	Trocadéro (pal. & pl. du) A, B,	
Th. du Châtelet	V . 20	TA, TB, TAB, TD, TN, TP) I	. 8
Th. du Gymnase	III . 24	Trois-Bornes (des)	27
Th. du Palais-Royal	I . 21	Trois-Couronnes (des)	30
Th. du Vaudeville	II . 18	Trois-Frères (des)	20
Th. Français	II . 21	Trois-Portes (des)	V . 22
Thénard	V . 19	Tronchet (X)	II . 18
Thérèse	II . 21	Trône (avenue du)	31
Thermopyles (passage des) 17	Tronson-Ducoudray	II . 18
Théry	6	Trousson (hôpital)	28
Thévenot	III . 24	Troyon	12
Thibaud 17	Trudaine (avenue)	20
Thiboumery	11	Truffault	14
Thierré (passage)	25	Tuileries (jard., palais, quai,	
Tholozé	20	& rue des) (H, X, Y, AG,	
Thorel	III . 24	TA, TB, TAB, TJ)	II . 17
Thorigny (de)	III . 26	Turbigo (de) (D, TF)	III . 24
Thouin	V . 22	Turenne (V)	III, V . 26
Tiers 23	Turgot (rue & place)	21
Tilleuls (avenue des)	1	Turin (de)	18
Tilsitt (de)	12	Ulm (d')	V . 19
Timbre (hôtel du) II, III	. 21	Union (passage de l')	II . 11
Tiphaine	10	Université (de l') I, II, IV	. 17
Tiquetonne	III . 24	Ursins (des)	V . 23
Tiron	V . 23	Ursulines (des)	V . 19
Titon 28	Usines (des)	7
Tlemcen	30	Uzès (d')	III . 21
Tocancier (passage)	31	Val-de-Grâce (hôpital du)	19
Tocqueville	14	Valence (de)	22
Tolbiac (de) 24	Valette	V . 19
— (pont de) 29	Valhubert (place) (T, TM,	
Tombe-Issoire (de la) 18	TS & S)	V . 25
Torcy (rue & place)	25	Valmy (quai de)	III . 27
Toullier	V . 19	Valois (rue & place de) II	. 21
Tour-d'Auvergne (de la)	21	Vandal	14
Tour-des-Dames (de la)	18	Vandamme	13
Tour (de la), Passy (AB) I	. 6	Van-Dyck (avenue)	12
Tourelles (des)	36	Vaneau	IV . 13
Tourlaque	17	Vannes (de)	III . 20
Tournefort	V . 22	Vanves (TS 2 & 5) 9
Tournelle (quai & pont de la)		— (de) (Q) 14
(G, K, AE)	V . 22	— (porte de) 11
Tournelles (des)	III, V . 26	Varenne (de)	IV . 16
Tournon (de) (H)	IV . 19	Variétés (théâtre des)	III . 21
Tourtelle (de)	30	Vauban (place)	IV . 13
Tourville (avenue de) I, IV	. 13	Vaucanson	III . 24
Toussaint-Féron	24		
Tracy (de)	III . 24		

PLAN D'ENSEMBLE DE PARIS











I. CHAMP DE MARS. TROCADERO. CHAMPS ÉLYSÉES.










III. GRANDS BOULEVARDS (EST). LES HALLES.




IV. INVALIDES. LUXEMBOURG.





V. CITÉ. JARDIN DES PLANTES. BASTILLE.



B. R. G.		B. R. G.	
Vaucouleurs (passage) . . .	30	Villejuif (de)	23
Vaudeville (théâtre dn) <i>II</i>	18	Villejnst (de)	9
Vaugelas	8	Ville-l'Evêque (rue & place	
Vaugirard (de) (<i>Z, AG</i>) <i>IV, V</i>	16	de la)	15
— (boul. de) (<i>V, Z</i>) . . . <i>IV</i>	13	Villeneuve (de la) . . . <i>III</i>	24
— (place de)	10	Villersexel (de)	17
— (station de)	8	Villette (de la)	33
Vanquelin	19	— (bassin de la)	29
Vanvilliers	20	— (boul. de la) (<i>TE</i>) . . .	27
Vavin (<i>Q</i>)	16	— (porte de la)	28
Véga (de la)	34	Villiers (av. de) (<i>TN AB, B,</i>	
Vélasquez (avenue)	15	& <i>C</i>)	14
Velpean	16	— (porte de)	8
Vendôme (passage)	27	Villiot	28
— (place)	18	Vinaigriers (des)	35
Vendrezanne	23	Vincennes (bois de)	34
Venise (de)	23	— (cours & porte de) (<i>TF</i>)	25
Ventadour	21	— (gare de) (Bastille) . . <i>V</i>	
Ventes (hôt. des)	21	Vincent	30
Vercingétorix	13	Vinense	18
Vernet	12	Vingt-Neuf-Juillet (du) <i>II</i>	
Vernueil (de)	17	Vintimille (rne & place) . .	17
Vernier	8	Violet (passage)	24
Véro-Dodat (passage) <i>II, III</i>	20	— (rne & pl.), Grenelle . .	7
Véron	20	Virginie, Grenelle	7
Verrerie (de la)	23	Visconti	20
Versailles (avenue de) (<i>TA,</i>		Vistule (de la)	24
<i>TB, TAB</i>)	4	Vital	5
Versailles (porte de)	8	Vitruve	35
Versigny	19	Vitry (porte de)	30
Verthois (du)	24	Vivienne (r. & pass.) (<i>I, V,</i>	
Verte (allée)	26	<i>AB</i>)	21
Vertus (des)	24	Voie-Industrielle	34
Vézelay	15	Voie-Verte (de la)	18
Viala	7	Volney	18
Viarms (de)	21	Volontaire (ruelle)	13
Vicq-d'Azir	27	Volta	24
Victoire (de la)	21	Voltaire (boul. & place) (<i>P,</i>	
Victoires (place des)	21	<i>TF, TI</i>)	27
Victor (boulevard)	8	— (quai)	17
Victor-Cousin	19	Vosges (pl. & rue des) (<i>F</i>) <i>V</i>	26
Victor-Hugo (av.) (<i>AB</i>) . . .	9	Vouillé (de)	11
— (place) (<i>AB</i>)	6	Voute (de la)	34
Victor-Massé	21	Vrillière (de la)	21
Victoria (av.) (<i>C, Q</i>) <i>III, V</i>	23		
Vieille-du-Temple (<i>O</i>) <i>III, V</i>	23	Wagram (av. de) (<i>TD, TP</i>)	12
		— (pl. de) (<i>F</i>)	11
Vienne (de)	18	Washington	12
Viète	11	Watt	29
Vieux-Colombier (du) . . . <i>IV</i>	16	Watteau	23
Vigan (passage du)	21	Wattianx (passage)	28
Vignes (des)	5	Wattignies (de)	32
Vignolles (des)	35	Wilhem	4
Vignon	18		
— (passage)	4	Xaintraillies	26
Vilin	30		
Villa-des-Fleurs (cité) . . .	16	Yvette (de l')	1
Villars (avenue de)	13	Yvon-Villarcéau	9
Villedo	21		
Ville-Hardonin	26	Zacharie	19

List of the Stations of the Chemin de Fer de Ceinture.

(Comp. the annexed Plans and p. 24 of the Handbook.)

Miles	
1	<i>Gare St. Lazare</i> (p. 23). <i>Place de l'Europe</i> (p. 201). Tunnel. <i>Les Batignolles</i> , where the St. Germain, Normandy, and Versailles lines diverge.
1 ⁴ / ₅	<i>Courcelles-Levallois</i> . Passengers for Clichy or Belleville change here, ascending the staircase opposite the exit. No time to lose.
2 ¹ / ₂	<i>Neuilly-Porte-Maillot</i> , the station for Neuilly (p. 156). Tunnels.
3 ¹ / ₄	<i>Avenue du Bois de Boulogne</i> , at the entrance to the Bois de Boulogne by the <i>Porte Dauphine</i> , not far from the lakes.
3 ³ / ₄	<i>Avenue du Trocadéro</i> (Henri-Martin), $\frac{1}{2}$ M. from the Palais du Trocadéro (p. 163) and near the Bois (p. 157). Two short tunnels.
4	<i>Passy</i> (p. 162). To the right the <i>Ranelagh</i> (p. 162). Handsome villas.
5	<i>Auteuil</i> , at the S. end of the Bois de Boulogne, near the race-course (p. 159). Then the * <i>Viaduct</i> mentioned at p. 162. On the right, beyond the fortifications, are the Bois de Boulogne, St. Cloud with its park (p. 310), the wooded heights of Sèvres and Meudon (p. 313), the viaduct of the Versailles line, Issy (p. 286), etc. On the left the city itself with the Eiffel Tower, Champ de Mars and its palaces, Trocadéro, etc.
5 ³ / ₄	<i>Point-du-Jour</i> . *View still more picturesque. The Seine is now crossed by an imposing bridge.
6 ¹ / ₄	<i>Grenelle</i> , where a branch diverges to the Champ-de-Mars and another to Les Moulineaux (p. 309). Embankment. View.
7 ¹ / ₄	<i>Vaugirard-Issy</i> . To the left, a former Jesuit college. Tunnel.
7 ³ / ₄	<i>Ouest-Ceinture</i> , where the line passes under the Rive Gauche railway; carriages changed for Versailles (see p. 286).
9	<i>Montrouge</i> . The next tunnel intersects the Catacombs.
9 ³ / ₄	<i>La Glacière-Gentilly</i> , where passengers for the Sceaux railway alight (p. 336). To the left is the Parc Montsouris. Goods station.
10 ¹ / ₂	<i>La Maison Blanche</i> . To the right is the <i>Hospice de Bicêtre</i> , for old men.
11 ¹ / ₄	<i>Orléans-Ceinture</i> , where the line intersects the Orleans railway. The train now crosses the Seine by the Pont National. To the left the new Halle aux Vins.
12	<i>La Rapée-Bercy</i> . The train crosses the Lyons line and the Avenue Daumesnil by a viaduct. To the right, the Bois de Vincennes (p. 212) and the Lac Daumesnil.
12 ³ / ₄	<i>Bel-Air</i> , where carriages are changed for Vincennes. St. Mandé, to the right, see p. 211.
13 ¹ / ₂	<i>Avenue de Vincennes</i> . On the left lies the Place de la Nation (p. 210).
14 ¹ / ₄	<i>Charonne</i> . Long tunnel on the E. side of Père-Lachaise (p. 176).
15 ¹ / ₄	<i>Ménilmontant</i> . A long tunnel passes under part of Belleville, and a cutting intersects a corner of the Buttes-Chaumont (p. 186).
16 ¹ / ₂	<i>Belleville-Villette</i> . To the left, the cattle-market and 'abattoirs' of La Villette (p. 187). We cross the <i>Canal de l'Ourcq</i> (p. 186).
17	<i>Pont-de-Flandre</i> , the station for the 'abattoirs'. Docks. Gas-works.
17 ¹ / ₂	<i>Est-Ceinture</i> . Carriages changed for the Ligne de l'Est.
18 ¹ / ₄	<i>Nord-Ceinture</i> , the junction of the Ligne du Nord. To the left, the Montmartre
19	<i>Boulevard Ornano</i> , near the cemetery of St. Ouen.
19 ³ / ₄	<i>Avenue St. Ouen</i> . St. Ouen village. Adjacent is a race-course (p. 201).
20 ¹ / ₂	<i>Avenue de Clichy</i> . Open view. The train passes under the Ouest line.
21	<i>Courcelles-Ceinture</i> . At this station the two ends of the line encircling the city unite. Passengers returning to St. Lazare alight here (no time to lose), and enter the St. Lazare train at the adjacent <i>Courcelles-Levallois</i> station (see above).
22	<i>Les Batignolles</i> (see above).
23	<i>Gare St. Lazare</i> (see above).

Omnibus and Tramway Routes with their Correspondances.

(Comp. the following Tables and Plan, and p. 20 of the Handbook.)

The letters in the first column, printed in heavy type (**B, C**, etc.), indicate the large omnibuses, the top of which is accessible to ladies. In the second column the single letters and AB to AJ indicate *Omnibuses*, the series TA to TS and TAB indicate the *Tramways of the Central System*, the series TNA to TNH the *Tramways Nord*, and the series TS1 to TS11 the *Tramways Sud*.

List of the Omnibus Lines.

Lines	Offices and 'Correspondances'
A. Auteuil-Madeleine (s. Pl. A 3-4 & C 2-3). — 4 M.	Auteuil: AH. — Pl. d. Passy: AB; TJ. — Trocadéro: B; TP, N. — Alma: TA, B, M, AB, S3. — Madeleine: D, E, X, AC, AF; TN AB, NB, NC.
B. Trocadéro-Gare de l'Est (Pl. A 3 & E 2). — 3 ³ / ₄ M.	Trocad.: A; TN, P. — Ch.-Elysées: C. — St-Philippe: D, R, AB. — St-Augustin: AF, TN, NAB, NB, NC. — St-Lazare: F, X, AI; TND, NE. — Trinité: G. — R. de Châteaudunn: H, I; TNF. — Sq. Mont-hol: J, T, AC. — Est: L, M; TG, H, I.
C. Porte Maillot-Hôtel de Ville (Pl. A 2 & E 4). — 3 ¹ / ₂ M.	Etoile: AB; TD, N, P, S3. — Ch.-Elys.: B. — Pal.-Roy.: D, G, H, Y, AG, AI. — Louvre: I, N, V: TA, B, C, F, J, K, AB. — Châtelet: G, J, K, O, Q, R, AD, AI; TC, G, H, K, Q. — Hôtel de Ville: Q.
D. Les Ternes - Boul. des Filles-du-Calv. (Pl. A 2 & F 3). — 4 ¹ / ₂ M.	Pl. des Ternes: TD, P. — Boul. Haussm.: AB; TN. — St-Philippe: B, R. — Madeleine: A, E, X, AB, AC, AF; TN AB, NB, NC. — Pal.-Roy.: C, G, H, R, Y, AG, AI. — Louvre: I, N, V, AG, AI; TA, B, C, F, J, K, AB. — Halles: F, J; TF, Q. — Calvaire: E, O, S.
E. Madeleine-Bastille (Pl. C 2-3 & F 4). — 2 ³ / ₄ M.	Madel.: A, D, X, AB, AC, AF; TN AB, NB, NC. — Boul. d. Ital.: H. — B. St-Denis: K, L, M, N, T, Y; TG, H. — Pl. d. l. Républ.: N, U, AD; TF, I, NG, NH. — Calvaire: D, O. — Bastille: F, P, R, S, Z; TC, K, L, S 4, 10.
F. Place Wagram-Bastille (Pl. B 1 & F 4). — 4 ¹ / ₄ M.	R. Legendre: AJ. — Boul. d. Batignolles: TD, P. — St-Lazare: B, X, AI; TND, NE. — Bourse: I, AB. — Pl. d. Victoires: N, V. — Halles: D, J; TF, Q. — R. Rambuteau: T. — Bastille: E, P, R, S, Z; TC, I, K, L, S 4, 10.
G. Batignolles-Jardin des Plantes (Pl. C 1 & E 5). — 4 ¹ / ₄ M.	Batign.: AJ. — Pl. Clichy: H; TD, P, ND, NE. — Trinité: B. — Pal.-Roy.: C, D, H, R, Y, AG, AI. — Louvre: I, N, V, AG; TA, B, C, F, J, K, AB. — Châtelet: C, J, K, O, Q, R, AD, AI; TC, G, H, K, Q. — Halle aux Vins: I, K, T, U, Z, AE; TL, M.
H. Batignolles-Clichy-Odéon (Pl. C 1 & D 5). — 4 ¹ / ₄ M.	Pl. Clichy: G; TD, P, ND, NE. — R. Châteaudunn: B, I, AC; TNF. — Boul. d. Italiens: E. — Pal.-Roy.: C, D, G, R, Y, AG, AI. — Quai d. Tuileries: AG; TA, B, J, AB. — St-Germ.-d.-Pr.: L, O, V, AD, AG; TL, M, S 1, 2. — St-Sulpice: L, Q, AH. — Odéon: Z, AF.

Lines	Offices and 'Correspondances'
I. <i>Place Pigalle-Halle aux Vins</i> (Pl. D 1 & E 5). — $3\frac{1}{4}$ M.	Pl. Pig.: D, P. — R. d. Châteaudun: B, H, AC; T, NF. — Bourse: F, AB. — Pl. d. Victoires: F, N, V. — Louvre: C, D, G, R, V, AG, AI; TA, B, C, F, J, K, AB. — Pl. St-Michel: J, L, Q, AE, AI; TG, H, Q. — Pl. Maubert: T, L, M. — Halle aux Vins: G, K, T, U, Z, AE; T, L, M.
J. <i>Montmartre-Place St-Jacques</i> (Pl. D 1 & D 6). — $4\frac{3}{4}$ M.	Montm.: A, J. — Boul. Rochech.: T, D, P. — Sq. Monthol.: B, T, AC. — Halles: D, F; T, F, Q. — Châtelet: C, G, K, O, Q, R, AD, AI; T, C, G, H, K, Q. — Pl. St-Michel: I, L, Q, AE, AI; T, G, H, Q. — Cluny: T, G, H, L, M, Q, S, 6, 7. — R. Soufflot: A, F; T, G, Q.
K. <i>Gare du Nord-Boul. St-Marcel</i> (Pl. E 1 & E 6). — $4\frac{3}{4}$ M.	Gare du N.: V, AC; T, I. — Boul. St-Denis: E, N, T. — Châtelet: C, G, J, O, Q, R, AD, AI; T, C, G, H, Q. — Halle aux Vins: G, E, I, T, U, Z, AE; T, L, M. — Boul. St-Marcel: T, Q, S, 4, 6, 7.
L. <i>La Villette-St-Sulpice</i> (Pl. F 1 & D 4). — $4\frac{3}{4}$ M.	Boul. d. l. Villette: M, AC; T, D, E, P, NG, NH. — Gare d. l'Est: B; T, G, H, I. — Porte St-Martin: E, N, T, Y; T, G, H. — Pl. St-Michel: I, J, K, Q, AE, AI; T, G, H, Q. — Cluny: T, G, H, L, M, Q, S, 6, 7. — St-Germ.-des-Prés: H, O, V, AD, AG; T, L, M, S, 1, 2. — St-Sulpice: H, Q, A, F, A, H.
M. <i>Lac St-Fargeau-Arts-et-Métiers</i> (Pl. G 2 & E 3). — $4\frac{3}{4}$ M.	R. Bolivar: N. — Boul. d. l. Villette: L, AC; T, D, E, P, NG, NH. — Gare d. l'Est: B; T, G, H, I. — Boul. St-Denis: E, T, Y; T, G, H.
N. <i>Belleville-Louvre</i> (Pl. G 2 & D 3). — $2\frac{1}{2}$ M.	R. Bolivar: M. — Boul. d. Belleville: T, E. — Pl. d. l. Républ.: E, S, U, AD; T, F, I, NG, NF. — Boul. St-Denis: E, K, L, T, Y; T, G, H. — Pl. d. Victoires: F, I. — Louvre: C, D, G, R, V, AG, AI; TA, B, C, F, J, K, AB.
O. <i>Ménilmontant-Gare Montparnasse</i> (Pl. G 3 & C 5). — $4\frac{1}{2}$ M.	Ménilm.: T, E. — R. Oberkampf: T, F, I. — Calvaire: D, E, S. — R. Bourg-Tibourg: R, T; T, K. — Châtelet: C, G, J, K, Q, R, AD, AI; T, C, G, H, K, Q. — St-Germ.-des-Prés: H, L, V, AD, AG; T, L, M, S, 1, 2. — Montp.: T, S, 1, 2, 3, 4.
P. <i>Charonne-Pl. d'Italie</i> (Pl. H 3 & E 6). — 4 M.	Père-Lach.: T, E. — Pl. Voltaire: T, F. — Bastille: E, F, R, S, Z; T, C, I, K, L, S, 10. — Gare d'Orl.: T, AE; T, M, S, 3, 8, 9. — Pl. d'Italie: T, Q, S, 6, 7, 8.
Q. <i>Hôtel de Ville-Plaisance</i> (Pl. E 4 & B 6). — $3\frac{1}{2}$ M.	Hôtel de Ville: C. — Châtelet: C, G, J, K, O, R, AD, AI; T, C, G, H, K, Q. — Pl. St-Michel: I, J, L, AE, AI; T, G, H, Q. — Cluny: T, G, H, L, M, Q, S, 6, 7. — St-Sulpice: H, L, A, F, A, H. — R. d. Vaugirard: Z.
R. <i>Gare de Lyon-St-Philippe-du-Roule</i> (Pl. G 5 & B 2). — 4 M.	Gare: T, M. — Bastille: E, F, P, S, Z; T, C, I, K, L, S, 10. — R. Bourg-Tibourg: O, T. — Châtelet: C, G, J, K, O, Q, AD, AI; T, C, G, H, K, Q. — Louvre: I, N, V, AG; TA, B, C, F, J, K, AB. — Pal.-Roy.: D, G, H, Y, AG, AI. — St-Philippe: B, D, AB.
S. <i>Porte de Charenton-Pl. de la République</i> (Pl. H 6 & F 3). — $3\frac{1}{2}$ M.	Bastille: E, F, P, R, Z; T, C, I, K, L, S, 4, 10. — Calvaire: D, O. — Pl. d. l. Républ.: N, U, AD; T, F, I, NG, NH.
T. <i>Gare d'Orléans-Square Montholon</i> (Pl. F 6 & E 2). — $3\frac{1}{4}$ M.	Gare: P, AE; T, M, S, 4, S, 9. — Halle aux Vins: G, I, K, U, Z; T, L, M. — Quais: T, C. — R. Bourg-Tibourg: O, R; T, K. — R. Rambuteau: F. — Boul. St-Denis: E, K, L, M, N, Y; T, G, H. — Sq. Monthol.: B, J, AC.

Lines	Offices and 'Correspondances'
U. <i>Montsouris-Pl. de la République</i> (Pl. DE 6 & F 3). — 4 M.	R. Pascal: TQ. — Halle aux Vins: G, I, K, T, Z, AE; TL, M. — Pl. de la Républ.: B, N, S, AD; TF, I, NG, NH.
V. <i>Place du Maine-Gare du Nord</i> (Pl. B C 6 & E 1). — 4 ³ / ₄ M.	R. d. Sèvres: X, AG. — R. d. Sts-Pères: AF, AG, AH. — St-Germ.-des-Prés: H, L, O, AD, AG; TL, M, S1, 2. — Quais: TA, B, C, J, K, AB. — R. du Louvre: C, D, G, H, R, AG, AI. — Pl. d. Victoires: F, I. — Bourse: AB. — Gare: K, AC; TI.
X. <i>Vaugirard-Gare St-Lazare</i> (Pl. A 6 & C 2). — 3 ³ / ₄ M.	R. d. Sèvres: V, AG. — Boul. St-Germ.: AF; TL, M. — Madel.: A, D, E, AB, AC, AF; TNAB, NB, NC. — Gare: B, F, AI; TND, NE.
Y. <i>Grenelle-Porte-St-Martin</i> (Pl. A 5 & E 2-3). — 4 ¹ / ₂ M.	R. du Théâtre: AH. — Ecole-Milit.: AD; TS 3, 5. — Boul. St-Germ.: AD, AF; TL, M. — Quais: H, AG; TA, B, J, AB. — Pal. Roy.: C, D, G, H, R, AG, AI. — Boul. St-Denis: E, L, M, N, T; TG, H.
Z. <i>Grenelle-Bastille</i> (Pl. A 5 & F 4). — 4 ¹ / ₄ M.	Pl. Cambronne: AH. — R. d. Vaugir.: AG. — R. Bonap.: Q. — Odéon: H, AF. — Sq. Monge: TH. — Halle aux Vins: G, I, K, T, U, AE; TL, M. — Bastille: E, F, P, R, S; TC, I, K, L, S4, 10.
AB. <i>Passy-la Bourse</i> (Pl. A 2 & D 3). — 4 M.	Pl. d. Passy: A, TJ. — Av. H. Martin: TN. — Etoile: C; TD, P, N, S3, NAB. — Boul. Haussm.: D; TN. — St. Philippe: B, R. — Madel.: D, E, X, AC, AF; TN 2, 3, 4. — Bourse: F, I, V.
AC. <i>Petite-Villette-Champs-Élysées</i> (Pl. GH 1 & C 3). — 4 ¹ / ₄ M.	Boul. d. l. Villette: L, M; TD, E, P, NG, NH. — Gare d. Nord: K, V; TI. — Sq. Monthol.: B, J, T. — R. d. Châteaudun: H, I; TN F. — Madel.: A, D, E, X, AB, AF; TNAB, NB, NC. — Concorde: TA, B, J, M, AB.
AD. <i>Pl. de la République-Ecole Militaire</i> (Pl. F 3 & B 4). — 4 ¹ / ₄ M.	Pl. d. l. Républ.: E, N, S, U; TF, I, NG, NH. — Châtelet: C, G, J, K, O, Q, R, AI; TC, G, H, K, Q. — St-Germ.-des-Prés: H, L, O, V, AG; TL, M, S1, 2. — Boul. St-Germ.: Y, AF; TL, M. — Ecole-Milit.: Y; TS 3, 5.
AE. <i>Forges d'Ivry-Place St-Michel</i> (Pl. G 6 & DE 4). — 4 M.	Gare d'Orléans: P, T; TM, S4, 8, 9. — Halle aux Vins: G, I, K, U, Z; TL. — Pl. St-Michel: I, J, L, Q, AI; TG, H, Q.
AF. <i>Panthéon-Place Courcelles</i> (Pl. DE 5 & A 1). — 4 ³ / ₄ M.	R. Soufflot: J; TG, Q. — Odéon: H, Z. — St-Sulpice: L, Q. — R. d. Sts-Pères: V, AG, AH. — Boul. St-Germ., 207: X; TL, M. — Boul. St-Germ., 225: Y, AD; TL, M. — Concorde: TA, B, J, M, AB. — Madel.: A, D, E, X, AB, AC. — St-Augustin: B; TN, N, AB, NB, NC. — Boul. d. Courc.: TD, P.
AG. <i>Porte de Versailles-Louvre</i> (Pl. A 6 & D 3). — 3 ³ / ₄ M.	R. d. Vaugir.: Z. — R. d. Sèvres: V, X. — R. d. Sts-Pères: V, AF, AH. — St-Germ.-des-Prés: H, L, O, V, AD; TL, M, S1, 2. — Quais: H, Y; TA, B, J, AB. — Pal.-Roy.: C, D, G, H, R, Y, AI. — Louvre: D, G, I, N, R, AI; TC, F, K.
AH. <i>Auteuil-St-Sulpice</i> (Pl. A 5 & D 4). — 4 M.	Aut.: A. — Pont de Grenelle: TA, B, AB. — R. du Théâtre: Y. — Pl. Cambronne: Z. — R. d. Sts-Pères: V, AF, AG. — St Sulp.: H, L, Q.
AI. <i>Gare St-Lazare-Place St-Michel</i> (Pl. C 2 & D 4). — 2 M.	Gare: B, F, X; TND, NE. — Pal.-Roy.: C, D, G, H, R, Y, AG. — Louvre: D, I, N, V, AG; TA, B, C, F, J, K, AB. — Châtelet: C, G, J, K, O, Q, R, AD; TC, G, H, K, Q. — Pl. St-Michel: I, J, L, Q, AE; TG, H, Q.
AJ. <i>Parc Monceau-la Villette</i> (Pl. B 2 & G 1). — 4 M.	Parc: TD, P, NAB, NB. — R. d. Lévis: F. — Pl. d. Batignolles: G. — Pl. Ste-Euphrasie: J. — Boul. Barbès: TI. — R. de la Chapelle: TH.

List of the Tramway Lines.

(Comp. the following Tables and Plan, and p. 21 of the Handbook.)

Lines	Offices and 'Correspondances'
TA. Louvre-St-Cloud (s. Pl. D 4 & A 4). 6¼ M. — 50 & 35 c.	Louvre: C, D, G, I, N, R, V, AI; TC, F, K. — Quai des Tuil.: H, Y, AG. — Concorde: AC, AF. — Alma: A; TJ, M. — Pont de Grenelle: AH.
TB. Louvre-Sèvres.	7 M. — 50 & 35 c. — Wie TA.
TC. Louvre-Vincennes (Pl. D 4 & H 5). — 5¼ M. — 40 & 20 c.	Louvre: C, D, G, I, N, R, V, AG, AI; TA, B, F, J, K, AB. — Châtelet: C, G, J, K, O, K, R, AD, AI; TG, H, Q. — Quai Hôt. de V.: J. — Bastille: E, F, P, R, S, Z; TI, K, L. — Pl. d. l. Nat.: TE, F, S, 9, 11.
TD. Etoile-la Villette (Pl. A 2 & G 2). — 3¾ M.	Etoile: C, AB; TN, P, NA, S3. — Ternes: D. — Boul. d. Concorde: AF. — Parc Monc.: AJ; TNAB, NB. — Boul. d. Batign.: F. — Pl. Clichy: G, H; TN D, NE. — Pl. Pigalle: I. — R. Rochech.: J. — Boul. Magenta: TI. — Pl. d. l. Chap.: TH, NF. — Boul. d. l. Villette: L, M, AC; TE, NG, NH.
TE. La Villette-Place de la Nation (Pl. G 2 & H 5). — 3 M.	La Villette: L, M, AC; TD, P, NG, NH. — Boul. d. Belleville: N. — Ménilmont.: O. — Père-Lach.: P. — Pl. d. l. Nation: TC, F, NS, 9, 11.
TF. Cours de Vincennes-Louvre (Pl. H 5 & D 4). — 4 M.	Pl. d. l. Nation: TC, E, S, 9, 11. — R. d. l. Roquette: P. — R. Oberkampf: O; TI. — Pl. d. l. Républ.: E, N, S, U, AD; TI, NG, NH. — Boul. Sébastop.: D; TG, H. — Halles: D, F, J; TQ. — Louvre: C, D, G, I, N, R, V, AG, AI; TA, B, C, J, K, AB.
TG. Montrouge-Gare de l'Est (Pl. CD 6 & E 2). — 4 M.	Av. d'Orléans: TS1. — Observat.: TS4. — R. Soufflot: J, AF; TQ. — Cluny: J, L, Q; TH, L, M, Q, S, 6, 7. — Pl. St-Michel: I, J, L, Q, AE, AI; TQ. — Châtelet: C, G, J, K, O, Q, R, AD, AI; TC, H, E, K, Q. — R. d. Turbigo: D; TF. — Boul. St-Denis: E, L, M, N, T, Y. — Gare: B, L, M; TH, I.
TH. La Chapelle-Square Monge (Pl. B 1 & E 5). — 4 M.	R. d. la Chap.: AJ. — Pl. d. l. Chap.: TD, P, NF. — Gare d. l'Est: B, L, M; TG, I. — Boul. St-Denis, R. d. Turbigo, Châtelet, Pl. St-Michel, & Cluny, wie TG. — Sq. Monge: Z.
TI. St-Ouen-Bastille (Pl. E 1 & F 4). — 4¼ M.	R. Ordener: AJ. — Boul. d. l. Chap.: TD, P. — Gare du Nord: K, V, AC. — Gare d. l'Est: B, L, M; TG, H. — Pl. d. l. Républ.: E, N, S, U, AD; TF, NG, NH. — R. Oberkampf: O; TF. — Bastille: F, P, R, S, Z; TC, K, L; TS4, 10.
TJ. Louvre-Passy (Pl. D 4 & A 4). — 3¼ M.	Louvre: C, D, G, I, N, R, V, AI; TC, F, K. — Quai des Tuil.: H, Y, AG. — Concorde: AC, AF. — Alma: A; TA, B, M, AB, S3. — Pl. d. Passy: A, AB. — Muette: TN.
TK. Louvre-Charenton (Pl. D 4 & G 6). — 5¼ M.	Louvre: C, D, G, I, N, R, V, AG, AI; TA, B, C, F, J, AB. — Châtelet: C, G, J, K, O, Q, R, AD, AI; TG, H, Q. — R. Bourg-Tibourg: O, T. — Bastille: E, F, P, R, S, Z; TC, I, L, S4, 10. — Quai d. l. Rapée: TM. — Charenton: TS.
TL. Bastille-Porte Rapp (Pl. F 4 & B 5). — 3½ M.	Bast.: E, F, P, R, S, Z; TC, I, K, S4, 10. — Halle aux Vins: G, I, K, T, U, Z, AE; TM. — Pl. Maubert: I. — Cluny: J, L, Q; TG, H, Q, S6, 7. — St-Germ.-d.-Pr.: H, L, O, V, AD, Q; TS1, 2. — R. du Bac: X, AF; TM. — R. Bellechasse: Y, AD, AF; TM.
TM. Gare de Lyon-Place de l'Alma (Pl. G 5 & B 5).	4 M. — Gare de Lyon: R. — Quais: TK. — Gare d'Orl.: P, T, AE; TS4, 8, 9. — Then as for TL.; and Pl. de la Concorde A, AC, AF; Pl. de l'Alma TA, B, AB.

Lines	Offices and 'Correspondances'
TN. <i>Rue Taitbout-la Muette</i> (Pl. D2 & A3). — 6,49km.	R. d. Rome: TND, NE. — St-Augustin: B, AF; TN AB, NB, NC. — Faub. St-Honoré: D, AB. — Etoile: C, AB; TD, P, NAB, S3. — Trocadéro: A, B; TP. — Muette: TJ.
TO. <i>Auteuil-Boulogne.</i>	13/4 M. — 15 & 10 c. — Egl. de Boul.: TR.
TP. <i>Trocadéro-la Villette</i> (Pl. A3 & G2).	43/4 M. — Trocadéro: A, B; TN. — Etoile: TD, thence as for TO.
TQ. <i>Halles-Porte d'Ivry</i> (omnib.; Pl. E3 & EF6). — 5,59km.	Halles: D, F, J; T.F. — Châtelet: C, G, J, K, O, Q, R, AD, AI; TC, G, H, K. — Pl. St-Michel: I, J, L, Q, AE, AI; TG, H. — Cluny, J, L, Q; TG, H, L, M, S6, 7. — R. Soufflot: J, AF; TG. — R. Pascal: U. — Gobelins: K; TS4, 6, 7. — Pl. d'Italie: P; TS6, 7, 8. 13/4 M. — 15 & 10 c. — Egl. de Boul.: TO.
TR. <i>Boulogne-Les Moulineaux.</i>	3 M. — 15 & 10 c. — Charenton: T K.
TS. <i>Charenton-Créteil.</i>	12 M. — 1 fr. & 85 c. — Same 'correspondances' as TA and TB.
TAB. <i>Louvre-Ver-sailles.</i>	
TNA. <i>Etoile-Courbevoie.</i>	Etoile: AB; TD, N, P, S3. — 50 & 40 c.
TNAB. <i>Madeleine - Courbevoie-Suresnes.</i>	Madel.: A, D, E, X, AB, AC. — St-Augustin: B, AF; TN. — Parc Monceau: AJ; TD, P. — NAB: 85 & 45 c. — NB: 50 & 25 c. — NC: 50 & 25 c.
TNB. <i>Mad. - Boulev. Bineau</i> (Neuilly).	
TNC. <i>Mad. - Levallois-Perret.</i>	
TND & E. <i>Boul. Haussmann-Asnières-Gennevilliers & St-Ouen-St-Denis.</i>	Boul. Hauss.: B, F, X, AI; TN. — P. Clichy: G, H; TD, P. — 5: 60 & 30 c. — 6: 50 & 25 c., 60 & 30 c.
TNF. <i>Rue Taitbout-St-Denis.</i>	R. d. Châteaudun: B, H, I, AC. — Pl. d. l. Chapelle: TD, H, P. — 60 & 30 c.
TNG & H. <i>Place de la Républ.-Aubervilliers & Pantin.</i>	Pl. d. l. Républ.: E, N, S, V, AD; TF, I. — Boul. d. l. Villette: L, M, A, C; TD, E, P. — 8: 50 & 25 c. — Nif: 45 & 25 c.
TS1 & 2. <i>St-Germ.-des-Prés-Montrouge-Châtillon-Fontenay-aux-Roses & St-Germ.-des-Prés-Clamart.</i>	St-Germ.: H, L, O, V, AD, AG; TL, M. — Montparnasse: O; TS2, 3, 4. — Av. d'Orl.: TG (only for TS4). — TNA: 50 & 25 c.; 60 & 30 c. — TNAB: 60 & 30.
TS3. <i>Etoile-Montparnasse.</i>	Etoile: C, AB; TD, N, P, NA. — Alma: A; T1, M. — Ecole-Milit.: Y, AD, TS5. — Montparn.: O; TS4, 2, 4. — 30 & 20 c.
TS4. <i>Montparnasse-Bastille.</i>	Montp.: O; TS1, 2, 3. — Observat.: TG. — Gobelins: K; TQ, S6, 7. — Gare d'Orl.: P, T, AE; TM, S8, 9. — Bastille: E, F, P, R, S, Z; TI, K, L, S10. — 30 & 20 c.
TS5. <i>Avenue d'Antin-Vanves.</i>	Ecole-Milit.: Y, AD; TS3. — 40 & 20 c.
TS6. <i>Square Cluny-Vitry.</i>	Cluny: J, L; TG, H, L, M, Q. — Boul. St-Marcel: K; TQ, S4. — Boul. d. l. Gare: TS8. — Pl. d'Italie: P; TQ. — TNE: 60 & 30 c. — TNF: 50 & 25 c.
TS7. <i>Square Cluny-Ivry.</i>	
TS8. <i>Gare d'Orléans-Villejuif.</i>	Gare: P, T, AE; TM, S4. — Pont d. Bercy: TS9. — Boul. d. l. Gare: TS7. — Pl. d'Italie: P, TQ, S6, 7. — 50 & 25 c.
TS9. <i>Gare d'Orléans-Place de la Nation.</i>	Gare: P, T, AE; TM, S4. — Pont d. Bercy: TS8. — Pl. Daumesnil: TS10. — Pl. d. l. Nation: TC, E, F, S11. — 30 & 15 c.
TS10. <i>Bastille-Charenton.</i>	Bastille: E, F, P, R, S, Z; TI, K, L, S4. — Pl. Daumesnil: TS9. — 50 & 25 c.
TS11. <i>Pl. d. l. Nation-Montreuil.</i>	Pl. d. l. Nation: TC, E, F, S9. — 30 & 15 c.

River Steamboats.

(Comp. p. 22 of the Handbook and the annexed Plan.)

Charenton-Auteuil. I. 10 or 15c.; II. 10 or 20c.; I. & II. 20 or 25c.	Bank	Pont d'Aust.-Aut. (10 c.; Sun. and holidays, 40 c.)	Bank	Pont-Roy.-Suresnes. (20c.; Sun. and holidays, 40 c.)	Bank
I.					
CHARENTON (p. 214)	r.				
Alfortville (p. 214)	l.				
Les Carrières	r.				
Quai d'Ivry	l.				
Pont National	r.				
Pont de Bercy	r.				
Pont d'Austerlitz	l.				
II.					
PONT D'AUSTERLITZ	r.	PONT D'AUSTERLITZ	l.		
Jardin des Plantes	l.	Jardin des Plantes			
Pont de la Tournelle	l.	(p. 263)			
Boul. St. Germain		Pont Sully	île		
Hôtel de Ville (p. 62)	r.	Boulev. Henri IV			
Pont-Neuf (p. 220)	l.	(p. 67)			
Palais de Justice		Pont St-Louis	île		
(p. 217)		Ile St-Louis (p. 224)			
Pont des Sts-Pères	l.	Châtelet	r.		
Ecole des Beaux-		Quai du Louvre	r.		
Arts (p. 246)		Louvre (p. 86)			
Pont-Royal (p. 270)	l.	Pont-Royal (p. 270)	r.	PONT-ROYAL (p. 270)	r.
Rue du Bac (p. 271)		Tuileries (p. 149)		Tuileries (p. 149)	
Pont de la Concorde	l.	Pont de la Concorde	r.	Pont de la Concorde	r.
Chambre des Dép.		Place de la Conc.		Place de la Conc.	
(p. 272)		(p. 81)		(p. 81)	
		Champs Elysées			
		(p. 153)			
Pont des Invalides	l.	Pont des Invalides	r.		
(p. 168)					
Invalides (p. 274)					
Pont de l'Alma	l.	Pont de l'Alma	r.	Pont de l'Alma	r.
(p. 168)		(e. 168)		(p. 108)	
Avenue Rapp		Hippodrome (p. 31)		Hippodrome (p. 31)	
Pont d'Iéna (p. 166)	l.	Trocadéro (p. 163)	r.	Trocadéro (p. 163)	
Champ de Mars					
(p. 280)					
Avenue de Suffren	l.	Quay de Passy	r.	Quay de Passy	r.
Passerelle de Passy	île			Quai d'Auteuil	r.
Pont de Grenelle	île	Pont de Grenelle	r.	Billancourt	r.
Quai de Javel	l.	La Galiote (Auteuil)	r.	Bas-Meudon (p. 313)	l.
Quai d'Auteuil	r.	AUTEUIL (Point-du-	r.	Sèvres (p. 312)	l.
POINT-DU-JOUR		Jour)		Boulogne (p. 309)	r.
(p. 287)	l.			St-Cloud (p. 309)	l.
				Longchamp (on race	
				days; p. 159)	r.
				SURESNES (15 & 25 c.	
				from St-Cl.; p. 287.	l.

Cab Tariff.

(Comp. also pp. 19-20 of the Handbook.)

Old Tariff (p. 19).


Within the City.		From 6 a. m. in summer (31st March to 1st Oct.), and from 7 a. m. in winter (1st Oct. to 31st March), till 12.30 at night:		From 12.30 at night till 6 a. m. in summer (31st March to 1st Oct.), and till 7 a. m. in winter (1st Oct. to 31st March):	
Cab hired in street:		<i>Per Drive</i>	<i>Per Hour</i>	<i>Per Drive</i>	<i>Per Hour</i>
		fr. c.	fr. c.	fr. c.	fr. c.
Ordinary Cabs for 2 pers.		1 50	2 —	2 25	2 50
Ordinary Cabs for 4 pers.		2 —	2 50	2 50	2 75
Omnibus for 6 pers. . . .		2 50	3 —	3 —	3 50

Beyond the Fortifications.		From 6 a. m. till 12.30 at night in summer, or from 6 a. m. till 10 p. m. in winter.	
		When the hirer returns to the town in the same cab:	When the hirer does not return, he must make additional payment of:
Cab hired in street:		<i>Per Hour</i>	<i>Return Money</i>
		fr. c.	fr. c.
Ordinary Cabs for 2 pers.		2 50	1 —
Ordinary Cabs for 4 pers.		2 75	1 —
Omnibus for 6 pers. . . .		3 —	2 —

New Tariff (p. 19).

In the City and adjacent Communes.	<i>Ordinary Cabs</i>		<i>Landaus & omn. with 6 pl.</i>
	<i>2 places</i>	<i>4 places</i>	
First Kilomètre or first 1/8 hr. (7 1/2 min.), when waiting or driving slowly at hirer's desire	— 75 c.	1 fr. —	1 fr. 25 c.
Each succeeding kil. or 1/8 hr.	— 25 c.	— 30 c.	— 40 c.
Extra payment at night, within the city (outside the city special agreement) .	— 50 c.	— 50 c.	— 50 c.
Extra payment on passing the forti- fications, in either direction	— 50 c.	— 50 c.	— 50 c.
Extra payment when cab is discharged outside the fortifications	1 fr. —	1 fr. —	1 fr. —

Under the new tariff each cab is to be fitted with a *Compteur Hora-Kilométrique*, which will register in view of the hirer the distance traversed, the time of day, and the fare due. Cabmen are bound to drive at the rate of not less than 8 kil. (5 M.) per hr. except when otherwise directed by the hirer. — There is no tariff-charge for drives beyond the fortifications at night; a special agreement should be made in each case.



LÉGENDE.

- Omnibus jaunes (gold, yellow).
- Omnibus bruns (brown, brown).
- Omnibus verts (green, green).
- Omnibus bleus (blue, blue).

■ Têtes de lignes et bureaux de correspondance des omnibus
Abgangs- u. Endstationen, sowie Correspondenz-
stellen der Omnibulien
Starting-points and Offices (Bureaux de correspondance) of the Omnibus.
Les différentes lignes sont désignées par leurs lettres, A, B, C, etc.
Die Busstationen A, B, C, u. s. w. entsprechen den von den Wagen angegebenen offiziellen Bezeichnungen der verschiedenen Linien.
The different lines are distinguished by their official letters A, B, C, etc.

Tramway (Pferdebahn).

- Tr. A
- Bateaux à Vapeur (Steamboats)
- Charenton-Auteuil
- Pont d'Austerlitz-Auteuil
- Pont Royal-Suresnes

ITINÉRAIRES
DES
OMNIBUS, TRAMWAYS ET BATEAUX
DANS
PARIS

LEIPSIC: KARL BAEDEKER,

1891.







